This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

THE LIBRARY OF CONGRESS
1800

U. S. DEPARTMENT OF AGRICULTURE,
DIVISION OF PUBLICATIONS.

FARMERS' BULLETINS

Nos. 301-325,

WITH CONTENTS AND INDEX.

PREPARED UNDER THE SUPERVISION OF
GEO. WM. HILL,
EDITOR AND CHIEF.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

2d set

S21
.A6
2d set

D. OF D.
MAR 1 1909

CONTENTS.

Farmers' Bulletin 301.—Home-Grown Tea.
- History of tea cultivation in the United States
- Climate required by the tea plant
- Selection of soil
- Planting
- Cultivation
- Pruning
- Plucking
- Curing
- How to prepare tea for drinking
- Conclusions

Farmers' Bulletin 302.—Sea Island Cotton.
- Introduction
- Geographical distribution of Sea Island cotton in the United States
- Ideal crop requirements
- Possible extension of the Sea Island cotton-production area
- Markets
- Factors governing prices
- Farm practices
- Defects in market conditions
- Cultivation of Sea Island cotton
- Fertilizers for Sea Island cotton
- Preparation of the land
- Seed selection
- Handling the crop
- Diseases of Sea Island cotton
- Insect enemies of Sea Island cotton

Farmers' Bulletin 303.—Corn-Harvesting Machinery.
- Introduction
- Corn cutting with knives
- Machines for harvesting corn
- Corn pickers
- Huskers and shredders
- Economy of corn-harvesting machinery
- Conclusions

Farmers' Bulletin 304.—Growing and Curing Hops.
- Introduction
- Conditions essential to hop growing
- Propagation
- Planting and cultivating
- Pruning
- Trellises
- Systems of training
- Picking
- Curing
- Baling
- Cost and yield of crop
- Marketing

Farmers' Bulletin 305.—Experiment Station Work, XLII.
- Extension of rice culture
- Growing seed potatoes under mulch
- Manure as a summer mulch in forcing houses
- Renewal of old orchards
- Injury by Bordeaux mixture
- Gluten flours and similar foods
- Laxative properties of wheat bran
- Emmer as a feeding stuff
- Roots for farm animals
- Cabbage as stock feed
- Pasturing hogs
- Cull beans as feed for hogs
- Healthy poultry

FARMERS' BULLETIN 306.—DODDER IN RELATION TO FARM SEEDS.

Page.
Introduction ... 5
Dodder an important impurity in seeds ... 6
Sentiment regarding dodder in Europe ... 6
The character of dodder plants ... 7
The various kinds of dodder ... 9
Kinds of dodder seed infesting farm seed ... 9
Preference of the dodders for certain host plants ... 10
Kinds of seeds infested with dodder ... 11
Relation of dodder to the seed trade ... 11
A knowledge of dodder seed of value to the farmer ... 14
How the seed of dodder may be detected ... 15
Descriptions of dodder seeds ... 16
Buying seed ... 19
Cleaning seed ... 20
Detecting the dodder plants in the field ... 22
Destroying the plants ... 24
Summary ... 27

FARMERS' BULLETIN 307.—ROSELLE: ITS CULTURE AND USES.

Introduction ... 5
History and geographical distribution of the roselle ... 6
Botanical characters and relationships ... 7
Varieties ... 8
Cultivation and fertilization ... 10
Yield ... 12
Harvesting and marketing the calyces ... 12
Composition and uses of the fruit ... 13
Use of the plant for fiber ... 14
Breeding ... 14
Fungous diseases and insect enemies ... 16
Summary ... 16

FARMERS' BULLETIN 308.—GAME LAWS FOR 1907.

Introduction ... 3
Legislation of 1907 ... 3
Close seasons ... 11
Shipment of game ... 25
Sale ... 34
Licenses for hunting and shipping game ... 39
Appendix.—Tables showing close seasons for game under county laws ... 49

FARMERS' BULLETIN 309.—EXPERIMENT STATION WORK, XLIII.

Ice for household use ... 5
Culture and varieties of root crops ... 7
Cowpeas and soy beans ... 15
Silage from frosted corn ... 19
Cooperation in marketing fruit and truck crops ... 20
Evaporation of eggs and other factors which affect incubation ... 24
Causes of death of young chicks ... 27
Substituting snow water for poultry ... 28
Eradication of cattle ticks ... 29
Bacteria in cream ... 31

FARMERS' BULLETIN 310.—A SUCCESSFUL ALABAMA DIVERSIFICATION FARM.

Introduction ... 5
Soil ... 6
Type of farming ... 6
Rotation ... 7
Arrangement of fields ... 8
Management of hogs ... 9
Operations for 1904 ... 12
Receipts and expenditures for 1904 ... 14
Operations for 1905 ... 15
Receipts and expenditures for 1905 ... 18
Operations for 1906 ... 19
Receipts and expenditures for 1906 ... 21
Future plans ... 23
Conclusion ... 23

FARMERS' BULLETIN 311.—SAND-CLAY AND BURNT-CLAY ROADS.

Introduction
Physical properties of sand and clay
The mixing of sand and clay
Methods of constructing a sand-clay road
Cost of sand-clay construction
The use of sand-clay roads in this country
The construction of burnt-clay roads
Cost of burnt-clay construction

FARMERS' BULLETIN 312.—A SUCCESSFUL SOUTHERN HAY FARM.

Introduction
Location
Management
Cultural Methods
Field shed
Equipment of the farm and its cost
Expenses and receipts of the farm
Application to other farms of the system described

FARMERS' BULLETIN 313.—HARVESTING AND STORING CORN.

Introduction
The silo
Corn as a forage crop
Stripping the blades
Topping
Cutting and shocking compared with husking from the standing stalks
Time of cutting
Methods of cutting
Shocking
Jerking and storing the ears unhusked
Husking from the shock
Husking from standing stalks
Hauling to the crib
Use of corn-picking machines
Use of huskers and shredders
Storing the stover
Storing the ears
Convenient cribs
Protecting the crop from insects, mice, and rats
Methods of harvesting in relation to soil fertility
What constitutes a bushel of corn
Shrinkage

FARMERS' BULLETIN 314.—A METHOD OF BREEDING EARLY COTTON TO ESCAPE BOLL-WEEVIL DAMAGE.

Introduction
The distinguishing characters of plants of early and rapid fruiting cotton
The individual cotton plant and its progeny
The type recommended for early rapid fruiting and for productiveness to escape weevils
Seed selection for early, rapid fruiting, and for productiveness to escape weevils
Early and rapid fruiting measured by the yield of the selections in the boll-weevil district
Early-maturing defoliate cotton
Restraining rank vegetative growth by seed selection
Crossing or hybridizing
Treatment to insure a stand of early-planted cotton
Summary

FARMERS' BULLETIN 315.—PROGRESS IN LEGUME INOCULATION.

Introduction
The use of pure cultures of nitrogen-gathering bacteria
Applications for cultures
Reports of results
The effect of soil conditions upon legume bacteria
The effect of incubation upon the composition of the crop
Green manuring and inoculation
Confusion of nematode galls with nodules
When inoculation is desirable

FARMERS' BULLETIN 315.—PROGRESS IN LEGUME INOCULATION—Cont'd.

Page.
When inoculation is useless ... 13
Danger in inoculation by soil transfer ... 14
Results of cooperative field tests ... 14
Reports of inoculation experiments classed as successes ... 15
Reports of inoculation experiments classed as doubtful ... 18
Reports of inoculation experiments classed as failures ... 19
Summary ... 20

FARMERS' BULLETIN 316.—EXPERIMENT STATION WORK, XLIV.

Distributing manure and fertilizers ... 5
Winterkilling of peach buds ... 6
Effect of fertilizers on the color of apples ... 8
Ringing herbaceous plants ... 9
Potato scab ... 11
Effects of escaping illuminating gas on trees ... 12
The tuna or prickly pear as a food for man ... 14
Cooking cereal foods ... 17
Some experiments in silage making ... 19
Recent horse-feeding tests ... 22
Supplements to corn in hog feeding ... 25
Tankage for hogs following cattle ... 28
Hoppers for poultry feeding ... 30

FARMERS' BULLETIN 317.—EXPERIMENT STATION WORK, XLV.

Improving the convenience and comfort of the farm home ... 5
Lining of ditches and reservoirs to prevent seepage losses ... 10
Cement pipe for small irrigating systems and other purposes ... 12
Pollination of forced tomatoes ... 15
Increasing the productiveness of corn ... 17
Shrinkage of corn in cribs ... 22
Feeding grain to milch cows at pasture ... 26
Practical use of starters in ripening cream ... 27
Water pans for poultry ... 28
Catching hook for poultry ... 31

FARMERS' BULLETIN 318.—COWPEAS.

Introduction ... 7
Cowpeas for hay ... 8
Cowpeas in mixtures ... 11
Cowpeas for pasture ... 13
Feeding value of cowpeas ... 14
Growing cowpeas for seed ... 15
Cowpeas for soil improvement ... 22
Varieties of cowpeas ... 24
Summary ... 27

FARMERS' BULLETIN 319.—DEMONSTRATION WORK IN COOPERATION WITH SOUTHERN FARMERS.

Introduction ... 5
The two branches of the demonstration work ... 6
Plan of organization ... 6
Scope of the demonstrations ... 7
The instructions ... 8
How farmers are influenced to adopt better methods ... 9
The cultural system for producing cotton under boll-weevil conditions ... 10
Demonstration work on various farm crops ... 15
Practical results accomplished ... 17
Conclusion ... 22

FARMERS' BULLETIN 320.—EXPERIMENT STATION WORK, XLVI.

Fish fertilizer ... 5
Reclamation of salt marshes ... 9
Bermuda hay ... 12
Protein content of forage crops ... 13
Quality in wheat ... 18
Does it pay to spray potatoes? ... 22
Use of anesthetics in forcing plants ... 23
Fattening cattle for market ... 25
Cotton-seed meal and corn silage for dairy cows ... 28
Carbonated milk ... 29
Preservation of fence posts ... 30

FARMERS' BULLETIN 321.—THE USE OF THE SPLIT-LOG DRAG ON EARTH ROADS.
- Introduction
- The construction of a split-log drag
- How to use a drag
- When to use a drag
- Use of a drag on rocky or gravelly roads
- Cost data
- Construction and use of a ditch cleaner
- Conclusion

FARMERS' BULLETIN 322.—MILO AS A DRY-LAND GRAIN CROP.
- What milo is
- Where to grow milo
- How to grow milo
- How to use milo
- Prussic acid poisoning
- Insect enemies and fungous diseases
- Summary

FARMERS' BULLETIN 323.—CLOVER FARMING ON THE SANDY JACK-PINE LANDS OF THE NORTH.
- Introduction
- Extent and character of the jack-pine lands
- Attractions of the jack-pine lands
- Reasons for failures on the jack-pine lands
- Facts every settler should know
- Clearing and breaking jack-pine lands
- Depth to plow jack-pine lands
- Preparation of the seed bed
- Clover the key to successful farming on jack-pine lands
- How to secure a stand of clover
- Clover inoculation
- Effect of winds on the clover catch
- Wind-breaks for sandy lands
- Rough fields desirable on sandy lands
- Handling clover for seed
- Clover straw
- Clover following clover
- Manures and fertilizers
- Summary and suggestions

FARMERS' BULLETIN 324.—SWEET POTATOES.
- Introduction
- Areas adapted to sweet potato culture
- Climatic conditions required
- Character of soil adapted to sweet potatoes
- Fertilizers for sweet potatoes
- Propagation of plants
- Preparation of land for sweet potatoes
- Setting the plants
- Cultivation of sweet potatoes
- Diseases
- Insects
- Harvesting sweet potatoes
- Storage of sweet potatoes
- Temperature and ventilation of storage houses
- Loss from shrinkage while in storage
- Marketing during winter months
- Varieties of sweet potatoes
- Cost of production and returns
- Uses of sweet potatoes

FARMERS' BULLETIN 325.—SMALL FARMS IN THE CORN BELT.
- Introduction
- A forty-acre farm in Saunders County, Nebr
- A forty-acre farm in Adams County, Nebr
- A twenty-acre farm in Pawnee County, Nebr
- General conclusions

Issued June 26, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 301.

HOME-GROWN TEA.

BY

GEORGE F. MITCHELL,
Scientific Assistant in Tea Culture Investigations,
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE
1907.

B. P. I.—292.

HOME-GROWN TEA.

HISTORY OF TEA CULTIVATION IN THE UNITED STATES.

A little more than one hundred years ago the French botanist Michaux successfully planted the first tea in the United States. This was at Middleton Barony, on the Ashley River, about 15 miles from Charleston, S. C.

In 1848, Dr. Junius Smith retired from an active life in London to ruralize and plant tea on his estate near Greenville, S. C. Both plants and seed were imported, and in an article in the American Agriculturist for 1851 Dr. Smith stated that his plants were doing finely and had withstood a snow 8 to 9 inches deep on January 3 of that year, and he added: "I can not help thinking that we have now demonstrated the adaptation of the tea plant to the soil and climate of this country, and succeeded in the permanent establishment within our own borders." Dr. Smith died soon afterwards, in 1852, and his plants, without protection, soon disappeared.

As early as 1858, the United States Government, through the Commissioner of Patents, sent Mr. Robert Fortune to China to obtain seeds to be planted in this country. In less than one year's time tea plants were distributed among private persons in the Southern and Gulf States, who later reported that the plants had been successfully cultivated by them and in a great many cases that tea had been made at their homes.

During the year 1880, Hon. William G. Le Duc, then Commissioner of Agriculture, employed Mr. John Jackson, who had been a tea planter for fourteen years in India, to carry on experiments to test the feasibility of growing and manufacturing tea in this country. The experiments were at first conducted in Liberty County, Ga., on a place bought by the Government from Dr. Jones, who had planted tea there in 1850.

Later, 200 additional acres of land near Summerville, S. C., were leased for twenty years from Mr. Henry A. Middleton to carry on these experiments. Seed was imported from Japan, India, and China and was also collected from the few plants then surviving in the United States that had been previously sent out by the Patent Office. From these seeds a small area was planted in tea, but before the plants had a chance to make very much growth Commissioner Le Duc was succeeded by Commissioner George B. Loring, who thought it best, because of the illness of Mr. Jackson and for other reasons, to abandon these experiments.

Since then the cultivation and manufacture of tea on a commercial scale has been practically demonstrated, in cooperation with the Bureau of Plant Industry, by Dr. Charles U. Shepard at his "Pinehurst" tea gardens near Summerville, S. C., where about 100 acres are planted to tea, of which the area in bearing yields about 12,000 pounds of dry tea each year. One of the gardens has yielded as much as 535 pounds of dried tea to the acre during a single season.

Although the distribution of the many plants and the establishment of the many home tea gardens in the South were steps toward encouraging the people to manufacture their own tea, these gardens soon died through lack of interest, because the important point of teaching the growers how to pluck and make the leaves into tea had been neglected.

Experiments were conducted during the summer of 1905 with a view to developing a simple process by which both the green and the black teas can be made successfully by any intelligent person with only such utensils as are found in every kitchen. These experiments indicate very strongly that the result sought can be accomplished and that farmers and others who have enough garden space to grow the plants for use or for ornamental purposes can with very slight expense and trouble make enough tea for their home consumption. It is a significant fact that much of the tea grown in China is planted in the corners and waste places of farms.

CLIMATE REQUIRED BY THE TEA PLANT.

The climate of the Southern and Gulf States is in general admirably adapted to the cultivation of the tea plant. Although the rainfall is much less than in a great many tea-producing countries, the average annual temperature is lower, causing less evaporation and consequently requiring less rainfall. The cultivation of the tea plant can safely be risked where the temperature seldom falls below 24° F. and never goes below zero, and where the annual rainfall exceeds 50 inches, 30 inches or more of this precipitation occurring during the cropping season.

SELECTION OF SOIL.

A well-drained, friable, and easily penetrable clay loam or sandy loam containing a large amount of organic matter is best adapted to the cultivation of the tea plant. Very tenacious undrained soils y sandy soils that lack water-retaining properties are not d to the growth of tea; neither will the plants tolerate stag-vater in the subsoil. The plants being of subtropical origin ıs much protection from the cold as possible; therefore, much results can be obtained where a southern exposure with an lance of sunshine is selected.

PLANTING.[a]

e seed should be planted in the autumn or winter just before a A convenient place protected from the prevailing winds by a



FIG. 1.—Frame erected over seed bed.

, a wind-break, or by the side of a house should be selected and red with a frame about 6 feet above the ground. (Fig. 1.)

---

or information concerning the vegetative propagation, veneer grafting, and her-us grafting of tea, see Bulletin No. 46 of the Bureau of Plant Industry, entitled · Propagation of Tropical Fruit Trees and Other Plants," 1903, pp. 19–23, and 'I and VII.

should have cracks about 1½ to 2 inches wide, so as to
y a little of the direct rays of the sun. It can be made
waste lumber or loosely woven wire netting covered thinly
of some kind.

should be pulverized to a depth of at least 8 inches and
eed from grass and roots. The seed should be placed 4 by
part in little holes about 1½ inches deep. One seed should
each hole and covered by simply raking the surface over
h a rake.

2. Tea plants serving ornamental purposes in hedge rows bordering a walk.

rsery bed should be covered uniformly with some kind of
protect the seed from the cold and also to mulch the bed.
w or needles, if procurable, will be found excellent for this
As the plants begin to shoot above the ground, a little of
should be removed from time to time and the nursery
ly weeded. This should be kept up until autumn, when the
uld be permanently removed and the top of the frame
with.

nly a few hundred plants are to be raised from seed, a large
ches deep provided with drainage holes and kept protected

rom the direct sunlight will suffice. In very dry weather, water hould be applied to the nursery bed or box either early in the morn-ng or late in the afternoon, when the sun is not very hot.

Seedlings are generally transplanted in the autumn or spring after heavy rain or when the soil is quite moist to a considerable depth. The plants may be set out twelve to eighteen months from the time f sowing the seeds, although it does no harm to let them remain in he nursery two years, but in such cases their tops should be slightly pruned to prevent them from growing too tall and slender. The plants can either be set 2 feet apart in hedge rows along fences or walks, where they can serve for ornamental purposes (fig. 2), or they can be placed from 2 to 5 feet apart in 5-foot rows.

The soil should be thoroughly pulverized by spading or plowing as deep as possible; then it should be leveled and holes 9 to 12 inches deep made at the proper distances with a trowel or spade. The plants should be placed in the holes with the taproot straight down. In cases where this can not be accomplished owing to extreme length the root should be pruned with a knife or other sharp instrument. The earth should be firmly compressed around the plant, which is best done with the foot. If the soil is rather dry and it seems desirable to water the plants, this should be done.

CULTIVATION.

Frequent and shallow cultivation that will maintain a loose mulch around the plants, as well as keep them free from weeds, is best during the spring and summer, when evaporation is very pronounced, because this shallow mulching breaks the capillary tubes in the soil and lessens the evaporation. In the autumn, after the plucking season is over, the soil should be turned up thoroughly to a considerable depth with a spade or a plow, so that oxidation and disintegration will take place during the winter, when there is very little evaporation.

Commercial fertilizers or barnyard manure should be applied late in the winter or early in the spring and well worked in around the plant but not too near the stalk, because the minute feeding roots which take up the plant food extend some distance from the stem.

PRUNING.

Every February or March after the plants are three years from seed they should be pruned down so that only two eyes are left on the preceding year's new wood. This can be done with either knives or pruning shears, making a clean slanting cut one-half inch above the top eye that is to remain.

times the plants get very thick after five or six years of service
l off in their yield; in such cases they should be "collar
" that is, pruned to the ground by sawing off the stems.
uses them to put out an abundance of new shoots, which can
ed late in the same season.

cases the prunings should be buried in the middle of the rows,
have considerable manurial value.

PLUCKING.

ucking, which in the Southern States should begin about the
May and continue until about the middle of October, only the bud (pekoe tip) and the first two or three leaves should be taken (fig. 3), as the other leaves are generally too tough to make good tea. This is done by pinching off the stem with the thumb nail and first finger just under the last leaf to be plucked. The bushes are generally plucked every seven to fifteen days, but this is determined by the development of the tender shoots, care being taken that they do not become too tough before plucking, because then they do not make good tea.



Tea plant, showing part to be plucked.

Leaves that are slow in developing always make a better flavored product than those that grow rapidly, so a small yield is always compensated for by a more highly flavored tea.

CURING.

e processes described, the use of a thermometer and other tech-
pparatus has been entirely eliminated and their places sup-
y the senses of touch, smell, and sight. The importance of
g the stove and kitchen utensils that are to be used absolutely
nd void of odor of every description can not be too strongly
because dry tea readily absorbs any odor that may be pres-
s only a few utensils are required it is best to obtain new ones
ep them for this purpose only. All that is necessary is a
t double boiler (a saucepan with a hot-water jacket), a large
referably agate-lined, a large wooden spoon or paddle, and a
ng board where the use of a clean kitchen table can not be had.

leaves are brought in the day before they are to be made into l are spread very thinly and evenly on a clean table or floor, :hey are allowed to remain from twelve to twenty-four hours, hey will lose about one-half their weight by the evaporation sture, become very soft and flaccid, and feel like an old kid In this condition they are ready for rolling. When wither-



FIG. 4.- Rolling the withered tea leaves.

near completion the leaves should be watched very carefully, se if allowed to go on too far they become parched and unfit for g.

out half a pound of the withered leaf is rolled or kneaded from y-five to thirty minutes on a clean table or kneading board. peration is similar to the kneading of dough. (Fig. 4.) The g should be very light for the first ten minutes so as to allow the s to begin to twist or take on the "roll"; then the pressure should be gradually increased until all that can be exerted is applied, so as to express the juice (which should be sopped up with the leaves) and give the leaves a tight twist. This tight rolling not only makes a strong tea but helps to preserve the flavor. Very often the leaves will be a little overwithered and rather brittle, in which case water should be sprinkled on the withered leaves until they are rendered soft enough to roll.

After rolling, the leaves are formed into a "ball" and allowed to remain in a cool and preferably damp place from three to six hours to ferment. The end of this stage in the process is indicated by the ball turning a yellowish copper color, which can be seen when the ball is broken open. The raw herby scent has also changed to an agreeable fruity one. This stage must be watched carefully, because if allowed to go too far the leaves become sour and unfit for tea.

After fermenting, the ball is broken up and spread about half an inch thick in a large clean pan (preferably of agate ware) and placed in the stove oven to dry. The pan should be removed at intervals and the tea turned. This should continue until the tea is very brittle to the touch and a very slight odor of tea is given off. The oven should not be too hot during this operation as too much heat prevents uniform drying. The tea is now ready for use and should be placed in air-tight tin boxes or cans.

SUN-CURED BLACK TEA.

Sun-cured black tea is the same as the ordinary black tea except that the withering is done in the sun in a much shorter time and produces a tea more acceptable to the average taste.

The freshly picked leaves should be spread very thinly and evenly on trays made by tacking cloth on wooden frames of any convenient size, or they may simply be spread on cloths, which in either case should be placed in the sun until the leaves become very flaccid. This will require from one and one-half to three hours, or more, depending on the intensity of the sun's heat and the humidity of the atmosphere. During this operation the leaves should be turned at intervals, so as to induce uniform withering. The further procedure is identical with that already described for the black tea from the point of withering.

This tea is generally made during the months of July and August, when the heat of the sun is very intense.

GREEN TEA.

The green tea is made from the same leaves as the black, although some varieties are best adapted to make each of these respective kinds. The green-tea process is the same as that for making black ea, except that instead of withering from twelve to twenty-four ours and fermenting from three to six hours (when oxidation takes lace, which renders it black) the green leaves are quickly brought in nd placed in a covered double boiler—that is, a saucepan with a hot-vater jacket (one pound of leaf to a 4-quart boiler)—and allowed to emain surrounded by boiling water from seven to nine minutes; the over should be removed and the leaves stirred at intervals. This vill render the leaves very soft and flaccid, ready for rolling. During his rapid process the oxidizing agencies of the leaf are sterilized by he boiling water and steam in the hot-water jacket surrounding the eaves, and the production of a green tea is rendered possible. These flaccid leaves are rolled in like manner to the black tea for about ten minutes, being stirred at intervals until they lose some of their moisture and become sticky; then they are again rolled from fifteen tc wenty minutes under all the pressure that can be applied. After olling they are immediately placed in the oven in a pan and turned t intervals (similar to the black tea) until they are dry and brittle to the touch and a slight scent of tea is given off.

HOW TO PREPARE TEA FOR DRINKING

Attention must be called to the fact that ordinarily tea is not drawn properly, which not only makes it less palatable than would otherwise be the case but also makes it very deleterious. Chemically, tea leaves yield principally thein and tannin. The former is the mild stimulant that is sought, while the latter should, as far as possible, be avoided. The thein is very soluble and nearly all dissolves in water that has been brought to the boiling point and allowed to remain on the leaves three or four minutes, whereas if the infusion be longer extended only a little more thein is extracted but much more tannin.

To make tea properly, bring freshly drawn water to a boil, pour it on the requisite amount of tea in a previously scalded pot, and allow it to remain covered from three to five minutes; then decant or strain into another receptacle. The spent leaves should not be used again because practically all the stimulating ingredient has been removed and that which is left is very deleterious to health.

CONCLUSIONS.

The cultivation of the tea plant in home gardens is not only profitable, but a great deal of pleasure can be derived from it at the same ime that the use of the much adulterated foreign article is avoided. This is often found to contain Prussian blue, indigo, turmeric, soapstone, and leaves of other plants than tea, some of which are injurious o health.

In the autumn this beautiful evergreen plant is covered with handsome, fragrant, whitish flowers, having a golden yellow center, making it an excellent ornamental plant.

The children as well as the older members of the family may derive abundant pleasure in plucking and making the leaves into tea, although the process is so simple that this work can easily devolve upon any intelligent servant.

The crop of an average tea bush is about 3 ounces of cured tea during the picking season, so that 100 plants will yield about 18 pounds a year. As a pound makes from 350 to 400 cups of tea, 50 plants should furnish a cup of tea apiece to a family of nine for every day in the year.

O

Issued August 24, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 302.

SEA ISLAND COTTON:

ITS CULTURE, IMPROVEMENT, AND DISEASES.

BY

W. A. ORTON,
PATHOLOGIST, BUREAU OF PLANT INDUSTRY.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

CONTENTS.

Page.
ıtroduction 7
eographical distribution of Sea Island cotton in the United States 7
leal crop requirements 9
- Soil 9
- Moisture 9
- Humus 9
- Location and exposure 9
- Labor 10

ossible extension of the Sea Island cotton-producing area 10
larkets 11
actors governing prices 12
arm practices 14
- Seed selection the first requirement 14
- Preparation of the staple for market 15
- Better culture means larger crops 16
- Credit and the rental system a bar to progress 16

efects in market conditions 16
ultivation of Sea Island cotton 16
- Rotation and diversification 16
  - Rotation systems 18
    - The choice of a legume 18
    - Resting land 19

Fertilizers for Sea Island cotton 20
- Present practices 20
- General principles governing the use of fertilizers 20
  - Effect of nitrogen 21
  - Effect of potassium 21
  - Effect of phosphorus 22
  - Lime usually unnecessary 22
  - The best formula 22
  - Quantity to the acre 22
  - Methods of application 23

Preparation of the land 23
- Ridge culture 23
- Level culture 25
  - Plowing should be deep 25
  - Vegetable matter should be ployed in 25
  - Fertilizing and bedding 25
  - Planting 25
    - Time of planting 25
  - Cultivation

Page.

- Seed selection 26
  - Origin of Sea Island cotton 26
  - Continued breeding necessary 26
    - Sea Island methods 27
    - Sea Island varieties 27
      - Breeders' rights 27
      - Sale of seed from the Sea Islands 28
    - Seed selection will succeed in the interior 28
  - Methods of selection 28
    - Roguing 28
    - General selection 29
    - Pedigree breeding 30
      - Beginning the selection 30
      - Second year: The progeny test 31
      - Third year: The increase plat 32
      - Fourth year: The general crop 32
      - Separate ginning of the seed crop important 32
    - Improvement of cotton seed by gravity separation 33
  - Ideal qualities of Sea Island cotton 33
    - Length of staple 33
    - Uniformity of staple 34
    - Strength of staple 34
    - Percentage of lint to seed 34
    - Color of staple 34
    - Fineness 35
    - Productiveness 35
    - Form and size of plant 35
    - Bolls 36
    - Seed 36
    - Earliness 36
    - Disease resistance 36
- Handling the crop 36
  - Preserving the full value of the crop 36
  - Grade: Definition, and importance 37
    - Defects influencing grade [illegible]
      - Loss of bloom or luster 37
      - Loss of strength 37
      - Nep 37
      - Broken leaf, etc 38
      - Short fibers 38
      - Weak fibers 38
      - Lack of uniformity in the bale 38
      - Yellow cotton 39
      - Sand 39
      - Moisture 39
      - Injury in ginning 40
  - Summary 40
- Diseases of Sea Island cotton 41
  - Sore-shin and damping-off 41
  - Bacterial blight 41

Diseases of Sea Island cotton—Continued. Page.
Wilt 43
Cause 44
Soil treatment not a successful remedy 45
The relation of soil conditions to wilt 45
Control through the use of resistant varieties 45
Control through originating new varieties 46
Root-knot 46
Anthracnose 47
Remedies 47
Rust 47
Blue cotton 48
Insect enemies of Sea Island cotton 48

ILLUSTRATIONS.

Page.
Fig. 1. Map of the Sea Island cotton area of the United States, showing distribution by counties 8
2. Bag of Carolina-grown Sea Island cotton, showing the style of package used on the Sea Islands 12
3. Bale of interior-grown Sea Island cotton, showing the style of package used in Georgia and Florida 12
4. Cross section of the beds on which cotton is grown on the Sea Islands 23
5. Double roller used on the Sea Islands to prepare the beds for planting cotton 24
6. Good and "run-out" seed cotton 29
7. Diagram of a pedigree breeding plat 32
8. [illegible] of cotton plant 35
[illegible] Sea Island cotton from healthy bolls compared with [illegible]ocks from diseased bolls 38
10. Disea[illegible] leaves, boll, and stems of cotton plant showing several forms of bacterial blight 42
11. A plant recently affected with cotton wilt, with a healthy resistant plant growing beside it 43
12. Roots of a cotton plant affected with root-knot 44
13. Cotton boll affected with anthracnose 47

B. P. I.—293.

SEA ISLAND COTTON: ITS CULTURE, IMPROVEMENT, AND DISEASES.

INTRODUCTION.

Our country can feel a just pride in the Sea Island cotton industry, for it produces the longest, finest, and most valuable cotton grown in the world. Its silky staple is used for spinning fine fabrics and laces and is of paramount importance to the thread industry, which requires a considerable part of the crop. Where great strength and durability are essential, as, for instance, in United States mail bags and in pneumatic tires, Sea Island cotton is also employed. The highly organized and laborious methods of culture, the excellent system of seed selection, and the painstaking care of the product which have maintained the high quality of the cotton grown on the Sea Islands are matters of special interest.

It is quality rather than quantity that gives economic importance to the Sea Island cotton industry, for the total annual production is less than 1 per cent of the American crop, or an average for the past seven years of 94,000 bales per annum.

An improvement in quality, an increase in production, and a greater profit to the acre are all possibilities of the future. They will result from the general adoption of improved methods and the extension over the whole Sea Island cotton belt of the careful system of seed selection and handling now practiced in one portion of the area. On the other hand, conditions are such that the industry may in time be crushed by competition unless the farmers awake to the necessity of considering the needs of the consumer as regards quality and purity and learn that the cost of production per pound can be reduced by increasing the yield per acre and that a diversified cropping system is safer and more profitable than the all-cotton plan.

GEOGRAPHICAL DISTRIBUTION OF SEA ISLAND COTTON IN THE UNITED STATES.

The successful cultivation of Sea Island cotton in this country is confined to the area lying southeast of a line drawn from Georgetown, S. C., to a point in western Florida. The accompanying map, figure 1, shows the approximate quantity produced in each county in this district, each dot standing for 500 bales or a fraction thereof.

In South Carolina the center of production is on the Sea Islands along the coast, where the finest staples are grown. The chief of these islands are James, Edisto, John, and Wadmalaw.

It is interesting to learn that in Georgia the coast counties produce scarcely any cotton, owing to the unfavorable character of the country, the absence of the necessary labor, and the predominance of the lumbering and trucking industries. The interior counties which grow Sea Island cotton extensively also produce considerable Upland cotton.



FIG. 1.—Map of the Sea Island cotton area of the United States, showing distribution by counties. Each dot stands for an average production of 500 bales.

In Florida a similar condition exists. Cotton is not grown on the coast, but is confined to the interior counties in the north-central portion of the State. Here the proportion of Upland to Sea Island cotton is much smaller, until one reaches the western counties, where conditions are less favorable for the long-staple cotton and where the Upland type is mainly grown.

The annual crop fluctuates widely, according to the nature of the season, but the average yield in bales of not quite 400 pounds each during the past five years has been as follows: South Carolina, 10,957 bales; Georgia, 50,311 bales, and Florida, 33,749 bales.

IDEAL CROP REQUIREMENTS.

Several factors must be considered when seeking a location for growing Sea Island cotton. Those mentioned here affect not only the yield but the quality of the staple, its color, and the percentage of lint to seed. The relative influence of the various factors is, however, not always determinable.

SOIL.

The crop requires a sandy or a sandy loam soil, preferably with a clay or compact sand subsoil about a foot below the surface. Most of the Sea Island cotton is grown on the soil type classified by the Bureau of Soils as Norfolk fine sand, with lesser areas of Norfolk sand, Norfolk sandy loam, and related types. On the Sea Islands, where a clay subsoil is rarely found, the growers seek to maintain a compacted layer beneath the plants by the tramping of stock during the year the land is resting. The interior growers prefer a clay subsoil, but sometimes plant cotton on quite deep sand, where the quality is satisfactory; the yield is smaller, however, in such cases.

MOISTURE.

A well-regulated water supply is the most important factor influencing Sea Island cotton. Thorough drainage is essential. On this account more and better cotton is grown on the slightly elevated margins of the Sea Islands than in the lower central portions. Tile drains make possible the cultivation of land otherwise too wet. In the interior, cotton is grown only where there is suitable drainage. On the other hand a liberal and regular supply of water is needed, and wherever cotton is planted on the dry hills in the upper edge of the Sea Island cotton belt inferior results are secured, the staple becoming shorter and harsher. The lower lying lands are better, provided they have adequate drainage.

HUMUS.

Soils very rich in humus appear to be unsuited to Sea Island cotton, producing too rank a growth; but a deficiency of humus is also a serious objection, as such land produces a small plant with a tendency to the shedding of bolls and to rust.

LOCATION AND EXPOSURE.

Atmospheric humidity appears to be a prominent factor influencing the quality of the staple. On the Sea Islands, fields having an ocean exposure are said to produce a finer and glossier staple on account of the moisture-laden ocean breezes, and in the interior one advantage of the lower lands is doubtless their moist air, which is conserved by protecting f [illegible] and near-by swamps. In the absence of suffi moisture in the air the staple becomes harsh and shorter. This is further shown by the fact that a wet season is more favorable to Sea Island than to Upland cotton, while the Upland varieties do better in a dry season. The relative production of Upland and Sea Island cotton in the northern counties fluctuates with the season and the changes in acreage due to varying market conditions.

The mixing of seed and the hybridization which result from planting cotton of both types in the same community is a serious handicap to the growers of Sea Island cotton. In this respect portions of Florida where only Sea Island cotton is grown possess a marked advantage, and the introduction of Upland varieties should be discouraged.

LABOR.

In addition to the effect of high prices in stimulating the industry and of low prices in depressing it, a factor which must be considered in connection with the production of cotton in either old or new sections is the supply of available labor. Until present methods are revolutionized a relatively large amount of fairly cheap labor is required, and it is a great advantage if the laborers have had long experience with the crop. Throughout the Sea Island cotton belt there is now a growing scarcity of labor, which is likely to restrict the acreage planted. The farmers must meet the new conditions by the adoption of labor-saving machinery in planting and in cultivation, but there will continue to be difficulty in getting the cotton picked.

The development of trucking and lumbering industries restricts the less profitable cotton crop, and there is a steady exodus of laborers to engage in railroad building, etc., making the labor problem still more serious.

POSSIBLE EXTENSION OF THE SEA ISLAND COTTON-PRODUCING AREA.

It has been predicted that there will be in the future a constant increase in the world's consumption of Sea Island cotton, requiring a corresponding increase in production. Sections outside the present Sea Island cotton belt have from time to time attempted to engage in its culture, but such extensions of area are unnecessary and do not promise a profit. No other portion of our cotton belt is as well adapted to the crop as the area in which it is now grown. This is shown by the fact that during the past hundred years very many attempts have been made to grow Sea Island cotton in other States, and all have failed. Such extensions are unnecessary, because several times as much as the present crop could be produced in the area ow devoted to Sea Island cotton, if circumstances required it. This eased production could be accomplished in part by clearing and planting new land, for neither on the Sea Islands nor in the interior counties is more than a small fraction of the land under cultivation, and in part by increasing the yield per acre, which could be doubled by better cultural methods and the practice of seed selection. An additional increase would result from the substitution of Sea Island for Upland cotton in the border counties where both are now grown.

Serious obstacles are met with in introducing Sea Island cotton into a new section. There is difficulty in securing the proper care in cultivation and in picking and handling the staple. Pickers accustomed to Upland varieties object so much to the small and partly closed Sea Island bolls that it is difficult to get the cotton picked even at the prices now paid—$1 to $1.25 a hundred pounds. The ginning must be done on a roller gin, as the saw gin injures the staple too much, and a specially equipped ginnery is therefore necessary. Further difficulties are met with in marketing the product, which at first can rarely be sold to advantage in a local market where the buyers are unaccustomed to the Sea Island staple. Shipment to a recognized market for Sea Island cotton is necessary in such cases.

MARKETS.

The cotton grown in South Carolina is marketed at Charleston, while the interior crop is handled at Savannah, Blackshear, and Valdosta, Ga., Madison, Fla., and other interior towns. There is a marked difference in the style of bale in the two cases. South Carolina cotton is put up in bags, 7½ feet long and about 2½ feet in diameter, containing 300 to 400 pounds. (Fig. 2.) They are filled by hand and pressed in a light hand-screw press. Compression for export is not practiced. As the use of this bag has been confined to the Sea Islands, it serves as a trademark to distinguish the crop in foreign markets.

In the Charleston district the finest cotton is that grown by a limited number of planters who have for many years paid the most careful attention to seed selection. Their cotton is not only long and fine but is picked with so much regard to cleanliness and uniformity that the grower's private brand on the package is often a sufficient guarantee of its quality.

These fine "crop lots" comprise about 35 per cent of the cotton marketed in Charleston and sell for from 30 to 60 cents a pound. They are all exported. The demand for this extra-fine and high-priced cotton is very limited. The remainder of the South Carolina crop is sold in the usual manner at lower prices. The higher price secured for South Carolina cotton is largely because of its superior preparation, all [illegible]ined and weak cotton and bits of leaf being removed befo[illegible]ing.

Interior Sea Island cotton is packed by a steam press into bales weighing about 400 pounds each, of the same shape and size as an Upland cotton bale, 54 inches by 27 inches (fig. 3). They are covered with heavy burlap, secured by sewing with strong cord instead of by the steel ties used on bales of Upland cotton.



Fig. 2.—Bag of Carolina-grown Sea Island cotton, showing the style of package used on the Sea Islands.

The buyers classify interior cotton first by length of staple into "East Floridas," 1¾ inches to 2 inches; "Floridas," 1⅝ inches to 1¾ inches; and "Georgias," 1⅝ inches but less fine than Floridas. These names have come to be applied without regard to the source of the cotton. The length of staple is mainly influenced by seed selection, but in part by the character of the soil. Each of these classes is subdivided into grades with reference to its preparation and appearance, the usual grades being fancy, extra choice, choice, extra fine, fine, and "dogs." The difference of 5 to 10 cents a pound between fancy and fine shows the possible gain to the farmer from careful preparation. Loss of grade is due to exposure to weather before picking, to storing or ginning when too wet, and especially to the presence of stained or yellow cotton and bits of leaf or other trash.



Fig. 3.—Bale of interior-grown Sea Island cotton, showing the style of package used in Georgia and Florida.

FACTORS GOVERNING PRICES.

There is a fairly uniform demand for a few hundred bags of extra-fine cotton with staple of 2 inches and over, and, for what the market requires, a high price, 50 to 80 cents a pound, will be paid. A larger quantity of this long-staple cotton is difficult to sell at any price. For the medium grades (1⅝ inches to 1⅞ inches) there is a liberal demand at prices determined by the law of supply and demand. The size of the crop in Georgia and Florida is the principal factor in establishing the price, but other long staples exercise considerable influence.

Sea Island cotton is only slightly affected by the fluctuations of short-staple Upland cotton, but the amount and quality of the long-staple Upland crop seriously affect the lower grades of Sea Island cotton. Staples less than 1⅝ inches long sell well only in a year when the long-staple Upland crop is inferior. This long-staple Upland cotton is grown mainly in the Mississippi Valley, and as it can be produced at a less cost than Sea Island cotton it is evident that the latter must not be permitted to become less than 1⅝ inches in length, in order to avoid this competition.

The next quality of staple competing with Sea Island cotton is the Egyptian. Of this an amount equivalent to about 1,500,000 Sea Island bales of 400 pounds is produced every year in the Nile Valley, and 147,000 such bales are annually imported into America. An average price is 15 cents a pound. Egyptian, while not as long and fine as Sea Island cotton, is very strong and free from waste, owing to careful preparation. It wastes in the mill 8 per cent less than Sea Island cotton, the average waste in the different processes of preparing for spinning being 33 per cent for the Sea Island and only 25 per cent for Egyptian. Much of the Egyptian cotton is decidedly shorter than Sea Island, but the Jannovitch variety and to some extent the Abassi are, in particular, competitors of Sea Island of 1⅝-inch staple or less and will continue to be used in preference to the American product, even in our own mills, until the interior Sea Island growers improve their product.

Mr. A. P. Brantley, a well-informed buyer and exporter of Sea Island cotton, writes as follows:

> Jannovitch has, during the last few seasons, commanded practically as much money as Extra Choice and Fancy Georgias. If, however, we could produce cotton with staple of 1⅝ inches which would not show a spinning loss of more than 25 per cent as compared with 33 per cent, the present average loss, and if at the same time we could grow a cotton with fewer neps, there would be a tremendous expansion in the demand for this style of cotton, for the reason that it is slightly stronger than Jannovitch; but as the case stands now Jannovitch is preferred at an even price in many cases on account of its being less wasty and having fewer neps.

The Egy an, although closely related to Sea Island cotton, can not be grow successfully in our southeastern States on account of its susceptibilit to the bacterial disease "black-arm."

Sea Island cotton produced in the West Indies is equal to the average American product, and indeed competes with the Carolina Sea Island cotton rather than with the interior product. The West Indian industry is new, having been developed mainly since 1902, and is as yet of small proportions, only about 4,000 bales per annum being produced; but the industry there may grow rapidly. It has already led the South Carolina planters to organize in refusing to sell seed.

The Sea Island grower will therefore recognize that the prices of his crop depend on several factors and that quality is more important than quantity. Organized efforts should be made to raise the standard of length and preparation in order to avoid competition with cheaper cotton. Of the better grades a larger quantity can be sold than is now produced.

Interior planters are advised not to aim to produce an extra long cotton. South Carolina and the West Indies can excel in this, and the market for such cotton is very limited. Furthermore, the increase in length is obtained at a sacrifice in yield which cancels the profit. Rather let the interior grower select for a staple 1⅝ inches to 1¾ inches long and for a vigorous and productive plant, and let the campaign for a reduction of acreage be directed against staples less than 1⅝ inches in length and against the planting of Upland cotton in Sea Island districts.

FARM PRACTICES.

On the Carolina Sea Islands the planters have worked out a system well adapted to the peculiar needs of that section. Their methods are in many respects excellent, and the recommendations in this bulletin regarding improvements apply less to these growers than to those in Georgia and Florida, where a brief survey will convince one that far greater profits could be secured by radical changes in farm practices.

SEED SELECTION THE FIRST REQUIREMENT.

Without seed selection Sea Island cotton can not be grown successfully for more than a few years in any latitude. The interior growers have always depended on the skillful seed selection of the Carolina planters and have continued to neglect the matter since this seed supply has been cut off by a growers' organization. No more improved seed can be had from the Sea Islands, and nothing is more certain than that the crop will continue to deteriorate rapidly until the interior growers begin work to improve it. They undoubtedly will rise to the occasion when they realize that their industry is at stake. They may be assured in advance that they will succeed to a degree ted only by the care and skill they expend.

Three points are to be sought by selection, as follows:

(1) Length and quality of staple must be maintained. Only by saving seed from plants having a long, fine, and uniform staple can these qualities be retained. Otherwise there occur in the fields an increasing number of plants with a shorter staple, due to the inherent tendency of this highly improved crop to revert to its original character. The farmer overcomes this tendency when he chooses his seed each year only from stalks that have maintained the desired quality.

(2) Good productive plants must be secured. A greater loss than farmers realize is due to the number of unproductive plants in every field. Even plants equally supplied with space and food differ much in the number of bolls they bear, the size of the bolls, and the way they open. These differences are mainly inherited, so that by careful attention to this point when selecting seed the producing power of any variety can be greatly increased.

(3) Run-out and hybrid plants must be eliminated. A conspicuous source of loss in the average interior field is the number of tall hybrid and run-out plants. These occupy double the space of good ones and yet produce a worthless crop. All such plants should be pulled out as soon as detected. Where careful seed selection is practiced and the neighborhood of Upland cotton avoided, very few of these undesirable plants will appear in the crop.

PREPARATION OF THE STAPLE FOR MARKET.

Next in importance to seed selection is the preparation of the staple for the market. Interior-grown Sea Island cotton has an unenviable reputation for poor preparation as compared with the Carolina Sea Island product. The farmers seem not to consider the delicate nature of the staple and handle it as carelessly as they would Upland varieties, whereas it requires special care at every stage from boll to bale. Too often it diminishes in value by exposure to weather in the field, by being mingled with broken leaves and yellow cotton in picking, by being stored undried when gathered damp, or by careless ginning. The luster of the staple once lost can never be regained. The admixture of weak and stained cotton means loss to the spinner from waste and the extra cost of cleaning, and this loss must be made good by a reduction in the price paid the farmer.

There is much complaint from the spinners of an undue amount of nep, or white knots of tangled fibers in cotton from diseased plants, or in cotton picked too green or not properly ginned. Much of this trouble can be avoided.

BETTER CULTURE MEANS LARGER CROPS.

The fact that the yield on some farms averages 400 pounds of lint per acre while the general average is perhaps less than 100 pounds per acre shows that there can be a great improvement in methods of growing the crop. The Sea Island cotton belt needs to diversify, to rotate crops, to use fertilizers more rationally, to build up the thin soil, to plow deeper and cultivate shallower, and to economize hand labor by modern farm machinery.

CREDIT AND THE RENTAL SYSTEM A BAR TO PROGRESS.

The cost of cotton production is greatly increased by the prevailing credit system, owing to the higher cost of supplies and the reduction of the farmers' ambition and efficiency. The rapid change from credit to a cash system now going on is a great gain for good farming.

The common practice of renting land for a share of the crop greatly hinders the adoption of improved methods. It means instead the continuous planting of cotton without attention to seed selection or soil improvement. When the owner can not operate his farm himself, he should retain strict oversight over the work done by his tenant and provide, through a written contract, for a specified system of rotation and seed selection.

If the period of rental were three or five years instead of one, there would be more incentive for the tenant to build up the soil. The owner who keeps his land in a high state of cultivation has no difficulty in securing the best class of tenants.

DEFECTS IN MARKET CONDITIONS.

There is a tendency among cotton buyers to pay an average price for all grades of Sea Island cotton, especially in the smaller markets. This means that good cotton brings less than its value, and inferior or dirty cotton too much. This practice is an injustice to the farmer who produces a superior article and it tends to discourage him from selecting for quality. Unless buyers are willing to pay full value for the best cotton, farmers can not be expected to improve their seed in any respect except to secure larger yields per acre.

It is an advantage to the farmer who has a superior grade of cotton to secure competitive offers from large buyers before selling. In this direction much good can be done by farmers' organizations.

CULTIVATION OF SEA ISLAND COTTON.

ROTATION AND DIVERSIFICATION.

Although Sea Island cotton always has been grown on the one-crop plan even on the Sea Islands, there are many reasons why er success can be had by making it a part of a system of diversified farming. By rotation of crops several purposes are accomplished, as follows:

(1) The productive capacity of the land is increased and maintained. The cultivation of cowpeas, velvet beans, and other legumes adds to the soil large quantities of nitrogen drawn from the air, enabling the farmer to secure at slight expense an element which is the most costly part of purchased fertilizers.

The physical condition of the soil is improved, especially by the addition of humus or vegetable mold, whereas continued cultivation in cotton or corn rapidly exhausts the humus. The importance of humus can hardly be overestimated. A soil rich in organic matter is more easily cultivated than other soil. It suffers less from washing because the water is absorbed, and because of this water-holding power it does not quickly become too wet, nor does it dry quickly; hence, injury from drought is lessened. A soil rich in organic matter is richer in the beneficial bacteria and other organisms that take part in rendering available to the plant the food hitherto locked up.

By rotation, crops with different fertility requirements are alternated so that the same elements are not drawn on so constantly. Cover crops which increase humus can succeed cultivated crops which exhaust it, and in the intervals of rotation any poisonous or injurious excretion from the roots of a crop is neutralized. Deep-rooted crops may be employed to bring up plant food from the subsoil and leave it at the surface when they decay, where it will be available for shallower rooted crops.

The test of successful farming is to produce large and profitable crops and at the same time to build up the fertility of the soil, making it each year more productive. Diversified farming permits this to be done; continuous cotton growing never will.

(2) A diversified cropping system places farm operations on a safer and more economical basis. Regular and continuous employment for labor is secured if crops are grown which require attention at different seasons. The danger of loss from unfavorable weather or glutted markets is much diminished when several crops are grown. It is particularly important that the growers of Sea Island cotton should begin at once to practice diversification in order to gain experience with other crops, because there is a possibility that the invasion of the boll weevil into the eastern States may in a few years make Sea Island cotton an unprofitable crop. Much hardship will result unless other crops are established meantime.

(3) Rotation of crops is one of the most effective means of controlling weeds, insects, and plant diseases. Crab-grass, nut-grass, and other weeds troublesome in cotton fields are reduced in numbers by the shading and smothering effect of a heavy growth of cowpeas or velvet beans. Most injurious insects and plant diseases attack only

one kind of plant. The continuous culture of any crop affords ideal conditions for the multiplication of its pests, while rotation of crops results in their destruction from lack of food.

For example, the nematode worm, causing the destructive root-knot of peaches, cotton, etc., is greatly increased by planting susceptible crops, but can be controlled by a succession of immune crops, such as corn, oats, velvet beans, or peanuts. For several cotton diseases, including anthracnose, boll-rot, and " black-arm," rotation is advised as one of several preventive measures.

Rotation Systems.

The term " rotation " implies a prearranged order of succession for the various crops cultivated. Every farmer should draw up a planting scheme for his farm, worked out with reference to the relation of each crop to the others. The details of this plan will differ in every case according to the number of crops and the acreage of each, but some general principles apply to all.

The crops in a rotation may be divided into two classes:

(1) Money crops, in the majority of cases Sea Island cotton or corn, from the sale of which the principal income is derived. These draw from the soil more than they add to it.

(2) Improvement crops, grown mainly to build up the soil. These are usually legumes, like cowpeas, velvet beans, peanuts, or beggarweed. If fed to stock they will return a revenue and improve the soil as well.

The choice of a legume.—Cowpeas have always been the most popular and widely grown crop of this class. They have many advantages over the others—adaptability to poor land, ease of culture, the value of the peas as food for man or stock, excellence as a hay crop, etc. On the other hand, they are open to the serious objection that they are very subject to root-knot and greatly increase this disease. On land infected by cotton wilt or black-root the loss is increased by the presence of root-knot. Fortunately the Iron cowpea is immune to root-knot and can be used with safety. In fields where it is certain there is no root-knot any pea can be planted, but the trouble is that root-knot frequently appears where its presence was not suspected. As all Sea Island cotton lands are sandy and subject to infection by root-knot and wilt it is urged that no other cowpea than the Iron variety be used in rotation with Sea Island cotton.

Velvet beans are a great addition to the resources of Sea Island cotton growers. They are entirely immune to root-knot and black-root and of much value in rotations for this reason. No other legume grown in the Sea Island cotton belt makes as much growth or adds as much vegetable matter and nitrogen to the soil. Velvet beans afford excellent grazing for stock in late fall and winter, and should be grown much more than at present. Their long season of growth is a disadvantage when a catch crop is needed to follow potatoes or grain. The vines are so long that harvesting for hay is nearly impossible.

Peanuts, or ground peas, are also free from root-knot, and are especially useful as feed for hogs. They appear to be somewhat less effective as soil improvers than cowpeas.

Beggarweed is native to Florida and seeds itself whenever permitted to grow. It makes a valuable hay when cut at the beginning of the blooming season and does good service in enriching the soil. In the cotton field it must be kept under control by thorough cultivation or the seeds will become tangled in the cotton, but if allowed to spring up late in summer it will serve as a winter cover crop to the great benefit of the land. The complete immunity of beggarweed to root-knot is an important point in its favor.

Resting land.—A practice common on the Sea Islands and in portions of Florida is to plant cotton alternately on half the farm, leaving the other half to grow up in grass and weeds. This is much better than continuous cotton planting, but is a defective system because the maximum capacity of the land is not obtained. It is better to grow a useful legume than coarse or obnoxious weeds, like fennel, coffeeweed, and sandspurs, or if pasture is needed rye may be sown between the cotton rows in the fall, grazed during the spring months, then plowed under and Iron cowpeas sown for hay or for fall grazing. Thus there may be substituted a two-year rotation, which is perhaps the most practicable plan for the conditions now prevailing. The two-year rotation in its simplest form is cotton on half the land and corn and Iron cowpeas on the other half, the cotton following the corn and peas each year. A better plan is to plant one-half of the land in cotton, one-fourth in corn and Iron cowpeas, and one-fourth in velvet beans, reversing the order so that velvet beans come on the same land once in four years, cotton twice, and corn and peas once. This is practically a four-year rotation. If, after this has been repeated several times, the land becomes too rich in nitrogen, as indicated by an excessive growth of the cotton to weed, the velvet beans could be omitted for a year or two. Velvet beans or cowpeas in these rotations should be fertilized with about 200 pounds of acid phosphate and potash to the acre. No nitrogen is required.

A three-year rotation is better than one of two years. The three-year rotation for the first year might consist of rye, oats, or wheat for hay, followed by Iron cowpeas; second year, corn with Iron cowpeas; third year, cotton. Cut the corn when ripe and shred the stalks. Do not waste time pulling fodder. Cut the peas for hay or pasture them. In early fall plow under the stubble and sow rye, oats, or wheat. This grain should be cut for hay just before it ripens, and should be off in time to plant velvet beans, if they are preferred to cowpeas. The field should be grazed during the fall, and the remaining litter plowed in early enough in the winter to decay before the cotton is planted. The advantage of the three-year rotation is that it permits keeping more live stock and will consequently improve the land more rapidly.

FERTILIZERS FOR SEA ISLAND COTTON.

PRESENT PRACTICES.

The character of the fertilizers and the amounts used per acre by farmers in different parts of the Sea Island cotton belt vary between wide extremes. The practices on the Sea Islands are characterized by heavy applications of home-mixed fertilizers, differing considerably in composition according to the ideas of the various planters, but usually rich in potash. The need for humus is recognized, and is supplied by growing cowpeas and by heavy applications of marsh mud, salt water grass, and compost. Three typical examples follow: (1) Two hundred pounds of kainit, 200 pounds of acid phosphate, 400 pounds of cotton-seed meal, 25 bushels of Sea Island cotton seed, 25 loads of marsh mud per acre; (2) 200 pounds of kainit, 200 pounds of acid phosphate, 200 pounds of lime, 1,000 pounds of Sea Island cotton seed per acre; (3) 300 pounds of kainit, 300 pounds of acid phosphate, 300 pounds of cotton-seed meal per acre.

In Georgia and Florida, on the other hand, light applications predominate. Occasionally, however, a farmer goes to the other extreme and puts on 1,000 to 2,000 pounds of fertilizer per acre. A common practice is to use a complete fertilizer of the 2-8-2 grade,[a] applying 100 to 250 pounds per acre. Some planters, however, use only acid phosphate and potash, while others use nothing but kainit.

GENERAL PRINCIPLES GOVERNING THE USE OF FERTILIZERS.

The fertilizer question is too complex to discuss fully here. Farmers' Bulletins Nos. 44 and 48 contain detailed information on this subject, and will be sent free of charge to any person requesting them. A few general rules to be remembered are the following:

(1) The best results from the use of fertilizers can be had only when the soil has been put in first-class physical condition by deep plowing and the addition of vegetable matter.

(2) Stable manure and compost made on the farm are cheaper and far more effective and lasting than commercial fertilizers.

---

[a] This means that the fertilizer contains 2 per cent of ammonia, 8 per cent of phosphoric acid, and 2 per cent of potash.

(3) The market value of commercial fertilizers is based on the nitrogen, potassium, and phosphorus they contain. The farmer should buy only the quantity of each element that will give the most profit on his soil.

(4) The amount of each element required varies with the soil so much that two sides of the same field often require different fertilizing.

(5) The proper fertilizer formula can not be told from a chemical analysis of the soil or of the plant, but an opinion can be formed from the appearance of the crop and verified by field trials.

(6) More plant food can be purchased for a given sum in high-grade fertilizers than in low-grade brands. Buy the best and use less per acre.

Effect of Nitrogen.

Sea Island cotton requires less nitrogen than most crops, especially on low or moist soils. All excess of this element stimulates vegetative development, resulting in tall, coarse, and relatively unproductive plants, with large, dark-green leaves. A lack of nitrogen is shown when plants are small, with a light yellowish-green cast of foliage.

The usual sources of nitrogen, or ammonia, are cotton-seed meal, dried blood, tankage, fish scrap, nitrate of soda, and sulphate of ammonia. It is the most expensive ingredient of fertilizers, costing 16 to 18 cents per pound as compared with 4 to 5 cents for potash and phosphoric acid, and for that reason should be supplied mainly by rotation with legumes. The effect of cowpea or velvet bean stubble plowed under at the Alabama Agricultural Experiment Station was to increase the next year's cotton crop 63 per cent, this figure being the average of four tests. In such cases it is often unnecessary to purchase nitrogen, except that it may be profitable to apply about 50 pounds of nitrate of soda before planting to stimulate the young seedlings to rapid growth. When commercial fertilizers are relied on, the nitrogen is best derived from cotton-seed meal or other organic materials, such as tankage or dried blood, which become available more slowly and are more lasting in their effects than the quickly soluble nitrate of soda or sulphate of ammonia. An exception should be made in the case of land subject to the blue disease, as stable manure or other organic fertilizers, unless very thoroughly decayed, aggravate this trouble. (See page 48.)

Effect of Potassium.

A liberal supply of potash is very important for Sea Island cotton, and farmers outside of the Sea Islands use too little of it. Potassium influences the formation of starches and sugars in the plant and appears to be indispensable for protein formation. A lack of it in the case of Sea Island cotton may lead to the appearance of "rust," a disease resulting from disordered nutrition. Fields or parts of fields known to be subject to rust should receive an additional application of potash in amounts varying in accordance with the severity of the disease (see page 48). Kainit is the most common source of potash, but as it contains only 12 per cent of potash it should be applied liberally. Muriate of potash containing 48 per cent of potash is more convenient on account of its concentration and is usually considered to be proportionately effective. Fifty pounds of muriate of potash per acre would thus be equivalent to 200 pounds of kainit.

Effect of Phosphorus.

This element in the form of phosphoric acid compounds is indispensable to the Sea Island cotton plant for its general development, and especially for the seed and lint. Most soils are deficient in phosphorus, which is therefore an important ingredient of fertilizers. Acid phosphate is the usual source, and on account of its low price forms an unduly large proportion of the average fertilizer.

Lime Usually Unnecessary.

With the exception of occasional applications of marl on the Sea Islands, lime is not used by cotton growers and there is little evidence that it would be profitable.

The Best Formula.

From the foregoing it will be understood that no fertilizer formula can be given that will fit all cases. The following is suggested, subject to modifications as the conditions vary: Nitrogen, 3 per cent; acid phosphate, 8 per cent; potash, 4 per cent. A ton of fertilizer having approximately this composition could be made from acid phosphate, 1,050 pounds; cotton-seed meal, 750 pounds; nitrate of soda, 62 pounds; muriate of potash, 138 pounds. The potash should be increased on land liable to rust, and the nitrogen increased or diminished according to the size of weeds the land will produce.

Quantity to the Acre.

The aim may well be to apply the maximum quantity of fertilizer that will return a sure profit. This will vary according to circumstances and can be determined only by experiments made on each farm. Two hundred pounds per acre is too little in almost every case, and if more than 1,000 pounds per acre are applied some of the fertilizer is likely to be wasted, particularly on thin land. The better the soil in tilth and the richer in humus the more fertilizer can be used.

Methods of Application.

Where less than 400 pounds of fertilizer per acre are used, it is probably best to apply all in the drill at the time of planting. For larger quantities many farmers prefer to divide the application, putting part in at the time of planting and the remainder during cultivation in June.

PREPARATION OF THE LAND.

Thorough clearing of the land, including the removal of all stumps, is essential for the use of modern plows and cultivators. The next requirement is drainage. If the land is wet or subject to overflow, it must be drained. This can be done by open ditches, but tiles are better. Farmers' Bulletin No. 187, on this subject, will be sent upon request. Many planters on the Sea Islands have greatly increased the producing capacity of their fields by drainage and have also much reduced the danger of loss from excessive rains.

RIDGE CULTURE.

On the Sea Islands cotton is invariably grown on ridges, or beds, 5 feet apart, as indicated in the accompanying diagram (fig. 4). The method of forming and handling these beds is briefly as follows: Beginning in January the old stalks are broken down, the limbs and trash raked into the alleys, and the coarser litter burned. In February cotton seed is strewn in the alleys at the rate of 1,000 pounds to the acre, and a compost of stable manure, pine straw, marsh grass, and other refuse applied to as much of the field as the quantity obtainable permits, giving preference to the poorer portions. With a two-horse plow a furrow is turned in from each side to cover the compost and seed. In late February or in March the commercial fertilizer is drilled in at the rate of 600 to 1,000 pounds per acre and covered. The beds are rolled with a double roller (see fig. 5) before planting. Strips of wood on these rollers mark the position of the hills. Planting is usually done by hand, sometimes with a planter. When the cotton is well up it is cultivated with a sweep and hoed by hand, the dirt being drawn around the plant. Cultivations and hoeings alternate. The cotton is worked every week—eight to ten times in all. Thinning begins when the plants are 5 to 6 inches high and is done gradually until only one plant is left in a hill. The cotton is laid by in July or August, when it becomes too large to work without injury. The plants are then growing on broad beds separated by alleys about a foot deep.



FIG. 4.—Cross section of the beds on which cotton is grown on the Sea Islands.

While level culture is generally practiced in Georgia and Florida at the present time, it is quite likely that a modification of the South Carolina broad bed would be more profitable. This ridge system gives better results in two classes of cases, as follows:

(1) On low and poorly drained land, where it permits greater root development on account of the improved aeration of the soil.

(2) When, on account of the land being rich and well fertilized, Sea Island cotton grows too much to weed under level culture. In such cases the grower is compelled to adopt measures to turn the energies of the plant from vegetative growth to fruiting. This is done by restricting the root development, (1) by maintaining a compact subsoil, which the Sea Island planters accomplish on their deep sandy soils by pasturing with cattle during the year of rest; (2) by regulating the moisture supply by the high beds, and (3) by root pruning by deep cultivation if the cotton needs it. It is also believed by the Sea Island planters that ridge culture permits better control of nutgrass, as this pest can be kept down more successfully by covering it with earth than by cutting it up.



FIG. 5.—Double roller used on the Sea Islands to prepare the beds for planting cotton. The strips of wood mark the location of the hills.

The ridge system has its limitations and disadvantages, which must be borne in mind. It will not do for light and droughty soils deficient in vegetable matter and scantily fertilized, where the cotton pl[illegible] [illegible]sture. Such soils should first be [illegible] [illegible] The greatest disad- [illegible] cultivation due [illegible] the plants. This [illegible] improved [illegible] without hand [illegible] thoroughly [illegible] their con- [illegible]

LEVEL CULTURE.

If level culture is preferred, the following instructions will apply:

Plowing should be Deep.

It is advised that the land be broken broadcast, with a two-horse plow, 6 to 8 inches deep, or as deep as practicable under the circumstances. In very shallow soils only an inch or so of the subsoil should be turned up at once, but by plowing an inch deeper each year such a soil can be deepened. Subsoiling has its advocates and may be profitable in some cases, but for the average Sea Island soil it is not recommended. If practiced at all, it should be for the corn or other crop preceding cotton in the rotation.

Vegetable Matter should be Plowed In.

All vegetable matter on the land and all that can be put on it should be plowed under in early winter, when it will have time to decay. The remains of a velvet bean crop, or grass, weeds, cornstalks, etc., all greatly improve the land.

The common practice of burning over land before plowing can not be too strongly condemned. It means the deliberate destruction of fertility worth more than the farmer can afford to purchase and the loss of the humus that should be conserved by every possible means. An exception to this rule should be made if boll-rot or black-arm has been troublesome. Diseased stalks should be burned to prevent the infection of the next crop.

Fertilizing and Bedding.

Having broken the land broadcast, apply the fertilizer with a fertilizer distributer in drills the proper distance apart. Bed over this with a disk harrow or with plows in the usual way.

Planting.

Plant with a good machine, preferably one that will drop the seed in hills at the desired distance, and thus save labor in chopping to a stand. A good distance for average conditions is 20 inches apart in 5-foot rows. The plants should finally be thinned to one in a hill. One plant every 20 inches will bear more cotton than two in the same space. It is furthermore very difficult to judge the plants properly when selecting seed if two plants grow in the same hill.

Time of planting.—It is advised that planting be begun as early as the season permits. This varies in different years and sections from March 15 to April 10. Early planted Sea Island cotton is found to make a more compact and fruitful plant, while late cotton tends to form a larger and coarser weed.

Long experience is required to judge truly the best time for planting, for the southern spring is variable and uncertain. On the one hand the cotton must escape frost, and on the other the spring droughts. Should dry weather prevail before planting is completed, the seed should not be put into the ground until there is ample moisture to bring it up, as otherwise it is likely to perish. Soon after the cotton comes up replant all missing hills. Every effort must be made to obtain a perfect stand. Every missing hill reduces the crop, while the cost of cultivation is the same as for a full stand.

Cultivation.

With level culture a weeder can be used to advantage for the first cultivation and at weekly intervals until the plants are too large. It must be used frequently, as it will not eradicate large weeds. Cultivation in general should be frequent and shallow. Cultivate deep only when the cotton is growing too fast and it is desired to stimulate fruiting. Economize labor by using cultivators rather than sweeps. Work the land as soon as dry enough after each rain, aiming to preserve a shallow dust mulch to conserve moisture. Never plow or cultivate when the land is wet. Lay by the cotton only when it is too large to cultivate without injury.

SEED SELECTION.

The high quality of Sea Island cotton to-day is due to the careful seed selection that has long been practiced on the Carolina Sea Islands. Seed selection is therefore a feature of prime importance, the keystone of the arch. To realize its influence on the industry one must trace its history from the beginning.

ORIGIN OF SEA ISLAND COTTON.

As indicated by its botanical name, *Gossypium barbadense*, the original home of the plant is thought to have been the West Indies. When first introduced into the mainland of America, about 1786, it is reported to have been considerably different from the present form. The plant was a perennial—larger, later, and less productive than now. The method of culture described on page 23 was adopted to reduce the size of the plant and stimulate fruitfulness, but the great change that has been wrought is due mainly to careful breeding. Through several generations the planters have selected seed from the earliest, most compact, and most productive plants, with the longest and finest staple, until the character of the plant has been radically changed.

CONTINUED BREEDING NECESSARY.

The cotton plant has become variable, enabling the breeder to select finer forms and to raise the standard of the crop far above its natural level. By reason of this variability, seed selection must be continued to prevent deterioration, for there is no standing still. The upward movement must be continued by perpetuating the finer types desired by the cultivator, or, if neglected, the inferior plants will increase rapidly in the crop and the cotton will tend to revert to its original type.

Sea Island Methods.

There has been developed on the Sea Islands a well-defined and uniform system of selection. It is based on the correct idea—that of discovering the best individual plant and preserving its offspring. A number of superior plants are marked and carefully compared in the field, then picked separately and the seed cotton critically examined. The best plant is retained and the seeds planted in a plot by themselves, one or two in a hill, making perhaps 500 plants in all. If this plot retains the good qualities of the parent plant the cotton is picked and the seed again planted separately, making a 5-acre plot the third year. The fourth year there will be seed enough to plant the whole crop, all descended from the single stalk first chosen. A new individual plant is selected every year, so that a fresh supply of seed is always being grown. Seed from the general crop is considered less desirable for planting at home and was formerly sold to Georgia or Florida growers.

Sea Island Varieties.

A number of planters on the Sea Islands have been practicing this system of seed selection for many years. Each man has his own ideals respecting the best form of plant and the most profitable length of staple and selects a type conforming most closely to this ideal. There have thus been developed a number of distinct varieties of Sea Island cotton, which differ in length and quality of staple, form of plant, size and appearance of seed, percentage of lint, and other features. They are not given varietal names as much as in the case of other cultivated crops, but when offered for sale are known by the name of the breeder, as Hinson, Seabrook, Rivers, La Roche, etc. These names have not been preserved when seed has been sold to interior points and there is consequently much confusion in the matter of varietal names.

Varieties of Sea Island cotton are constantly changing. Each breeder renews his stock annually and in doing so may propagate from a plant differing from his old type, in which case his entire crop four years hence would be influenced.

Breeders' rights.—Many of the Sea Island varieties, particularly the finer ones, are considered the personal property of the originator, who will not part with any of his seed, even to his neighbors. To do so would be likely to result in an overproduction of that particular staple and a lowering of prices, as the market demand for the higher-priced staples is exceedingly limited. Furthermore, the breeder is as much entitled to reward for his labors as the inventor of a new machine is to patent rights. A strain of fine cotton is the product of many years of careful selection and could not be duplicated without long-continued work requiring much skill and care.

Sale of seed from the Sea Islands.—On the Sea Islands the growers of medium staples, for which there is a larger market than for the finer product, have for many years sold their seed, both at home and to buyers in Georgia, Florida, and foreign countries. In 1904, however, West Indian competition stimulated the formation of an association to prevent the sale of seed outside the Sea Islands, and at the present date this embargo is still in force. The right of these growers to dispose of their product as they see fit is not questioned. Their action, however, will have great influence on the interior sections, which have always depended on Sea Island seed. Georgia and Florida produce eight-ninths of the American crop, but because of total neglect of seed selection deterioration has been rapid there, requiring renewal of seed every few years.

Seed Selection will Succeed in the Interior.

Thrown on their own resources, the interior growers will find that they can grow their own seed and maintain a satisfactory quality. The success of the Carolina planters is due to their methods more than to their soil and climate. There are already men in Georgia and Florida who have maintained the quality of their cotton for fifteen years or more by selection without renewal from the Sea Islands. In fact, it should be possible to produce a variety better fitted for interior conditions than any imported seed, for adaptation to climate and soil can be secured together with greater productiveness.

METHODS OF SELECTION.

The amount of gain from seed selection will depend mainly on the method employed: the more care taken, the better will be the results. If any farmer is so situated that he can not select his own seed, let him at least obtain seed for planting from the middle picking in a field of known good quality, or purchase from some near-by seed breeder. He should not risk an entire season's labor by planting seeds of unknown value taken at random from a public gin.

Three methods of selection will be described. Under varying circumstances all of them may well be employed.

Roguing.

The simplest method of selection is called "roguing," because it involves merely the removal of inferior or varying plants, called "rogues" by seedsmen. This practice will serve to lessen deterioration in a variety already of satisfactory quality, but will not effect a very rapid improvement. Every grower of Sea Island cotton should destroy all hybrid and "run-out" stalks whenever observed. The hybrid plants are the results of crossing between Sea Island and Upland varieties, or between Sea Island and other hybrids. They are the tall stalks, often called "male stalks" or "bull cotton," which are quite common in the average interior field. They do harm in three ways: (1) On account of their great size and vigor, one of them takes up as much room in the field as two good plants; (2) they bear a scanty crop which is so inferior that it reduces the price of the whole crop when detected in the sample; and (3) every seed from one of these plants produces a hybrid plant the following year.



FIG. 6.—Good seed cotton at the right compared with a "run-out" form at the left. The lower figures are the locks as picked. The upper figures are seeds with the fibers straightened out.

"Run-out" plants are pure Sea Island stalks which have deteriorated until the staple is short and too scanty to cover the seed. (Fig. 6.) They can not be detected until the bolls begin to open, when it is best to pull them out, as the crop they will bear has no value and only lowers the quality of the rest of the crop.

General Selection.

A simple method of improving seed is to pick from the best plants in the field enough to plant the next crop, or to select with still m care a smaller quantity to plant a seed plat of 3 or 4 acres to grow seed for the general planting the following year. The selection of the seed is best done by the farmer himself, assisted by two careful pickers. Select from the middle picking before the main crop is gathered. Search through the whole field for the best and most productive plants. Before directing the pickers to pick a plant, examine the staple and reject every plant with lint less than 1⅝ inches long. It would be a vital error to select without regard for length of staple, because plants with wide-opening bolls would then be chosen and this quality is often accompanied by a short staple. Gin this selected cotton separately on a clean gin.

This method of selection can easily be followed by every farmer and will produce good results, though not equal to the next plan described.

Pedigree Breeding.

Pedigree breeding, while requiring more careful attention than the methods already described, will effect the greatest improvement in the least time and should be followed by all who undertake the production of improved seed for sale. It is substantially the same as the plan followed by the planters on the Carolina Sea Islands, where no other method would maintain such a high quality. All progressive farmers would profit by adopting this system.

The fundamental principle is to breed from a single plant of exceptional merit, which must also prove its ability to transmit its good qualities through its seed to its progeny. Instead of planting mixed seed taken from a large number of good plants, as in the preceding method, the choice is narrowed first to a few plants, which are compared not only as to productiveness, length and quality of staple, etc., but also with regard to their prepotency and the uniformity of their offspring, as determined by a planting test the following year, until finally the progeny of the best individual is chosen. The seed thus obtained is increased as rapidly as possible until enough is secured to plant the whole crop.

A similar method is practiced by successful breeders of other crops, as, for example, in the "ear-row" plan of improving corn now so generally followed in this country. Plant breeders agree that too much stress can not be laid on the importance of searching for the exceptional individuals that may have great potential value for crop improvement. The best varieties of all our cultivated crops whose history is known came originally from a single plant or tree of unusual merit discovered by some observing grower.

Beginning the selection.—It is assumed that the farmer who desires to improve his cotton has already planted a field from the best obtainable seed and has pulled out all objectionable hybrid or "run-out" stalks. He should begin to make selections as soon as the first bolls open. Choose the plants having a long staple and in other respects conforming to the ideals described. Mark these plants with a white cloth and a tag bearing a number. It is advisable also to set a tall stake by each selected plant so that it can be found more readily. Pick each separately and at the end of the season spread on a table and compare the various lots critically and at leisure with regard both for length and fineness of staple and for yield. Discard the inferior ones until from ten to twenty-five are left. These are to be further tested by planting the second year to discover the prepotency or transmitting power of each.

Second year: The progeny test.—Plant the seeds from the selected plants in adjoining rows, keeping each lot separate. These small lots can be planted in the lint, provided care is taken not to cover them very deep. Select ground adapted to cotton and have it well prepared. Plant with care, dropping only two seeds to the hill. If possible, have 100 hills to the row. The location should be as far from other cotton as possible to lessen the crossing. Isolation can usually be secured by planting the seed plat in the section of the farm used that year for other crops—in the middle of a cornfield, for instance. If it is necessary to plant near other cotton, plant a wide border of the same variety around the breeding plot. By all means avoid proximity to Upland cotton, which is the most serious factor in the deterioration of inferior Sea Island cotton.

The object of this planting is to determine the relative merit of the different selections, and particularly their uniformity. The general excellence of the plants in each row should be considered—their vigor, productiveness, and freedom from disease. Any row lacking uniformity to a marked degree should be eliminated from consideration. When the bolls open, compare the staple, length, fineness, and uniformity, and finally choose the row possessing the greatest merit. This is to be the beginning of the new strain. In this row mark and pick separately the best ten plants. (Fig. 7.) Pick together the remaining plants in the row. The other rows in the plat, although not retained for breeding, ought to be better than unselected seed and may be used for planting the general crop.

The desirability of this method of breeding will not be appreciated until it has been tried and the variations in the offspring of different plants observed. It is common to find one row with plants all alike possessing a staple longer than the average and also more productive, while another row may be widely variable in form of plant and quality of staple. Plants of superior merit often appear in the variable rows. They should not be saved, however, as the chances are that their offspring will be variable like the row in which they appear.

Third year: The increase plat.—The seed from the best row of the second year is to be planted in a small field to produce seed for planting the general crop. Any inferior plants that chance to appear in this field should be destroyed, but no other selection need be practiced, as it is not intended to plant this strain permanently, but to renew the seed annually from a new increase plat.

In addition to the increase plat, the progeny test is to be repeated, using the ten plants chosen from the best row and any others of exceptional merit that may be discovered in the general field. Select in the same manner as before the best row and the best plants therein.

Fourth year: The general crop.—In this year and each succeeding year the same process of selection is carried out. This should become a part of the regular farm practice, to be considered of equal importance with cultivating and fertilizing. The several stages under way from now on are as follows:

(1) Selection of the finest plants.
(2) Progeny test to determine uniformity and productiveness.
(3) Increase plat.
(4) General crop.



FIG. 7.—Diagram of a pedigree breeding plat. Row No. 10 has been selected and 10 plants in it marked to be saved separately.

If seed from the general crop is to be sold, careful attention must be paid to removing tall hybrid or "run-out" stalks from the field whenever they are observed. Seed from the last picking had better be rejected, as the upper bolls do not mature their seed as well as the lower ones.

Separate ginning of the seed crop important.—Cotton from the breeding plats or from other fields intended for seed should be ginned separately and the gin and conveyors first thoroughly cleaned of foreign seed. The farmer should personally superintend the ginning of his selected seed, as a mistake at this stage might lose him the fruits of several years' work. Owners of ginneries should realize their opportunities and obligations in this direction and afford their ons every facility for the separate ginning of selected seed cotton.

The sale of cotton in the seed is a hindrance to seed improvement, unless there is at the same time an organized movement for the distribution or sale of improved seed to the farmers.

Improvement of Cotton Seed by Gravity Separation.

It has been found possible to secure a marked gain in the percentage of germination and the vigor and productiveness of the cotton crop by removing the light weight and imperfect seed before planting. For example, in an experiment by the writer the heavy seed germinated 27 per cent better than unselected seed and 42 per cent better than light seed thrown out by the air blast.

The separation is effected by means of an air blast produced by a fanning mill modified for the purpose. All who handle considerable quantities of Sea Island cotton seed will find it profitable to use such an apparatus. Seed from which the unginned locks and tufted seeds have thus been removed is much better adapted for use in cotton planters. Another very important gain in this process is the removal of the fuzzy seeds of Upland hybrids, which on account of their greater surface area are blown out with the light seed. Persons interested in the matter should write to the Secretary of Agriculture for Farmers' Bulletin No. 285, entitled "The Advantage of Planting Heavy Cotton Seed," by Webber and Boykin, which describes the method and apparatus fully. All ginneries should be equipped to treat in this way seed intended for planting.

IDEAL QUALITIES OF SEA ISLAND COTTON.

Length of Staple.

In Georgia and Florida the breeder should work for a staple not less than 1⅝ inches or more than 1¾ inches in length. In South Carolina each planter is guided by his own preferences, some planters choosing the medium kinds on account of their greater productiveness and others finding it profitable to grow the extra fine and long varieties. Experience has shown, however, that these fine strains, having a staple 2 inches to 2½ inches long and selling from the Sea Islands at 40 to 60 cents per pound, are not profitable in the interior. As compared with the medium sorts, they are less productive and more subject to disease, while the bolls are smaller and the cotton harder to pick. The fine staple requires more care in handling than the interior farmers are accustomed to give, and the interior markets will not pay as high prices as Charleston. In the past the best results in the interior have been obtained with strains classed on the Sea Islands as medium fine, such as Hinson and Seabrook.

To determine the length of staple from a sample of seed cotton, pull a lock apart and take a single seed and carefully straighten out the fibers with the fingers or a fine comb. Measure the length of the greatest number of fibers; then test several other seeds from the same plant.

Uniformity of Staple.

After determining the length, estimate the amount of shorter staple in the sample and discard plants having a portion of their staple either very long or too short. Uniformity is an important quality, as the spinner can not utilize the short fibers, which are combed out as waste.

Strength of Staple.

Pull a tuft of fibers until it breaks. Diseased plants show a marked weakness, and some healthy ones produce a weak staple and should be discarded.

Percentage of Lint to Seed.

This quality, or the "ginning average," is important, but farmers often lay too much emphasis on it, forgetting that it is the total yield of lint per acre that determines their profit.

The percentage of lint should be determined by ginning and weighing both lint and seed. The result is usually expressed in terms of the amount of seed cotton required to produce one pound of lint. To determine this, divide the weight of seed cotton by the weight of lint. To express the same in per cent, divide the weight of lint by the weight of seed cotton. Having the ginning rate, to reduce it to a percentage basis, divide 1 by it; for example, 3.33=30 per cent. The per cent of lint varies considerably in different varieties of cotton, from 25 per cent, or 1 to 4, in extra fine Sea Island cottons to 39 per cent, or 1 to 2.56, in small-seeded Upland cotton. It varies among plants in the same field, and there is a marked variation in different seasons, the per cent of lint being higher in favorable seasons. Even with the same variety and the same season, differences in soil and culture influence the per cent of lint. For example, a consignment of Seabrook seed was divided among several farmers in 1904 by the A. P. Brantley Company of Blackshear, Ga. The ginning rates of the different crops produced from this seed varied from 3.96, or 25 per cent, to 3.10, or 32 per cent, the average of 41 fields being 3.42, or 29 per cent.

Color of Staple.

The staple should have a lustrous creamy tint in preference to a dead white. The color should be uniform, as mixtures of white and creamy cotton are not desired by the buyers.

Fineness.

Fineness depends on the diameter of the fibers, which can be measured exactly only with a microscope. An excellent opinion can be ormed from the feeling of the cotton, if not too dry. Fineness is a ery important quality to the spinner.

Productiveness.

Next to length of staple, productiveness is the most important quality. In making selections a preliminary estimate can be made by the eye or by counting the bolls. Sea Island planters estimate that every 15 bolls per plant equals 100 pounds of lint per acre under ordinary conditions. In breeding, the principal weight should be placed upon the yield from the progeny rows the second year of the selection. Strains derived from different plants in the same field have been found to vary greatly in productiveness, and careful selection will greatly improve any variety in this respect.



FIG. 8.—Ideal form of cotton plant. The leaves have been removed to show manner of branching.

Form and Size of Plant.

The plant should be compact, 4 to 6 feet high, with a strong central stalk and 2 to 4 well-fruited basal branches. Fruiting branches should occur at close intervals, 1 to 2 inches, and a habit of double bearing or producing an axillary branch at each node should be developed. All branches should be close jointed and bear a boll at every joint. (See fig. 8.)

Bolls.

The bolls should be large, long, and well filled to the end, not tapering too abruptly. As a rule a long boll indicates a long staple and a short or obtuse boll a shorter staple. The number of locks should be four. The majority of Sea Island bolls have but three. More than four locks, even if obtainable, would not add to the yield or to the convenience of picking. The bolls should open well, as such bolls ripen their cotton better and are far easier to pick. In making selections do not choose wide-opening bolls without examining the staple, as a wide-opening boll is usually correlated with short staple. If the size of the involucre, or "square," could be reduced by breeding, there would be less trouble from bits of dry leaf in the cotton at picking time.

Seed.

The seed should be small, but well filled, black, with a small green tuft at the end. A large, perfectly bare seed is correlated with a low ginning rate and a large, coarse plant, and is usually taken as an indication that the strain is running out. An excess of short fuzz is characteristic of some Sea Island varieties, but such cotton can not be ginned as rapidly as other kinds. Large seeds entirely covered with white or green fuzz indicate hybridization with Upland cotton, but occasionally occur in pure Sea Island cotton.

Earliness.

Very early varieties are usually less productive than later ones, while very late ones may be caught by frost before fully mature. A medium season of maturity is to be preferred.

Disease Resistance.

In some instances disease resistance may be a feature of fundamental importance, as when the land is infected with wilt. In such cases one of the disease-resistant varieties described on page 46 should be planted. In all selections attention should be paid to this point, particularly to secure resistance to black-arm and to anthracnose of the bolls.

HANDLING THE CROP.

PRESERVING THE FULL VALUE OF THE CROP.

After devoting his best energies for a whole season to the production of a fine crop of cotton, the farmer must still continue his vigilant oversight until the staple has left his hands. Sea Island cotton is a fine and delicate product and there are many ways in which it may be injured and its value reduced. All defects in the cotton are ultimately charged to the farmer's account and reduce the price paid to him. If the spinner finds in a lot of Sea Island cotton 10 per cent ore waste than in Egyptian cotton available for the same purpose, will manifestly be unable to pay as much by 10 per cent for the a Island. By a little care much of the present waste can be oided; hence strict attention should be paid to these factors.

GRADE: DEFINITION AND IMPORTANCE.

In the cotton market the term "staple" refers to the length and neness of the fiber, and these points are influenced most by seed lection.

The term "grade," on the other hand, indicates the appearance of he cotton as regards cleanliness and color, qualities influenced mainly y the manner in which the cotton has been handled. The price is onsiderably influenced by the grade.

Defects Influencing Grade.

(1) **Loss of bloom or luster.**—The best Sea Island staple has a gloss r luster which adds greatly to its beauty and is indispensable for ertain kinds of fabrics. This bloom is destroyed by exposure to un and storm when cotton is left long unpicked, and the staple then as a gray, lifeless appearance, sometimes termed "mildewed" or weather-beaten." A similar effect is produced by picking cotton when wet with rain or dew and storing it in piles without first drying t in the sun.

To preserve the staple at its best, pick often—once a week, if possible—and expose the seed cotton to the sun to dry. This is done by spreading it in a shallow layer on a low roof or arbor, where it is turned frequently until so dry that the seed will crack between the teeth.

(2) **Loss of strength.**—The loss of luster is accompanied by a lessened strength, so that a staple originally good fails to make as strong thread as before—an added reason for better care. Very dry cotton is also not as strong as that which, under proper treatment, has retained its natural moisture.

(3) **Nep.**—Spinners designate as "nep" small white specks in the baled cotton, which they find very difficult to remove in spinning and which often go into the thread and appear in the completed fabric as white dots. These neps are in reality tangles in the fibers, which when viewed under a microscope are seen to be weak and undeveloped. They are due in part to picking cotton before maturity; a boll that is forced open to extract the lint is a source of nep, as the cotton in it loes not get the necessary exposure to the sun to dry and straighten nd strengthen the fiber. Other nep originates with weak cotton from liseased bolls or from any other cause that prevents the fibers from ttaining full development. Such undeveloped staple comes from t gin full of nep Poor ginning, however, by weakening and br

fibers increases loss from this cause. Pickers should be cautioned against picking unripe bolls. Thorough sunning will in part remedy the trouble, and good culture, by producing healthy plants, will do more.

(4) **Broken leaf, etc.**—The presence of fragments of leaf, weed seeds, and other foreign matter in the cotton reduces its grade. These are often difficult to avoid, particularly after storms, when bits of the dried square, or involucre, are often mingled with the cotton; but pickers should be watched and cautioned against picking dirty cotton. Fortunately, the spinners find it easier to remove this class of impurities than the nep previously mentioned.



FIG. 9. Locks of Sea Island cotton from healthy bolls (at the top) compared with hard locks from diseased bolls (underneath).

(5) **Short fibers.**—A large part of the waste is due to short fibers, which have to be combed out. They originate in part in variations in the length of the staple on the seed, a serious fault, to be remedied by seed selection as discussed under uniformity (page 34.) Short fibers are in other cases due to imperfect ginning, which breaks or crimps the staple and may be avoided by better management.

(6) **Weak fibers.**—The greater part of the waste is due to the presence in the baled cotton of staple from undeveloped or diseased bolls. The bolls in such cases do not open and the fibers do not expand but remain matted together in a "hard lock" (fig. 9). All locks that do not open out after drying may be assumed to be worthless on account of weak and undeveloped staple. Pickers should be instructed not to gather hard locks, and in the assorting after picking all remaining ones should be thrown out. Seed cotton still containing hard locks when it reaches the gin can be improved by setting the stripper bars well back from the roller to allow the locks to fall through. Close ginning is a mistake, for it costs the farmer more through deterioration of his cotton than he gains by the slight increase in weight.

The number of hard locks can be greatly reduced by bringing the cotton to perfect maturity through attention to fertilization and culture and to the control of diseases.

(7) **Lack of uniformity in the bale.**—Separate late from early pickings. Buyers desire to have each bale uniform within itself. If, therefore, a late picking is inferior to an earlier one, it should not

e ginned and packed with it, as the price of a bale is determined by e poorest cotton found in it after thorough sampling.

(8) **Yellow cotton.**—Buyers invariably complain when a sample of tton contains yellow staple, and the grade and price are conse- ently reduced. Yellow tufts in the ginned cotton come from dis- lored locks that should have been left unpicked or been sorted out fore ginning. They originate, as a rule, in bolls attacked by the thracnose or bacterial boll-rot (see page 47). Their presence in a le is an indication of too close ginning.

(9) **Sand.**—A bale of cotton always contains considerable sand hich has been blown into the open bolls. This is quite unavoidable, t when cotton has been left unpicked and has blown out on the ound the quantity of dirt is increased.

(10) **Moisture.**—An element of waste from the spinner's standpoint the moisture which evaporates during the process of manufacture. his moisture may be excessive in cotton picked early in the season nd ginned without drying. There may, on the other hand, be a ck of moisture. The cotton may be overdry and appear harsh and rittle. Such cotton gives trouble in spinning, because of the electric urrent it develops.

The question of moisture is one of the most important connected with the handling of cotton. Either an excess of moisture or a lack of it reduces the grade. The farmer, however, must never add water to the cotton, but he should seek to retain the optimum amount of natural moisture. This means that to drive off excessive moisture freshly picked cotton should be sunned until the seeds will crack in the teeth. The staple will then be slightly overdry and unfit to gin or offer to the buyer. To restore its grade it should be "bulked." Bulking, as practiced on the Sea Islands, is placing the seed cotton, after sunning, in a large, deep, square pile in a cool room. It should be packed down solidly and, if the air is dry, covered with blankets or boards and left from three to six weeks before ginning. When it comes out of bulk the staple has lost its harsh feeling and is soft, oily, and glossy.

Care must be taken never to bulk cotton that has not previously been well dried, or the pile will heat. On the other hand, a loose, onical pile, formed by throwing seed cotton into a storeroom, is not bulk, for it does not prevent the cotton from drying out still more. As a rule, cotton brought to the gins early in the season is too green nd damp and needs sunning to put it into good condition, while hat coming in late or taken from the storehouses during the winter s overdry and consequently harsh and brittle. Both the lint cotton nd the thread spun from it lack their full strength if too dry. Everyone knows how a dry twig will snap in the fingers, while a green one only bends. The same to a less degree is true of the cotton fiber. The quality is best maintained, however, by avoiding over-drying rather than by the addition of moisture.

(11) **Injury in ginning.**—The grade of cotton is often reduced during the process of ginning. This may be the fault of the farmer, as when he brings his cotton to the gin damp or full of hard or yellow locks or broken leaf and insists on close ginning; or the fault may lie with the ginner, who has failed to adjust his machines so that no seed can be broken. Briefly stated, seed cotton must be dry; if green or wet, "crimping" invariably results, to the serious injury of the fiber. The seed cotton should be free from hard locks or else the stripper bar should be adjusted to let them fall through with the seed. Close ginning is a form of adulteration instantly detected by the buyer and very costly to the farmer. The modern fruit grower has learned that he can not profitably mix his culls with his first-grade fruit, and the cotton grower must come to a similar conclusion.

The most frequent defects due to ginning are the presence of portions of broken seed and the cutting or crimping of the fiber. Since poor ginning costs the farmer, at a conservative estimate, 1 cent a pound, the ginner should be required to maintain his gin in perfect adjustment and to gin the cotton free from cracked, clipped, mashed, or whole seed and free from crimp.

The ginned cotton should come from the roller steadily and in an unbroken flake. Whenever it does not do this, an examination will show that the adjustment is not perfect, and the cotton is liable to sustain injury unless the trouble is corrected.

SUMMARY.

The best practice in handling the crop may be briefly stated by describing the method followed on the Sea Islands, which should be adopted in the interior in so far as the labor conditions will permit.

Picking is done whenever enough cotton is open, about every ten days. The cotton is gathered as free from trash as possible and carried to the storehouse, where the next morning each picker sorts his own picking. The cotton is then spread on arbors to dry in the sun. It is watched and turned frequently, and usually dries in one day. After sunning, the seed cotton is assorted by women, who remove any yellow locks, bits of leaf, etc. If very dirty it is whipped over a coarse wire screen stretched across a small box to take out the sand. Very fine cotton is again sorted or overhauled by another set of laborers. The cotton is then bulked and allowed to remain from four to six weeks before ginning. During the ginning, one or two hands inspect the cotton as it passes to the gins, to remove impurities, and one or two others "mote" the lint as it passes from the gin to the ress, by picking out yellow tufts, etc. By all these means a high rade is maintained for Sea Island cotton, which is reflected in a rice per pound several cents higher than that paid for interior otton.

DISEASES OF SEA ISLAND COTTON.

SORE-SHIN AND DAMPING-OFF.

Cotton seedlings sometimes become diseased shortly after coming up, particularly when soil or weather conditions are unfavorable. The term "sore-shin" is applicable to diseased spots or cankers formed on the stem or root of the seedling. These spots result in a cessation of growth, in yellow leaves, and, if they encircle the stem, in death.

A fungus (Rhizoctonia) is usually held responsible for the trouble, but it is only after cold and wet weather has checked growth and weakened the plants that serious loss results. If warm and favorable weather prevails the cotton soon outgrows the disease. No direct remedial measures are practicable. Danger of loss can be minimized by thorough preparation of the land before planting, by draining lower lying fields, and by thick seeding. Broken stands must be filled by replanting.

Damping-off, or the collapse of the stem at the surface of the ground, may be due to the sore-shin fungus or to other parasites. It is often caused by anthracnose, in which case the seed was probably infected before planting. The recommendations for the treatment of anthracnose on page 47 apply also to this form of it.

BACTERIAL BLIGHT.

There is a bacterial disease of cotton (*Bacterium malvacearum* Erw. Sm.) which is found to occur on different parts of the plant, producing various symptoms and receiving various names, such as angular leaf-spot, black-arm, boll-spot, etc., according to the point of attack. We describe all these together.

The earliest appearance of the disease is perhaps on the leaves, where it produces what is commonly known as the angular leaf-spot. These spots are at first a water-soaked green, becoming black when older. They are angular in outline, one-eighth to one-fourth inch in diameter. They are scattered over the leaf, but are often more numerous near the large veins. When one of these veins is attacked the disease rapidly extends its whole length.

Infection of the petiole is less common, but sometimes occurs, causing the leaf to turn yellow and fall off.

Infection of the pedicel of the bolls is a common cause of shedding and of failure to open. The bolls themselves are also attacked, the points of infection being water soaked at first and then growing darker. This organism does not appear to be as active a cause of boll-rot as the anthracnose fungus and several bacteria which appear to follow it and which very likely gain entrance through the bacterial spot.

Young plants in June are sometimes attacked on the main stem, near the ground or higher up, where a canker is formed which so weakens the stem that it is broken off later by winds or during cultivation. It is later in the summer that most damage occurs, when the disease attacks the fruit-bearing limbs. The spots on the limbs are dark—nearly black—and, though not deep, so sap the vitality as to cause the shedding of all the smaller bolls. In many cases, when the season is wet, infection by anthracnose follows and adds to the injury. Several forms of the disease are illustrated in figure 10.



FIG. 10.—Diseased leaves, boll, and stems of cotton plant showing several forms of bacterial blight.

Egyptian cotton is peculiarly subject to this trouble—so much so that its cultivation in the Southeastern States appears to be impracticable. There is considerable variation in the resistance of different ies of Sea Island cotton, Rivers, for instance, being rather suscepti-le, while Centerville is nearly immune.

Remedial measures must be indirect. Resistant varieties can be leveloped by selection. Diversification and rotation of crops will end to reduce the amount of infectious material remaining on the and and will lessen the disease. Black-arm is probably carried through seed to some extent, and the selection of seed from healthy bolls only will greatly aid in its control. It may be expected that a reduction of the nitrogen and an increase in the amount of potash in the fertilizer, by inducing development of less succulent branches, will reduce the danger of infection



FIG. 11.—A plant recently affected with cotton wilt (on the right), with a healthy resistant plant growing beside it.

WILT.

Cotton wilt, often called black-root, is one of the most serious diseases of the crop wherever it occurs. It is characterized by the death of the plants in gradually enlarging spots in the field, where the disease reappears year after year. The plants are attacked at any time after they are a month old, but die fastest in June and July. The affected plants wilt, or a few leaves at a time turn yellow between the veins and fall off. (Fig. 11.) When the stem or root is cut the woody portion is found to be brown or black. The discoloration is one of the most characteristic symptoms of the disease and has given it the name black-root.

Wilt is most prevalent on the sandy or sandy loam soils best suited for Sea Island cotton. Low spots and rich bottom lands often escape the disease long after the cotton on the higher portions of the field is killed. Clay soils are, as a rule, free from it, though some cases are reported. Geographically wilt occurs more or less in all the Sea Island cotton-growing districts, both in South Carolina and in the interior. It is also serious in Upland cotton fields from North Carolina to Louisiana.

Cause.

Wilt is due to a fungus (*Neocosmospora vasinfecta* [Atk.] Erw. Sm.) which enters the small roots from the soil, grows into the water-carrying vessels of the root and stem, and fills them, thus shutting off the water supply of the plant.

This fungus spreads by direct growth through the soil and also forms four kinds of spores, viz, one in the interior of the stem, another in cushions on the outside of dead plants, a third in the soil or on the surface of the plant, while the fourth or perfect spore stage is produced in minute bright-red sacs (perithecia) borne under ground on the bark of the dead roots. This fungus is without doubt spread to some extent by the feet of stock passing through the fields, carried in drainage water from high to low land, and distributed by plows and cultivators. When it appears in a field, attempts to restrict its spread are useless, so far as the writer's knowledge goes. As wilt attacks only cotton and okra, good yields of corn and other crops can be obtained on infected land. A long period of rotation tends to diminish the amount of disease, but the fungus can live in the soil for several years, cases being on record where seven years' rest failed to free the land from wilt.



FIG. 12.—Roots of a cotton plant affected with root-knot.

An important point in connection with the question of rotation is the danger from root-knot, another disease, described on page 46, which often occurs along with the wilt.

Enlargements of the roots of cotton (fig. 12) indicate that root-knot is present and that a rotation of crops must be practiced to control it. The combined treatment of wilt and root-knot is based on the following principles:

(1) Cotton wilt attacks only cotton and okra. It does not disappear after rest or rotation. Resistant varieties can be secured.

(2) Root-knot attacks cotton, cowpeas, sweet potatoes, vetch, mel-

ns, and many other crops, but does not attack corn, oats, velvet eans, or the common grasses. It diminishes and finally disappears hen all susceptible plants are kept off the field, and in ordinary rm practice can be held in check by a suitable rotation of crops. o variety of cotton is wholly resistant to root-knot.

A rotation similar to the following should therefore be adopted: irst year, corn with Iron cowpeas or peanuts; second year, winter ts, or, if preferred, rye or wheat cut early for hay and followed at ce with velvet beans; third year, cotton of a wilt-resistant variety.

Soil Treatment not a Successful Remedy.

It has been found impossible to kill out the fungus in the soil by y treatment with fungicides. Experiments have been made with me, sulphur, copper sulphate, formalin, carbolic acid, and numerous ther substances, none of which had any effect in reducing the amount f wilt.

The fungus is so spread through the soil that it is unlikely that it an ever be killed by any treatment that would be cheap enough to be racticable.

The Relation of Soil Conditions to Wilt.

It should be emphasized that wilt is due to the presence of a parasitic fungus, not to any unfavorable soil conditions. The fungus is, therefore, to be looked on as a weed and the disease may be expected to appear wherever its spores are carried. There are no chemical or physical differences between wilt-infected and healthy soils of the same type. Wilt is not due to the continual use of commercial fertilizers nor to the exhaustion of any element of plant food. Its preference for light and sandy soils has already been noted. Our experiments indicate that the free use of stable manure will assist in the control of wilt by increasing the vigor of resistant varieties, but the ordinary nonresistant kinds are not sufficiently protected by stable manure. In the same way other organic fertilizers, like compost and leguminous crops plowed under, will effect an improvement of the crop.

Control through the Use of Resistant Varieties.

It has been found possible to secure by seed selection varieties of Sea Island cotton resistant to wilt which will yield full crops of good quality on badly infected land, provided there is not too much root-knot present also. They were developed on the Sea Islands by selecting seed from exceptional plants that withstood the disease and remained healthy in the most infected spots. The first and best of these varieties is the Rivers, bred by Mr. E. L. Rivers, of James Island, S. C., in connection with the experiments of this Department. The Rivers cotton is productive, vigorous, compact, branching low, and with small, close-jointed limbs, often double bearing; bolls medium size, 3 to 4 locks; seed small, black, with a small green tuft; average per cent of lint to seed 28, giving a ginning rate of 3.57; staple fully to extra fine, and when grown on the Sea Islands 2 inches long. The Rivers cotton is an excellent variety for the Sea Islands and for the best localities in the interior, but has too low a ginning rate to be popular there, although its total yield per acre compares favorably with any other. It has also shown some susceptibility to black-arm when cultivated in Georgia.

A second variety, the Centerville, was selected with special reference to interior conditions. It differs from the Rivers in having smaller and more numerous bolls and a shorter staple—1⅝ inches—with a ginning rate of 3.30. The Centerville variety is noteworthy in being almost immune to black-arm. It is not fine enough, however, for the Sea Islands, and has defects when grown in the interior, especially in that its bolls are small and are often set in greater numbers than the plant can mature, resulting in a tendency to dry up toward the end of the season.

Other resistant strains have been developed, but as they are not at present obtainable for cultivation in the interior they are not described here.

Farmers who have wilt-infected land should secure seed of a resistant variety or, failing in this, should plant some other crop than cotton on the disease-infected field.

Once a wilt-resistant variety is obtained its quality should be maintained by the method of selection already described. Dependence can no longer be placed on the hope of obtaining seed from outside growers.

Control through Originating New Varieties.

Anyone who will give the necessary time and care can develop new resistant strains from the resistant plants that occasionally appear in fields of ordinary cotton. He must be prepared, however, to continue the breeding for several years before the desired results are attained.

No one should gather seed promiscuously from an infected field with the idea of gradually developing a resistant variety, for such methods are costly and usually fail. Breed from individual plants instead.

ROOT-KNOT.

Root-knot is a common and widely distributed disease in sand soils throughout the southern tier of States. The effect on the plar is to lessen its vigor and dwarf its size. The seat of the trouble is the root, which becomes distorted and covered with small swellin or knots. (See fig. 12.) These are produced by a minute nemato worm (*Heterodera radicicola* [Greef.] Mül.) which penetrates th roots and lives within them. On breaking open a large knot one ca ten detect minute pearl-like bodies, which are the female worms dis- ided by masses of eggs.

Root-knot is a more serious enemy of peaches, vegetables, tobacco, d cowpeas than of cotton. It becomes of great importance to the :ton planter when it occurs in connection with wilt, which it very :en does. The treatment required is the rotation of crops that has eady been discussed under wilt.

ANTHRACNOSE.

The greater part of the loss from rotting of bolls is due to the sease known as anthracnose. This occurs as dark-colored spots the bolls, which as they enlarge become pressed and gray or pink in the center. ee fig. 13.) The seed cotton in the bolls is scolored and spoiled. The cause is a para- ic fungus (*Colletotrichum gossypii* Swth.) iich is very common throughout the cotton lt. While most of the injury is done to e bolls, the fungus can attack any other rt of the plant. The disease is worse in et seasons than in dry ones.



Fig. 13.—Cotton boll affected with anthracnose.

Remedies.

No direct remedy is practicable on account f the expense involved, but there are impor- nt preventive measures based on the fact at the disease is spread in part by seed om diseased plants. Where trouble from is disease is experienced, the seed for the ext crop must be selected with care from erfectly healthy bolls. If a boll has one ck affected, there is danger that the fungus as penetrated all the seed. Avoid, if possible, running the selected ed cotton through a gin that has just been handling diseased cotton. ll accessible parts of the machine should be wiped clean to prevent he fungus spores from remaining to infect the selected seeds.

Finally, when the crop is all picked, the old cotton stalks should e burned. Of these precautions the seed selection is the most im- ortant. It will not do as well to send away for seed from a healthy ield, for the disease occurs everywhere.

RUST.

The disease commonly known as cotton rust is not primarily a fungous disease, but is caused by unfavorable soil conditions. Sea Island cotton fields affected by rust take on a reddish color, the leaves drop off, sometimes leaving the stalk bare, and the upper bolls fail to open. The cotton from such rusted plants is very weak and inferior. Rust is likely to develop in definite spots in a field, and unless a remedy is applied will appear year after year. Though other factors sometimes influence particular cases, there are three principal causes of rust in cotton, as follows:

(1) Exhaustion of the humus. Continued cultivation in cotton, by destroying the vegetable matter of the soil, is the most frequent cause of rust. The color of these old fields in midsummer is a lighter green, with a tinge of yellow, followed, when the bolls begin to mature, by the appearance of rust. A newly cleared field or an old fence row is, on the other hand, always green and free from rust. Stable manure is the most effective remedy in such cases, but a crop of velvet beans or cowpeas plowed under will effect a great improvement.

(2) Deficiency of potash. Most soils where cotton shows a tendency to rust lack potash, and an application of 200 pounds of kainit or 50 pounds of muriate of potash per acre will prove an effective remedy. Such soils are, as a rule, also deficient in humus, and a rotation of crops is usually advisable also.

(3) Lack of drainage. Rust often develops in low, wet places in a field where the higher portions are free from it, and for the same reason heavy and continued rains in August and September may lead to the development of rust in certain fields. Drainage by ditching or by tiles will be required in extreme cases. Most of these fields, however, become stagnant because the soil has no water-absorbing capacity on account of its lack of humus. If a leguminous crop were turned under every other year or stable manure applied liberally and the land plowed deep, the soil would soon be so changed in condition that heavy rains would not injure it and rust would disappear.

BLUE COTTON.

Blue cotton is a peculiar disease which occurs to a limited extent on the Sea Islands and in Florida. It is characterized by the deep green or bluish color of the leaves, the prostrate habit of the plant, which develops numerous lateral sprouts, and the shedding of the fruit. It is caused by some physiological or nutritional disturbance of the plant due to soil conditions not fully understood. The use of cotton seed and other organic manures aggravates the trouble. It has been successfully remedied on the Sea Islands by the use of salt mud, by liming, and by drainage.

INSECT ENEMIES OF SEA ISLAND COTTON.

The cotton caterpillar or leaf worm is the principal insect pest the Sea Island planter has to deal with, though slight injuries are sometimes inflicted by other insects. Readers are referred to Farmers' Bulletins Nos. 47 and 223 for full information relative to their control.

O

1015 Issued August 8, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 303

Corn-Harvesting Machinery.

BY

C. J. ZINTHEO,

Expert in Farm Mechanics, Office of Experiment Stations.

PREPARED UNDER THE SUPERVISION OF THE OFFICE OF EXPERIMENT STATIONS,
A. C. TRUE, Director.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Office of Experiment Stations,
Washington, D. C., June 19, 1907.

Sir: The demand for the report on corn-harvesting machinery prepared by C. J. Zintheo and published as Bulletin 173 of this Office has been much greater than the somewhat limited edition of that bulletin would supply. For this reason it has been deemed advisable to condense the original report within the limits of a Farmers' Bulletin and so provide for a wider distribution of the more important information it contains. Such a condensed summary is transmitted herewith and recommended for publication as a Farmers' Bulletin of the Department.

Respectfully,

A. C. True,
Director.

Hon. James Wilson,
Secretary of Agriculture.

CORN-HARVESTING MACHINERY.

INTRODUCTION.

inery for the care of the corn crop has been much more difficult develop than any other line of farm implements. Although as been considerable progress in methods of harvesting corn, ger part of the crop is still husked by hand from the standing only the ears being gathered, while the leaves and stalks are a total loss. This results in an enormous waste of valuable or it has been demonstrated that when properly harvested corn is as nutritious as good hay, and that the farmer who would the full value of his corn crop should secure this fodder with h care as he gives his hay.

r the success of mowing and reaping machines, inventors tried eloped a corn harvester along the lines followed in the construction those machines. Their success is not as yet complete, but the aving devices so far perfected have largely changed conditions. rn may now be cut, husked, and shredded with less labor than tting alone formerly required. At the same time all of the fodmade available for feeding purposes.

CORN CUTTING WITH KNIVES.

mmon method of harvesting corn is to cut the stalk close to the l at a time when no damage is done to the ripening grain and onsiderable of the saccharine juices still remain in the stalk.

implement first used for corn cutting was the hoe, but as this ther heavy and awkward the more progressive farmers subd the corn knife. For a long time scythe blades were largely making corn knives, but these have now given way to all sizes apes of factory-made knives. The corn hook (fig. 1), which is xtensively used, is generally considered more convenient than n knife.

n the corn is cut it is customary to set it up in shocks to cure. vary greatly in size, ranging from 6 hills square (36 hills to ck) to 16 hills square (256 hills); a very common size is 12 hills (144 hills). Shocks of the smaller sizes are common in the Atlantic States, where, according to the Connecticut Station, it e difficult to preserve flint-corn stover; while 10 hills square and 12 hills square are common sizes in the North Central States. The common or four-saddle shock method consists in tying the tops of four hills together as they stand and then cutting and shocking the rest of the hills around these. Another method of making the shock is to use a wooden horse as a temporary support. In either case the shock is built around the support with great care to prevent it from being blown over by heavy winds or damaged by rain. In some cases the corn is tied into small bundles, which are set together to form the shock; more commonly the stalks are gathered as cut and set up an armful at a time. Where the wooden horse is used the shock is built about the horse by leaning the first bundles or armfuls against a pair of projecting arms formed by inserting a pole through a hole bored at right angles to the horse (fig. 2). When the shock has been set up the pole is withdrawn and the horse removed. When completed the shock is tied tightly near the top. A rope with a hook at one end is sometimes used to draw the tops together before tying. Sometimes shocks are not tied.


FIG. 1.—Corn hook.

After the fodder has become cured, which usually takes about a month, the shocks are generally husked by hand in the field, and the stover is commonly tied into bundles and reshocked. Frequently the stover from two or more shocks of corn is put up in a single shock. For convenience in husking a movable table is sometimes used, on which the stalks are laid while being husked. The ears are thrown in piles on the ground near the shocks and afterwards hauled to the crib. The stover is sometimes hauled to the barn and stored, but often it is left standing in shocks in the field till needed for feeding during the winter. It is important to choose suitable weather conditions for husking, since if the plants are too dry the stalks will break and blades will fall off and be lost. On the other hand, extremely wet weather makes the ground too soft for hauling in the corn.


FIG. 2.—Wooden horse used to support shock.

The cost of these methods of caring for the corn crop varies with the locality and the year. Taking the average of the replies to 200 inquiries, it appears that one man is able to cut and shock by hand about 34 shocks 12 hills square, or nearly 1½ acres of corn per day. The average cost per shock for cutting by hand is reported to be 6.5 cents, or $1.50 per acre.

MACHINES FOR HARVESTING CORN.

SLED HARVESTERS AND SIMILAR DEVICES.

ly as the year 1820 attempts were made to construct a mechan- harvester. From that year until 1892 all attempts to perfect achine were unsuccessful. The machines invented were pat- fter the mower and the reaper, but owing to the size of the t these machines either would not cut at all or were soon nder the heavy strain. Some of the machines, however, had dable mechanical fea- hich were embodied nes invented later.



FIG. 3.—One-row sled harvester.

ade sled harvesters.—omemade harvesting of the sled pattern n made from time to me of which are illus- n figures 3, 4, and 5. t harvester of this s patented by J. C. n, of West Mansfield, Ohio, who put one in the field in 1886. ollowed and added improvements until eight or ten harvesters ind were in the field.

most of the sled harvesters the driver rode on the platform, as necessary for him to gather the stalks in his arms in advance utting edge, so as to prevent them from falling in various s. This method of harvesting was very exhausting. The r shown in figure 5 was an improvement, in that the guiding arm collected the stalks on the platform, and it was only necessary for the driver to pick the stalks from the sled at intervals and throw them on the ground.



4.—Two-row sled harvester.

A sled harvester mounted on wheels.—As an improvement, in order to reduce the draft, the sled was mounted on wheels (fig. 6). This machine cuts two rows at a time, and two men sit latform, one facing each row, to guide the corn against the dge with one hand and with the other hand and arm to collect orn on the tilting side part or wing of the platform, drawing gainst the leg, where it is assembled until enough has been to form a shock.

omplicated machines.—To reduce the labor involved in cutting h the machines described, another style of corn harvester was invented, two forms of which are shown in figures 7 and 8. This machine consists of two driving wheels, between which is mounted the frame for the driving mechanism and platform. It is drawn by one horse, which walks between the two rows that are cut at the same time. The dividers pick up the lodged corn, except such as lies in the row of corn away from the machine, and guide it to the cutting apparatus, which consists of two stationary side blades, above which is a movable sickle, which cuts the corn and deposits it horizontally on a platform that is elevated about 6 inches above the cutting apparatus. On the inner side is a guide chain, which assists in directing the stalks of corn to the knife and the platform. The rear part of the machine is provided with a small wheel, above which is a tilting lever, by means of which the dividers in front can be raised or lowered to gather up the lodged corn until it comes in contact with the endless chain, which carries it backward until it is cut and deposited on the platform. The machine shown in figure 7 has low wheels and stationary cut, while



Fig. 5.—Improved one-row harvester.



Fig. 6.—Corn harvester with automatic knife guards.

one shown in figure 8 can, by means of side levers, be adjusted ut the corn from 2 to 15 inches from the ground.



FIG. 7.—Two-row corn harvester with stationary lift.

Machines of this type gather and cut the corn and drop it on the latform. When there is enough to start a shock, the horse is stopped nd the corn is set up.



FIG. 8.—Another two-row corn harvester—rear view.

Cost and efficiency.

These different forms of corn harvesters vary in price from $5 to $55, and, while their low cost is a great advantage, their degree of efficiency is not very high. The cheap sled harvesters can be used only when the corn stands straight, and the horse must walk rather fast in order that the work may be perfectly done. It is also hard work for the men to gather and shock the corn. The work of harvesting corn is such that only the best construction can withstand the strain for any great while, and hence these machines are being used less than formerly.

From 90 replies to a letter of inquiry regarding the cost of harvesting with these machines, sent to a large number of farmers in different parts of the country, it was learned that the minimum in area of corn cut per day was 2 acres and the maximum 10 acres. The average from all the replies was 4.67 acres of corn cut per day by two men and one horse, using the sled harvester. As to cost per acre for harvesting corn the minimum price reported was 55 cents per acre and the maximum $2. Taking the average of all the replies received, the cost of harvesting corn with a sled harvester was $1.18 per acre. This is estimated on a basis of 18 cents per acre, or 84 cents per day, for the use of the machine and repairs; 4 cents per acre, or 19 cents per day, for twine; 58.5 cents per acre, or $2.75 per day, for one horse and a man who does part of the shocking, and 37.5 cents per acre, or $1.75 per day, for the other shocker. Comparing this cost per acre with that of hand cutting (p. 6), it will be noted that there is a saving of 32 cents per acre in favor of the machines. It will also be noticed that two men and a horse with a sled harvester can cut and shock 4.67 acres per day, as against 1.47 acres per day for one man with a knife, which gives a credit of 1.73 acres per day for the work of the horse, or a considerable saving in favor of the machine.

CORN BINDERS.

Historical.

The credit of inventing corn-harvesting machinery belongs to Edmund W. Quincy, of Illinois, as he obtained the first patent on a corn-harvesting machine in October, 1850. This machine, like many others, was intended to pass over the row and pick the ears from the stalks. Another form of corn harvester (fig. 9), invented in the eighties, cut the cornstalks and elevated them into a wagon. The elevator could be removed and a binder attachment put on by which the corn was bound into bundles. One of the earliest forms of corn harvester and binder was constructed as a modified form of the grain binder. This machine also was so constructed that for the binder attachment there might be substituted a device to elevate the corn into a wagon.



FIG. 9.—An early corn harvester.

A machine embodying principles which were destined to prevail in corn harvesters was invented by A. S. Peck, of Geneva, Ill., and was patented January 5, 1892 (fig. 10). It consisted of a corn harvester with the two dividers passing one on each side of a row of corn, which



FIG. 10.—Vertical corn harvester in the field.

was cut and carried back in a vertical position to the binder attachment by means of chains and gathering arms. A standard twine binder was used, set in a vertical position so as to receive the stalks and keep them in this position until the bundle was discharged. The horses were hitched behind the machine as they are on the header.

The Peck patent received very little attention at first. It showed very few elements that were new, as the vertical principle of cutting grain had been tried and failed to give satisfaction. It was rather a rearrangement of well-known principles used in harvesting machinery than a new departure. However, after two years' use by the inventor and a few other persons, its merit was recognized by one of the prominent harvester manufacturers.

From the date of the Peck patent until 1895 many machines were made which would work well in the hands of the inventors, but few were so perfected as to be entirely successful in general use.

Since 1895 the self-binding corn harvester has had a considerable sale. In practically all of the corn binders now built the features of the Peck type predominate. Even the most divergent forms still retain the general organization of parts used in the Peck machine. Among the practical and successful corn binders in the market the widest divergence from the Peck type is probably to be found in the machine invented by John A. Stone, of Chicago. In this machine the binder is in an almost horizontal position, instead of vertical. When the corn is cut the stalks move a little rearward in an upright position, and then they are tripped so that the tops fall rearward onto an inclined deck, being guided in their fall toward the binder by curved guide arms. The butts are pushed out of the way of the incoming cornstalks, and are evened for a bundle by means of a butt adjuster.

A type of corn binder, which comes about halfway between those already described, was invented by Tarrall and Maul, of Batavia, N. Y. It is designed to occupy an inclined position over the deck for the purpose of binding the stalks in a semiprostrate position.

Construction.

There are, therefore, three different forms of corn binder, namely, the vertical, the horizontal, and the inclined, the latter being rather a blending of the two preceding types. These machines differ only in the relative position of their elements, being composed of the same essential parts. Binders consist essentially of the dividers, of which previous mention has been made, and of cutting and binding devices. (See figs. 11, 12 and 13.) A bundle carrier is usually also attached, but this is not essential to the smooth operation of the machine.

ders.—The dividers consist of two diverging jaws opening at the ɔf the machine. The jaws begin in two points at the front, but ılly widen vertically to where they join the frame of the machine, they have a width, or rather a height, of 4 feet or more. By rangement of levers the points may be raised or lowered. ıed to each jaw are two or three traveling chains, whose purpose › bring the stalks to a vertical position and carry them back to nding deck. The chains are placed one above the other (fig. 11). ower one is known as the short-corn chain, the middle one is nveyor chain, and the upper one is the tall-corn chain. The e chain passes around a sprocket wheel close to the point of the and extends back almost to the binding deck. The upper begins farther back and extends some distance over the binding



FIG. 11.—Skeleton frame of corn binder, showing chains.

:. This chain is meant to carry the tops of tall corn. The lower ı is of about the same length as the upper one, begins nearer the t of the jaw, and does not extend so far back. These chains are ›lied with fingers, which take hold of the stalks and lift them to a ical position as the machine advances. The jaws have such a :ion relative to each other as will bring the fingers of the opposite ıs almost in touch with each other at or near the cutting blades. chains receive their motion from the main driving mechanism, ıre driven at such speed as will bring the stalks to the proper ion for cutting without shaking them too severely.

tters.—The cutting arrangement consists of a serrated knife which ›s to and fro across two stationary blades, one of these being hed to each jaw. This serrated knife is driven by a pitman attached to a weighted wheel called a "fly wheel." The added weight gives enough stored energy to sever the toughest stalks without shock to the small gear wheels (fig. 12).

Attached to the rear of the dividers and extending around the binding deck are several guide springs (fig. 10) which keep the tall corn from bending over and becoming entangled in the binding gear.

Binding apparatus.—Just behind the knife and thence extending back to the bundle carrier is the butt shoe, or butt carrier (fig. 11). This device carries the weight of the stalks after they are cut. It is fastened to the frame just behind the knife, but through the rest of its length it is adjustable vertically, so that the binding twine may be placed at the proper place on both tall and short corn.



FIG. 12.—Frame of corn binder, showing mechanism for driving cutter knife, gear shaft for driving chains and binding device, and roller bearings.

As the stalks are cut they are carried back by the conveyor chain, with their butts resting in the butt carrier until they reach the binding deck, where they are pushed backward by the packers, which have such a motion as will carry them perpendicularly through the binding deck and parallel to it while conveying the stalks to the knotter. Their motion is more rapid than that of the chains, but they have the advantage of yielding slightly while a bundle is being tied. This is important, as many ears would otherwise be knocked off by jamming the stalks behind the needle.

The needle and the knotter form the binding attachments. They are in nearly all cases of the same pattern as are those of the grain binders of the same makes, but are made heavier to meet the requirements of the work.

The packers on these machines (fig. 13) must have such a motion as to travel toward the back of the machine as long as they project above the binding deck, their travel through the deck being fast and ıort duration. There is one machine on the market which does ıse packers at all, but has instead several chains with collapsing rs. While the bundle is being formed, these fingers assume a ion perpendicular to their chains, being held so by the guides which they travel. As soon, however, as the needle moves, these es no longer bear against the fingers, which collapse when pres- is brought to bear against them. This prevents their jamming ncoming corn against the rib of the needle while a bundle is being and avoids the break- ɔff of ears that would ı occur otherwise.

hen the bundle has ı bound the two or e discharge arms on binding shaft have hed the back side of bundle, and by the inuous motion of the t the arms force the dle off the deck and harge it, after which compressor hook re- ıs automatically to its e and the binding ft stops until another dle is formed, when operation is repeated. ure 13 shows the bind- mechanism and the eral arrangement of several parts referred



FIG. 13.—Binder attachment: *a*, Needle; *bb*, packers; *c*, knotter cam; *dd*, compressor hook; *eee*, discharge arms; *f*, butt table or butt shoe; *g*, twine cam.

pecial features.—The ts that are adjustable ever are the butt shoe, dividers, and in some machines the binding deck and knotter and dle. The whole frame of the machine may be raised or lowered by ıns of the two worm-and-pinion arrangements, one on the grain eel and one attached to the main drive wheel.

n the vertical machine the binding mechanism has a vertical posi- ı; in the horizontal machine it sits horizontally on the frame, l in the inclined machine it is inclined.

n the horizontal machine it is necessary to extend a conveyor in farther back than in either of the other types, so as to bring tops of the stalks into a horizontal position. In this type, too, bundle carrier extends in a direction parallel to the length of the machine. This arrangement is very apt to give trouble from the butts of stalks becoming lodged in stubble or soft earth and spreading the bundles in disorder upon the ground. This might be avoided more or less by giving the bundle a sharp toss, thus freeing the carrier before any part of it touches the ground. The fingers of the carrier are sometimes made free to move backward and forward so as to prevent the drag above referred to. On the vertical and inclined machines there is less danger of trouble from this source, as the bundle carriers extend across the path of the machine. The smooth operation of the carriers depends greatly on the skill of the operator. Too many bundles crowd the carrier and prevent the binding attachment from properly freeing itself, causing the leaves of the stalks in one bundle to become wrapped about the stalks in another.

The tall-corn chains may be removed where the corn is short or of medium height, and in clean fields of tall corn the short-corn chains are unnecessary. In short corn the lower chain has sometimes proven inadequate alone to properly convey the stalks to the binding deck. By the addition of a small iron rod or spring (shown at *a*, fig. 11, p. 13) on each of the dividers the choking of the binding gear is prevented and a more nearly perfect bundle is made. A short iron bar has also been added on many machines to serve the same purpose. This is usually placed in a horizontal position between the lower and middle chains. The dividers are adjustable vertically, allowing them to pick up corn that is lying flat upon the ground, the lever being in reach of the driver.

To protect the mechanism from the stalks of the uncut rows a guide rod of hickory or other tough wood is usually attached to the dividers and extended as far back as is necessary. It may be raised or lowered independently of the dividers, however, so as to give protection against either tall or short corn. This bar is shown at the left in figure 14 and the tilting lever on the right.

Badly tangled fields make the progress of one of these machines slow, but it is remarkable with what precision the chain conveyors right the stalks. The adjustment is accomplished by tilting the machine forward or backward by the tilting lever, according to whether it is desired to lower or raise the points of the dividers. As the weight is almost evenly distributed on either side of the main shaft it takes but a very little power to bring the dividers into the desired position.

There are two types of these dividers—the vertical (see fig. 10, p. 11) and the inclined (fig. 14). For the vertical it is claimed that little jostling is given the corn, decreasing the danger of knocking off ears, while advocates of the inclined pattern claim to accomplish the same result by allowing the stalks to recline against the inner jaw and be carried kward between the fingers of the conveyor chain on that side.

wing to the great variation in height of corn, even in the same
l, the binding attachments are given great range of operation.
ome machines they are placed as high as 32 inches. On machines
his range it is customary to have two needles, each covering half
he variation in the position of the knotter. With such a large
ge as this it is possible to tie the bundles sufficiently low without
ing the stalks any great distance, thereby reducing the work
uired of the machine. In most machines the motion is taken
m the inside; in some, however, it is taken from the outside hub of
main driver. (See fig. 12, p. 14.) The arrangements for reducing
tion and excluding dust from the bearings receive careful atten-
n, as may be noted from the numerous roller bearings and brass
aring boxes. Gears are also protected wherever possible, to pre-
nt wear from dirt and grit. Where gears are not properly protected
d oiled, there is apt to be a great loss of power, to say nothing of
e wear. When they receive careful attention, however, the power
quired to move them is reduced considerably below that required
r chain and sprocket. The driving power is increased by means of
gs cast or riveted on the rim of the main drive (fig. 14). They are
ade of various shapes, the object of all being to sink into the earth
n such a way as to prevent slipping. Tubing, angle iron, and bar
ron are used almost exclusively in the construction of the frames.
These give strength and lightness, features which are most essen



FIG. 14.—Inclined corn binder, showing tilting lever and guide rod.

to a perfect machine. The attendant, from his seat on the machine, has perfect control over all parts. The levers at his side operate all adjustments, and the position of the bundle carrier is controlled by a foot-lever attachment.

These machines weigh, complete, from 1,400 to 1,800 pounds. Generally speaking, those weighing in the neighborhood of 1,500 pounds have been most successful, this weight seeming to give the proper relation between driving power and durability.

The corn binder is used to greatest advantage in fields where the corn is check-rowed, as it is possible to cut around a block, keeping the machine constantly in operation.



FIG. 15.—Corn-stubble cutter, attached to corn harvester.

The corn-stubble cutter.—When the corn is cut high with a corn binder, the farmer experiences considerable difficulty in getting rid of the corn stubble. In order to obtain a clear field and to have the cornstalks cut close to the ground, an attachment has been invented as shown in figure 15. This knife is attached to the under side of the machine and floats on the ground, cutting the stalks even with the surface. The cutter (D) has a drawing, slanting cut against spring resistance (E), making a clean cut. When this attachment is used, the binder is usually set to cut higher. The stubs, if cut when sappy, will decay quickly, and are left on the ground to form humus in the soil; and the ground may be prepared for the next crop with greater thoroughness.

Draft.

The average draft of corn binders is about the same as that of a 6-foot grain binder. The corn binder should therefore be propelled by three horses, the same as are required for grain binders. Draft tests of the corn binder, with a stubble-cutter attachment, shows the following results:

Draft of corn binder with and without stubble cutter.

	Pounds.
Draft with stubble cutter	437
Draft without stubble cutter	420
Draft of stubble cutter	17

Cost and efficiency.

The average results, taken from the several hundred replies received to a letter of inquiry, indicate that for all conditions of corn the average number of acres of corn cut per day with a corn binder using three horses was 7.73 acres. The average number of acres which one man can shock per day after a corn binder was 3.31 acres. The average number of pounds of twine used per acre of corn cut was 2.44. The average life in years of corn binders was 8.17, and in acres of corn cut 668.77. The average first cost of corn binders was $125. The average cost of machine per acre cut, which includes price of machine, repairs, and interest on the investment, was 29 cents per acre; the cost of driver and team per acre cut 46 cents, or $3.55 per day; the cost of twine 30.5 cents per acre. The cost of shocking the corn after a corn binder is 44.8 cents per acre. This gives the total cost per acre of harvesting corn with a corn binder, $1.50.

The cost of cutting corn with the corn binder is therefore the same as the cost for cutting corn by hand, and 32 cents per acre higher than the cost of cutting with a sled harvester. This extra cost of cutting with the corn binder over the cost of cutting with the sled harvester may be attributed to the cost of the twine and the interest on the investment in the higher first cost of the machine.

One disadvantage in the use of the corn binder is that it knocks off more or less ears of corn, which either have to be picked up by hand, at a cost of about 10 cents per acre, or left to waste or to be found by the cattle after the field is cleared.

Farmers sometimes hire their corn cut at a rate of 75 cents to $1 per acre for the use of the machine, the driver, and the team. The average cost of cutting given above was 29 cents per acre for the use of the machine and 46 cents per acre for the driver and team, or 75 cents per acre. The charge for hiring the work done is only slightly above this.

THE CORN SHOCKER.

Although the earlier efforts were centered upon the construction of the corn shocker, the perfection of this machine was delayed until after the introduction of the corn binder. In the first machines the inventor attempted to engage the stalks by extending rods or springs in advance of the cutting knives, but this did not prove as successful as did the dividers of the corn binder. With these the corn could readily be brought to an erect position and thus made into a perfect shock.

Description.

The present corn shocker was invented in 1888, and a machine was constructed that year by A. N. Hadley. It was built with a frame mounted on two wheels, the same as the corn binder, and consisted of a corn-gathering device—revolving reels on vertical standards—the upper bearings of which were arranged for adjustment laterally and fore and aft. It had as a cutting device two circular rotating cutters, operating against each other and cutting the corn as the machine advanced toward it. Behind the cutting device was a circular rotating table, 5 feet in diameter, upon which the corn was collected vertically to form a shock. On this table were several radial ribs, which aided in revolving the standing corn. In the center of this table was a rotating shock-forming standard, having radial arms around which the corn was collected. A revolving crane was mounted on the frame and a rope and pulley attached above the shock, by which it could be lifted from the platform and deposited on the ground.



FIG. 16.—Corn harvester and shocker.

In 1893 a shocker was constructed by J. M. Shively, similar in principle but somewhat departing in its construction from the Hadley shocker in that the cutting apparatus and the dividers were like those of the corn harvester, and the retaining wall surrounding the shock-forming table was somewhat higher than that on the Hadley shocker.

The present form of shocker (fig. 16) consists essentially of the dividers already described in connection with the corn binder, a revolving table for assembling the shock, and a crane for removing it. The knives and fly-wheel attachment for cutting the stalks, and the arrangements for raising or lowering the dividers, and the frame are similar to those used on the corn binder. The table revolves in the ction indicated by the arrow, and receives its motion from a bevel driven from the main drive and meshing into a rack on the outer e of the table. As the machine advances the stalks are carried ough the opening in the guard band. They are then caught by the al plates and the arms and forced around the central post. The is also revolve, receiving their motion through the central pin from ear located just beneath the table. Their motion is somewhat ver than that of the table. The guard or tension springs keep the lks firmly compressed about the central post. Sometimes the twine ied to one of the arms and allowed to assist in bringing the stalks vard the center by being wound about them as the arms revolve. is practice adds to the expense of operating the machine and does t materially improve the character of the work. At the outer edge posts which support the tension springs.

When the shock is fully assembled on the table it must be tied by nd. The shock may then be raised from the table by turning the ank, and winding the rope about a spool. The shock must be lifted gh enough to clear the retaining wall. The tension springs are ung aside and the crank acting on a sector gear swings the shock ee from the machine.

The arms (fig. 16), which are held in a horizontal position by the eight of the shock, are released the instant the rope is given slack. his release of the arms is brought about by a unique arrangement of cam and pawls. When the rope is tight owing to the weight of the ock, the pawls are held in the grooves of the cam because the weight carried from the pulley. When the rope is given slack the pawls e no longer kept from slipping out of the grooves in the cam, the ock moves through a small arc of a circle and drops to the ground, d the central supporting post is then raised to its position on the achine. The whole operation of forming, tying, and setting a shock n be done in five minutes. The shocks are somewhat smaller than ose ordinarily made where corn is cut by hand or with a binder, eraging about 100 hills per shock, but the smaller size is necessary d makes it possible to reduce the weight of the machine. The naller shocks also tend to cure more rapidly. The adjustment of e frame admits of the low cutting of the stalks. This results in greater weight of fodder per acre and leaves a short stubble that easily turned under at the spring plowing.

Cost and efficiency.

Corn shockers cost about as much as corn binders and weigh approx- ately the same. The shocker has the advantage of requiring the ork of but one man, whereas the binder requires, besides the driver, o or three men to follow and shock the corn.

The replies to inquiries indicate that the average number of acres of corn which can be cut per day with a corn shocker, three horses, and one man, is about 4.7 acres. The wear and tear is less than on a corn binder, and the life of the machine ought to be greater. Assuming that the allowance for first cost, life of machine, and interest on investment is the same as that for the corn binder—i. e., 29 cents per acre; allowing $3.55 per day for driver and team, or 75 cents per acre; and estimating that the twine required per acre cut with the shocker will not cost over 2 cents, we have a total cost of harvesting corn with a corn shocker of $1.06 per acre, as compared with $1.18 per acre for harvesting with a sled harvester, and $1.50 per acre with corn binders or by hand.

The shock made by the corn shocker is not so easily loaded on a wagon as is that made by a corn binder, as the individual bundles may be loaded with a pitchfork, whereas the whole shock made with a shocker can best be loaded at once, and this requires some form of loading device or horsepower derrick.

The corn binder is well adapted for cutting corn for the silo, as the bundles are bound into convenient size for handling, but this saving of labor is accomplished at the cost of twine. A corn shocker arranged to load the shocks on a wagon would no doubt prove the cheapest method of harvesting corn for the silo.

The general verdict of farmers who have used both the corn binder and the shocker is that the shocker is the preferable machine for harvesting corn.

A CORN-SHOCK LOADER.

A loading device for handling the shocks adds greatly to the value of the shocker, for with it the corn can be more cheaply handled than by the present methods. One of the first devices of this kind consisted of a long pole or pipe supported on a fulcrum at the rear end of the wagon in such a way as to give considerable leverage. The idea was much like that of the old well sweep with the semirotary motion added.

An improved loading device which can be carried along with the wagon or left in the field and driven about independently, is mounted on four wheels, and consists of an adjustable vertical mast on which is a horizontal steel cross arm. On this is mounted a traveling block fitted with pulleys through which a rope passes. To the end of this rope is hitched a horse which lifts the load. For loading corn shocks a grapple fork is used, which is slipped under the shock. The grapple arms are closed and with the pull of the horse the shock is lifted up on the wagon and laid on its side or stood on end, the grapple arms being released by simply turning the handle of the fork. This machine was originally designed to load corn shocks, and it handles two shocks per minute, and will bear a stress of 2,000 s. It can also be applied to many other uses, such as loading manure, small grain, dirt, lumber, telephone poles, and other objects.

CORN PICKERS.

the so-called "corn belt," where corn is the principal crop l, it has not been possible so far to utilize all of the cornstalks. rop is raised for the ears, which are picked by hand at maturity. lieve farmers of this somewhat tedious work, for which it is often lt to get sufficient labor, inventors have busy for over fifty years trying to build erfect a machine to pick the corn from alks.

DESCRIPTION.

icking machine was invented by Quincy 0, and another by William Watson, of go, shortly after. Practically all of the r corn pickers consisted of rollers ing up in such a way that the front end rollers would pass below the lowermost nd rake the stalk from the bottom to op. A great many devices were emd for removing the ears, such as cutters, ring prongs, rotating-toothed cylinders, and breaker devices, parallel vibrating etc. The early machines were designed pushed from the rear and were provided some form of dividers to guide the corn e snapping devices, as shown in figure The snapping-roller type of corn picker ed serious attention from manufacturers 1874, when the first machine of this type nvented, but it was ten years later that patented. The rollers were placed in nclined position for the stalks of corn to etween them. The end portions of the s where the stalks entered were provided bars designed to aid in snapping off the s the stalks passed down between the rollers during the advance machine. For the remainder of their length the rollers were nstructed as to tear the husks from the ears and continuously he ears along, to be finally discharged, husked, onto a conveyor, elivered into suitable receptacles. This particular machine v



FIG. 17.—A corn-picking machine.

s

thought to promise success, but when the corn binders began to be developed and came into use the interest in corn pickers abated, as it was thought that with a successful corn binder there would be no need of corn pickers. However, the use of the corn binder and the shocker, while quite extensive, does not solve the corn-harvesting problem in the purely corn-raising regions, where a large share of the corn is still picked by hand from the stalks as they stand in the field.

About 1902 the attention of manufacturers was again turned to corn pickers, and several machines are now being introduced for picking corn. The corn picker as now constructed resembles the corn binder in the construction of the main frame, drive wheels, and dividers. It passes along the row of corn, which is straddled by the dividers, and the stalks, after being righted by the points, chains, and other devices, pass between a pair of inclined, corrugated rollers that snap or strip off the ears. The rollers are so placed that the ears fall naturally into a trough that extends along beside them. In order to provide snapping rollers to remove the ears and force them to fall always to the same side, yet permit free entrance of the upright stalks at the receiving end without the necessity of auxiliary means to bend the stalks laterally, James E. Goodhue arranged the snapping rollers in slightly skewed relation, by which the upright stalk may be gradually forced to one side as the picking rolls pass along, and the ears are broken off and directed to one side. The ears are carried back by a traveling conveyor and either delivered to a set of husking rolls or else, without being husked, carried by an elevator and delivered into a wagon which is driven alongside the machine.

Another form of modern practical corn picker has the guide chains with the usual prongs for straightening up the stalks. The chains form a stalk passage extending rearward through the machine. A rapidly moving chain provided with fingers is located at one side and between the guide chains in such a position that, as the machine passes over the row, the fingers engage the ears on the stalks and snap them off. By means of a deflector the ears are directed to a receptacle from which they are carried to the husking rollers and thence to the wagon. The tops of the cornstalks are cut off, and by means of a conveyor this and other trash is carried to the rear and dropped on the ground.

OBJECTIONS AND ADVANTAGES.

The corn picker is intended to remove the ears from the stalks, which are left in the field. Most of the machines are built on the assumption that the stalks are valueless, and therefore they are practically destroyed. It has not been possible to construct a picker it will not to some extent break down or tear down the stalks. is is somewhat objectionable because, where the corn is picked by nd, the dried corn leaves and stalks serve as roughage for cattle ring the fall and winter. The machine has, however, this advan- ge, that the field can be picked quicker and the cattle turned in rlier to make use of the roughage before the snow falls.

Another objectionable feature of the corn picker as compared with e hand method of picking corn is that it shells considerable corn; d, if the corn is lodged and tangled, more or less ears are missed by e machine. The corn picker with the husker attachment requires nsiderable motive power, at least four horses being required to pull For this reason some manufacturers have dispensed with the isking attachment and depend upon the snapping rollers for moving most of the husks. Machines of this kind will remove from . to 75 per cent of the husks, depending upon the stage of maturity the corn, the brittleness of the stalks, and the effects of freezing d damp weather. Where machines without the husker attachment e used a stationary husker may be provided at the crib, in which e corn is husked and elevated into the corncrib.

There is a variance of opinion among the farmers as to the advisa- lity of husking the ears clean. In the South the common practice to leave the husks on the ears, and it is claimed that this practice nds to prevent injury by insects. In the North it is the common actice to husk the ears clean before they are cribbed. The objec- ons offered, in reply to inquiries, to using a corn picker which leaves ie husks on the ears are that more crib room is required for the ears; iat they will serve to attract and harbor rats and mice; that the ears ill not dry out, but will be liable to mold; that the husks interfere ith the shelling; that, while for feeding cattle and hogs the husks ill be advantageous, as they will serve as a roughage, horses will toss he ears in trying to remove the husks, and thus lose ear and all. For elling purposes the corn needs to be husked clean in order to com- nand the best market price.

COST AND EFFICIENCY.

The corn picker should last about as long as the corn binder, or 8.17 ears, and pick about the same number of acres per day as can be arvested with a corn binder, or 7.73 acres. The first cost of the iachine is, however, practically twice that of the corn binder, or, on n average, $250. This makes the cost of machine, interest on the ivestment, and repairs equal to 58 cents per acre. The cost of driver id team is $3.55 per day, or 46 cents per acre. There is required ro wagons with teams to remove the corn from the machine and liver it into the crib, which, at $3 per day for each, costs $0.77 per acre, or a total cost of $1.81 per acre for picking corn with a corn picker.

From 300 replies received to questions sent to numerous farmers in different parts of the country it was learned that the average yield of corn was 44 bushels per acre; that the average cost per bushel for picking corn by hand was 3¼ cents, and that the average man picked 59 bushels of corn per day. This yield is considerably above the average given in the crop reports of the United States Department of Agriculture, but it represents the yield of corn in States where pickers are used. Considering, now, that the number of acres which the corn picker can cover per day is 7.73, this would, for the average yield, be 341 bushels of corn per day. It would require the time of 3.8 men to do the same work in the same time by hand as is done with the machine, at a cost of $11.93 for labor, but in addition to the wages of the men there is need of a team and wagon for every two men who pick corn by hand to haul the corn to the crib. These teams are worth at the very least $1 each per day, or three teams for the 7.73 acres would cost $3. The total cost for picking the same number of acres of corn by hand as can be picked with a corn picker, per day, would be $14.93, or $1.93 per acre, as compared with $1.81 per acre for machine picking. While the saving effected with the corn picker is not large, the use of a machine makes the farmer more independent of the labor market, as the work may be done without hiring extra men at a time when they are hard to secure. But the advantage of hand over machine picking in the removal of the husks should not be overlooked.

The corn picker is still an experimental machine, and not until it has been perfected should the farmer purchase it.

HUSKERS AND SHREDDERS.

SIMPLE HUSKING DEVICES.

One of the earliest devices used for husking corn was the husking peg. Several patterns of this are in common use. There are also other aids to corn husking made in the form of gloves, with projecting points or pegs. Equipped with such a glove the man husks the ears by tearing off the husks and snapping the stems.

EARLIER MECHANICAL HUSKERS.

The first patent on a corn husker was issued in 1837. The machine comprises essentially a pair of roughened parallel rollers designed to tear off the husks.

In 1866 a New York concern began the manufacture of a husker having a single snapping roll made of hardwood. Another roller set

. stiff knives located just behind the hardwood roller cut the stalk short lengths. The ears of corn, as they were broken off by the ping roll, fell down upon the husking rolls. These were about 2 es in diameter and rotated toward each other. A small revolving t set with spikes and located directly above the line of contact of husking rolls caused the ears to revolve so as to present all of the ks to the action of the husking machine.

nother form of husker consisted of a snapping roll much the same hat described above and several husking rolls whose effectiveness ended upon the action of rubber aprons. These passed over each ler like belts over a pulley and tended to draw the husks in with m. Later, about 1880, Phillips and Jones added to this idea by tting on a pair of snapping rolls. These were the first really cessful huskers.

COMBINED HUSKERS AND SHREDDERS.

Thus far no machine had been produced designed to perform more an one operation on the stalks, except some of the unsuccessful and er experimental harvester types designed to pick and husk the



FIG. 18.—Skeleton of husker and shredder.

ars, as previously described. Between 1880 and 1890 a great deal of ttention was given to thrashing corn. This practice so battered the talk as to make every part of it available as a cattle food, putting it n more palatable form than the ordinary fodder cutters then in use. The repeated shortages and failures of the hay crop during the decade 880–1890, together with the results of attempts at thrashing corn, led o the invention of the combined husker and shredder, which takes he stalks with the ears on them, removes the ears, husks them, and repares the stalks for feeding. A combined husker and shredder atented by J. F. Hurd, of Minnesota, in 1890, application having een filed in 1887, is one of the earliest of the shredder type.

There are at this time many different makes of this machine in the market. They are of various designs and are frequently made so as to be fitted with exchangeable cutter and shredder heads. The general construction of all machines of this class is very much the same, however. Some are rather complicated in their construction, while others are very elementary. By referring to figure 18 the construction will be easily understood.

The stalks are first fed to the snapping rolls, where the ears are broken from them. The stalks are driven forward by the snapping rolls until they meet the shredder head, where they are cut to shreds by knives of special forms shown in figure 19. The shredded parts of the stalk fall upon a vibrating carrier whose motion is complemented by the action of arms. The shreds fall from this carrier into the blast from the fodder blower, which carries them up through the stacker.



FIG. 19.—Forms of shredder heads.

The ears which are broken from the stalks by the snapping rolls drop upon the husking rolls, where the husks are torn from them. The husked ears gradually descend along the inclined husking rolls until they finally fall upon an elevator which carries them to the bin or other place provided for them.

The husks fall upon a conveyor chain which drags them back to the fodder blower, where they join the shreds from the stalk. The loose grain falls from the vibrating carrier and husk conveyor upon a screen. As it falls it is met by a mild blast, which removes the dust from it.

ain is then collected in a trough or chute and is driven by ›f a screw conveyor to one side of the machine.

machine combines in its construction many elements used in machines, both huskers and fodder cutters. The snapping d husking pegs are both ideas n machines described in preparagraphs, while the shredads are not greatly different hose of the fodder cutters of design. The blower and g and carrying devices are uch like those of the thrasher. eding and safety devices are ırgely used as a protection the danger of having one's r arm caught in the mechan- ;. 20). Where the self-feeder l, a revolving band cutter is ›nly placed a little ahead of ıpping rolls.

superior convenience of hav- stalks bound into bundles is vident where these machines ed. In bundles the stalks keep straight and thus avoid the caused by having them come to the machine in a disordered on. There is also less danger of choking the machine.



FIG. 20.—Safety device for shredders.

ECONOMY OF CORN-HARVESTING MACHINERY.

HARVESTING WITH THE BINDER.

ıave found that the average life of the corn binder is 8.17 years cost $125. If a man has only 20 acres of corn to cut per year t for the use of the binder for each year would be $15.30. To ould be added $7.20 for interest, making the total annual cost machine $22.50. Other expenses for cutting the 20 acres of ccording to the previous averages derived, would be $9.20 for nd driver, $6.10 for twine, and $8.96 for shockers; or a total r cutting 20 acres of corn with a corn binder of $46.76, or $2.34 e. We have seen that the work may be done by hand for $1.50 e and that by hiring a neighbor's team and binder at 75 cents re the work may also be done for $1.50 per acre. We may nclude that a farmer who has only 20 acres of corn to cut per ınd does not intend to cut any for his neighbors, would lose by purchasing a corn binder.

If a farmer has 30 acres of corn to cut per year the annual cost of the machine, including interest, would be 75 cents per acre. It will require a cut of at least 80 acres per year before the farmer can properly estimate the cost per acre for the use of the machine to be 29 cents, as already given. It may, therefore, be concluded as a general proposition that unless this number of acres is available for cutting each year the investment in a corn binder is not profitable.

These estimates may not be exactly fair, because if the corn binder cuts but 20 acres per year the life of the machine with proper care would probably be considerably longer than eight years. There is no doubt that in general half the money spent for implements could be saved if they were given better care when in use and when not in use protected in an implement shed from wind, rain, sunshine, and farm animals. In general it is better not to invest in expensive implements unless there is sufficient work in sight to make them profitable.

PREPARING CORN FODDER.

The cost of preparing corn fodder by the various methods and with the different machines depends upon a great many variable factors. It depends upon the yield of corn per acre; upon the method of harvesting; upon the distance the fodder is to be hauled, the size and efficiency of the working force, the size, capacity, and speed of the machine, and the motive power used.[a]

We have already learned the cost of cutting the corn and putting it into shocks, and also that the average cost per bushel of husking corn from the shock in the fields is 5.3 cents per bushel, or at an average of 44 bushels per acre the cost will be $2.33 per acre. To this should be added about 35 cents per acre for hauling the ears to the crib, or a total of $2.68 per acre for husking the corn by hand, and this leaves the stover in the field. If the stalks are hauled to the feed lot it will involve an additional cost. When huskers and shredders are used for husking the corn and shredding the fodder the farmer will have to decide the question as to what method of doing the work he desires to employ. There are machines on the market which will husk but 100 bushels per day and there are those which will husk 1,000 bushels per day. The smaller ones are for the farmer who desires to do his own work.

With the general introduction of the gasoline engine on the farm a small individual outfit is very desirable. With such an outfit the farmer may do his work at his convenience, as he needs the corn and the fodder, and may also do some work for neighbors, which will aid in paying for the machine. It requires one man to feed; one to look er the engine, shredder, and the corn in the wagon; one man in the ›w to remove the fodder, one to unload the wagons, two teams, and e loader in the field. Six gallons of gasoline will supply the fuel r a ten-hour run. The computed cost would be:

---

[a] The question of methods and cost of preparing silage from corn is discussed in U. S. Dept. Agr., Farmers' Buls. 32 and 292, and need not be further considered here.

Cost of shredding corn.

Use of engine and shredder and repairs, per day	$1.00
Five men, at $1.50 each	7.50
Two teams, at $3 each	6.00
Power, 6 gallons of gasoline, at 15 cents per gallon	.90
Total cost per day	15.40

From experiments conducted by the author with the above outfit was found that the number of bushels husked per hour varied ›nsiderably with conditions, but that the average was 18 bushels, r 180 bushels per day. This, at the average yield of corn per acre reviously derived, would be equal to 4 acres per day. To husk 180 ushels by hand and put it in the crib would cost $10.96. This would ›ave a cost of $4.44 for 4 acres of corn fodder shredded and delivered ı the mow. The average yield of shredded fodder is 2 tons per acre. his would give a cost of 55 cents per ton for hauling the fodder from ıe field, shredding it, and placing it in the barn ready to feed. When ›rn has been husked in the field and the farmer wishes the fodder ıredded it costs him about $1.50 per acre for shredding the fodder y machine.

With large machines the work of husking and shredding corn is ›ually custom work. The owner of the machine furnishes the ıredder and engine, with two men, charging the farmer from 4 to 5 ›nts per bushel for this work. The farmer will have to furnish the ıel and the teams, as well as the balance of the help, to run the ıachine. These large machines require from 6 to 8 teams and 20 to 5 men for full operation. The large machine, while it does the ork quickly, has the disadvantage of requiring a large crew of men ıd teams and if anything goes wrong with either engine or shredder ıis force is idle at the expense of the farmer until the machine is ›paired.

From some investigations conducted by sending out letters of ıquiry from the Iowa Experiment Station to all parts of the State, ıe following results were obtained:

From the entire number of reports received the average cost of machines for shredng was $1.55 per acre; the cost of fuel was 31.4 cents; and the total cost of shredg, per acre, varied from $2.45 to $6.65. This is a wide range, but the conditions ıder which the shredding was done varied correspondingly according to the disnce hauled, yield of stover per acre, kind and size of machine used, and work quired in moving the outfit; also as to physical conditions of the fodder and cidents with machine.

The average cost of shredding 1,600 acres was found to be $4.41 per acre, and this believed to be a fair average under ordinary conditions.

The estimate of yield of corn per acre in the above case was 57.25 bushels, which is rather high, even for Iowa; the yield of fodder 2 tons per acre, and the cost of husking in the field 5 cents per bushel. At these figures the cost of shredding the fodder would be 77 cents per ton.

SUMMARY.

Summarizing the comparative returns per acre of husking corn from the field, of cutting and feeding from shock, and of cutting and shredding by the various methods, it is found that the net value of the crop is $17.93 for husking by hand and leaving the stalks standing in the field. This is obtained by adding to the net value of the corn 55 cents per acre for the stalks and subtracting the cost of husking by hand.

By allowing 25 cents per acre as the value of the fodder in field where a corn picker is used, and adding this to the net value of the corn and subtracting $1.80 per acre for picking with the machine, we derive the net value of the crop of $17.81 for this method of harvesting, which indicates a small loss per acre as a result of using the corn picker.

The net value of the crop by feeding the stalks whole ($23.18 for hand husking, $23.50 for harvesting with large machines, and $23.62 for small machines) is obtained by taking the total value of the corn and fodder and subtracting the costs of cutting and husking by hand, cutting with sled harvester and husking by hand, and cutting with corn shocker and husking by hand.

The net value of the crop by utilizing the fodder in the shredded form ($24.68 for hand harvesting, $25.45 for harvesting with large machines, and $26.45 with small machines) is obtained by assuming a greater value of shredded fodder over whole cornstalks of 33 per cent, adding this value of the fodder to the value of the corn and subtracting the various costs of cutting, husking, and shredding the corn by the various hand and machine methods.

CONCLUSIONS.

The farmer who would secure the full value of his corn crop should secure the fodder with as much care as he gives his clover hay, harvesting it at the proper period, and not allowing it to become ruined by rain or frost. By the use of the proper machinery for harvesting the corn crop, the farmer may considerably increase the net income from his crop over hand methods of harvesting the ears and wasting the stalks and still allow full price for the use of the different machines.

There is a limit beyond which it is not profitable for a farmer to invest in corn-harvesting machinery, and the amount of work to be done by the machine each year should be carefully considered before a purchase is made.

303

O

Issued September 17, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 304.

OWING AND CURING HOPS.

BY

W. W. STOCKBERGER,
Expert, Drug-Plant Investigations, Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

CONTENTS.

Page.
7
ential to hop growing 7
7
8
9
on from seed 9
ttings 9
g new varieties 10
cultivating 10
plant 10
e roots 11
g 11
12
13
trellis 14
trellis 16
aining 16
16
17
17
ick 17
tages of unripe hops 18
ripe hops 19
19
t of curing 19
y of drying 20
the curing process 23
drying 23
g 26
kilns 26
stove kiln 27
ir-blast kiln 29
t in the cooler 31
33
l of crop 36
37

P. I.—295.

GROWING AND CURING HOPS.

INTRODUCTION.

In keeping with the great progress made in agriculture within recent ears the methods employed in hop production have not remained nchanged. Nevertheless certain practical principles of great impor- ınce to successful hop growing merit a much wider consideration nd use than they now enjoy. These will be discussed in the follow- ıg pages, in which is also presented a brief general outline of hop ulture.

It is manifestly impossible to give a detailed account of methods f hop growing which would apply in all sections of the United tates. The peculiar conditions of soil, climate, and location influ- nce the prevailing methods of culture as well as the varieties grown nd render it necessary for the practical grower to adopt those nethods which, according to his experience, are best suited to his onditions.

CONDITIONS ESSENTIAL TO HOP GROWING.

CLIMATE.

The hop plant can be grown generally throughout the United tates, but at present its commercial production is practically stricted to areas situated in the States of Oregon, California, New ork, and Washington. Small quantities are raised in Wisconsin, aho, Massachusetts, Pennsylvania, Michigan, Vermont, Kentucky, d Ohio. The accompanying map (fig. 1) indicates the distribu- n of the hop-growing regions in the United States and shows aphically how the industry has become sharply localized in districts ich furnish the most favorable conditions. Long and severe win- s frequently kill out many of the plants, and continued damp or ggy weather is usually followed by severe attacks of lice or mold.

While from the map it appears that hops are grown under very fferent climatic conditions, they are produced most successfully in e milder regions, where abundant early rainfall is followed by warm dry weather as the crop approaches maturity. The accompanying chart (fig. 2) shows the average monthly rainfall in the chief hop-raising sections of the United States. In the Yakima Valley, Washington, where the rainfall is very scanty, irrigation is necessary. The hop plant readily adapts itself to very different conditions of rainfall, but when the harvest months—August and September—are accompanied by much rainfall the crop frequently suffers heavy damage from lice and mold.



FIG. 1. Map showing the hop-producing areas of the United States.

SOIL.

The selection of the best soil on which to grow the hop plant involves the consideration of several factors, depending on the peculiarities of the plant itself and the physical conditions of the region in which the land lies. In general, rich alluvial lands or deep sandy or gravelly loams are preferred for hop raising. The soil with a high percentage of sand is readilly tillable, while the cultivation of a stiff soil is difficult and expensive. Owing to variations in the rainfall, amount of sunshine, and force of the prevailing winds, land suitable for hop culture in one region would be entirely unsuitable if located in another. Since the roots of the hop plant penetrate the earth for a distance of many feet, a well-drained subsoil is essential. Especial attention must be given to the depth, fertility, drainage, and fineness of the soil. Heavy wet soils are avoided and stiff clayey soils are in general disfavor.

PROPAGATION.

PROPAGATION FROM SEED.

Hop plants may be raised from the seeds, but this method is sel- m employed, since by using cuttings strong plants are more easily d quickly secured. Moreover, seedlings have a tendency to vary eatly, both as to the time of maturing the hops and the quality of e product. Yards planted with seedlings usually show little uni- rmity in the variety of hops produced and in the time of ripening. eedlings will not produce hops the first year, and only a small yield ay be expected the second year.

USE OF CUTTINGS.

The simplest method of growing hop vines is from root cuttings, lso called "roots" or "sets." In some localities roots that have een in the nursery for one year are called "sets." The numerous



G. 2.—Chart showing rainfall in the principal hop-growing regions of the United States. The chart hows the average rainfall during each month in the year for the period of years indicated in the pace below. The totals given are average totals for the years indicated.

urface runners sent out by the hop plant are removed when the lants are pruned in the spring, and these, cut into pieces each bear- ng at least two sets of "eyes" or buds, are used to produce new lants.

In some sections of the Pacific coast a crop may be obtained from uttings planted in the spring, but in general a full crop is not har- ested until the second year.

The best cuttings are those taken from young plants, as they are nore resistant to disease and should be more productive than those rom old plants. All cuttings should be carefully inspected before planting and the diseased or damaged ones rejected.

ORIGINATING NEW VARIETIES.

The important subject of originating new varieties, as well as the no less promising one of improving existing varieties, merits the attention of every hop grower. The plants of every field are more or less variable. Some bear more heavily than others, some are richer in the desirable resins, and some will show other high-grade qualities. New varieties may be sought for among the plants in the nursery when these are grown from seed. After the seedlings have been transplanted to the yards and have matured a crop a careful examination at picking time may show that some have superior qualities. These should be suitably marked and cuttings made therefrom the next season for further selection. There is no good reason why this method if persisted in should not produce valuable new varieties. The favorable results secured with new and improved varieties of corn, wheat, grapes, and other crops may be duplicated in hop culture and suggest lines along which improvement may be made, particularly in regard to bettering the quality of the product.

The opportunity for producing improved sorts by selection of the stocks from which cuttings are taken offers a promising field for the progressive hop grower. Many growers who give much attention to improving the fertility of their fields and their methods of cultivation take their cuttings for planting from the nearest available supply without any consideration of the productiveness and other qualities of the plants from which the cuttings are taken. This has resulted in many yards in the loss of certain distinct varietal characteristics, and in almost every field mixed varieties and light and heavy producers occur indiscriminately.

A decided improvement in quality should follow the careful selection of cuttings with reference to productiveness, uniformity, disease resistance, and general adaptability to the cultural conditions in the region where they are to be grown. The selection should be made at picking time, when the hills containing plants of superior quality and productiveness can be staked, so that cuttings may be taken therefrom the next season.

PLANTING AND CULTIVATING.

TIME TO PLANT.

The time at which planting is done depends very largely on the local conditions existing where the crop is grown, but in general the best results are obtained by planting as soon as the soil can be worked into a fine mellow condition. In California planting should be done in January or February, although in some seasons planting as late as the 1st of May has yielded good results. In Oregon and Washington hops are planted in March or April, and in New York successful plantings have been made in April in favorable seasons.

SETTING THE ROOTS.

In California practically all new hops are now set out in rows at distance of 6½ to 7 feet apart each way. When set 6½ feet apart, ere will be 1,031 hills to the acre and 42¼ square feet of soil to the ants of each hill; when set 7 feet apart, there will be 898 hills per re and 49 square feet of soil to the plants of each hill. In Oregon d Washington, where two horses are used in cultivating, the disnce between rows is usually 8 feet, requiring but 680 plants per acre. The methods of cultivating the hop yards necessitate straight rows. ree and often four cuttings are set in each hill. Differences of inion and practice exist, and the number which it is advisable to t is in a measure dependent on the system of training employed d the cost of roots. The setting of a fourth root is a measure of ecaution against the possibility of loss by rotting or injury of one more of the cuttings after they are set out.

A good method of setting the roots is first to mark the center of ch hill by a small stake to which are attached the strings on which e vines are to run; then, about this stake to make three holes rming roughly the apices of an equilateral triangle with a side easuring about 6 inches. These holes are usually made with a ibble, but in very compact soils an iron crowbar is frequently used. he roots are then placed singly in these holes in an upright position, ith the buds pointing upward, at such a depth that they will be rom 1 inch (in Oregon) to 3 inches (in California) below the surace of the soil, which is then slightly tamped about them. Another nethod is to make a hole with a spade at the location of the hill nd to plant therein from one to four roots, according to their strength. This is the more rapid method but is less desirable, since the roots are crowded together and are more subject to decay.

The price of roots is quite variable, ranging from $1 per 1,000 when they are plentiful to from $8 to $10 per 1,000 in years when they are scarce.

CULTIVATING.

Thorough cultivation is important and should begin early and continue until the plants are well armed out. This is necessary not only to keep down the weeds, but also to prevent the topsoil from forming a crust and becoming hard, for when it is in this state the moisture of the undersoil rises to the surface and evaporates quickly. The frequent stirring of the topsoil to a depth of 2 or 3 inches will produce a layer of finely divided soil which conserves the moisture near the surface, where it is more readily reached by the young feeding roots which develop at about the time the hops go into the burr. If these small feeding roots are destroyed or seriously injured by late cultivation, growth will be checked and early ripening favored.

Careful growers agree that the young buds do not set so well if the feeding roots are seriously disturbed, and that the crop is shorter in consequence. Nevertheless, if the soil is becoming hard and the moisture is readily evaporating, it may be best, at least in dry sections, to cultivate and depend upon a second growth of the feeding roots for the proper maturing of the crop. The existing soil conditions must determine the advisability of cultivating after the appearance of the feeding roots.

PRUNING.

By the process of pruning, the excess shoots from the rootstock are removed and the formation of fewer but at the same time stronger vines is favored. The rootstock itself also is reduced to an acceptable form and suitable depth below the surface of the soil, and the formation of undesirable runners is retarded or suppressed. The working over of the ground incident to pruning also is an important part of cultivation.

Within certain limits determined by local conditions, the length of the growing period and the time of ripening may be influenced by the earliness or lateness of pruning. The general practice is to prune early in the spring, the exact time being determined by the season and the locality.

A common practice is to draw four or five furrows with a small plow on each side of the row, turning the earth away from the hills. The yard is then cross-plowed in a similar manner, leaving each hill a small undisturbed square. The earth is then hoed and grubbed away from the roots, and the superfluous roots and runners, together with an inch or two of the top of the root crown, are cut off with a sharp knife. After pruning, the hoe is used to pull the soil back upon the hill, covering the rootstock to a depth of 2 or 3 inches. Too much pruning by this method causes disease, and frequently uneven pruning causes the late coming out of the overpruned vines.

Another method which offers several advantages over the former is to prepare the ground by plowing as before, using a coulter on the plow in drawing the last two furrows. The hill is not dug into, but instead a sharp spade is used, with which each side of the hill is cut down on a slant from top to bottom, leaving the hill about 4 inches square at the top and 12 to 14 inches square at the bottom. With this method baking of the soil over the hill is avoided and the new shoots come through much more easily. The pruning is more even and the rootstock suffers less from wounds and bruises than by the former method.

TRELLISES.

Except in the hop-growing regions of New York, the use of hop oles (fig. 3) has been largely discontinued in those regions where iere is a scarcity of available timber, and even in heavily wooded ctions many growers have dispensed with them. This is not ue to the labor and expense of handling alone, but experience as proved that the advantages of growing hops on strings so ır surpass the growth on poles that it is only a question of time hen poles will be almost entirely abandoned. The hops are healthier on strings, more successfully sprayed, mature earlier, are usually richer and brighter, arm out lower, and are not so leafy; they do not wind-whip so readily, can be picked cleaner, and are much more easily torn down for picking. Also the hops can be picked without cutting the vine, a practice which is harmful, since it prevents the return of materials from the vine to the root of the hop, and, by causing a loss of food reserves to the stock, produces a weakening effect on the succeeding crop.



FIG. 3.—A field of hops growing on poles.

For a permanent yard some form of the wire trellis shown in fig. 4 will doubtless give the best satisfaction in most sections. In sections where timber is plentiful the first cost somewhat exceeds that of the pole system, but the saving in labor, the advantages afforded in spraying, and the heavier crop obtained by this method have uniformly reduced the cost of hop production where poles have been replaced by wire trellises.

The wire trellis is constructed in almost numberless ways, but these may all be included in two general classes or types—the high and the low trellis. The high trellis is most widely used, and upon it the greatest improvements have been made.



FIG. 4. Roadway between fields of hops, showing a fine growth of vines on high wire trellises.

THE HIGH TRELLIS.

The high-wire system consists essentially in setting posts at every sixth or seventh hill throughout the yard. Over the tops of these posts wires are stretched across the yard each way at right angles (fig. 5). Posts are also set at the ends of the intervening rows, between which wires are stretched over the rows. These wires are fastened to the cross wires, and strings led up to them from the hills support the vines.

For posts, which may be either split or sawed timber, suitable hard wood or creosoted pine is used. These posts are usually from 4 to 6 inches in diameter and 20 feet long. The end posts should not be less than 6 by 6 inches, but somewhat lighter timbers may be used for r supports. The posts are set from 1½ to 2 feet in the ground, erior ones upright, those in the outside rows inclining some- outward. At a distance of about 14 feet outward from the f each end post an anchor, made of a piece of timber 6 by 6 and 4 feet long, is buried at a depth of 4 to 6 feet, according tenacity of the soil. Anchors made from locust are preferred, e of the lasting quality of the wood. A strong guy wire is om the top of the post and fastened securely to the anchor; or ing wire may be run over the top of the end post and down to chor.

permit easier access to the field, posts are frequently placed at ds of alternate rows only. The string wires of the rows with- d posts are then either run over the end cross wire to the ground nchored or they are forked and fastened to the end posts on



FIG. 5.—Field of hops, showing details of the drop-wire trellis and method of picking.

side. For the principal or cross wires running across the field shortest way and fastened on the top of each post with heavy les, No. 0 annealed iron wire is used. These wires are keyed up and fastened securely to anchors at each end. For the other or ıg wires Nos. 6 to 8 annealed iron wires may be used. On the st improved or drop-wire trellis shown in figure 5 the string wires held in place underneath the cross wire by short S-hooks made of 2 wire. At picking time the string wires may be unhooked and down, thus bringing the hops within easy reach of the pickers. s trellis can usually be erected at a cost of from $80 to $90 an , and twine for supporting the vines necessitates an annual enditure of about $5 an acre.

In another successful form of this system an additional wire, known as the "breast wire," runs over each row below and parallel to the string wire at a height of about 6 feet from the ground. The strings rise vertically to the breast wire; then they are taken on the slope to the top or string wire, which is above the next row of hills. The angle of the sloping string is affected by the distance between the rows as well as by the height of the breast wire. The steeper the slope the better the growth of the vine. At half slope hand training will be necessary, but a flat slope gives better exposure to the sun and increases productiveness.

THE LOW TRELLIS.

The low form of trellis appears in several modifications. In one form poles about 8 feet long are set at each hill. Over the tops of the poles wires are run the full length of the yard each way, crossing at right angles. The vines are led up the poles or stakes and then find support on the wires. In many cases stout twine is used instead of wire, and in some instances the poles are set at every third hill.

Except in situations swept by strong winds, the high trellis is much more satisfactory. It is a permanent structure which gives easy access for teams to every part of the yard. The hops receive more uniform exposure to light and air and are in consequence better developed. Cultivation is not interfered with by drooping arms so much as in the low-trellis system. The hops can be readily sprayed even at picking time, when the worst attacks of lice are likely to occur. Since a hop vine will not follow a horizontal support, when it reaches the wire or string of the low trellis it must be trained by hand, thus materially increasing the cost of cultivation.

SYSTEMS OF TRAINING.

STRINGING.

Where the high-wire trellis is employed, cotton cord is used to form supports for the vines until they reach the wires. The string consists of two portions knotted together; one, a cord 4 feet long having a breaking strain of 80 pounds, is attached to the wire, and the other, a cord 15 feet long having a breaking strain of 20 pounds, is tied to a small stake set in the hill. The smaller cord is strong enough to support the vine until it reaches the heavier cord at the top. Good hemp is often used for the top string instead of cotton cord. The string may be fastened to the wires by means of a special knot-tying device attached to the end of a long pole, but the plan pursued in the trellis fields where the drop-wire system is used is simply to unhook and lower the string wire (fig. 5), to which the strings may then be attached by the workmen while standing on the ground. The strings, which are cut to the desired lengths and notted in advance, are fastened to the wires about 20 inches from point on the wire directly over the center of each hill. Usually ut two strings are used for each hill, and when all have been fasened to the wire it is again hooked up in place on the cross wires.

Another plan is to use a "trellis wagon," on which is a platform f such elevation that the workmen thereon may move about freely eneath the wires while attaching the strings. The wagon follows he string wire across the field. Two or three men on the wagon will put the strings on two wires as fast as the team can walk. Four men following the wagon can fasten the ends of the strings to small stakes set in the ground at each hill.

In the pole yards of New York a loop in one end of the string is passed over the top of the pole by means of a forked stick, and then drawn taut. The remaining end is then fastened to the adjacent pole in the next row about 5 feet from the ground. Frequently another string is fastened from pole to pole at the same distance above ground.

TRAINING.

When the young vines are about 2 feet long training is begun. Usually the four runners most closely approaching in length the average of the field are selected from each hill and the remainder are cut off. In case of an uneven stand it may be well to cut off the whole field and wait for the second set of runners. However, vines which may be inferior at first sometimes develop a vigorous growth after they have reached a length of 4 or 5 feet. As a general rule, in all light producing sections it is advisable to train the first runners; in heavy producing sections the second runners should be chosen. Two runners are usually trained to each string, care being taken to twine them from left to right about the string.

In the New York yards many farmers train seven vines up each pole, three for the long string and two each for the other string and the pole.

PICKING.

TIME TO PICK.

The time when hops should be picked varies with the locality, the season, and the variety cultivated. When the acreage is large there is a tendency to start picking before the crop is fully mature, as otherwise a portion may be lost through becoming overripe. Also a great consideration with many growers is the early securing of pickers. To this end it is customary in some sections to plant an early-bearing variety, e. g., Fuggles, which ripens from a week to ten days earlier than the other standard varieties and enables the grower to begin picking so much earlier.

A second consideration is the capacity of the drying plant to handle the crop as fast as harvested. If the acreage is large and the crop heavy, the facilities for handling and drying the hops will be taxed to their utmost, and if more hops are picked than can be put upon the kilns and dried without delay they undergo heating and are thereby seriously damaged in quality or lost entirely. Because of inadequate facilities, therefore, growers frequently begin picking before the hops are ripe and continue picking after they have passed what is recognized as the most suitable stage for harvesting.

A third consideration, which is recognized by all progressive growers, is the effect of the picking time upon the quality of the product. The development of the essential oil, the desirable soft resins, and other valuable constituents reaches its height about the time the hops become fully ripe, in which condition they are generally regarded as possessing the finest flavor.

From the standpoint of the consumer the time of picking is a matter of great interest, and it should be also to every grower, as a much higher quality of hops would result from picking at the proper time. However, for reasons previously mentioned it is often very difficult to secure pickers when the crop is just ripe. In addition to the difficulties just mentioned, the several parts of the field rarely ripen exactly together; often when a field is practically level slight variation in quality of soil or moisture content will result in unevenness in ripening, and while it is customary in picking to work around and through the field, choosing first the ripe portions, it is rarely possible to pick all of the crop at the most desirable degree of ripeness.

While growers recognize in a general way the importance of a proper picking time, the disadvantages arising from a disregard of this time are not appreciated by all. There are several important objections to improperly picked hops which reduce their market value.

DISADVANTAGES OF UNRIPE HOPS.

Unripe hops contain more water in proportion to their weight of dry substance than those which are ripe; consequently in drying the "conversion" is not so high; that is, the ratio of the dry hops to the weight of green hops put upon the kiln is smaller when the hops are unripe. Unripe hops are also more difficult to dry on the kiln, probably because of their higher water content and tendency to pack together as soon as wilted, and also they do not keep so well when stored. Since the lupulin in unripe hops has not reached its full development, there is an absolute loss of weight by picking in this condition. The aroma is not so well developed and the amount of resins is smaller in the unripe hop. Not only is there a loss of weight due to too early picking, but practically all of the desirable qualities n which the value of the hop depends are also in large measure ished.

TESTS FOR RIPE HOPS.

neans of certain practical tests the degrees of ripeness and ity for picking of the hop may be readily determined. (1) robiles or cones, which are bright green in color in the veg- state, change gradually to a bright yellowish green as they ch ripeness. This is not always an exact test, as the color is hat dependent upon the soil and some other factors. Some ave a greenish color when they are ripe. Sometimes in fields d by the wild morning-glory a yellowing of the cones may which is not due to ripening, but rather indicates an unhealthy ion in the plants themselves. (2) Immature hops are soft and e and have no resiliency or elasticity. As they ripen, however, become more and more elastic, and if slightly compressed en the fingers will, on being released, assume at once their orig- ondition. (3) When hops have a crisp feeling and give forth ling sound when crushed in the hand they are regarded as ripe. 'he so-called seeds of the hop are in reality fruits, the seed being d by a closely adhering pericarp, which, when the hop is ripe, on a dark purple color. At this time also the seeds fill out and e hard. (5) The bracts at the point of the cone close as ripen- rogresses, and the cones themselves feel sticky or greasy. (6) ture hops have little odor aside from the natural green or plant ntil they are near ripeness, when the characteristic lupulin odor es very marked. (7) As the hops approach maturity the upper e leaves change from light green to dark green, while those on ver part of the plant turn yellowish and drop off.

CURING.

THE OBJECT OF CURING.

primary object of curing hops is to reduce rapidly their mois- ontent to such a degree that they may be safely stored and their rties preserved. Hops must be dried soon after their removal the vines, as otherwise they undergo a process of oxidation or g which seriously injures their appearance as well as their , and other valuable qualities. According to the variety and gree of ripeness when gathered, freshly picked hops contain 75 per cent of moisture, but when in a dry state fit for storage rketing they should contain only from 10 to 14 per cent of re. Increased knowledge of the constituents and properties of as extended the idea of curing to include the production of a hich not only has a fine physical appearance, but which also ns the maximum amount of the desirable principles upon which rinsic value is based. The most important of these principles e tannin, found mostly in the bracts of the cone, the soft resins, the volatile oil, and the bitter principles which occur chiefly in the lupulin. Curing is all too frequently conducted with regard to the physical appearance alone, and the methods employed often injure the quality of the hop through their harmful effects on the oil, lupulin, etc.

THE THEORY OF DRYING.

The removal of moisture from hops constitutes drying. In the atmosphere this is ordinarily accomplished by evaporation, a process which is dependent upon the ability of the air surrounding the drying hops to carry off the surface moisture in a vaporized state. The amount of moisture in the form of vapor which the air can take up depends upon its dryness, since there is a maximum amount of vapor which the air can contain. When this maximum is reached the air is saturated or at the dew point and will take up no more moisture. In order that drying may proceed the saturated air must be constantly replaced by drier air, and a brisk artificial circulation therefore hastens the process.

The ability of the air to take up moisture varies with its temperature, and an immediate effect of heat on the atmosphere is to increase its capacity to absorb aqueous vapor; for example, it has been determined that the moisture in 10,000 cubic feet of air saturated with aqueous vapor at 62° F. weighs 8.81 pounds. On raising the temperature of the air to 82° F. the 10,000 cubic feet of air can take up 7.86 pounds additional moisture; and by increasing the temperature to 122° F. 42.61 pounds additional can be carried. If, however, the air at 62° F. is only half saturated, 10,000 cubic feet will contain but 4.4 pounds of moisture; then raising the temperature to 82° F. will enable the 10,000 cubic feet to take up 12.27 pounds additional, and increasing the temperature to 122° F. admits of 47 pounds additional being carried.

The volume of air necessary to effect drying within a given time is dependent upon its temperature. Because of its greater moisture-carrying power a small volume of air at a high temperature will absorb and carry away an amount of vapor the removal of which would require a relatively large volume of air at a low temperature. If half-saturated air heated to 162° F. in passing over a moist surface at the rate of 10,000 cubic feet per minute removed therefrom in that time 130 pounds of moisture, it would require about twenty-three minutes to carry away 3,000 pounds of moisture. If, now, the same air were cooled to 82° F., 10,000 cubic feet per minute could remove about 12 pounds, and nearly four and one-half hours would be required to remove 3,000 pounds of moisture. To carry away the moisture in the same time as the air at 162° F. a volume of about 108,000 cubic feet per minute would be required.

tice it has been found that the air driven through a mass of
not become fully saturated with moisture, and only during
stages of drying does the amount of moisture actually
approach the quantity which would be removed if the air
s full capacity. At the temperature commonly used in dry-
efore, a much larger volume of air must be provided to
given amount of moisture than apparently would be re-
om a consideration of the figures given.
ain degree of heat is always advantageous in drying hops
of the conditions under which the moisture in them occurs.
f this moisture is free water and is the first to be exhausted
g. The rest forms a part of the sap and tissues, and its
affects the physical condition of the drying hops. Heat, by
he temperature of the tissues and cell sap, promotes the pas-
water to the surface, where it may be removed by vaporiza-
n artificial supply of heat is also necessary to replace that
n the hops by the process of vaporization; otherwise the
ure of the moisture held in the cells will remain so low that
t move readily to the surface and drying will be retarded.
ying hops good results, however, are not obtained merely
lying a high degree of heat below the floor of the kiln.
ps are piled on the floor at a depth of from 14 to 30 inches,
m an extremely poor conductor of heat. Not only are the
mselves a poor conductor, but the air heavy with aqueous
ling the spaces between the hops offers much resistance to
sfer of heat. It thus happens that when heat is applied
oor of hops the moisture of the lower layers is driven off,
n contact with them becomes saturated, and, rising quickly,
to contact with cooler layers. Here the saturated air is
vith the result that its moisture is condensed and deposited
pper layers of hops until they become wet and soaked. The
us application of heat thus results in the lower layers
dried out and overheated, while the heat gradually working
through the wet layers of hops subjects them to a harmful
process. The difficulty is frequently increased by the prac-
rning the hops, as in this way the overdried layers from the
re brought to the surface and again steamed and dried.
vident that a rapid and continuous removal of moisture is
, and to accomplish this draft and ventilation are necessary.
draft is necessary to insure a rapid movement of the heated
gh the layers of hops, since by rapid replacement of the air
t with the moist hops time is not afforded to approximate
of saturation; hence the air can undergo quite a degree of
n the upper layers without reaching the dew point and depos-

iting its moisture. Top ventilation is necessary to remove the vapor-laden atmosphere from above the hops; otherwise the point of saturation would be quickly reached and the moisture deposited on the sides of the kiln and the hops themselves. Ventilation is closely connected with draft and is dependent upon it. Conditions which secure good natural draft usually provide sufficient ventilation.

Draft and ventilation, as well as drying itself, are very dependent on the temperature and humidity of the atmosphere. Draft or a definite upward movement of the air in a kiln occurs when heat is applied at its base. The cold air outside the kiln being heavier than the warm air within constantly tends to establish an equilibrium of pressure by flowing down to the base of the heated kiln. As a direct consequence the heated air is forced upward, and the cold air taking its place is in turn heated and will follow the same course. A continuous circulation is thus established, its velocity and volume depending on the difference in density of the outside air and the air within the kiln.

The changes of temperature in the external atmosphere have very marked influence on draft. In hop drying it is observed that the best draft is usually secured about 2 or 3 o'clock in the morning. This is about the time when the greatest temperature differences exist between the outside and inside air, with a corresponding difference in pressure resulting in increased draft. This advantage, however, is largely offset by the great increase of humidity in the atmosphere at night. In the daytime when the air temperature is high great difficulty frequently arises in securing a draft without at the same time overheating the hops. Usually a difference of about 50° F. between the temperature under the kiln floor and that over the top of the kiln is necessary in California to cause a sufficient pressure to force the air through the hops. In Oregon a difference of 30° F. is generally sufficient to accomplish the same result, the reason for the difference being that the hops are not laid so deep on the floor and twenty to twenty-four hours are used in drying as against ten to twelve hours in some districts in California. Assuming that a difference in temperature between the atmosphere and the air in the kiln of from 30° to 50° F. is necessary to cause a draft through the hops, it is apparent that the greatest care must be used to avoid damage to the hops through overheating.

Many of the difficulties attendant on the use of natural draft have been overcome by recourse to forced draft. By this means a large volume of air is driven through the hops, instantly setting up a good circulation of air and rapidly carrying off the moisture, so that the hops do not undergo the long sweating and steaming process which is a necessary accompaniment of the use of a natural draft. Drying

ossible also at a much lower temperature, and this method presents
ny other advantages, among which is absolute control of a low,
en temperature, giving an increase of soft resins, flavor, aroma, and
ight.

NATURE OF THE CURING PROCESS.

When the hops are placed upon the floor of the kiln the cells which
mpose their tissues are still alive. Proper curing consists in bring-
g about the death of these cells through the gradual withdrawal
water from them at a moderate temperature. Within each cell
e many chemical substances which remain separated so long as the
ll is alive, but which are thrown out of solution by the loss of water
om the cell and left in a form in which they are very readily
luble. If the removal of water does not proceed steadily, or if the
pors are allowed to settle back, moisture condenses on the hops and
readily reabsorbed and, coming in contact with the readily soluble
bstances, dissolves them. In this condition these substances cause
ackening or discoloration and the hops are injured in other ways.

Death of the cells may be caused without much water loss by
dden exposure to high temperature. In such a case the chemical
bstances no longer remain separated, but flow together and form
ew compounds with resultant changes in color, aroma, and other
esirable qualities. The cells may sustain a considerable water loss
efore they are killed, provided the temperature is kept below a cer-
ain point (about 110° F.). As soon as the death of the cell occurs
nd the flowing together of its compounds begins, drying should be
forced somewhat more rapidly, in order to reduce the amount of water
present as fast as possible, but even in this stage of drying the temperature can probably not long exceed 140° F. without injury to the
quality.

PRACTICAL DRYING.

The most important and at the same time the most difficult part of
hop production is proper drying. No other factor affects the quality,
appearance, and market value as much as the manner in which the
hops are handled during the curing process.

In the drying process three factors are of primary importance.
These are (1) degree of temperature used; (2) length of time of
drying; (3) volume of air passing through the hops. Also, in drying
t a very low temperature the humidity of the air is an important
actor. Only the first two of the factors mentioned have been gen-
rally recognized, and the high temperatures used at present are the
sult of shortening the time of drying. It is possible to diminish
e temperature materially without lengthening the time of drying
forcing through the hops a large volume of air at low temperature.

The first care is to properly lay the hops on the drying floor. They should be spread out evenly and loosely to a depth of 14 to 24 inches, depending upon the ripeness. In an uneven floor the heat will break through first in the thinner places, which quickly become dry, while the thicker portions remain damp. If the hops are trampled or otherwise packed together on the floor the heat will not readily pass through them and drying is rendered uneven. Some practical growers set a stout wire screen of about 5-inch mesh at the desired height above the floor and the hops emptied from the bags upon this fall lightly and evenly to the floor beneath. The top is then carefully leveled with a rake.

As soon as the floor is laid the fires are started and the heat is gradually brought up to the desired point. In from three to five hours the hops will have become heated throughout and sufficient moisture will be driven off so that the hot air will readily pass through them. Until this point is reached the temperature must be closely watched, as too rapid firing at first will cause the under layers to scorch. In sections where drying is accomplished in ten to twelve hours a very common practice is to turn the hops with a wooden barley fork when the lower layers are dry enough to rattle when stirred. This should be done only when absolutely necessary, as turning breaks and shatters the hops and a portion of the lupulin is lost. Since the hops can not be turned evenly this practice hinders uniform drying.

During the course of drying sufficient ventilation must be provided to carry off the moisture without at the same time cooling the sides of the kiln and the top of the hops enough to cause the moisture to be deposited. Warming the air and the sides of the kiln above the hops materially aids drying. In the more northerly hop regions the most successful kilns are ceiled to the top, thus better retaining the heat.

The almost universal failure to recognize the harmful effects of high temperature in drying has caused wide diversity in practice. Temperatures of over 200° F. are not uncommon. That this is far too high has been shown by experiments made in the field with hops cured on various kilns at different temperatures. Aside from ruining the flavor by overdrying or scorching, there is a distinct loss of valuable essential principles by drying at high temperatures. The volatile oil, to which the aroma is largely due, is partially evaporated and the lupulin is rendered inferior, since the amount of the desirable soft resins becomes proportionately less as the drying temperature is increased. The best temperature for drying is yet to be determined, but every consideration indicates that it should be much lower than that commonly employed, probably between 100° and 140° F. Pracical experience has shown that good drying may be accomplished ith a temperature of 110° F., and the general trend of opinion is ward the use of the lower temperatures in drying. No fixed tem- erature, however, can be assigned as the most suitable for drying, ecause a degree of heat which at one stage of drying would probably e detrimental, at another would have no injurious effects. In taking e temperature care should be used to see that the thermometer is laced where the heat on the hops is greatest. This point has been ound to be just below the drying floor. During the first part of the rying a thermometer below the cloth of the drying floor will register igher than one placed on the floor at the bottom of the hops, and ne placed just above the hops will register 30° to 40° lower until drying is perhaps half finished or until the heat breaks through the hops. During this period of drying the heat is concentrated on the lower layers of hops, and here the greatest care is necessary to avoid injury. When the heat begins to break through the hops the upper thermometer will show a rapid rise of temperature, while the one below the floor will show a decline. From this point on to the end of the drying the two thermometers will show approximately the same degree of temperature.

As already stated, hops are frequently cured in from ten to twelve hours, but, other conditions being equal, a higher temperature must be used than when the time is extended to eighteen or twenty hours. The advantages of slower curing or curing at a lower temperature should be universally understood by hop growers. Even a moderately high temperature continued too long will damage the quality of the hops, the same as too high a temperature. In order that the hops may be dried at as low a temperature as can be made to do the work a strong draft is necessary during the drying to continuously carry off the moisture from the hops. There is no doubt that the principle of the air-blast kiln at present most satisfactorily meets these requirements.

No definite rule has yet been given for determining when hops are sufficiently dried. The condition in which they may be safely removed from the kilns can at present be told only by experience. The amount of drying will vary from day to day, being dependent upon weather conditions and the ripeness of the hops. In general, drying should continue until nearly all the stems or cores are shriveled, but are still soft and pliable. If overdried, the stems crumble and break readily, and the lupulin loses its bright, clear yellow appearance and turns brown. If hops are taken off the kilns slack or underdried they are very apt to heat, which turns the lupulin brown, and to develop a sour musty smell which makes them undesirable. If they are high dried or overdried they will break badly and become chaffy, and they also develop a burnt, peanutty odor.

The thin leaflike portions of the hop usually become dry enough to break readily by the time the stems are dried sufficiently to make safe the removal of the hops from the kiln. This condition may be remedied by closing the ventilators half an hour before the drying is finished. This will also somewhat restore hops that have been overdried, as the further escape of moisture from the kilns is prevented, which then tends to equalize in the hops, soon softening and toughening them. Many careful dryers make a regular practice of gradually closing the ventilators as drying proceeds, and finish the kiln with them tightly closed. The same result may be indifferently accomplished by opening all the doors of the kiln and letting the hops cool for about an hour, as by this process they absorb moisture from the air and become less brittle.

SULPHURING.

The practice of sulphuring hops, which is now almost universal, is a response to the demands of the market chiefly for the pale yellowish green grades. The use of sulphur not only gives the hops the desirable yellow color, but makes them more uniform in appearance, thus increasing their salability. Many dealers are guided more by color than by other qualities, and such dealers have been known to rate unsulphured hops as inferior, while sulphured hops from the same field were classed as choice.

The use of sulphur improves the color by bleaching, injures the micro-organisms present, thus probably improving the keeping quality, and, according to a widespread belief, accelerates the drying. The sulphur is usually burned beneath the kiln floor at the commencement of drying. The usual practice is to use from 2 to 6 pounds of sulphur for each 100 pounds of undried hops. The action of the sulphur is most energetic while the hops are yet fresh and damp. Only refined sulphur of guaranteed purity should be used, as the crude sort usually contains impurities which may injure the quality of the hops. The best results are secured with what is known commercially as rock sulphur. Roll sulphur differs from this only in the form in which it is cast and has no greater bleaching power.

TYPES OF KILNS.

With respect to construction, there are many kinds of kilns. Whatever kind of structure is used for drying hops certain features are essential, and these may be comprehended in the description of a typical kiln. As regards methods of operation in the United States two general types must be recognized. In the stove kiln the hops are heated by a stove or furnace placed under the floor; in the air-blast kiln a current of heated air from the outside is forced in by a fan.

The. Stove Kiln.

This type of hop drier consists essentially of a furnace room heated by a large stove or furnace and a drying room immediately overhead, into which the heated air from the furnace passes through cracks in the floor. The stove may be situated in the center of the furnace room, but is commonly placed at one side and so arranged that the firing can be done from the outside. A very successful type of kiln is shown in figures 6, 7, 8, and 9. This combines the features of the simple furnace room with those of a style of kiln used on the Pacific coast and known as the " double-hopper " kiln. The building is a well-sided frame 36 feet square and measures 32 feet to the plate, from which the four-sided roof is carried up at one-half or two-thirds pitch. At the top an opening 8 feet square is left, over which is built the ventilator or cupola to a height of 12 feet. Two, or sometimes four, shutters, hinged to the sides of the cupola at the top, are fitted with ropes and pulleys, by means of which they may be opened and closed. Six feet below the plate, or 26 feet from the ground, are placed the joists which support the drying floor, which is composed of slats 1 to 2 inches wide carefully spaced at the thickness of one slat apart (fig. 7). Over the slats is



FIG. 6.—Ground-floor plan of stove kiln.



FIG. 7.—Plan of second or drying floor of stove kiln.

stretched a kiln cloth or carpet of 8 to 10 ounce jute, similar in quality to the ordinary barley sack. From the drying floor to the plate the inner wall of the kiln is ceiled in order to retain the heat. In humid regions the best results are secured when the ceiling is carried up on the rafters nearly to the top of the roof. In the center of the room below the drying floor is a second inclosure 18 feet square, made of 2 by 4 inch studding, 10 feet high, and lathed and plastered on the outside to within 10 inches of the floor, leaving next the ground an open space for the admission of air. The draft is largely controlled by means of large doors opening to the outside from the main room. In the type of kiln without the hopper air is admitted through openings in the outside walls close to the ground. These draft openings are provided with shutters which in case of a strong wind are closed on the windward side to prevent uneven drying.



FIG. 8.—Sectional elevation of stove kiln.



FIG. 9.—Perspective of stove kiln the plans of which are shown in figures 6, 7, and 8.

From the top of the studding used in making the wall of the inner inclosure, timbers run on a slant to the outside walls, which they join just below the drying floor. These timbers are likewise lathed and plastered, forming as it were a huge hopper below the drying floor (fig. 8). The furnace is set in one side of this inner room, and the large pipe therefrom makes a circuit of the hopper at about 10 feet from the ground and is then led to the imney outside. This kiln may be single or double, as shown in fig- es 6, 7, and 8. The size may be reduced to suit the needs of the user, d brick or stone may sometimes be used with advantage in its con- uction. The drying floor, however, should never be less than 20 et above the ground, on account of the danger of scorching the hops. The superior advantages claimed for this kiln are the even distribu- on of the heated air to the drying floor, the strong draft induced causing all the air to pass in through the small furnace room here it is highly heated, and in the distance of the drying floor from e furnace, whereby the danger of scorching the hops by direct radia- on is largely diminished. In this kiln, also, the objections to the al hopper form are largely overcome, since the lower portion of the oodwork does not come so close to the stove as to be in danger of tching fire.

On a level with the drying floor at one side of the kiln a platform constructed, from which the green hops are transferred to the dry- g floor. When possible the kiln is erected on sloping ground, so at the hops may be unloaded thereon from wagons, which approach e kiln on a driveway formed by a slight embankment. Inclined ooden driveways, as shown in figure 14, are sometimes used, but the ore common practice is to bring the hops from wagons on the round to the platform by means of an elevator (fig. 9).

At one side of the drying floor doors sliding vertically permit the ops to be readily shoved off into the hop car, which is brought longside the kiln with its top just below the level of the floor fig. 8).

The "double-hopper" kiln has failed to realize the advantages oped for on its introduction some years ago. It is not only very able to destruction by fire, but the lower hopper limits too much e air space below the hops and does not give the necessary draft t the temperatures most suitable for curing.

The Air-blast Kiln.

The desirability of maintaining a strong draft through the hops hile drying on the kiln has led to the employment of various arti- cial means for this purpose. A device for producing a forced draft hich has long been used in England, and frequently tried in the nited States, but with poor success, is an exhaust fan placed in the entilating shaft of the kiln. In an improved method of drying with forced draft which has been used successfully on the Pacific coast uring the last few years a blast fan is used to drive the air through e hops from below. The main features of this method are illus- ated in the air-blast kilns of the Pacific coast shown in figures 10, l, 12, and 13.

These kilns, constructed of wood, of corrugated iron, or of concrete blocks, are from 30 to 36 feet square, and for economy and convenience three or more are usually operated in series under a single roof (fig. 13). Two drying floors are provided in each kiln (fig. 12), the first 9 feet from the ground and the second 7 feet above the first. The lower floors are generally made of slats and covered with a kiln cloth in the usual manner (fig. 11), but the upper floor is made of removable wire-covered sections. The distance from the ground to the plate is 18 feet and to the comb of the roof 30 feet. A low ventilator, fitted with shutters at the sides, terminates the roof and runs the entire length of the building. The draft in these kilns is produced by a blast fan from 7 to 9 feet in diameter, driven by a steam engine at a rate of speed high enough to produce a slight pressure in the air-tight room below the hops. As soon as the fan is started the pressure is established and the air quickly passes through the hops and escapes at the ventilators in the roof.



FIG. 10.—First-floor plan of air-blast kiln.



FIG. 11. Plan of second or drying floor of air-blast kiln.

The air intake is outside the kiln, and just before the air enters the fan it is drawn through a sectional steam heater, constructed of 1-inch iron pipes, whereby its temperature may be maintained constant at any desired point. A large pipe, about 5 feet in diameter, conveys the air into the kilns (figs. 10 and 12). At the center of each kiln the air is delivered downward through a curved outlet of the main pipe, 34 inches in diameter, and fitted with a damper by means of which the amount of air admitted to the individual kiln is controlled. Below each outlet pipe is a saucer-shaped concrete-lined depression in the kiln floor which, receiving the inrushing air, deflects and distributes it evenly to the drying hops above.

In a kiln 36 by 36 feet, when the hops are laid 15 inches deep, the reen weight is estimated at 7,500 pounds. The conversion of the ops—that is, the number of pounds when green required to produce pound when dry—varies from 3½ to 4. This means, therefore, at in drying a floor of hops of the dimensions just given, from ,000 to 5,500 pounds of moisture must be carried off. To accomlish this speedily a very large volume of air is necessary if the mperature is kept elow the point here the quality of e hops is affected. he superiority of his type of kiln hen equipped with blast fan of suffient size lies in the possibility of driving through the hops a large olume of air at a low temperature, thus carrying away the moisture d perfectly drying the hops, while overheating, overdrying, and orching are avoided.



FIG. 12.—Sectional elevation of air-blast kiln.

The ordinary stove kiln may be readily converted into an air-blast ln by the installation of blowers and devices for heating the air. igure 14 shows a group of six stove kilns so modified at an expense uch less than that necessary for the construction of an entirely ew plant.



FIG. 13.—Perspective of air-blast kiln the plans of which are shown in figures 10, 11, and 12.

TREATMENT IN THE COOLER.

A very important part of the successful curing of hops is the andling which they receive in the cooling or storage room. The uilding used for this purpose (fig. 15) is now generally detached rom the drying kiln and placed at a distance of 100 to 200 feet as safeguard against fire. Figure 16 shows a sectional elevation of cooling house with the two storage floors above the baling floor.

If necessary the lower floor may also be used for storage, but this necessitates elevating the hops to the second floor for baling. The building should be of tight construction, especially in humid regions.



FIG. 14.—Group of six stove kilns converted into an air-blast plant.

to prevent the loose hops from absorbing too much moisture from the air.

The kiln is connected with the cooler by an elevated tramway.



FIG. 15. Elevation of cooling house, showing position of baling press.

over which is run a large car carrying the freshly dried hops. The sides of the car are hinged so as to swing open from the sloping bottom, allowing the hops to be readily removed with little handling.

The hops are spread out on the floor of the cooler, where they lose their heat and absorb some moisture from the air. The stems are usually not so dry as the other parts of the hop, and during the sweating process the moisture is equalized and the hops become tough and pliable. The best-informed growers recognize that other important changes occur during the sweating process which materially affect the quality of the product. A finer and more pleasing aroma, as well as a better physical appearance, is developed during sweating, provided the process is carefully watched and the hops prevented from becoming too moist or heated. Under ordinary circumstances these two evils are avoided by loosening up the hops and turning them over with forks or by moving them to another part of the cooler. If taken in time, slack hops may be brought out in this way and practically freed from their sour, musty smell. If the hops in the cooler become too moist, their condition may be improved by dumping over them a car full of hot dry hops just from the kiln. Likewise hops that have become too dry in the cooler may be helped by mixing with them hops taken from the kiln a little before they are properly dry. Great care and good judgment are necessary for proper handling in the cooler, and more attention given to this phase of hop curing will certainly result in an improved quality of product.



FIG. 16.—Sectional elevation of cooling house.

BALING.

After the hops have been in the cooler for a week or ten days they will have passed through a sweating process and be in good condition to bale. Hops may be left in bulk for many weeks and suffer little injury if the storehouse is tightly closed to exclude atmospheric moisture. When suitable for baling, hops contain just enough moisture to make them pliable and to prevent their breaking when compressed. If too much moisture is present in the bale, the hops will soon heat and turn black, being damaged thereby both in color and aroma, or they may be ruined entirely.

For pressing the hops into bales several styles of hop baler are used. In some sections where only a small crop is produced a hand-lever press is used. The form of this style of press, shown in figure 17, produces a bale measuring 24 by 18 by 63 inches.



Fig. 17.—A baling press operated by hand.

For handling large crops some form of power press is always employed. A modern press which is easily operated with one horse is shown in figure 18. This is a vertical machine 10 feet 4 inches high and 30 inches wide. The doors swing upward to open and when closed are locked by a bar lock that fits a lug at each end of the press. The end gates are loose and may be easily removed when the doors are open. The follower is made of 4 by 4 inch timber and 1¼-inch boards, with a 1 by 6 inch steel bar across the top, to the ends of which twin cables are attached, by means of which the follower is brought down. The cables wind on a winch made with a 26-inch sheave and a 6-inch drum, using a sweep 12 feet long. Since the cable is wound first on the 26-inch sheave and then feeds onto the 6-inch drum, the downward motion of the follower is rapid at first, but becomes very slow as the volume of hops reaches the proper size for the bale. In this press the box is refilled and the follower brought down the second time for each bale. The bale produced usually measures 19 by 26 by 53 inches.



Fig. 18.—A power press operated by one horse.

rhe so-called Sacramento or "bull wheel" press (fig. 19) requires o horses for its operation. The box of the press measures 20 52 inches and is 8 to 10 feet high. Below the box is a 3-inch el shaft, on one end of which is fastened a power wheel from 10 12 feet in diameter. On the shaft are two 8-inch pinions which sh into cog racks 4 inches wide bolted to two 4 by 4 inch 16-foot ıntlings which work up and down. These scantlings are con- cted at the top by a 4 by 12 inch crosspiece 7 feet long. From the osspiece drop two by 4 inch pieces om 8 to 10 feet ng, to the free ends which is attached e follower, which s into the box and, hen the power is ɔplied by means of ıe rack and pinion, resses down the ɔps.



FIG. 19.—A power press operated by two horses.

The lower section f each side of the ɔx consists of a door inged to open up- ard. In baling, the ottom of the press covered with a iece of baling cloth ½ yards long and rom 42 to 46 inches ide, the doors are closed, the box is filled with hops, another similar loth is spread over the hops, and the follower is brought down. The oors are then opened, the edges of the cloth sewed together with emp baling twine, and the bale is removed from the press. The verage bale from this press measures 20 by 24 by 52 inches and eighs 180 to 200 pounds.

The practice of trampling the hops to facilitate filling the box hould be entirely discontinued, since the broken hops resulting therefrom detract from the selling qualities. While filling the box the orners of the bale may be slightly tamped, but even this should be carefully done, especially if the hops are dry. More careful handling is urged, as the hops are often broken and crushed on the floor before being baled and this gives them a bad appearance.

Hops are baled in jute bagging, 16 threads or less to the inch. About 5 running yards of bagging are required for each bale. This weighs from 7½ to 10 pounds, and for it 5 pounds tare is allowed in selling.

COST AND YIELD OF CROP.

The cost of production varies so greatly, owing to differences in the value of land, price of labor, yield, and methods of operation in different sections of the United States, that it is not feasible to attempt to estimate the total expense of producing a crop. The danger of loss incident to unfavorable weather or attacks of insect pests renders hop growing much more precarious than raising other staple crops. The difficulty of securing sufficient help at picking time has added much to the hazards of the crop in recent years. Some estimates of the more important expenses of production are as follows:

Important items of cost in hop production.

Roots	per thousand	$2.00	to	$8.00
Trellis	per acre	80.00	to	90.00
Twine	do	4.00	to	7.00
Cultivating	do	6.50	to	18.00
Training	do	11.00	to	22.00
Spraying	do	4.00	to	12.00
Picking	per dry pound	.03½	to	.05
Curing	do	.01	to	.01½
Baling:				
For cloth and twine	per bale	.60	to	.90
For labor	do	.15	to	.25
Hop press		30.00	to	400.00

The yield varies widely according to the locality, and within the locality according to soil conditions. In the following table is shown the average production of hops per acre for the principal hop-growing States, according to the report of the United States Census for 1900:

TABLE 1.—*Average production of hops to the acre in the United States for the years 1879, 1889, and 1899.*

States.	1879.	1889.	1899.
	Pounds.	*Pounds.*	*Pounds.*
New York	554	547	630
Oregon	840	1,155	951
California	1,022	1,648	1,469
Washington	1,317	1,626	1,287

In seasons of good production, on the better soils, the yield will usually be much larger. In California an acre may produce 1,800 to 2,400 pounds; in Washington, 1,200 to 2,000 pounds; in Oregon, 1,000 to 1,600 pounds, and in New York, 800 to 1,500 pounds.

The following figures from Bulletin No. 50 of the Bureau of Statistics, United States Department of Agriculture, give the aproximate annual production for the United States as compiled from nofficial estimates for the years 1901-1906:

ABLE 2.—*Annual production of hops in the United States from 1901 to 1906, inclusive.*

States.	1901.	1902.	1903.	1904.	1905.	1906.
	Pounds.	*Pounds.*	*Pounds.*	*Pounds.*	*Pounds.*	*Pounds.*
w York	9,000,000	5,850,000	9,000,000	11,880,000	9,360,000	12,060,000
lifornia	9,360,000	10,335,000	10,920,000	12,285,000	14,235,000	20,475,000
egon	13,845,000	16,965,000	17,550,000	17,550,000	22,191,000	23,985,000
ashington	6,630,000	5,850,000	6,825,000	7,410,000	9,750,000	8,775,000
Total	38,835,000	39,000,000	44,295,000	49,125,000	55,536,000	65,295,000

MARKETING.

The most serious problem confronting the hop grower is how to arket his product at a figure which will give a fair return for in-estment and labor. Owing in part to great fluctuations in prices, op growing from a business point of view is extremely variable and ncertain. The state of the market is determined largely by the stock f hops held in storage from the previous year, by the crop condi-ions at home and abroad during the current year, and by the proba-le demand as judged from a comparison of the two conditions just nentioned. While the state of the market is conditioned by these hree factors, it is influenced heavily by the dealers, hop merchants, r middlemen who stand between grower and consumer.

Hops may move into the market in a number of ways and reach the onsumer through various channels. The relations of grower and consumer in some of the more direct lines of transfer are illustrated in the accompanying diagram (fig. 20).



FIG. 20.—Diagram showing movement of hops into market.

Only a small percentage of hop growers sell direct to consumers, so the bulk of the trade passes through the hands of middlemen. Sales may be made to the large dealer direct through his buyers or to the local dealer, who in turn sells to the large dealer; or growers may sell through a commission merchant who may act as agent for both grower and consumer. The broker, or factor, serves as a go-between for dealers or for dealer and consumer. All these middlemen occupy a recognized legitimate place in the trade so long as they confine their operations to buying and selling at market prices as fixed by supply and demand and depend for their profits upon the favorable terms which they may be able to make in the regular course of trading. Under existing conditions the hop crop could not be marketed without the middlemen. Growers with small holdings remote from consumers could scarcely find a market for their product. even if the difficulties involved in arranging credit were overcome. The grower is usually in need of money and demands immediate payment; on the other hand, the consumer may not have funds available to pay cash for his hops at the time when it is necessary to make the purchase. The dealer solves the difficulty by relieving the grower of his stock and making cash payment therefor or a suitable short-time arrangement and by selling to the consumer on terms to suit his convenience.

Although much significance is commonly attached to the locality in which the hops are produced, it is apparent that too much emphasis is laid on geographical origin as a standard of quality. It has been repeatedly demonstrated that dealers and consumers can not tell with certainty the section of the country a sample comes from by examination alone. Even samples from the same yard, when the conditions of drying have differed somewhat, have been ascribed to widely different sections by expert judges of hops.

The price which a consumer will pay for hops depends largely on their origin, thus making it frequently possible to deliver hops grown in one section when the sale was made on hops from another which commanded a different price. Unfortunately, there is no definite standard of quality in judging hops, and there is apparently too much importance attached to origin alone. While geographic origin may be of some importance, its usefulness as a standard of quality is small compared with the tests usually applied in judging the value of hops. In determining the relative quality of different lots of hops a fixed standard of valuation founded on intrinsic qualities rather than preference would be exceedingly valuable to both producer and consumer.

The present unsatisfactory conditions of marketing offer opportunities for improvement along several lines. One of the greatest needs of the hop industry is more complete and accessible statistics of production and consumption, not only that growers may govern their acreage by the prospective demand, but that, by knowing the amount consumed during the current year, the stocks remaining in the hands of the consumers, and the crop conditions at home and abroad, an intelligent opinion may be formed as to the probable relabetween supply and demand and what prices may therefore be nably expected. From the return made by the officers of the nal-revenue service a quarterly statement would show the total ınt of hops consumed, and from the consumption—its increase lecrease—the market possibilities could be inferred. Also the ssity is very great for frequent reliable statements of European conditions. The hop market is controlled by the production in United States, England, Germany, and Austria; and, since the plus production of the United States is exported almost entirely England, crop conditions abroad practically control American es. More reliable and detailed statistics of home production are led. So many exaggerated reports are circulated for the purpose nfluencing the market that an exact census of the acreage set out, acreage harvested, and the number of bales produced would be ncalculable benefit to the producer; and this end would be much thered by thorough cooperation on the part of the hop growers nselves.

n the Pacific coast several hop growers' associations have been anized along similar lines and with the same general purpose as citrus growers' associations and others in southern California. ier organizations modeled along the lines of the hop growers' ociations or cooperative unions of Europe should enable growers protect their interests better and to secure recognition unobtain- as individuals. The industry is so centralized in the various tes that a very small number of associations could easily include ctically all the growers in their membership. With proper peration on the part of the members of the associations and the ndonment of the attitude of suspicion and distrust which too n characterizes the relations of producers with each other, it uld be possible for growers to secure the adequate collection and ribution of the most necessary statistics of production and con- ption and to more fully acquaint themselves with the need of er methods and of greater facilities for handling the business.

O

Issued August 26, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 305.

Experiment Station Work,

XLII.

Compiled from the Publications of the Agricultural Experiment Stations.

EXTENSION OF RICE CULTURE.
GROWING SEED POTATOES UNDER MULCH.
MANURE AS A SUMMER MULCH IN FORCING HOUSES.
RENEWAL OF OLD ORCHARDS.
INJURY BY BORDEAUX MIXTURE.
GLUTEN FLOURS AND SIMILAR FOODS.
LAXATIVE PROPERTIES OF WHEAT BRAN.
EMMER AS A FEEDING STUFF.
ROOTS FOR FARM ANIMALS.
CABBAGE AS STOCK FEED.
PASTURING HOGS.
CULL BEANS AS A FEED FOR HOGS.
HEALTHY POULTRY.

JULY, 1907.

PREPARED IN THE OFFICE OF EXPERIMENT STATIONS.
A. C. TRUE, Director.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

THE AGRICULTURAL EXPERIMENT STATIONS.

Alabama—
  College Station: *Auburn;* J. F. Duggar.[a]
  Canebrake Station: *Uniontown;* J. M. Richeson.[b]
  Tuskegee Station: *Tuskegee;* G. W. Carver.[a]
Alaska—*Sitka:* C. C. Georgeson.[c]
Arizona—*Tucson:* R. H. Forbes.[a]
Arkansas—*Fayetteville:* W. G. Vincenheller.[a]
California—*Berkeley:* E. J. Wickson.[d]
Colorado—*Fort Collins:* L. G. Carpenter.[a]
Connecticut—
  State Station: *New Haven;* E. H. Jenkins.[a]
  Storrs Station: *Storrs;* L. A. Clinton.[a]
Delaware—*Newark:* Harry Hayward.[a]
Florida—*Gainesville:* P. H. Rolfs.[a]
Georgia—*Experiment:* Martin V. Calvin.[a]
Hawaii—
  Federal Station: *Honolulu;* J. G. Smith.[c]
  Sugar Planters' Station: *Honolulu;* C. F. Eckart.[a]
Idaho—*Moscow:* H. T. French.[a]
Illinois—*Urbana:* E. Davenport.[a]
Indiana—*Lafayette:* A. Goss.[a]
Iowa—*Ames:* C. F. Curtiss.[a]
Kansas—*Manhattan:* C. W. Burkett.[a]
Kentucky—*Lexington:* M. A. Scovell.[a]
Louisiana—
  State Station: *Baton Rouge.*
  Sugar Station: *Audubon Park, New Orleans.*
  North Louisiana Station: *Calhoun:* W. R. Dodson (*Baton Rouge*).[a]
Maine—*Orono:* C. D. Woods.[a]
Maryland—*College Park:* H. J. Patterson.[a]
Massachusetts—*Amherst:* W. P. Brooks.[a]
Michigan—*Agricultural College:* C. D. Smith.[a]
Minnesota—*St. Anthony Park, St. Paul:* W. M. Liggett.[a]
Mississippi—*Agricultural College:* W. L. Hutchinson.[a]
Missouri—
  College Station: *Columbia;* H. J. Waters.[a]
  Fruit Station: *Mountain Grove;* P. Evans.[a]
Montana—*Bozeman:* F. B. Linfield.[a]
Nebraska—*Lincoln:* E. A. Burnett.[d]
Nevada—*Reno:* J. E. Stubbs.[a]
New Hampshire—*Durham:* W. D. Gibbs.[a]
New Jersey—*New Brunswick:* E. B. Voorhees.[a]
New Mexico—*Agricultural College:* L. Foster.[a]
New York—
  State Station: *Geneva;* W. H. Jordan.[a]
  Cornell Station: *Ithaca;* L. H. Bailey.[a]
North Carolina—*Raleigh:* B. W. Kilgore.[a]
North Dakota—*Agricultural College:* J. H. Worst.[a]
Ohio—*Wooster:* C. E. Thorne.[a]
Oklahoma—*Stillwater:* W. L. English.[a]
Oregon—*Corvallis:* J. Withycombe.[a]
Pennsylvania—*State College:* T. F. Hunt.[a]
Porto Rico—*Mayaguez:* D. W. May.[c]
Rhode Island—*Kingston:* H. J. Wheeler.[a]
South Carolina—*Clemson College:* J. N. Harper.[a]
South Dakota—*Brookings:* J. W. Wilson.[a]
Tennessee—*Knoxville:* H. A. Morgan.[a]
Texas—*College Station:* J. W. Carson.[d]
Utah—*Logan:* E. D. Ball.[a]
Vermont—*Burlington:* J. L. Hills.[a]
Virginia—*Blacksburg:*
Washington—*Pullman:* E. A. Bryan.[a]
West Virginia—*Morgantown:* J. H. Stewart.[a]
Wisconsin—*Madison:* H. L. Russell.[a]
Wyoming—*Laramie:* B. C. Buffum.[a]

---

[a] Director. [b] Assistant director. [c] Special agent in charge. [d] Acting director.

EXPERIMENT STATION WORK.

ted by W. H. BEAL and the Staff of the Experiment Station Record.

---

riment Station Work is a subseries of brief popular bulletins compiled e published reports of the agricultural experiment stations and kindred ions in this and other countries. The chief object of these publications sseminate throughout the country information regarding experiments at erent experiment stations, and thus to acquaint farmers in a general th the progress of agricultural investigation on its practical side. The herein reported should for the most part be regarded as tentative and ive rather than conclusive. Further experiments may modify them, and nce alone can show how far they will be useful in actual practice. The the stations must not be depended upon to produce "rules for farming." apply the results of experiments to his own conditions will ever remain blem of the individual farmer.—A. C. TRUE, Director, Office of Experi- tations.

CONTENTS OF NO. XLII.

Page.
ion of rice culture 5
g seed potatoes under mulch 8
e as a summer mulch in forcing houses 9
al of old orchards 11
by Bordeaux mixture 12
flours and similar foods 13
ve properties of wheat bran 16
r as a feeding stuff 17
for farm animals 19
ge as stock feed 22
ing hogs 24
eans as a feed for hogs 25
y poultry 28

ERIMENT STATION WORK.[a]

EXTENSION OF RICE CULTURE.[b]

uction in this country and the acreage allotted to the crop t years undergone an enormous increase. As pointed out lfth Census, only 161,312 acres were grown in 1889 and s in 1899, while according to statistics gathered by this the area devoted to the crop in 1905 was 482,479 acres l production for the year amounted to 13,606,989 bushels.

e was grown in the United States about the middle of the century, and the crop was introduced into South Caro- its close. For years our rice culture was limited to cer- s along the South Atlantic coast, until within recent years prairie lands of Louisiana and Texas were opened up to of the crop.[c] During the last four or five years a good n rice culture has also been made in Arkansas, with results the possibility of widely extending the area of profitable on lands not hitherto considered adapted to this crop.

the Arkansas Experiment Station, in cooperation with a o conceived the idea of growing rice on Arkansas prairie duced rice culture on a limited scale in Lonoke County, theast of the center of the State. A good stand was ob- n the first sowing, and the result secured demonstrated op can be successfully grown on these prairie lands when gation facilities are provided.

wing year the station, in cooperation with the Irrigation ge Investigations of the Office of Experiment Stations of tment, sank a well, installed machinery, and constructed ut a greater area under irrigation. In 1904 10 acres were although the crop was not sown until late it was success- e beginning, one plat yielding as high as 75 bushels per

---

s record of experimental inquiries, published without assumption of by the Department for the correctness of the facts and conclusions he stations.

from Arkansas Sta. Buls. 89 and 94.

U. S. Dept. Agr., Farmers' Bul. 110, Rice Culture in the United A. Knapp.

acre. In 1905 the area was increased to 30 acres, but owing to unfavorable weather conditions only 25 acres were harvested. About 17 acres of Honduras rice yielded 53 bushels and about 8 acres of Japan 67.53 bushels per acre, the average for the two varieties being 57.8 bushels.

In 1906 the acreage of rice was greatly increased over that of previous years. The industry had extended from Lonoke to Prairie, Arkansas, Lee, and St. Francis counties, and the total area devoted to the crop was about 5,000 acres. The total production was estimated at over 100,000 bushels. The season was in many respects very unfavorable for growing rice, yet where the soil was well prepared, the crop planted early, irrigated properly, and harvested at the right time the yield was satisfactory. A rain and wind storm on September 23, when the late planting had not yet been harvested, damaged the crop from 5 to 12 per cent, and still greater injury was sustained from an early frost in October. Much of the loss was due to late sowing, on account of heavy rains, and also the result of showers during the period of pollination.

For the experiment station crop in 1906 is was impossible to plow the land early on account of heavy rains in the fall and winter of 1905, and it was not until April 16 that the stubble was turned and not until April 28 that the land was finished. The ground was very rough and cloddy and it was necessary to disk it three times and to smooth it down with the harrow. The seed was sown broadcast at the rate of from 1¼ to 1½ bushels per acre, then disked in and crossed with a smoothing harrow. The first sowing was made April 20 and the maximum yield, 77.76 bushels per acre, was harvested from that plat.

The Honduras variety produced at the rate of 61.84 bushels and the Japan 52.44 bushels per acre, the average being 57.5 bushels. The irrigation period of this crop was eighty-four days. Contrary to the experience of the two preceding years, Honduras rice produced the maximum yield, probably owing to the fact that the Japan plats were all planted much later and therefore suffered from storms, cool nights, and early frosts. Where the two varieties were sown on sod land under the same conditions Japan made a much better yield. Honduras rice is named for the country from which the seed came, and Japan, a hardy variety, was recently introduced from that country by this Department. These two varieties, which are the only kinds now planted in Arkansas, are briefly described as follows:

The Japan has a short, thick kernel, a thick hull, and heavy grain. It is not so tall as the Honduras, and the straw is smaller and green when the grain is ripe. The percentage of bran in the Japan is small. Since the grains do not break so badly it will mill more head rice than the Honduras. The market price for Japan, however, is a little less than for Honduras, but the yield is greater.

The Honduras has a large grain, a tall, stiff stalk, and is not so easily blown down. Both varieties have their advantages and disadvantages. Our experiments, based upon two years' tests, proved that Japan is well adapted to our oil and climate. Japan may be planted later than Honduras with good results.

The character of the soil of the Prairie Longue and Grand Prairie regions of Arkansas, which have been found especially adapted to rice culture, are thus described:

> The low, level character of the land, the stiff texture, and impervious subsoil are peculiarly favorable to holding water during irrigation, thus economizing the amount necessary. The ground dries immediately after the water has been turned off, so the binder and team will pass over it. An abundant supply of pure water can be secured from wells ranging in depth from 100 to 200 feet. The geological formation is such that the lift is not usually more than from 20 to 40 feet. Delta lands of the Mississippi and those of the rivers of the Carolinas and Georgia produce a fine grade of rice, which reaches the market early and brings fancy prices. However, in many cases these lands are not adapted to the use of the improved machinery, consequently the expense of growing the crop is greater than that of the prairie lands.
>
> The alluvial lands of south Arkansas are in many places adapted to rice culture. Pure warm water, with nitrates and other soluble plant food, can be taken from lakes, ponds, bayous, and rivers at very little expense.

It is stated that the lands which are now devoted to rice are lands that, owing to lack of drainage and reclamation, were not adapted to other field crops and were almost exclusively used for grazing. A farmer planted 40 acres of bottom land lying adjacent to Bearskin Lake with rice in order to determine whether irrigation would kill nut grass, which was very abundant in the field, and at the same time produce a crop of rice. The experiment was successful and an average yield of 46½ bushels of rice per acre was secured.

The time of planting largely depends upon the season, but it is recommended that for southern Arkansas the crop be planted as soon as all danger of frost is over and the ground warm enough to germinate the seed, which will usually be from April 1 to May 15. Honduras should be planted earlier than Japan, which may be sown any time until May 15.

So far few insect pests and fungus diseases and no noxious weeds, except red rice, have appeared in the rice fields of the State.

Red rice, according to Dr. S. A. Knapp, "is so called from the red color of the grains. In most cases the grain is colored a dark red through the entire substance. In other instances seeds may present any shade of color between the red and the white; again, only the seed coat contains the coloring matter, and in this case the grain comes from the mills clean and white, or with little stripes of red where the coat has been imperfectly removed." The presence of a few grains of red rice in milled rice lowers its grade and reduces its price. It is, therefore, important to keep red rice out of rice fields.

In order to keep red rice from the rice field it is advised to grow a few acres isolated and planted on sod or new land for seed, and to select the largest, earliest, and best heads for the next crop. When red rice appears the field should be plowed, disked, and harrowed as soon as the crop is harvested. If the land is dry and hard, flooding will germinate many of the seeds, which will then be killed during the winter. Other seed germinating in the early spring may be killed by spring plowing. When red rice has obtained a firm hold in the field, some other crops should be grown until the weed has disappeared, and if the land is too low and acid to produce good crops, it may be fall plowed and left in fallow until spring, plowed again, fallowed until midsummer, and then plowed for a crop of rice.

Suggestions regarding methods of culture adapted to Arkansas conditions are given in the bulletins from which this article is compiled.[a]

GROWING SEED POTATOES UNDER MULCH.[b]

R. A. Emerson, of the Nebraska Experiment Station, has reported an interesting comparison of the value for seed purposes of potatoes grown under mulch with those grown with ordinary cultivation under like conditions, which indicates that the mulch method offers a convenient and practical means of producing good home-grown seeds under Nebraska conditions. The theory of the method and the results obtained in the comparative tests are thus stated:

> Potatoes are a cool-weather crop. It is because of this that they succeed so well in the far north. Moreover, potatoes require for their best development fairly uniform conditions, especially as regards soil moisture and soil temperature. This being the case, why should not potatoes grown under a litter mulch be especially well developed and therefore make strong seed? The soil beneath a mulch not only has a moderately low temperature during summer, but its temperature is also exceptionally uniform, varying not more than a degree or two between day and night and only a few degrees from day to day. The soil moisture beneath a good mulch is also more abundant and much more nearly [illegible] bare ground, even though the latter is given [illegible]
>
> [illegible] ers grown under a litter mulch has been
> [illegible] ment station. In 1904 a plat of potatoes
> [illegible] joining plat was given careful cultivation.
> [illegible] uniform and the seed planted on the
> [illegible] ubers. Seed was saved from the
> [illegible] under the same conditions during
> [illegible] of 1905, and given identical
> [illegible] the experiment was repeated with
> [illegible] ground the year before. The same
> [illegible] irst test. Uniform seed was used to start

---

[a] [illegible] Dept. Agr.' Farmers, Bul. 110.

[b] [illegible] Nebraska Sta. Bul. 97.

ith in 1905. The seed saved from the mulched and from the cultivated plats as taken as it came, without selection, and was kept over winter under the ame conditions. Both kinds of seed were cut in the same way, planted in the ame way, on adjoining plats, and treated alike as regards tillage, spraying, etc. nder these conditions any constant differences in yield between the two plats ust be ascribed to the effect of the methods of culture employed the previous eason. The yields obtained from the mulched and from the cultivated seed ere as follows: Cultivated seed, 384 pounds in 1905; mulched seed, 563 pounds n 1905; cultivated seed, 123 pounds in 1906; mulched seed, 174 pounds in 1906.

The use of seed that had been grown under a mulch the preceding year ncreased the yield of potatoes 47 per cent in 1905 and 41 per cent in 1906. If urther tests confirm the results reported here, it would seem that mulching ight be used for the production of high-grade seed potatoes at home. Moreover, mulching usually results in increased yields if properly handled. Mulchng potatoes on a large scale is of course impracticable, but most farmers could asily mulch enough of their potato field to produce the seed that they would equire the following year, and in doing so they would not necessarily increase the cost of production per bushel.

The method migh be tried with advantage in other regions than Nebraska, where warm, dry seasons prevent the production of vigorous seed by ordinary methods.

MANURE AS A SUMMER MULCH IN FORCING HOUSES.[a]

In experiments made by G. E. Stone, of the Massachusetts Experiment Station, it was found that the practice common among those engaged in forcing vegetables under glass of allowing the soil of beds to become very dry during that portion of the season when the houses are not in use has an injurious effect on the growth of lettuce by increasing the activity of the " drop " fungus in the soil and the extent of infection in the succeeding crop of lettuce. Other injurious effects were also observed which were " manifested in a stunted growth and abnormally colored and worthless crop." Doctor Stone therefore recommends that the soil of houses used for forcing lettuce should never be allowed to become too dry in summer, and explains that " if such drying occurs the soil can be entirely renovated by applying hot water or steam to it."

The Ohio Station reports experiments begun three years ago to determine " what effect the use of strawy manure would have on the soil when used as a mulch during that part of the summer when rops are not growing in the greenhouses," which gave results bearing pon the question of the advantage of keeping greenhouse soils moist n summer.

The manure was applied as soon as the tomato and cucumber vines were emoved from the houses, or about the first of August. It was put on to a epth of from 5 to 6 inches and spread evenly over the entire surface of the eds. As soon as it was on, water was applied in the form of a spray until he manure and soil were thoroughly wet.

---

[a] Compiled from Ohio Sta. Circ. 69.

The object of this wetting was, first, to leach the fertility of the manure into the soil, and, second, to wet the soil sufficiently so that with the strawy mulch it would remain moist for several days. The operation of watering was repeated as often as needed; two or three times a week in bright weather.

When it came time to plant the lettuce, about the middle of September, the coarse part of the manure was removed from the beds and carried outside. The finer portion of the manure was worked into the soil at the time of spading.

It was noticeable that the soil which had been treated with the mulch was in excellent mechanical condition when it was worked up for the first crop. There were no lumps, as there often are in soil which has been allowed to bake in the sun for weeks at a time. It was also darker in color than unmulched soil. The lettuce plants which were planted in this soil started off nicely and grew rapidly and satisfactorily in every respect. No further application of manure or fertilizer of any kind was made for the second and third crops of lettuce. The growth of these crops was very satisfactory, as was that of the first crop.

The method gave such favorable results at the station that a practical grower of forcing-house vegetables was induced to try it.

Taking the results of the station tests for the two seasons, together with the results secured by the [practical grower] for the same length of time and gleaning what information it has been possible to obtain from various sources, the station does not hesitate to recommend this treatment for soils which are to be used for vegetable forcing. It must be borne in mind, however, that no half-way or slipshod methods of using the mulch will give satisfactory results. There should be sufficient fertility in the manure to furnish enough plant food, when leached into the soil, to supply the three crops of lettuce. The quantity of manure must be sufficient, also. At least 5 or 6 inches should be applied. A considerable quantity of coarse material in the manure, such as straw, corn stover, etc., is an advantage. Fresh manure has been used at the station each time, and, while we have had no chance to see the effect of the use of the well-rotted manure, we are satisfied with fresh manure, as we know that it will give good results.

Where it is the practice to mulch the cucumber or tomato crop, the manure used for that purpose can be left on and more added, provided the cucumbers or tomatoes have been free from disease. In case these crops have been diseased, it would be advisable to remove the mulch used on them and apply new.

Frequent sprinkling of the manure on the beds is very essential.

When it comes time to put in the first crop, if the soil is in need of humus, the entire mulch may be spaded into the soil, but most greenhouse soils do not need the addition of so much coarse material. Where the soil is fairly well supplied with humus, the coarser part should be taken off and removed from the houses and the finer portion worked into the soil.

The fact that the greenhouses in which the mulch was used were very free from lettuce disease "would lead us to expect beneficial rather than detrimental results from the proper use of summer mulch in so far as it affects the diseases of lettuce." If the use of mulch has any beneficial effect as regards diseases, it is entirely a preventive measure and not a cure. Neither this method nor any other will prevent damage which results from bad methods of handling the crop.

RENEWAL OF OLD ORCHARDS.[a]

F. H. Ballou, of the Ohio Experiment Station, maintains that old neglected orchards, which have been overgrown with weeds and brambles and have become not only worthless but a menace to new, well-cared-for orchards, may be "renewed" so that they may be a valuable source of fruit, especially while new orchards are coming into bearing.

Instead of these orchards being destroyed to prevent the spread of diseases and noxious weeds to newly planted orchards he explains how they may be renewed in such a way that the injurious insects and diseases may be effectually and easily combated and controlled, and the old trees made to produce fine fruit for home and market while the young fruit trees are growing.

Mr. Ballou explains at the outset that "renewal is a reversal of the generally prevailing idea of 'pruning up' old trees. It is distinctly a process of 'pruning down.'"

The type of trees with which renewal is not practicable is that type whose heads have been formed at an extreme height from the ground, and whose naked branches, from that elevated point of divergence, extend many more feet upward and outward with no intervening smaller branches. Usually a tree that was originally headed moderately low, and whose lower branches are in good condition, can be successfully renewed.

Cut out the topmost branches the first season of renewal, leaving all healthy side branches. The next season these horizontal branches may have their extremities lopped back with the pruners in such a way as to promote a uniform, well rounded, symmetrical head or top.

It will be necessary to saw large branches first on the under side, then on the upper side, a few inches farther out or up the branch in the direction of its growth. This allows the branch to break off without splitting the part remaining. A second cut, at an angle, can then be made without difficulty, leaving a smooth, clean-cut stub.

All wounds should be dressed, a few weeks after cutting, with a thick paint made of pure white lead and boiled linseed oil.

The benefits of heading back will be lost, in time, unless the work be followed up by annual, discriminate thinning of the new shoots, and cutting back of those selected for future fruit bearing.

Renewal of orchards may profitably be accompanied by the addition of stable manure, either worked into the soil beneath the extremities of the branches, or allowed to remain upon the surface to be covered later with straw or other coarse material applied as a mulch. The combination of renewal and fertilization will work wonders in the rejuvenation of many old orchards long considered unprofitable and valueless.

---

[a] Compiled from Ohio Sta. Bul. 180. See also U. S. Dept. Agr., Farmers' Bul. 160, p. 16.

INJURY BY BORDEAUX MIXTURE.[a]

While it is recognized that Bordeaux mixture is the most efficient fungicide now known for combating many diseases of fruit, particularly those of the apple, evidence has been collected by the New York State Station which shows that it is not a perfect application for use in apple orchards, since under certain conditions the mixture itself, even when made and applied with extreme care, may spot the leaves and mark or deform the fruit.

On the foliage, Bordeaux injury greatly resembles the leaf spot supposed to be caused by fungi. Dead, brown spots first appear, which may be small, circular or roundish, or larger and of irregular shape as though several small spots had run together. The living and dead tissue are separated by a distinct line, so that the spotting is very conspicuous. Later, if the injury is severe, the leaf turns yellow over more or less of its surface and finally drops off as in natural falling. Many of the orchardists reporting place the amount of defoliation during 1905 at one-half or more of the leaves; while in a few instances nearly all of the first leaves fell.

On the fruit the injury first appears as minute, round, black, or brown spots or specks, less than pin-head size, which are clustered either (1) at the apex of the fruit if the injury results from spraying before the little fruits have turned down, or (2) at the base of the fruit if the injury results from later sprayings. Subsequently the characteristic "spray russeting" or "cork russeting" appears. The plant cells injured by the spray form thick, corky tissue, which roughens or russets the apple, the extent of the marking varying with individual fruits. These characters give the fruit the appearance of having been attacked by a fungus. Brightly colored fruit is much marred, both by the russeting and by a decreased brilliance of the unspotted areas. Badly injured specimens are always more or less distorted in shape, the affected areas being usually shrunken. Occasionally unsightly, teat-like malformations are produced, or gaping cracks in half-grown fruits which heal over as the fruits develop, leaving rough sunken scars.

These injuries affect the keeping qualities of the fruits to a marked extent, the moisture being rapidly given off, in dry rooms or cellars, through the corky tissue, so that the flesh below shrivels or becomes mealy, or in extreme cases may turn brown as if bruised or exposed to the air. In such cases decay sets in rapidly. With late-keeping apples this phase of the injury is very important, as the keeping quality is affected, no matter how slight the russeted area.

In cold storage the depreciation of russeted apples is not very rapid, but such fruit is not wanted by retailers, as it keeps very poorly when brought from storage into a dry atmosphere.

Certain injuries to foliage and fruit may be confused with Bordeaux injury, though usually there are points of difference easily separating them.

A perfect method of preventing the injury has not been devised, but U. P. Hedrick and F. H. Hall, of the New York State Experiment Station, give the following suggestions which will aid in reducing it:

---

[a] Compiled from New York State Sta. Bul. 287.

) Distinguish, in spraying, between varieties very susceptible to spray y and those resistant or less susceptible. Among such susceptible varie- which must be sprayed with great care, are: Baldwin, Ben Davis, Graven- , Jonathan, Rhode Island Greening, Twenty Ounce, Wagener, Wealthy, ow Newton, Yellow Transparent. Among those less susceptible are: ander, Esopus Spitzenburg, Fall Pippin, Hubbardston, Northern Spy, Red achan, Red Canada, Rome, Roxbury, Tolman Sweet, Tompkins King, Yel- Bellflower.

2) Varieties resistant to scab should receive light applications of Bordeaux, ecially if they are very susceptible to injury by the copper sulphate. Among h scab resistant varieties are: Alexander, Ben Davis, Gano, Hubbardston, lenburg, Red Astrachan, Rome, Roxbury, Sutton, Tompkins King, Tolman eet, Wealthy, Yellow Newton, and Yellow Transparent.

(3) It will probably be best to use less copper sulphate. On this point it is t possible at present to speak positively. * * *

(4) An excess of lime will not prevent Bordeaux injury nor greatly lessen it; erefore it is not advisable to use more than one part of lime to one part of pper sulphate in making the mixture.

(5) Use moderation in spraying. Since the injury increases with the amount copper sulphate, an excessive application that leaves, by evaporation, larger ounts of the chemicals on the tree will be more harmful than lighter applica- ns. Spray to cover the foliage and fruit with a thin film and yet not have trees drip heavily.

6) Avoid spraying in rainy, foggy, damp weather. Applications made just ore showers are quite certain to produce injury; hence the Bordeaux mixture uld be used, as far as possible, only in dry weather. If necessary to spray wet weather it may be advisable to increase slightly the proportion of lime he mixture.

n general it is pointed out that while spray injury is a serious mat- apple scab is worse, and "no fruit grower can afford to give up use of Bordeaux mixture in fighting apple scab."

GLUTEN FLOURS AND SIMILAR FOODS.[a]

Vhen wheat flour is made into dough and frequently washed, pre- ably in running water, the starch may be removed, leaving behind enacious gummy mass known as gluten, which contains practically of the nitrogenous material originally present in the flour. This y be dried and ground or manipulated in various ways, and gluten ds are manufactured on a commercial scale and sold under such nes as wheat gluten, gluten flour, etc. The experiment stations ve examined such goods, which are widely used by persons suffering th diabetes and others who are compelled to exclude starch from ir diet, and it has been found that they vary very greatly in ality. For instance, some of the products examined by the Maine periment Station were found to contain practically the same ount of protein and only a very little less starch than ordinary

---

Compiled from Connecticut State Sta. Rpt. 1906, pt. 2, p. 153; Maine Sta. ls. 55 and 75.

wheat flour, while other goods showed a high percentage of protein and a low carbohydrate content.

An extended study of the composition and nutritive value of gluten flours, gluten bread, and similar goods, nut products, soy-bean meal, and other commercial diabetic foods and homemade gluten rolls and soy-bean rolls was recently carried on by the Connecticut State Experiment Station. According to A. L. Winton's report of this work, all the samples of flour and meal examined, except the wheat and barley goods, the soy-bean meal, almond meal, nut meal, and the flours purporting to be made from milk casein, "were shown by microscopic examination to be wheat products."

> The samples with less than 15 per cent of protein had the appearance of being untreated mill products with or without the bran coats and germ. Some were gritty—that is, felt rough between the fingers as compared with ordinary wheat flour, which feels soft and smooth. The starch was nearly or quite normal in its appearance under the microscope, showing that it had not been gelatinized as in the manufacture of true gluten flour.
>
> The gluten flours and other flours made from wheat containing 26 per cent and upward of protein showed under the microscope flakes of crude gluten—i. e., a dried mixture of gluten and starchy matter, the latter in some cases being gelatinized. Some of the samples consisted entirely of this material, while others contained in addition what appeared to be untreated flour with normal starch grains.
>
> The samples claimed to be wheat and barley, soy-bean meal, and almond meal were true to name.
>
> The [commercial] bread, biscuit, and rusks for the most part showed under the microscope only wheat starch distorted by cooking, wheat tissues, and, in the case of those with high protein, gluten flakes like those found in the flour. * * * Calculated to the water-free basis, nearly all the samples guaranteed to contain a certain percentage of protein fulfilled the claims of the manufacturers.

All of the wheat preparations contained a certain amount of starch, although in most of them the percentage was considerably reduced. The beneficial results from their use are not due solely to the reduced percentage of starch, but also to the increased percentage of protein. The products are "richer" or "heartier" and the patient eats less of them. For example, ordinary wheat flour contains about 75 per cent of starch and 11 per cent of protein, whereas some of the diabetic flours examined contain about 50 per cent of the former constituent and about 40 per cent of the latter. Pound for pound, the amount of starch is reduced only to two-thirds the original amount, but the protein has been increased nearly fourfold, so that 25 parts of the preparation contain as much protein as 100 parts of the original, but only one-sixth (one-quarter two-thirds) as much starch. But a gluten flour with any considerable amou of carbohydrates (for example over 10 per cent) should be used in very sma amount, if at all, by diabetics. A safe flour for those suffering with the disea is casein flour entirely free from carbohydrates, or else a vegetable flour containing the smallest possible amount of these substances, such as may be prepared from soy beans by simply grinding with removal of the hulls, fro almonds and other starch-free nuts after expressing a portion of the fat, o from wheat after washing sufficiently to remove nearly all the starch. A gua to protein and starch content should be furnished with each product, so sicians can calculate dietaries for their patients.

homemade gluten biscuits and the homemade soy-bean meal biscuits] d comparatively low percentages of nitrogen-free extract. Although bean biscuit contained about four times as much nitrogen-free extract gluten biscuit, it should be borne in mind that * * * only about d the nitrogen-free extract of the soy-bean meal is starch, sugar, and also that the nitrogen-free extract as given for the gluten foods is owing to the use of an erroneous factor for protein. With our present lge it may be safe to assume that both biscuits are about equally unobible so far as their carbohydrate constituents are concerned. They are, r, of a very different nature as regards protein and fat, the soy-bean being relatively rich in fat, whereas the gluten biscuit is rich in protein. al trials alone can decide which is the more wholesome. It seems le that both can be used to advantage, thus serving to relieve in a e the monotony of the diet.

regards the use of foods with little or no starch, the following ients are made:

necessity of excluding so far as possible from the diet of diabetic ts sugars and substances, such as starch and dextrin, yielding sugar he digestive juices, has led to the introduction of saccharine and other r derivatives and preparations containing, or purporting to contain, no or starch derivatives, or else diminished amounts of these substances. raving of the patient for sweets is sometimes satisfied, at least tempoby the use of saccharine, a coal-tar product several hundred times as as sugar which is free, so far as diabetes is concerned, from the injurious ties of sugar, but the preparation of a harmless but palatable substitute ead requires a special flour containing a relatively small percentage of and special methods of breadmaking.

alled diabetic flours may be made from wheat flour by washing out a n of the starch and drying. If the process of washing is carried far ı, crude gluten is obtained containing very small amounts of starch, and this, after drying, may be prepared gluten flour. Crude gluten, obtained y-product in the manufacture of wheat starch, is said to be utilized for eparation of gluten flour as well as a concentrated cattle food. The al of so large a proportion of the starch materially alters the physical ters of the flour and the bread made from it is quite different from ry bread. * * *

t of the commercial diabetic flours, however, are not true gluten flours, hey still contain a considerable amount of starch—some of them so much ender them positively dangerous for diabetic patients.

only all of the cereal grains but also most of the seeds of the legumes, s field and Lima beans, peas, and lentils, contain large amounts of starch ust be avoided by diabetics; the soja or soy bean, however, is a striking ion as it contains, when ripe, no true starch, or only traces. This inous seed is an important food in Japan and is being used in this country e manufacture of meal for the use of diabetics. * * *

peanut, another leguminous seed, although very rich in oil, contains 11 per cent of starch, sugar, and dextrin, of which about half is starch. t of the nuts, including walnuts, Brazil nuts, almonds, and filberts, since ontain no starch and only small amounts of sugar and dextrin but are rich in protein and oil, are valuable additions to the diet of diabetics. Almond meal is used in the preparation of various biscuits and bread substitutes. The chestnut is a notable exception among nuts, in that it is rich in starch and poor in fat, the composition of the shelled nut being much the same as that of wheat flour; it is therefore entirely unsuited for the use of diabetics.

Casein prepared from skimmed milk is used for making a kind of bread entirely free from starch. * * *

In making out dietaries for diabetic patients it should be borne in mind that starch, sugar, and dextrin are all about equally injurious, since starch and dextrin are converted by the saliva and pancreatic juice into sugar (chiefly maltose) and it is the sugar, not the starch itself, which is directly injurious. For example, changing a portion of the starch into dextrin, as is done to some extent by toasting bread, does not render it less injurious; in fact it actually hastens the formation of sugar through the action of the digestive juices, since dextrins are intermediate products in the change. For this reason the sum of the percentages of starch, sugar, and dextrin, and not the starch alone, should be considered in valuing diabetic preparations.

Investigations like those noted above have a decided value, as they furnish information regarding the character of food products in which a great many persons are interested. It should be remembered, however, that those who, for any reason, must exclude starch from their diet should follow the advice of a competent physician and should not depend upon general information and their own opinions in regulating their food.

LAXATIVE PROPERTIES OF WHEAT BRAN.[a]

The laxative properties of bran have long been recognized in the very general use of bran mash to correct a tendency to constipation in farm animals, but the exact reason for this action of the bran has never been clearly understood.

Some recent experiments by W. H. Jordan, E. B. Hart, and A. J. Patten, of the New York State Experiment Station, indicate quite positively that there is a laxative action due to a soluble phosphorus compound known as phytin, which occurs in considerable amounts in the bran, for when cows were fed bran from which this compound [illegible] largely removed by washing they showed a decided tendency [illegible] on besides [illegible] physiological disturbances.

[illegible] obtained [illegible] iments, while not considered in [illegible] important bearing on [illegible]

[illegible] is not definitely established—that [illegible] for persons of a constipated habit. This [illegible] usually [illegible] to the effect of the coarser material upon [illegible] tion of the intestines. The outcome of this investigation very [illegible] suggested the thought that if whole-wheat bread really possesses the laxative proper[illegible] assigned to it, this may be due to the amount of phytin it [illegible] its mechanical condition. * * *

---

[a] [illegible] State Tech. Bul. 1.

The phosphorus compounds of the wheat kernel are found mainly in the uter coatings and germ from which are derived the bran and middlings. As he bran phosphorus is mostly contained in the compound phytin, it is self-vident that this substance exists in much larger proportion in the whole-wheat read than in fine flour.

Phytin is widely distributed in nature and has been found in the seeds of the red fir, pumpkin, peas, beans, white and yellow lupines, and potatoes, as well as in wheat.

EMMER AS A FEEDING STUFF.[a]

As fully explained in an earlier Farmers' Bulletin of this Department, emmer, which is a species of wheat (*Triticum dicoccum*), often incorrectly called speltz, was introduced from Russia into the northwestern United States, more particularly Minnesota and the Dakotas, where it has been so successful, especially for dry-land planting, that its culture and use have assumed considerable importance. J. W. Wilson and H. G. Skinner, of the South Dakota Station, say of this grain that "although better adapted to the more arid regions [it] has produced a yield of 63 bushels to the acre on the low land of the college farm. It is now quite generally grown as a grain crop and is highly spoken of wherever fed to live stock."

The characteristics and culture of this crop are fully treated in the Farmers' Bulletin referred to. The purpose of this article is to summarize investigations recently reported by the Minnesota and South Dakota stations, relating to its composition, digestibility, and general feeding value for different classes of farm animals.

The composition of emmer, as compared with other common cereals, is shown in the following table:

Composition of emmer and other cereals.

Kind of grain.	Analyst.	Water.	Protein.	Fat.	Nitrogen-free extract.	Fiber.	Ash.
		Per ct.	*Per ct.*	*Per ct.*	*Per ct.*	*Per ct.*	*Per ct.*
Unhusked emmer grain as it came from the thrasher.	Snyder, Minn. Station.	10.88	10.50	2.32	60.71	11.70	3.89
Do	Shepard, S. Dak. Station.	10.17	11.58	2.46	61.40	11.45	2.96
Husked emmer	Shepard	10.03	11.69	2.80	70.70	2.94	1.84
Emmer husks	do	8.12	2.39	1.48	41.54	39.02	7.45
Wheat		10.50	11.90	2.10	71.90	1.80	1.80
Barley		10.90	12.40	1.80	69.80	2.70	2.40
Oats		11.00	11.80	5.00	59.70	9.50	3.00

The table shows that unhusked emmer is very similar in composition to oats; the husked emmer more closely approaches barley in chemical composition. In experiments made by H. Snyder, of the

---

[a] Compiled from Minnesota Sta. Bul. 90; South Dakota Sta. Bul. 100. See also U. S. Dept. Agr. Farmers' Bul. 139.

Minnesota Station, with sheep, unhusked emmer showed a high digestibility, the digestible nutrients in 100 pounds of emmer as compared with other cereals being as follows:

Digestible nutrients in 100 pounds of emmer and other cereals.

Kind of grain.	Protein.	Fat.	Carbohydrates.
	Pounds.	*Pounds.*	*Pounds.*
Emmer (unhusked)	9.11	2.14	68.40
Barley	8.70	1.60	65.60
Oats	9.20	4.20	47.30
Spring wheat	10.20	2.70	39.20

As measured by chemical composition and digestibility, as determined in the above experiments, emmer should have a high feeding value. Nevertheless, in the actual feeding experiments that have been made this grain has hardly shown as high nutritive value as would be expected from its composition and digestibility.

Summarizing the experiments which have been carried on for several years at the South Dakota Station with all of the more common kinds of farm animals, J. W. Wilson and H. G. Skinner report that in experiments in fattening sheep it required 5.09 pounds of barley as compared with 7.17 pounds of emmer to produce a pound of gain. In comparison with eight other feeding rations in experiments with lambs, it required 7.2 pounds of unground emmer or 8.3 pounds of ground emmer as compared with 5.3 pounds of corn to produce a pound of gain.

In fattening experiments with range lambs emmer was fed as a single grain and mixed with corn, barley, and wheat, half and half by weight. It was found that it required from 1 to 2 pounds more of emmer than of the other grains to produce a pound of gain. The lambs fed a mixture of emmer and barley, half and half by weight, made a larger gain for feed consumed than the average of the two lots fed on barley and emmer fed separately. This was also true of the lambs fed corn mixed with emmer in the same proportions as above. The results thus indicate that the emmer had a greater feeding value for lambs when mixed with other grains than when fed alone.

In feeding experiments with dairy cows it required 2 pounds more of emmer to produce a pound of butter fat than it did of barley or corn, other conditions being equal. The cows made a gain in weight of 18 pounds per head during the period. They consumed one-third more of emmer per head daily than did the lots receiving barley or corn. The cows did well on the emmer ration.

In an experiment in feeding for the production of baby beef emmer was used as one of the grain rations, with the result that the lot ttened on this grain made an average daily gain of 1.69 pounds, hile the lot fattened on corn made an average daily gain of 1.84 ounds. During the grazing period the lot fed on emmer gained 12 pounds more than that fed on corn. It required only 5.16 pounds f emmer for a pound of gain, as compared with 7.03 pounds of corn o produce a pound of gain during the grazing period.

The lot fed on emmer did not consume as much hay per pound of gain as did ther lots, indicating that the husk of emmer is a good substitute for hay.

Emmer produces a hard fat, about the same as oats, and as good a quality of neat as corn.

With the exception of the emmer lot, the spayed heifers brought the same price as the steers. In this case a reduction of 50 cents per hundred was made n account of the spayed heifer being smaller than the steers in the lot which brought $6 per hundred.

The lot of calves fattened on emmer sold for 40 cents a hundred less on the Chicago market than did the lot fattened on corn, and dressed 2 per cent less than did the corn lot.

In experiments with 2-year-old grade steers it was found that a pound of corn was equal to 1¼ pounds of emmer. Where the corn and emmer were mixed half and half by weight the relation is about the same with a small increase in gain in favor of the mixture. With hogs it required 7 to 8 pounds of emmer, as against about 5 pounds of corn, to produce a pound of gain. Other experiments showed "that there was very little feed for swine when following steers fed on ground emmer."

The results show, in general, that while emmer has a high nutritive value it is hardly equal to corn in this respect. The economy of its se as feed will depend upon its availability and cost.

ROOTS FOR FARM ANIMALS.[a]

Roots as a part of the ration have a decided value for all kinds of omestic animals. Prof. T. F. Hunt and associates, in a recent bullein of the New York Cornell Experiment Station, in discussing this ubject, call attention to the fact that their effect is tonic as well as utritive, and that breeders and feeders of farm animals for exhibiion purposes find roots invaluable.

For most purposes the roots are chopped or sliced before feeding. Various and and power machines are on the market for this work. Generally speakng, roots should not be fed alone, as they carry too much water. A feed may ary from 25 to 50 pounds per day for a thousand pounds of animal, according o the amount of dry concentrates and roughage fed. It is usual to put the cut oots into the feed box and distribute the ground grain over them. For poulry, however, the whole roots may be given, allowing the fowls to pick them. It is said by some that turnips and ruta-bagas impart a flavor to milk. However, if no roots are in the milking room at the time of milking and they are fed just after milking this may be avoided.

---

[a] Compiled from Michigan Sta. Bul. 240; New York Cornell Sta. Buls. 243, 244

In feeding experiments at the Michigan Experiment Station, in which roots were fed at the rate of 15 to 20 pounds in addition to a silage and grain ration, R. S. Shaw and H. W. Norton, jr., found that—

> The addition of roots to an already complete ration of silage, clover hay, and grain, for a dairy cow, stimulated both milk and butter-fat production.
>
> The cost of the ration, however, was raised to such a degree as to lessen the profit of production, milk costing 4.2 cents more per hundred pounds, and butter fat 1.1 cents more per pound, as a result.
>
> In case a large production is desired, as in making records, roots might be used to advantage.
>
> The cows gained in weight more on the root ration than when fed without roots, but the difference was not great.
>
> The percentage of butter fat in the milk was constant, whether on the "root ration" or without roots.

The roots and tubers most commonly used for feeding farm animals in this country are potatoes and sweet potatoes, beets of different sorts, mangel-wurzels, ruta-bagas and turnips, carrots, parsnips, and artichokes. Many analyses of these roots have been reported in publications of the experiment stations, and the average figures given in the following table are based upon such work:

Average composition of roots and tubers.

Kind of roots.	Water.	Protein.	Fat.	Carbohydrates.		Ash.	Fuel value per pound.
				Starch, sugar, etc.	Crude fiber.		
	Per cent.	*Per cent.*	*Per cent.*	*Per cent.*	*Per cent.*	*Per cent.*	*Calories.*
Artichokes	79.5	2.6	0.2	15.9	0.8	1.0	360
Red beets	88.5	1.5	.1	8.0	.9	1.0	195
Sugar beets	86.5	1.8	.1	9.8	.9	.9	230
Carrots	88.6	1.1	.4	7.6	1.3	1.0	195
Potatoes	78.9	2.1	.1	17.3	.6	1.0	365
Sweet potatoes	71.1	1.5	.4	24.7	1.3	1.0	215
Parsnips	83.0	1.6	.5	11.0	2.5	1.4	295
Mangel-wurzels	90.9	1.4	.2	5.5	.9	1.1	150
Ruta-bagas	88.6	1.2	.2	7.5	1.3	1.2	190
Turnips	90.5	1.1	.2	6.2	1.2	.8	160

As will be seen from the above table, the roots and tubers are succulent foods—that is, they contain a large quantity of water in proportion to their nutritive material. Their feeding value depends in large measure upon the carbohydrates, chiefly starch, which they supply, though the ash constituents are of undoubted value.

The data obtained in investigations reported in the Cornell bulletin referred to on the value of root crops for stock feeding are based on extended experiments on the total dry matter yield per acre of a number of the more important root crops. The results obtained indicate that such root crops as mangel-wurzels, beets, carrots, ruta-bagas, and turnips yield a profitable stock feed under usual conditions.

greater average yield of dry matter per acre may be obtained from mangels, sugar mangels, sugar beets, and ruta-bagas than from an average yield orn. While it costs somewhat more per pound to produce this dry matter, it is quite probable that the higher digestibility and palatability of roots et this lesser cost of corn. * * *

omparing mangels and sugar beets, the former are more succulent, while sugar beets produce a higher average yield of dry matter. It should be embered, however, that because the sugar beets grow into the ground they more difficult to harvest, and, furthermore, they do not keep so well as igels. It may seem that the yield of sugar beets is more uniform than that mangels, but this is due to the fact that the yield of different varieties of ngels varies more widely than that of the varieties of sugar beets.

'he ruta-bagas produce profitable yields of food material, and the fact that y are well adapted to early feeding, and also to the feeding of swine, as l as to sheep and cattle, adds to their value.

'urnips, as a general rule, do not yield as well as the above-mentioned roots, l, furthermore, they are more liable to attacks of disease. However, they are ful for early feeding, and are especially valuable for sheep.

'arrots and parsnips, while yielding a fair percentage of dry matter, do not ld a sufficient quantity of food material to warrant general planting for ck feeding. However, they are exceptionally good as a condimental food, l for horses.

The results of the experiments carried on in 1904–5 at Cornell, the thors believe, show plainly that early planting of roots for stock eding is desirable. "Ruta-bagas, however, may be planted a little er than the others. It has not been shown that the more fibrous d heavier ruta-bagas of a longer-growing season are less digestible palatable than the more succulent roots of the shorter-growing ason."

The proper methods of harvesting and storing roots are obviously the utmost importance in the use of such crops for winter feeding. ie deductions from the New York Cornell Station experiments iich have to do with this subject follow:

Roots are generally harvested by hand, except in the case of the sugar beets, en a plow may be used to raise them from the ground. When turnips, ruta-gas, and mangels are grown for succession feeding, the turnips are generally rvested first, before frost. Slight frosts in the late fall will not injure a-bagas or mangels, although the first frost should be a sign of harvesting ie unless it be exceptionally early and very sure to be followed by later warm ather. In late summer and early fall the tops do not grow much, yet the its are developing and ripening rapidly.

n the case of mangels, ruta-bagas, and most turnips the plants can be pulled hand, the tops twisted off as they are pulled, and the roots piled or thrown ectly into the wagon. It is thought that piling and afterwards loading is s fatiguing than throwing the roots directly into the wagon as pulled. The its should reach their place of storage with as little dirt and bruising as sible.

Roots may be stored in a cellar or in a pit in the field. The cellar is the ter whenever practicable. It may be a part of the barn structure, or built ler the driveway of a bank barn, or it may be built as a dugout in a side-hill near the barn. Perhaps concrete is the best material for construction. It should be not over 7 or 8 feet deep and large enough to hold the yield or supply. It is best to have it located and constructed in such a way that the roots can be dropped in from above, preferably through trapdoors in the bottom of the wagon and the roof of the cellar. It is essential that the walls (if built in the ground) and the floor have good drainage and that ventilation be provided through the top, and that the construction be frost proof. The ventilators should be left open until sweating has ceased, when they may be closed for the winter. In winter the cellar should be kept closed as much as possible on warm days. Roots should be so placed that turnips may be fed first, ruta-bagas next, and after these mangels and carrots.

If stored in a pit in the field, a high, dry place should be chosen. If the ground is clayey, the roots should be placed on top of the ground; if it is gravelly and drainage is good, a shallow pit about 5 feet wide and of necessary length may be shoveled out. The roots should be carefully placed in a gable-shaped pile about 5 feet wide and as long as convenient. A thin layer of straw should then be laid over the pile and this covered with 6 to 8 inches of earth. Another and thicker layer of straw and a final layer of earth will complete the work. Ventilators should be placed at intervals of 10 or 15 feet, which should be closed when sweating has ceased. The pit should not be opened on warm days in winter. A ditch for drainage should be cut around the pit. Roots stored in this way do not keep as well as when stored in a good cellar, therefore they should be fed out as early as possible.

A later bulletin (No. 211) of the New York Cornell Station gives in detail the best methods of growing different varieties of root crops for stock feeding.

CABBAGE AS STOCK FEED.[a]

In a recent bulletin of the New York Cornell Station S. Fraser says: "In the search for good succulent feed for live stock, the cabbage should not be overlooked. For this purpose the cabbage is to be compared with roots." It is stated that the only kind of cabbage grown in New York for stock feeding "is the common or heading cabbage, usually spoken of as 'cabbage,' and the one kind which is understood when this term is used. The Savoy is used for stock feeding in Europe, but not in America, so far as known to the writer. The cabbage, kales, turnips, rape, and kohl-rabi are closely related. Among the kales practically none are grown in America, although the British farmer is extending his acreage of the thousand headed cabbage or kale, and other forms are grown in parts of Europe. That none of these latter are of value to this country hardly seem possible and, no doubt, in time some will receive a fair trial."

As high as 50 tons per acre of crop yielding nearly 4 tons of dry matter containing about 1 ton of nitrogenous matter was obtained in the Cornell experiments. The essentials for a high yield are a rational rotation to prevent the soil from becoming infected with the

---

[a] Compiled from New York Cornell Sta. Bul. 242.

fungus, early planting to give time for full growth and
ient of the heads, and uniform stand of from seven to ten
plants per acre.

ıbbage differs from almost every other farm crop in that its
ıl production is little influenced by the type of soil on which
wn. It shows a wide range of soil adaptability and it can be
n almost any type of soil provided it is well supplied with
matter, is in good physical condition, and supplies an ade-
ıount of water. A loose friable soil well prepared by deep
ving and manured with 10 to 20 tons of barnyard manure per
ore plowing, followed by an application of 1,000 pounds of
ıe per acre after harrowing in the spring, is considered well
to large yields of cabbage.

ınts must never receive a check. Three or four days after transplant-
er thinning they should receive an application of 50 pounds of nitrate
er acre; this may be applied near the rows with a drill if feasible,
vn broadcast and harrowed in at some time when the leaves of the
e dry, for if they are wet and it dissolves on the leaves it will burn
his application may be repeated twice more, at intervals of from ten or
days, making a total application of 200 pounds of nitrate of soda per
n 300 pounds may frequently be used with profit. No crop will give
turns for such treatment and for clean and constant culture. The
f soda aids leaf growth at a time when one green worm may eat a
day, and forces them through this critical period.

ollowing varieties were tested at the Cornell Station and all
ɔd results: Surehead, Volga, Autumn King, and Danish Ball.

ed in the proportion of heat to total plant, and it kept better than Sure-
Autumn King. Autumn King seemed to be better suited to clay loam
gravel loam. Surehead did better than Autumn King in 1904 on
ım. Danish Ball is the lowest in yield, but has compact head. * * *
es are good food for cattle, sheep, and swine. When they are grown for
ling it has not been a general practice to remove them from the field.
ınvenient for feeding to continue into early winter they are pulled and
ely, then fed directly from the field. When fed to sheep they are gen-
cut. The sheep can nibble them very well. When fed to cattle they
cut either by a cutting machine or they may be chopped fairly well
quare-pointed shovel. They should be fed as soon after being cut as
Sometimes the grain or chopped feed is mixed with them.

aimed by many feeders that cabbages are likely to lend a disagreeable
aste to the milk when fed to dairy cattle. This may be avoided, how-
feeding just before or just after milking, care being taken to remove
from the presence of the cabbage as soon as possible.

ɔllowing methods of storing the cabbage are described:

1.—One of the simplest ways is to store in an orchard or some shel-
e, often alongside a fence which has been made tight by a liberal use
The cabbage are stored with their stems on and are placed head down
se together as possible. Two or three tiers are often made, the heads
ond tier being placed between the stems of the lower, and so on, the

piles being made of any width and length desired. The whole is covered with leaves, salt-grass hay, or straw and a little soil, rails, brush, or litter. Small unsalable heads when stored in this way in November will continue to develop during winter and frequently sell as well as any in February.

Method 2.—Small quantities may be stored by plowing out two or three furrows, 10 or 12 inches deep, on a well-drained site, and placing the heads with their stems up as close together as possible. Some prefer to lay them but one or two thick, while others will pile them up 2 to 2½ feet high, bringing them to a point. The pile is then covered with straw, salt-grass hay, or a thin layer of straw, and then several inches of soil. They are stored before freezing, and when the soil covering them is frozen it may be covered with strawy manure or any other litter to keep the soil frozen until the cabbages are needed for sale.

Method 3.—Large quantities are stored in cabbage houses, this being the best way commercially for a large part of the State. The houses are often built alongside the railroad in order to facilitate shipment, but a small one can be built on the same principle if desired. The walls are frequently about 8 feet high at the eaves, built with three walls and two air spaces, papered on the outside, with a close-boarded and tar-papered roof. The building may be 30 feet wide and of any desired length, with a driveway through the center and well provided with ventilating arrangements. The building is divided into compartments or bins, which run across the house from the driveway to the wall, one on each side. These are 5 feet wide, made of slats on 4-inch studding. This permits of a 4-inch air space all round each bin, the end near the outside wall included. The floor of the bin is raised from the ground about 10 inches, and is also made of slats, thus securing free circulation of air. When the bins are filled, the driveway may be filled if desired. The heads are cut close, practically ready for shipment, and are piled in the bins from the floor to the ceiling. The filling is done in cold weather, if possible, and care is required in ventilating to keep the temperature of the building as near 30° to 35° F. as possible, opening during cool nights and keeping it closed on warm days or when cold snaps occur.

Method 4.—One or two carloads may be stored in the following manner: Select a dry site, excavate about 1½ feet deep and 9 feet wide and of the desired length. Set posts in each corner and every 4 or 5 feet along the side, letting them project about 4 feet above ground level. Board up the inside, 16-foot boards being useful. Set 2 by 4 inch rafters on the studding and roof with wide boards, lapping them a little. Cover the apex of the roof with two boards fastened together like an inverted V. Bank up the outside of the house, and in cold weather cover the roof with straw or horse manure.

PASTURING HOGS.[a]

In a bulletin of the Mississippi Station E. R. Lloyd discusses the subject of hog raising from the standpoint of Mississippi conditions but states some facts which have a wider application, especially in the South. He points out that Mississippi now imports about 50 per cent of the pork consumed in the State, while with the facilities for producing cheap feed there should be an export of hog products.

There are some features in hog raising that should appeal to every thoughtful farmer. No other meat-producing animal is capable of producing so many young in a year. In our mild climate, where suitable pastures can be provided early every month in the year, the sow should farrow twice annually, acing one litter in early spring which can easily be made ready for the late or early winter market, and another litter in early fall to be made ready the spring market. The small amount of capital required to begin with the quick returns on the investment should make hog raising especially ctive to the small farmer with limited means. The hog will make a pound ain on less food than most live-stock, and will profitably utilize the waste lucts around the farm, dairy, and kitchen.

---

[a] Compiled from Mississippi Sta. Bul. 100. See also U. S. Dept. Agr., Farmers' Buls. 56, p. 6; 84, p. 18; 124, p. 25; and 276, p. 20.

t present there is a strong demand at very attractive prices for what is wn as the light market hog, weighing from 130 to 150 pounds. A hog of weight can easily be produced with ordinary care at from 4 to 6 months old.

o man should attempt to raise hogs without adequate pastures. For pas- es woven wire is the best fencing material, all things considered. Around field to be used for pasture run a woven-wire fence 30 inches high with three ands of barbed wire above. This fence will not only turn hogs but other e stock.

For convenience in preparing the land and planting the crops, it is best not divide the pasture up with permanent fences. When the crops are ready r the hogs, by using the hurdle or portable fence the field may be divided into ts of any size. The hurdle fence is simple and cheaply made, and when not use can be taken down and stored under a shed until needed again.[a]

There is a mistaken idea held by some that alfalfa, red clover, rape, and milar crops will produce profitable gains when pastured without grain. The ractical trials made at many experiment stations prove this not true. Of the any forage plants, alfalfa is one of the most satisfactory for hogs, since it an be made a permanent pasture and is rich in protein, making an excellent ombination with corn. The leaves are tender and the stem small, which make t easily masticated and it is very much relished.

At the Mississippi Station careful tests have been made to determine the alue of alfalfa pasture without grain for hogs. Pigs ranging in age from 3 to months have been used, and the results of two years' work show that alfalfa little more than a maintenance ration for growing hogs without grain. Satis- ctory gains have always been secured from alfalfa pastures by supplementing e pasture with from 1 to 2 per cent of the weight of the hogs in corn or other ain.

owpeas without grain so far have given better results than any other crop hog pasture. In one test the crop was grown on thin hill land, where 1 acre cowpeas produced 350 pounds of pork. In another test on rich valley land cre of cowpeas produced 483 pounds of pork. The hogs were put in the field en the peas were about ripe.

CULL BEANS AS A FEED FOR HOGS.[b]

Beans are a very important agricultural crop in Michigan, the total op ranging between 1,500,000 and 5,000,000 bushels per year. It s been estimated that from 5 to 10 per cent of the total crop consists culls or damaged beans, the proportion being influenced by the culiarities of the season and weather conditions at the time of har- st. Of these cull beans about one-half are probably used for feed- g purposes.

---

[a] For construction of hurdles, see U. S. Dept. Agr., Farmers' Bul. 78, p. 12.

[b] Compiled from Michigan Sta. Bul. 243.

R. S. Shaw and A. C. Anderson, of the Michigan Experiment Station, who have recently studied the value of cull beans as a feed for young pigs and for fattening pigs, state that—

> Mixed with other grains, cull beans may be fed to sheep, and large quantities are used in this State for this purpose each year. It is reported that they are used as a food for dairy cows; they are also fed to swine. * * *
>
> It is not desired to advocate the extensive use of beans as a swine food, especially in the fattening or finishing period. Pork from hogs which have been fattened quite largely on beans is generally soft and lacking in quality. If a considerable portion of the pork produced in the State were of this kind it would lower prices and work serious harm to the swine industry. It is generally conceded that bean-fed hogs store up a fat having a lower melting point, and consequently a softer fat, than hogs fed upon many other feeds, and that a considerable portion of the element called quality in pork is dependent upon the melting point or character of the fat stored up.
>
> In the case of mutton finished upon beans no such criticism has been made, probably because there is relatively less fat in the carcass of the sheep, and its character is not so essential to the quality of the meat as in the case of the pig.

In the Michigan experiments the cull beans used were cooked in two ways: "The one by injecting live steam into a barrel containing the food to be cooked, the other by the use of the ordinary feed cooker, consisting of a caldron kettle, with a cast-iron stove as a jacket for the same. A large variety of cookers of similar sorts are upon the market. In cooking small amounts, the kettle gave the better results, while the steam was more convenient for larger quantities."

When cooked beans mixed with corn meal in the proportion of 3:4 were fed for ten weeks to pigs weighing on an average 50 pounds there was an average daily gain of 0.95 pound per head at a cost of 2.8 cents per pound. "It was apparent that the food combination, while it possessed the proper amounts of carbohydrates and protein, was not well enough adapted to the requirements of the pigs to produce adequate growth. It was thought that the introduction of a less concentrated food factor would give variety to the ration, and at least a physical composition better suited to the age and digestive powers of the pigs." Accordingly, middlings were substituted for a part of the beans in a trial made with two lots of five similar pigs weighing on an average 73 pounds, and covering ten weeks, the ration consisting of cooked beans, corn meal, and middlings 2:3:2. The average daily gain was 1.34 pounds per head per day, and the cost of a pound of gain 3.1 cents.

Check tests made with two lots of similar pigs fed a ration of sour skim milk and corn meal 5:1 showed an average daily gain of 1.34 pounds per head at a cost of 3.7 cents per pound of gain.

When cooked beans alone and mixed with corn meal 1:1 were compared with pigs averaging 150 pounds in weight, three lots fed beans only made in eight weeks an average daily gain of 1.1 pounds per ad, 4.21 pounds of beans at a cost of 2.53 cents being required per und of gain. On beans and corn meal the average daily gain was 52 pounds and the cost of a pound of gain 3.25 cents, 4.1 pounds of e bean and corn meal mixture being required per pound of gain.

> It would appear that hogs of the weights and ages of those fed in this experi-ent could reasonably be expected to make a gain of about a pound per day a ration consisting of beans only, and that the same sort of hog could reason-ly be expected to make a gain of about 1¼ pounds per day if an equal amount corn were supplied with the bean ration. Further, it would appear that the ins made by the bean-fed hogs would cost about $2.50 per hundred pounds d those made by the beans and corn-fed hogs would cost about $3.50 per undredweight.

If the cost of the additional labor and equipment is eliminated the ains made from the beans alone were cheap, but other factors must e taken into account and, when judged by experts, the bean-fed pigs ere rated as being worth less per pound than those fed the beans and orn meal.

The general conclusion from the investigation seems to be that cull eans rightly used may be a valuable factor in pig feeding, but that xcessive amounts should not be fed, as beans have a tendency to pro-luce soft pork.

> From many inquiries and reports received from the farmers of the State it was nown that many were using beans alone for fattening swine. Some of these told of large gains and others of unsatisfactory ones. Some that had corn were even selling this and buying damaged beans, feeding these exclusively instead of making a combination of the two feeds. Such feeding must necessarily be accompanied with some losses of protein, and from the standpoint of food economy is open to considerable criticism. However, if the beans were cheap the practice might be financially allowable. When any feed is cheap and a large stock of it is on hand there is a great temptation to supply it too freely, and to feed it to the exclusion of other feeds which experience and judgment would suggest.

As regards methods of feeding beans, Professors Shaw and Anderson state that—

> Beans can be fed to swine only in the cooked form. The pig seems to be unable to utilize beans which are at all hard or firm, even though they have been boiled for some time, hence it is very essential that they be thoroughly [and carefully] cooked. To supply a single feed of half-cooked beans to a pen of hogs robs them of their appetites and relish for their food, if indeed it does not put them off feed. * * *
>
> The amount of water used will be governed somewhat by the way the beans are to be fed, whether they are to be mixed with other feeds or fed alone. In either case the water content of the ration should not be above the bodily requirement of the pigs fed. In fact, it is usually better to have the water content of the ration below the daily requirement of the pig and then allow the pig access to water at will or supply it regularly. When the food is excessively sloppy, the pig is compelled to consume unnaturally large amounts of the ration given in order to properly supply his bodily needs. This distends the stomach,

unbalances the whole digestive system, and makes a paunchy, ill-formed pig, and one which at slaughtering time yields a very low per cent of dressed carcass. Such feeding is neither good practice nor good economy. * * * All refuse grains contain more or less foreign material. Cull beans are no exception to the general rule, perhaps the most objectionable ingredient being the gravel stones. In some samples there was from 5 to 10 per cent of gravel stones. * * *

By the use of a hand fanning mill adapted for bean cleaning a considerable portion of the stones may be eliminated. * * *

It will be found advantageous to use some salt with every mess of beans cooked; about the same amount as would be used for human food would probably be sufficient [but it must be remembered that an excessive amount of salt may cause serious disturbance].

Salt is an appetizer and renders the food more palatable. It also possesses laxative properties, and on this account will be found valuable to use in connection with any ration containing beans. * * *

It is a general rule in all feeding operations that when any change is to be made in the ration of an animal it should be done gradually. This is especially applicable in the use of a ration containing any large quantity of beans.

In winter feeding it will be advisable to supply the feed while warm, but in the use of all warm feeds every pailful used should be stirred until at an even temperature and then tested with the finger. It is a cruel neglect to supply hot food to a hungry pig. Sore mouths, dislike of food, and apparent loss of appetite are sometimes traceable to no other cause. Such mistakes will sometimes occur unless the feeder adopts the plan of stirring and testing every pailful fed.

Pails used should be rinsed after each feeding, and especial care should be taken to clean the kettle or barrel after each cooking and not allow sour or moldy material to collect about the food receptacle.

HEALTHY POULTRY.[a]

Dr. C. A. Cary, of the Alabama College Station, makes the following suggestions regarding the maintenance of sanitary conditions in poultry raising and the treatment of certain common poultry troubles, which it is believed will be useful to those who are engaged in the business on either a large or a small scale. Pure water and wholesome feed are of course prime requisites. Of the first, Doctor Cary says:

Water.—The water supply for poultry should be the very best. Fresh water in clean, uncontaminated vessels should be kept constantly within reach of the chickens, or all kinds of poultry, especially during the hot weather. Good well water is preferable to running surface water. Protected earthen-ware vessels or any form of water vessel should be so constructed that it can be cleaned: in fact, it should be cleaned daily with boiling hot water.

The relation of the feed to health is thus explained:

Feed.—The feed is responsible for the health, growth, and flesh of poultry. Young chicks are often overfed and usually fed in filthy places or in unclean troughs or vessels. More young chicks die from overfeeding and sour, fermenting, decomposing feed than from any other cause. Especially is this true where s or liquid or moist feed is used. Some poultrymen use milk with bread irse meal in it. Milk is a good food, but if given to chickens it must be or it should be boiled or cooked with the bread or meal in it and fed as is sufficiently cooled. Always feed it in clean vessels, not in too large quan- and never leave the excess to sour. In feeding milk and all forms of feeds to chickens be sure to thoroughly clean and boil or scald out the ig vessels once or twice per day during hot weather. Look well to the feeds. Many of them are made of refuse corn, wheat, sorghum, and other s. As a rule it is best to make your own mixed grain feeds, and then you know the quality of each grain ingredient and will not be compelled to pay prices for the heavy grit that is so plentiful in the average mixed chicken It is cheapest and safest and best for the health and growth of the ens or other fowls to buy the separate grains and the grit and do your own ng.

---

[a] Compiled from Alabama College Sta. Bul. 136.

he arrangement and management of the poultry houses and yards shown to have a most important bearing upon the health of the ipants.

rangement and management of houses, yards, etc.—The chicken houses ld be separated from all other buildings, and all the sides should be of ce work or quite open during the summer. The north, east, and west may losed during late fall and winter. The floors, roosts, and nests should be so nged as to be readily removed, cleaned, and disinfected. Portable or mov- chicken houses are useful if so built that they will not come to pieces when ed. In cases of infection with disease germs, or of infestation with mites, stinal parasites, lice, etc., it makes the work of disinfection and eradication arasites more easily and quickly and permanently done if the house can be kly moved to a new uninfected locality.

lost chicken coops are too close, too heavy, and too inconvenient to clean. ie one should invent a "knock-down" brooding coop that can be cleaned lily, and one that will not easily break, and retain firmness and solidity en set up.

he yards and runs are usually too small and insufficient in number. Poul- men can greatly lessen their work by having large yards or runs and many them.

he placing of 20 to 40 chickens in a small yard (say 50 by 100 feet) and ping them there eight to twelve months in a year is one of the means of ensifying the propagation of intestinal parasites of all kinds. The degree infestation of a yard or run or poultry house depends upon the size, the nber of poultry kept in them, the length of time poultry are kept in them, l, to some extent, on weather conditions. A large area, as a yard or pen, will become alarmingly infested with intestinal or other parasites as quickly a small area. Likewise, the fewer the birds and the shorter the time the ls are kept in a given place, the less, in degree, the infestation. This often lains why a man with very few chickens having good feed and wide range raise fine, healthy birds. But when this same man attempts to raise a e number on a small range, yard, or run, he fails, and his chickens are less rous or healthy and consequently less profitable. The number of houses, s, yards, and runs should always be in excess of the immediate demands. pose a man has yards, runs, houses, and coops for three different lots of kens. He should at least have three extra yards and runs into which he d shift the disinfected houses, coops, and birds as soon as the other yards uns became infested. It would be best to have yards and runs sufficient in number to enable the poultryman to make three or four shifts before coming around or back to the first. This may seem extravagant, but it is the only means by which you can breed healthy, vigorous birds without an immense outlay in cleaning and disinfecting yards or runs. Immediately after vacating a yard or run, plow it up and seed it down to wheat, rye, oats, barley, cowpeas, sorghum, or anything that will make a growth upon which the chickens can graze when brought back to this yard or run. Young chickens should not be allowed to range over ground where old chickens run; if it be possible, have the young chicks in a pen or yard where no old chickens have been for six or eight months. This will prevent young chicks from becoming infested with roundworms and tapeworms.

Doctor Cary recommends that when new fowls are purchased they should be confined in some place remote from the flock for one to four weeks. This will give time to determine the presence or absence of such an infectious disease as fowl cholera, a precaution which may save the flock and avoid the difficulty of disinfecting houses and yards.

In spite of great care and strict observance of the precautions enumerated, however, insect pests and diseases may get into the flock and remedial treatment becomes necessary.

Insect pests and diseases.—Chicken mites are the most common pests in nests and houses. Cleanliness is the best means of preventing their multiplication. They develop best in filthy nests and in cracks and under boards in chicken house. Clean the house (move if portable) and then spray the house with kerosene oil emulsion. If possible apply tar in cracks and under roosting boards and this will catch many which escape the spray. Clean and spray the infested houses and coops once per week and dip the infested chickens in weak kerosene oil emulsion, or a 2 to 4 per cent creolin solution. Never dip chickens in a poorly mixed kerosene solution. It will blister the skin, if the kerosene is not thoroughly emulsified. Copper sulphate solution, if applied hot [to roosts, walls, etc.], will kill mites. It should not be applied on the chickens.

The following directions are given for the preparation of the kerosene emulsion and copper sulphate solution needed for the treatment recommended:

Kerosene emulsion. Dissolve one-half pound of hard soap in 1 gallon of hot water, add 2 gallons of kerosene and stir or churn until a milky mixture (or emulsion) is formed; now add 8 to 10 gallons of water; stir or mix with a spray pump, or keep the first emulsion of soap, water, and kerosene and use as much of it as you desire after diluting with 8 to 10 parts of water.

Copper sulphate solution.- Dissolve 4 to 6 pounds of copper sulphate (blue stone) in 20 to 50 gallons of water. Spray this over dusted or cleaned boar walls, nests, or other places. When dry, or the next day, whitewash with spr or brush. If applied hot this copper sulphate solution will kill mites.

Whitewash is used to a large extent in connection with poult houses, and is an efficient means of filling small cracks and makin smooth surfaces which can not harbor vermin. An excellent wash f this purpose is the so-called Government whitewash, which is pr pared as follows:

overnment whitewash.—Half a bushel of unslaked lime, slaked with warm ter. Cover it during the process to keep the steam. Strain the liquid through ine sieve or strainer. Add a peck of salt previously well dissolved in warm ter, 3 pounds of ground rice boiled to a thin paste, and stir in boiling hot a lf pound of powdered Spanish whiting (plaster of Paris) and a pound of glue ich has been previously dissolved over a slow fire, and add 5 gallons of hot ter to the mixture. Stir well and let it stand for a few days. Cover up m dirt. It should be put on hot. One pint of the mixture will cover a square rd if properly applied. Small brushes are best. There is nothing that com- res with it for outside or inside work, and it retains its brilliancy for many ars. Coloring may be put into it and made of any shade, Spanish brown, llow, or common clay. To it may be added 2 pints of carbolic acid, which will ake it a disinfectant.

Doctor Cary gives the following useful list of drugs needed by the ultryman and suggestions as to their uses:

FOR INTESTINAL WORMS.

(1) Isolate infested birds and destroy or disinfect their droppings while eing treated.

(2) Put 1 to 2 drams of copper sulphate in each gallon of drinking water for ne week; or

(3) Powdered pomegranate root bark (for tapeworms), followed by 2 or 3 blespoonfuls of castor oil; or

(4) Oil of turpentine, 1 to 2 teaspoonfuls, followed in four to six hours with astor oil.

(5) Powdered santonin in 5 to 8 grain doses is especially good for round- orms.

(6) Chopped-up pumpkin seed for tapeworms.

FOR WORMS IN THE AIR PASSAGES.[a]

(1) Turpentine introduced by stripped feather into the windpipe.
(2) Steaming with creolin and turpentine in the hot water.
(3) Feeding garlic in the food.

FOR DIARRHEA.

(1) Subnitrate of bismuth, 1 to 4 grains, two to three times per day; or
(2) Pulverized chinchona bark, 1 to 2 grains three times per day, and
(3) Quinine one-eighth to one-half grain two times per day.
(4) Dry feed or cooked and slightly moist feed.

CONSTIPATION.

(1) Epsom salts, 20 to 30 grains in 1 tablespoonful of water; or
(2) Castor oil, 1 to 2 teaspoonfuls; or
(3) Calomel, 1 to 2 grains, and
(4) Soft feed.

FOR LICE.

(1) Lard or vaseline over head, under wings, and around anus.
(2) Dipping in 15 per cent kerosene-oil emulsion; or
(3) Dipping in 2 to 5 per cent creolin solution.
(4) Pyrethrum powder dusted among the feathers.
(5) Clean nests, yards, and houses.

---

[a] U. S. Dept. Agr., Farmers' Bul. 84, p. 28.

FOR INTESTINAL DISINFECTANT.

(1) One-half to 2 drams of copper sulphate in 1 gallon of drinking water; or
(2) One-half to 2 drams of iron sulphate in 1 gallon of drinking water; or
(3) Salol, one-half to 1 grain, once or twice daily.
(4) Naphthol, one-half to 1 grain, once per day after eating.
(5) Resorcin, one-fourth to one-half grain, once per day after eating.
(6) Hyposulphite of soda, 4 to 10 grains in 1 tablespoonful of water.

FOR CHICKEN MITES.[a]

(1) Lard or vaseline on legs, feet, and head applied once or twice per week. Wash off scales.

(2) Kerosene emulsion sprayed on walls, roosts, floors, and nests once per week for what is commonly called chicken mites or chicken ticks.

(3) Two to 5 per cent creolin solution sprayed on same places as (2).

(4) Formalin, 1 part to 200 parts of water, sprayed as (2).

(5) Corrosive sublimate (very poisonous), 1 part to 1,000 parts of water, sprayed as (2).

(6) Boiling hot water freely applied by pouring over walls, roosts, nests, and floor.

(7) Clean chicken house every day until mites are gone.

Doctor Cary recommends that every farmer and poultryman should take one or more good poultry journals and should get all the publications on poultry issued by this Department and by the State experiment stations.

---

[a] U. S. Dept. Agr., Farmers' Bul. 190, p. 6.

O

Issued September 21

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 306.

DODDER IN RELATION TO FARM SEE

BY

F. H. HILLMAN,
Assistant Botanist, Seed Laboratory,
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., July 1, 1907.

Sir: I have the honor to transmit herewith a paper by Mr. F. H. Hillman, Assistant Botanist in the Seed Laboratory, entitled "Dodder in Relation to Farm Seeds."

Dodder, on account of its parasitic nature, is the most dangerous weed in alfalfa and clover fields, and also often affects flax. On account of the large quantity of low-grade seed containing dodder imported from Europe and the prevalence of dodder in the alfalfa-growing regions of the West, its seed is becoming more and more common in commercial seeds.

In this paper an attempt has been made to point out the dangerous character of the various kinds of dodder and to give practical suggestions for the eradication of dodder from infested areas.

I recommend that this paper be published as a Farmers' Bulletin.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

306.

DDER IN RELATION TO FARM SEEDS.

INTRODUCTION.

is probable that commercial seeds representing forage crops, ially the clovers and grasses, are the most effective medium gh which weed seeds are disseminated. The custom in vogue in ountry and in foreign countries of producing seed of these crops econdary feature of their culture and without special attention e character of the foreign plants which may grow with the crops iefly responsible for the great number and variety of weed seed rities commonly disseminated in the product. Such foreign seeds haracterized primarily by ripening at about the same time as the , and as they possess a similarity to the crop seeds in size and ht they are not readily removed by the sifting accompanying the shing of the crop. It is in this way as incidental to the culture of in crops that the seed of dodder or love vine becomes an impurity rtain kinds of commercial seed.

odder is not in itself a means of direct seed adulteration, but as a common impurity of low-grade seed it becomes a prominent fea- of adulteration when such seed is used as the adulterant.

odder, especially as a menace to clover and alfalfa culture, is ming more and more prevalent throughout the country and is ywhere commanding attention from farmers who are observant onditions affecting their crops.

he most important step in controlling the dodders is to prevent, if ible, the introduction of their seeds in commercial seed. While lute freedom from dodder in farm seed can not be assured, er care on the part of the purchaser can reduce to a minimum chances of dodder introduction. This involves the recognition of dodder if present in seed and the recleaning or rejection of the r, as the case may require.

e farmer should know what crops are liable to damage from ler, to what extent their seeds carry dodder seed, that several s of dodder are involved, that the source of the crop seed ences the kind of dodder likely to be present, that dodders have pronounced host preferences, that dodder seed production may fluenced by climatic conditions, etc.

DODDER AN IMPORTANT IMPURITY IN SEEDS.

The seed of dodder becomes an important impurity of commercial seeds both on account of the injurious nature of the plants and the fact that they occur in nearly all the regions where clover, alfalfa, and flax seeds are produced. The size and weight of the dodder seeds and the period of their maturity agree so closely with those of red clover and alfalfa seeds that their presence in the seed crop is practically sure to follow the occurrence of maturing dodder plants in fields devoted to these crops. The same is true of flax seed which has not been especially well cleaned. The extent to which dodder may infest clover and alfalfa seed is indicated by the fact that of 521 samples of red clover seed secured by the Seed Laboratory in the open market in the spring of 1906, 116 samples contained dodder. Again, of 352 samples of alfalfa seed 160 contained dodder.

Clover and alfalfa seeds as sold to farmers have frequently followed a devious course from the grower to the consumer and are especially likely to represent a mixture of lots from different places of production. If one ingredient of such a mixture is infested with dodder the whole becomes contaminated. Not many dodder seeds may occur in a particular lot bought by a farmer, to be sure, but owing to the peculiar nature of the dodder plants a single live dodder seed in a field is a menace to the entire crop.

It is very important that the farmer purchasing clover, alfalfa, or flax seed be qualified to determine for himself whether dodder is present, because it usually is not conspicuously abundant and may escape the notice even of the most conscientious dealer.

SENTIMENT REGARDING DODDER IN EUROPE.

The dangerous character of the dodder plants as pests of flax and leguminous crops, together with their wide distribution throughout the regions which have long grown these crops, especially in Europe, has caused them to be looked upon with dread by farmers. The result is that under the existing seed-control regulations generally in vogue in Europe dodder seed as an impurity of commercial seeds is singled out for special consideration and seed containing it is usually rejected. Reports upon seed tests at the European seed-control stations usually make particular reference to the presence or absence of dodder. As a result of its unpopularity seed containing it is practically unsalable in the domestic trade of most of the European countries.

It is owing to this adverse sentiment in Europe regarding dodder-infested seed and the absence in this country of a national law prohibiting the importation and sale of such seed that so much dodder annually distributed throughout the United States.

THE CHARACTER OF DODDER PLANTS.

Dodder is a parasite deriving its food not from the soil, but directly rom the crop plants which it infests. In this respect it is unlike the rdinary weeds of the farm. It starts from a seed, at first deriving ts nourishment from the food supply stored within the seed. During his period it develops a slender, threadlike, and leafless stem. It is he habit of the dodder to climb by twining, and the young stem ways about in search of a support. Failing to find a suitable support t dies when the food stored within the seed is exhausted. If a suit-ble support, such as the stem, leaf stems, or even leaf blades of a clover, is found, the dodder rapidly twines about it, sending out from ts stem numerous suckers which penetrate the tissues of the plant upon which it rests, termed the host plant. The dodder is subsequently dependent on its host for both its mechanical support and its food supply. The twining of the dodder stem and the clinging effect of the suckers secure the mechanical support necessary, while the penetration of the suckers to the sap-conveying tissues of the host plant insures direct communication with the food prepared by the latter for its own use.

After becoming established on the host plant the part of the dodder plant below the point of attachment dies. Above this point the plant makes rapid growth, branching repeatedly, its branches ultimately forming a tangled mass of threadlike filaments when under conditions favorable for luxuriant growth. At first the growth is apparently insignificant, but with the rapid increase in the branching the total growth soon becomes very conspicuous, and in some instances progresses with exceptional rapidity, rendering its control very difficult.

Dodder depends on prepared food. Independent food manufacture becomes unnecessary, and consequently the plant is devoid of leaves, as well as of root, and usually is devoid of the green color common to other plants. Certain species are strongly tinged with green, however, and doubtless are capable of food production to some extent.

Sections of the dodder stems removed from the main plant retain their vitality and power of coiling and producing suckers for several days at least under favorable conditions. In consequence of this, if pieces of plants are allowed to remain in contact with a suitable host plant for a short time they become attached to the latter and form new centers of growth. In this way new patches of the pest may become established in the field.

Dodder plants are to be distinguished by their slender, threadlike stems, which are lemon yellow, orange, or pink. They may appear to confine their attack to a single plant in a place or may spread uniformly from plant to plant, either near the ground or from the tops of the plants. Small white flowers, mostly in clusters, are produced [illegible] The flowers may be few and scattered, or, owing to [illegible] becoming crowded. [illegible] Fig. [illegible]



[illegible]

[illegible] from the middl [illegible] are profuse see [illegible] by the characte [illegible] the host, its treatment as a crop, and by the condition of the ather during the flowering season of the dodder.

THE VARIOUS KINDS OF DODDER.

Farmers commonly look upon dodder as representing but one kind plant. On the contrary, there are several kinds which infest uminous crops, irrespective of the kind infesting flax. This dis ssion relates in the main to the class of dodders whose seeds are ried by commercial seeds, but it may be said that there are other ds indigenous to certain parts of the country which are more or s injurious. These kinds attack certain cultivated plants which y be brought near them. If the seeds of such cultivated plants are t in the trade, the dissemination of the dodders affecting them is omplished by the transmission of plants or cuttings bearing living ces of the dodder.

As a matter of passing interest, it may be stated that aside from the urious kinds of dodder there is a large number of kinds which have recognized relation to cultivated plants or crops. They live on rious wild plants, and it is the common experience of those who quent fields and uncultivated lands to meet one or more of these ds of dodder which command the attention of the most unobserving rson by their peculiar threadlike, tangled stems.

KINDS OF DODDER SEED INFESTING FARM SEED.

There are at least six different kinds of dodder whose seeds are mmonly disseminated in commercial seeds and therefore are worthy the farmer's consideration, as follows:

(1) Flax dodder (*Cuscuta epilinum*) is a parasite on flax especially. sometimes infests other plants, including certain shrub fruits, but is not a pest of clover or alfalfa fields. It occurs in foreign coun es and also in those States where flax is grown in this country. The her kinds of dodder under discussion are all parasites on clover or alfa, or on both, but do not infest flax.

(2) Clover dodder (*Cuscuta epithymum*, often referred to as *Cuscuta folii*) infests both the true clovers and alfalfa indiscriminately. It widely distributed in foreign countries and in the United States east the Mississippi River and in the Northern Pacific States.

(3) Small-seeded alfalfa dodder (*Cuscuta planiflora*) as it occurs in is country appears to confine its attacks to alfalfa in preference to true clovers. Thus far there is no evidence of any damage from is dodder to red, alsike, or white clovers. This is by far the most undant and destructive of the dodders in the Western States.

4) Field dodder (*Cuscuta arvensis*, as recognized in the botanies) is lely distributed throughout the United States. It infests both the

clovers and alfalfa and also many wild herbaceous plants. It has proved injurious to sugar beets in Utah.

(5) Large-seeded alfalfa dodder (*Cuscuta indecora*) is common in the West, especially in Utah. It infests alfalfa as well as various wild plants, but it does not appear to damage the true clovers.

(6) Chilean dodder (*Cuscuta racemosa chileana*) is not generally known in this country. It is common in South America and has been reported from Europe. It is said to have flourished for a time in California many years ago, but subsequently disappeared. It is of interest because of its prevalence in alfalfa and red clover seed-producing regions of South America from which seed is being sent to the United States, for this dodder infests both alfalfa and red clover. Little is known of this dodder in its relation to forage crops in this country, but since it is being brought here in considerable quantity from South America it is very likely that it will become one of the several injurious species established in the United States.

PREFERENCE OF THE DODDERS FOR CERTAIN HOST PLANTS.

The dodders exhibit a peculiar preference, so to speak, for certain plants over others as hosts. It is more evident with some dodders than with others, and in consequence certain kinds have come to be popularly designated in accordance with this evident preference. This fact has been so long recognized that in some instances the Latin names were selected with regard to it. Thus the dodder universally attacking flax is known as flax dodder in several languages, and its habit of infesting the flax crop is expressed in its Latin name *Cuscuta epilinum*, since flax belongs to the botanical genus Linum. Another kind known thoughout Europe and in this country as clover dodder has been generally recognized by botanists under the Latin name *Cuscuta trifolii*, given to it in recognition of its preference for the true clovers, which belong to the genus Trifolium.

This host preference becomes of interest from a practical standpoint from the fact that certain classes or kinds of crops are subject to infestation, while others are not. Thus, of the forage crops the leguminous plants are infested, while the grasses are not affected, to a material extent at least.

Notwithstanding this more or less decided selective power exhibited by the dodders toward host plants, they will attack other kinds of plants under favorable conditions and for a time derive their nourishment from them. They are very likely not to thrive, however, an often do not produce flowers and develop seeds when on such host Clover dodder, for instance, will be found growing on various grass and weeds among the clover plants of a field, yet when the clover su cumbs to the dodder such grasses and weeds begin to thrive, th lder they have supported largely or wholly disappearing. On the ier hand, the small-seeded alfalfa dodder of the West confines its acks almost exclusively to alfalfa, other plants in the field as a rule ing immune to it. Field dodder is more indiscriminate in its pref- nces. While it grows actively on various wild plants throughout e country, it is a most luxuriant and destructive pest of both clover d alfalfa.

KINDS OF SEEDS INFESTED WITH DODDER.

The host preference possessed by the dodders limits both the kinds seeds which carry dodder seed and the kinds of dodder disseminated this way. Both are further limited by the relative sizes of the eds of the host and of the dodder.

Dodder seed dissemination as a seed impurity is practically restricted the seeds of flax and of leguminous crops or to seed mixtures in hich leguminous seed forms an ingredient. Most of the leguminous rops may be subject to dodder infestation, but it is confined chiefly those whose period of ripening coincides with that of the dodder nd whose seeds are small enough to admit the dodder seeds as an npurity. This restricts the list of seeds for this country to flax, the d clovers, alsike clover, white clover, and alfalfa. To these may be dded yellow trefoil, which as an adulterant frequently used may ntroduce dodder to otherwise dodder-free clover or alfalfa.

The list of leguminous seeds mentioned as subject to dodder infes- tion is given because tests of these seeds have shown that dodder is t least sometimes present in all of them. The source of the seed t once becomes important in this connection, because American-rown alsike and white clover seeds rarely, if ever, contain dodder, hile those produced in Europe often contain it. Again, the place f production of red clover and alfalfa seeds has a most important earing on the probability of the presence of dodder seed, its kind nd quantity. Dodder as a seed impurity becomes from a practical tandpoint of most interest to the American farmer in its relation to ed clover, including the mammoth variety, and to alfalfa. With egard to these kinds of seeds the presence of dodder becomes a serious natter and in the purchase of seed is always worthy of careful consideration.

RELATION OF DODDER TO THE SEED TRADE.

The most direct relation between dodder seed and the business of seed buying and selling is based upon the regions of growth of the dodder and the size of its seed as compared with that of the commer- ial seeds handled. The kind of dodder is largely influenced by the lace of seed production, while the size of the dodder seed, which is dependent chiefly on the kind, has much to do with the result of efforts at recleaning and the consequent condition of the seed when it reaches the consumer. Large quantities of the flax, clover, and alfalfa seeds on the American market are imported, often from regions where certain kinds of dodder are abundant.

REGIONS OF SEED PRODUCTION.

With regard to flax seed little is to be said of the relation of the place of production and flax dodder. This dodder is so widely prevalent in flax regions that its presence in flax seed is always possible.

Red clover seed is imported largely from Germany and to some extent from France, England, and Canada. Chilean red clover seed grown in South America is being imported in considerable quantity. There is also an active domestic traffic in red clover.

Alsike clover seed when imported comes chiefly from Ontario, very little being imported from Europe. It is also produced in the northern United States.

White clover is often imported from Europe, but is also produced in this country.

Crimson clover, which figures largely in the import as well as the domestic trade, bears practically no relation to dodder dissemination when not adulterated, owing to its early seeding period, which precedes that of the dodders by a month or more. Dodder seed, therefore, practically never appears in pure crimson clover seed.

Alfalfa seed is imported from Germany, southern France, Italy, Turkestan, and Argentina. Much of the seed used in this country is produced in the Western States, particularly Utah, Wyoming, and Colorado.

Seed reaching the consumer may have come from any one of the regions just mentioned, or, if mixing the seed is practiced by the dealer, more than one region of production may be represented by the seed purchased.

Clover dodder is so widely distributed that it is liable to appear in clover or alfalfa seed from almost any source. It is commonest, however, in seed from Europe. This dodder grows in Canada; but little, if any, clover dodder is found in Canadian seed of red clover or alsike clover. While it is known that this species of dodder produces seed in this country to some extent, the fact remains that very little, if any, of its seed appears in American-grown clover or alfalfa seed.

Small-seeded alfalfa dodder is very common throughout the alfalfa-producing States of the West. It often totally destroys fields of alfalfa, while others continue to produce hay and seed for a long time after becoming infested. So abundant is this dodder in some cases that the seed crop, according to statements made to the writer by 's in Utah, often contains from 10 to 20 per cent of dodder This is mostly removed from the alfalfa before it is marketed. rmer producing large crops of alfalfa seed in Weber Valley, old the writer that he obtained 60 bushels of dodder seed by ing his alfalfa-seed crop for 1904. The condition of his own neighboring fields gave excellent support to his statement.

native home of this alfalfa dodder is in the region of the Medi- ean Sea. Comparatively little alfalfa seed comes to America he Mediterranean region of Europe, so this dodder is rarely, if ound in European alfalfa seed; neither has it been found in American seed. Turkestan alfalfa seed often contains the seeds dder which appears to be a form of this species.

d dodder is widely distributed within the United States and its a common impurity of both red clover and alfalfa of domestic ction. This dodder is supposed to be an indigenous species, but to the fact that much clover and alfalfa seed produced here is ted to foreign countries it is probable that seed of this species is oming back to us in imported seed. Unless another very similar s of dodder be involved it may be said that field dodder is a on impurity of red clover and alfalfa seeds from nearly all places duction, including the Chilean seed from South America.

ge-seeded alfalfa dodder is found thus far exclusively in alfalfa rom the western United States, particularly Utah. It does not r in seed from Europe, although it might be looked for in seed France, where it is probably the species said to have come from nited States and which is referred to as *Cuscuta gronovii*.

lean dodder is common in red clover and alfalfa seeds from Chile rgentina. It is not known that its seeds occur in domestic- seed.

COMPARATIVE SIZES OF SEEDS.

ds of the same kind of dodder always differ somewhat in size. lifference is more pronounced in some kinds than in others. is a more marked difference, however, in the average size of the of different kinds.

ile there is similarity in size between the seeds of the various s and alfalfa, there is sufficient difference between the kinds and en the largest and smallest seeds of each kind to strongly influ- he question of dodder infestation.

abundance or even presence of dodder in farm seeds is there- rgely dependent on the relative sizes of the two kinds of seed. ombination of the smallest seeded dodders and large-seeded ercial seeds renders successful recleaning possible, while the ce of the larger seeded dodders, especially in small-seeded of commercial seeds, gives a practically hopeless mixture.

First-class red clover seed or alfalfa seed should be free from clover dodder. Such alfalfa seed from the West should be free from the small-seeded alfalfa dodder. The large-seeded alfalfa dodder can be only partially removed from average-sized alfalfa seed. Field dodder should be largely removable from the best alfalfa seed, but doubtless can not be even partially removed from any except the large-seeded grade of red clover seed. It is not likely that the seed of any of the dodders can be wholly removed from infested alsike and white clover seed. Pure crimson clover seed, as previously stated, is not under consideration, owing to its early maturity. Such seed should be free from dodder, but if imported yellow trefoil or red clover screenings are used as an adulterant, which form of adulteration appears probable in some instances, dodder may readily be introduced in this way. Clover dodder has been found to be the kind involved in such adulteration. Thorough recleaning in which the trefoil or red clover and the smallest crimson clover seeds are discarded would remove all of this dodder.

Owing to the wide distribution of clover dodder and the small size of its seeds, it becomes the commonest of the various kinds found in commercial seeds. This is largely the result of the use of low-grade seed and screenings.

The question before the seedsmen regarding freedom of seed from dodder is seen to relate not only to the source of the seed, but very largely to its quality and to the size of individual seeds.

It would seem that attention to the stock with regard to its source and the kind or kinds of dodder it may contain would tend to improve the quality of seeds offered for sale. Such consideration certainly could prevent the mixing of lots some of which are free from dodder or contain a kind which is readily removable if present. Careful attention to individual lots of dodder-infested seed could be made to yield a smaller bulk of high-grade dodder-free seed worthy of a correspondingly higher price.

Lastly, the whole matter can be controlled by the dealer whose purchasing agents are personally familiar with the different kinds of dodder in the field and who, guided by this knowledge, will buy only dodder-free crops or such as contain only those dodders whose seed is removable in recleaning.

A KNOWLEDGE OF DODDER SEED OF VALUE TO THE FARMER.

Since seed from different regions is likely to contain dodder of different kinds, the kind has considerable weight as indicating the source of the seed. Indeed, if carefully considered a knowledge of the kinds of dodder seeds is very valuable in determining the region where the crop seed was grown. The purchaser is thus enabled to decide whether seed is of domestic or of foreign origin and in some instances to termine the part of the country from which it comes.

The custom of seed mixing to establish a certain trade grade is often ry evident in the character of the dodder the seed contains.

Recognition of the several kinds of dodder seed is essential as pre- inary to practical methods of recleaning dodder-infested seed. It furthermore of interest with regard to the relative importance of e several kinds respecting different host plants and climatic condi- ns, since we have reason to believe that certain species are less jurious under certain conditions than under others.

Ready recognition of the seeds of the different kinds of dodder is sential to these ends. This is easily accomplished in the main so far practical requirements are concerned.

HOW THE SEED OF DODDER MAY BE DETECTED.

Detection of the presence in commercial seed of dodder, irrespective its kind, demands first consideration, because its presence justifies fusal to purchase such seed. A magnifying glass is necessary, as it ill enable one to readily distinguish any kind of dodder seed from over, alfalfa, or flax seed. Dodder seeds are, as a rule, about the me size as red clover seeds, including the smallest and largest seeds. he surface is finely roughened and dull, and the general form varies om nearly spherical to strongly flattened and oval or nearly circular. he color is gray, yellowish, brown, or reddish brown, depending rgely on the kind. In contrast, clover and alfalfa seeds are smooth, ften with a slight luster. Their triangular, oval, or kidney form ds in distinguishing them from the seeds of dodder.

The use of a sieve with which a considerable quantity of the seed, if bulk, or all of a sample can be sifted affords the most practical eans of detecting the presence of dodder. The sieve should be such at only the smallest or medium-sized crop seeds will pass its mesh. he smaller dodder seeds, such as those of flax dodder, clover dod- er, and small-seeded alfalfa dodder, will readily be concentrated to naller bulk by this means. The large-seeded kinds will be repre- ented by their small seeds. Care should be taken to sift only a small uantity of seed at a time.

As a final resort in case of doubt, examination of the structure of e dodder seed shows it to contain a slender threadlike embryo coiled ithin the endosperm, which becomes gelatinous when wet. If a few odder seeds are boiled in water for a time, the embryo emerges from e ruptured seed coat, often becoming separated from it as a slender, iled object.

DESCRIPTIONS OF DODDER SEEDS.

The seeds of the several kinds of dodder are distinguished by differences in size, form, and surface texture, by the seed scar, and by color. Size and form are modified by the number of seeds developed in the seed vessel. The surface texture varies considerably with the different kinds. The seed scar consists of a more or less distinct circular area surrounding the hilum or immediate point of attachment to the parent plant.

FLAX DODDER.

Individual seeds of flax dodder (*Cuscuta epilinum* Weihe) are much smaller than flax seeds, but a considerable part of this dodder seed consists of two seeds stuck together. This increases the size and weight of the seed and renders it more likely to be retained in the cleaned flax seed. Single seeds are somewhat oval; one face rounded, the other more or less flattened in two planes which slope from a central ridge extending lengthwise of the seed. The scar is a minute whitish point at one end of this ridge, which is flattened. When the seeds are double, they are rounded on one face, practically plane on the other, and angular, oval, or nearly circular in outline. The surface of these seeds is comparatively rough, sometimes even finely scurfy. The color is gray or light brown. Double seeds are about the size of average red clover seeds. (Fig. 2.)



Fig. 2. Seeds of flax dodder and three seeds of flax, showing relative sizes. Enlarged. (From a drawing by the author.)

The frequent occurrence of double seeds serves to distinguish this kind of dodder from all the others. Again, this dodder is rarely, if ever, found in seed other than flax.

Flax dodder is closely related to the small-seeded alfalfa dodder (*Cuscuta planiflora*) and the seeds of the two kinds are very similar in form. Those of the flax dodder are, however, distinctly larger than the latter.



Fig. 3.—Seeds of clover dodder and red clover, showing relative sizes. Enlarged. (From a drawing by the author.)

CLOVER DODDER.

The seeds of clover dodder (*Cuscuta epithymum* Murr) are not larger than the smallest red clover seeds, some of them being even smaller. They are nearly spherical when well developed, but some seeds which e not well filled are flattened somewhat, even shriveled. The general lor is brown, but some seeds e gray. The darker seeds, least, appear as finely pit- l when seen under a lens. ie scar area appears as a nute rounded spot some- iat smoother and sometimes hter colored than the rest the surface. (Figs. 3, 4, d 5.) Small particles of iy which are likely to oc- r in clover seed sometimes come rounded by friction, ien they very closely re- mble clover dodder seeds. Such particles yield readily to slight essure with a knife blade, under which they crumble to dust.


FIG. 4.—Seeds of clover dodder and alfalfa, showing relative sizes. Enlarged. (From a drawing by the author.)


i. 5.—Seeds of clover dodder and hite clover, showing relative sizes. nlarged. (From a drawing by the uthor.)

The use of a sieve allowing only the smallest clover or alfalfa seeds to pass renders the detection of clover dodder very easy.

Clover dodder and the small-seeded alfalfa dodder as impurities of alfalfa seed are likely to be confounded. The clover dodder is distinguished by its more spherical form, pitted surface, and darker or ashy-gray color.

SMALL-SEEDED ALFALFA DODDER.

Seeds of this alfalfa dodder (*Cuscuta planiflora* Ten.) are minute, ich smaller than alfalfa seeds. They are therefore readily detected using a sieve only sufficiently ie to hold practically all of the falfa seed. The seeds are oval or al-oblong, rounded on one face, e other flattened in two planes iich meet at a central ridge ex- iding lengthwise of the seed. At e end of the ridge this face is bev- d. The resulting area contains e hilum as a minute whitish int. The surface is compara- ely rough as viewed under a lens. The color is variable. Some eds are greenish; others are strongly tinged with purple. As a le the seeds have a yellowish straw color. (Fig. 6.)


FIG. 6.—Small-seeded alfalfa dodder and alfalfa seeds, showing relative sizes. Enlarged. (From a drawing by the author.)

The oval and angular form and the yellowish or greenish color of these seeds render them readily distinguishable from those of clover dodder.

FIELD DODDER.



FIG. 7.—Seeds of field dodder and red clover, showing relative sizes. Enlarged. (From a drawing by the author.)

The seeds of field dodder (*Cuscuta arvensis* Beyrich) are larger than those of any of the preceding kinds, except the double seeds of flax dodder. Their size varies as a rule between that of the smaller and that of average red clover seeds. These seeds are oval or nearly circular in outline, rounded on one face, and variously flattened and angled or deeply grooved on the other. The scar as a rounded area containing a short whitish hilum appears at one end of the flattened face. The color is lemon-yellow, gray, or light brown. (Figs. 7 and 8.)



FIG. 8.—Seeds of field dodder and alfalfa, showing relative sizes. Enlarged. (From a drawing by the author.)

LARGE-SEEDED ALFALFA DODDER.

Seeds of this alfalfa dodder (*Cuscuta indecora* Choisy) are similar in a general way to those of field dodder. They appear to show greater variation in size than the other kinds. There is also considerable difference in form. Seeds of a certain size and form therefore are very similar to those of field dodder, but are scarcely to be confounded with seeds of the first three kinds described. The largest seeds are most characteristic of this species. They are nearly circular in outline, but are usually somewhat broader than long—that is, the scar appears to be at one side of the seed, whereas it is really at the basal end. Such seeds are convex on one face and plane or badly grooved on the other bearing the scar, which is comparatively



.9.—Seeds of large-seeded alfalfa dodder and alfalfa, howing relative sizes. Enlarged. (From a drawing by the author.)

indistinct. The color is gray or brown, sometimes very dark. The surface is often very rough or scurfy. These seeds are to be looked for in alfalfa seed from the western United States. (Fig. 9.)

CHILEAN DODDER.

Seed found in South American red clover and alfalfa seed and determined to be of the species and variety *Cuscuta racemosa chileana* Engelm. is larger and usually more plump than seed of field dodder (*Cuscuta arvensis*). It is reddish brown and the surface is often strongly roughened. The most evident point of difference between this and field dodder lies in the scar. The hilum appears as a point-like depression in the center of the circular scar area. In field dodder a short whitish line not depressed represents this part of the scar.

The seeds of this dodder appear to occur at the present time only in South American seed. Along with this seed are found seeds of a different kind, however, which are similar to and perhaps identical with field dodder.

BUYING SEED.

Every purchaser of clover or alfalfa seed in the open market is likely to receive dodder-infested seed unless it has been found by thorough test to be free from dodder. As previously shown, this liability is due to the several kinds of dodder involved, the extensive field of seed production, the custom among dealers of mixing different lots, and the practice of using low-grade imported seed in adulteration. The average farmer has himself to blame for some of these adulterants, which are often employed by dealers to meet the farmer's demand for cheap seed. With respect to dodder, as well as other impurities, cheap seed is always to be looked upon with suspicion and as a rule is to be avoided.

Often seed of local production from fields known to be free from dodder can be obtained. If well cleaned it is preferable to the average seed in the market. Seed from dealers should be bought by sample, accompanied by a time limit within which the dealer agrees to furnish the same seed in bulk. Such samples should be tested for dodder. If tested at a State agricultural experiment station or at the United States Department of Agriculture some delay is sure to result. The test is so simple and so quickly made that the farmer should himself make it, thus permitting an immediate order for the seed if desired.

The responsibility of any test ends with the particular lot sent for test, and the presence of a few dodder seeds in the bulk lot of any seed represented by a small sample is always possible. The ill effects likely to result will be evident in the young stand of the crop.

With regard to the importance of using only dodder-free seed, it may be said that badly infested fields are practically ruined by certain kinds of dodder and that the loss of the crop is proportional to the extent of the infestation. The seed crop is reduced in quantity and quality. The reduced quality of the seed crop is not represented wholly by a dodder-infested crop, but also by the fact that the dodder so reduces the clover plants' food supply that the crop is likely to be of lighter weight than it otherwise would be. Again, dodder seed production is likely to so contaminate the land with seeds that a return to clover or alfalfa may be accompanied by dodder infestation, even though pure seed be used.

The period of seeding probably has considerable bearing on the results from using dodder-infested seed. Spring seeding is most favorable for growth of the dodder. It is an unsettled question whether dodder plants in the field ever live over winter. It appears that very few, if any, survive. In consequence of this fact, summer or early fall seeding, too late to enable the dodder to produce seed, tends to free the crop of the following season from dodder. Considerable damage from the dodder might occur to the seeding, however, during the first season. Furthermore, some dodder seeds might not germinate till the following spring.

CLEANING SEED.

Under certain conditions it may become necessary to remove the dodder seeds from an infested lot of seed in order to prevent its loss. While the average farmer might hesitate to discard a purchase of seed because of its dodder seeds, badly infested seed would be far more profitably discarded than sown without thorough recleaning.

The successful removal of dodder depends on the kinds of seeds involved and their consequent relation respecting size. It is doubtful if alsike and white clovers can be cleaned of dodder, although the amount of clover dodder can be reduced somewhat by the use of proper sieves, which, however, necessitate the loss of considerable clover seed.

Red clover and alfalfa seeds can be cleaned of clover dodder and small seeded alfalfa dodder by the use of a sieve having 20 meshes to the linear inch and made of wire ranging from No. 30 to No. 34 of Washburn and Moen gauge. This statement is based on experiments with sieves of this mesh made of Nos. 30, 32, and 34 wire. Samples of the above kinds of dodder, as found in commercial seeds and as taken from fruiting plants, were employed in the experiments. Especial attention was given in the trials to the largest of the seeds of these kinds. It was found that either of these sieves will admit all the seeds of these species with proper care in the sifting. If a sieve of this

made of wire coarser than No. 30 of Washburn and Moen gauge
d, the largest dodder seeds of the above kinds will be retained
while, if the mesh is coarser than provided by No. 34 wire, there
›e an undue loss of crop seed, especially in the case of small-
d red clover. The loss of alfalfa seed is comparatively small
using any of the sieves recommended. The same is true of the
r, large-seeded grades of red clover seed. In the case of the
-seeded grades of red clover the loss of seed when a sieve of No. 34
is used may amount to the greater part of the bulk. The sieves
of the coarser wire are better adapted for such seed. Small-
d grades are usually low-grade screenings which carry small weed
, many of which are removed by the sieve.

e farmer may find it difficult to secure the proper sieve. Manu-
rers do not carry all of the sizes in stock. The writer has found
0-mesh No. 30 wire in the stock of one firm and the No. 32 wire
at of another. The other sizes may be carried by other dealers,
'rom what has been learned these sizes have to be made to special
r, and an order for a considerable quantity is demanded.

ıe efficient use of any of these sieves requires that much care be
n to do thorough work. Only a small quantity of seed should be
d at a time. The sifting should be continued until all of the seed
ɔeen brought in contact with the wire. It is believed that the most
:tive work will result from using first a No. 34 wire sieve and then
ing the siftings thus obtained over a sieve of No. 30 wire.

'ith respect to the other kinds of dodder discussed in this bulletin
found in clover and alfalfa seeds it may be said that none of the
es mentioned will remove all the seed, even with repeated sifting.
:h of the dodder seed will be removed, especially if a sieve having
34 wire is used. Thus far no means of wholly removing these
e-seeded kinds is known.

eep seeding of the crop appears to be the most promising course
the farmer to follow in using seed known to contain seeds of the
e-seeded dodders. By this means many of the dodder seeds will be
ed too deep to permit their plants reaching the surface. Sifting
seed, by which as much as possible of the dodder is removed, is
efore most advisable.

lax dodder can be removed from flax with very little loss by the
of a sieve of 14 meshes to the linear inch and made of No 29
, W. & M. gauge.

often happens that seed is retained by unopened dodder capsules,
h permit it to remain with the seed held by the sieve.

DETECTING THE DODDER PLANTS IN THE FIELD.

It has been shown that notwithstanding every precaution against the introduction of dodder, seeds may find their way to the field in the seed used. The ultimate control of the plants may depend upon early efforts to discover and destroy them. This is particularly true if the plants appear in few places in the field.

The proper time to destroy the plants is before rapid branching enables them to reach many host plants. Then every firm hold of the dodder suckers becomes a point of independent growth, and the difficulty of reaching all of them is greatly increased. New seedings, therefore, should be carefully examined for this pest.

Under favorable conditions the dodder seeds germinate but little slower than seeds of clover and alfalfa. The young plants therefore appear at about the same time as the clover. Their discovery in the seeding at first is practically impossible. By the time the crop is 6 or 8 inches high the dodder will have branched sufficiently, as a rule, to render its presence noticeable for a short distance. This permits removal of the plants with the least loss to the stand and with the most likelihood of success.

Different kinds of dodder exhibit in the field individual habits well worthy of consideration in detecting their presence, such as low-growing or high-growing tendencies and their manner of spreading from plant to plant.

Field dodder grows to the top of the host plants, throws out its branches, and rapidly extends from plant to plant, often forming a dense yellow carpet of tangled branches covering and bearing down the crop. (Fig. 10.) Small-seeded alfalfa dodder, on the other hand, confines its growth exclusively to the lower part of the host plant, rarely exceeding a foot from the ground. It spreads slowly from plant to plant, confining itself chiefly to the several branches of the individual alfalfa plant. While a patch of field dodder can be seen a long distance, the other, when the stand is at all thick, can be observed for but a few feet.

The habit of clover dodder differs from that of each of the kinds previously described. Its flowering stems usually climb the host stems for a foot or more. The vegetative stems, by means of which the plant spreads to new host plants, form a dense mat, or carpet, close to the ground, winding in and out among the host stems, often completely surrounding them and hiding the ground. In this way the spreading of the plant is rapid and very effective. The early growt of this plant is not readily detected at a distance.

The effect on the crop differs with these different habits of growth. Field dodder destroys its host plants in irregular patches, probably in many instances as much by bearing down and smothering the crop y the withdrawal of plant food. All of the crop plants within an inested area are likely to be attacked. Small-seeded alfalfa dodder, onfining its attacks chiefly to individual resistant and naturally long-ved plants, eventually causes a general thinning of the stand through ne death of scattered individual plants. Healthy, infested, and nearly ead alfalfa plants thus often occur in close proximity.

Clover dodder attacks every clover plant and to a greater or less xtent other plants within the infested area. It destroys rapidly, and ts progress from the original point of attack is so uniform that distinctly circular areas bared of living clover or alfalfa result. These circular spots of dead plants are very characteristic marks of the destruction caused by this species. A narrow band of living dodder stems will be found bordering the circle of destroyed plants



FIG. 10.—Field dodder covering red clover and grasses. From a photograph of an infested field.

Flax dodder bears down the flax plants and is therefore sometimes alled "pull-down." It also draws the tops of the plants together. oth large-seeded alfalfa dodder and Chilean dodder ascend to the top f the host plant. The former produces dense flower and fruiting lusters; the latter appears to have a more open habit and scattered lower system.

The form and appearance of the flower clusters differ with the different kinds of dodder. Clover dodder flowers are in small compact clusters of several flowers each. The clusters as well as the stems are often tinged with red. Small-seeded alfalfa dodder flowers are in similar clusters which are not colored. Field dodder flowers are in looser clusters scattered among the branches or crowded in bunches.

DESTROYING THE PLANTS.

When failure to prevent the introduction of dodder seed occurs, the destruction of the plants becomes the final resort. The questions of success and the extent of the necessary damage to the crop at once arise. Their answers rest with the kind of crop infested, the stage of development of the dodder, the extent of the attack, and the methods of eradication employed.

The problem of dodder control is strongly influenced by the character of the crop infested. Red clover remains but two, or at most but three, years without reseeding. If the dodder is prevented from seeding it should be eradicated within this time, or at least should not interfere with the course of crop rotation. Alfalfa should remain indefinitely, and if dodder reseeds itself its control becomes much more difficult or impossible. This is the prevailing condition in the West. The fact that the small-seeded alfalfa dodder of the West has not become established in the East is of special interest in this connection. Clover dodder appears likely to prove most troublesome in alfalfa culture in the East.

If the dodder occurs only in patches in the field it usually can be controlled by hand methods. If it covers the greater part or all of the field, plowing under the stand will probably be found necessary. It then becomes important to know how far the crop can be utilized without reseeding the land to dodder.

It is first important to gain control before the plants have spread far from the point of attack; secondly, and of greater importance, they should be subdued before they produce seed. Success therefore depends very largely on early discovery of the plants, followed by immediate work in subduing them. Thoroughness involves the destruction of every living piece of dodder stem lying within its own length of a host plant.

Cutting and burning infested plants and spraying them with copper sulphate or iron sulphate are methods which have been employed. Spraying has not proved successful as a rule, owing to the impossibility of thoroughly wetting every part of the dodder stems under field conditions. The plants have appeared to be destroyed, but a sufficient number remained to continue growth after receiving a temporary check. Burning is successful when thoroughly done his may or may not destroy the crop roots. The burning may take lace on the infested spot or the cut plants may be removed to be urned elsewhere. Burning on the spot is an advantage, on account of s destroying dodder missed in cutting and seeds which have fallen. urning endangers the life of the roots of the crop, however. The moval of infested plants to another place requires great care to preent any of the pieces of dodder falling on the crop and establishing ew centers of growth, and the use of sacks or some similar means of moval is advised.

In cutting infested plants care should be taken to carry the work r enough on the borders to include all of the dodder. Cutting close the ground is equally important. The recognition of the different abits of different kinds of dodder may be helpful in this connection. mall-seeded alfalfa dodder is confined largely to individual plants, d if all these can be located and destroyed there may be little daner of further damage. This plant grows very low, however, and ere is little hope of saving the crown of individual alfalfa plants. ield dodder spreads in every direction, but irregularly, and all rough the crop plants from their tops to the ground. It may be ifficult to determine the borders of an infested patch. All of the fested area should be cleared, but often the stand may be saved. n the case of clover dodder, particularly in an advanced stage, all he plants of a circular area are killed, while the active growth of he dodder is confined to a band of infested plants immediately urrounding this area. Cutting and burning this ring of plants here it falls will probably be found most effective, because the arpet of dodder stems is so dense and so low that its complete removal is practically impossible. Careful examination of the ground may show individual dodder stems creeping a foot or two farther into the crop than otherwise would be evident. Success depends on destroying such stems. Patches of ground cleared of clover by this dodder may contain its seed. Such areas should be burned over to kill this seed before resowing to clover.

The small-seeded alfalfa dodder as a pest of alfalfa in the West is a problem in itself. It has become so widely prevalent that its permanent eradication locally becomes practically impossible in many cases. Not only is much of the seed used in the West likely to contain its eed, but it is readily carried from farm to farm in irrigating water. unches of dodder-infested hay fall in various places in the field and long the roadsides, and in this way scatter seeds. Thus conditions re conducive to keeping the fields infested.

Methods of reasonable control of this dodder appear to be more romising in the West than attempts to eradicate it. Observations ave shown that low-lying, well-irrigated lands are not infested to the same extent as the higher and drier lands. It is, therefore, possible that confining alfalfa culture to lands capable of abundant irrigation and destroying the stand of alfalfa on the drier land when infested with dodder will tend to reduce the loss from the pest, even though it may remain.

Plowing should precede the seeding of the dodder. In this way all danger of future occurrence of the pest is averted if all infested plants are covered. If the plowing is delayed until after the dodder develops its seed the crop can be burned over, producing a hot fire before the surface soil is disturbed. This should destroy the greater part of the seeds lying exposed on the surface of the soil and in unopened seed vessels. In lieu of either plowing or burning over dodder-sown ground, shallow cultivation, followed by some crop requiring frequent surface tillage, will tend to keep the seeds near the surface and perhaps lead to the destruction of the greater part of them.

It is believed that as a rule dodder plants will not injure such a cultivated crop. This is doubtless true of clover dodder and small-seeded alfalfa dodder. Certain crops might, however, be injured by field dodder or large-seeded alfalfa dodder. The injury to beets in Utah caused by field dodder, previously noted, and the observations of the writer upon the growth and effect of large-seeded alfalfa dodder on various coarse plants justify the recognition of the possibility of damage from these kinds.

It is important in such surface cultivation that the dodder seeds do not become covered too deep, as it is known that they are capable of remaining alive for several years when buried. In one authentic case at least 16 per cent of a quantity of buried seed germinated at the end of three years.

An infested stand of clover or alfalfa may safely be allowed to produce a crop of hay or be used for pasturage or for soiling provided the crop is removed before the dodder produces seed. The removal of a bulky crop aids in the complete covering of the stubble, which is important. [illegible] immediately after the removal of the crop; [illegible] seeds will be buried and possibly prove [illegible] might [illegible] face.

[illegible] dense bunches of [illegible] farmer previously [illegible] seed by recleaning [illegible] without ill effect.

SUMMARY.

(1) Dodder is a parasitic plant dependent on a host plant for its od. It reproduces by means of seeds and from pieces of stems pertted to come in favorable contact with a suitable host plant.

(2) There are several kinds of dodder especially destructive to flax d to leguminous crops.

(3) The dodders exhibit pronounced preferences for certain kinds of st plants, with the result that a crop is not equally subject to injury om different kinds of dodder.

(4) Climatic and weather conditions strongly influence the growth d productiveness of the dodders. Thus, small-seeded alfalfa dodder, common in the West, appears to be unknown in the Eastern States, d clover dodder produces so little seed in this country that its seed rely, if ever, is found in American-grown red clover seed or alfalfa ed.

(5) Dodder seeds are a very common impurity of clover, alfalfa, and x seed in the trade. Certain kinds are more commonly found in mestic than in foreign seed, while the contrary is true of other kinds. w-grade seed imported from Europe generally contains dodder.

(6) Dodder seeds can readily be distinguished from crop seeds by a edsman or farmer using a magnifying glass.

(7) Certain kinds of dodder seeds can be thoroughly cleaned from e best grade of farm seed. Other kinds can not be wholly separated om the seed which carries them.

(8) Some dodder seed is likely to escape removal in recleaning, and e young seeding should therefore be examined for dodder plants.

(9) The dodder plants should be discovered early and destroyed by moval or burning.

(10) Dodder plants should not be allowed to seed, thereby contaminting the land.

(11) Hand methods may subdue the dodder plants if they are not o abundant; otherwise plowing under before they go to seed or rning the stand if seeds have already ripened will be necessary.

(12) The early crop of clover or alfalfa preceding the ripening of e dodder seeds can safely be used as pasturage, for soiling, or in hay aking. The infested stubble should be plowed under immediately.

(13) The most generally effective means of preventing the introducon of dodder is to use seed free from dodder seeds. The purchasing rmer can easily make a reasonably satisfactory test for dodder seed.

(14) Where irrigation is practiced dodder seed may be carried from ace to place in the water used.

FARMERS' BULLETINS.

ing is a list, by number, of the Farmers' Bulletins available for distri-
• bulletins entitled "Experiment Station Work" give in brief the results
its performed by the State experiment stations. Titles of other bulletins
anatory. Bulletins in this list will be sent free to any address in the
s on application to a Senator, Representative, or Delegate in Congress,
retary of Agriculture, Washington, D. C. Numbers omitted have been
, being superseded by later bulletins.

ng of Farm Animals. Pp. 40.
ra and Swine Plague. Pp. 16.
eed and Fiber. Pp. 16.
id How to Kill Them. Pp. 30.
id Other Changes in Milk. Pp. 22.
ases on the Pacific Coast. Pp. 15.
ilage. Pp. 30.
wing for Market. Pp. 24.
nposition and Cooking. Pp. 31.
ture. Pp. 24.
ed and Its Products. Pp. 16.
it Milk. Pp. 32.
il Fertilizers. Pp. 38.
ecting the Cotton Plant. Pp. 32.
ring of Cotton. Pp. 16.
Varieties of Chickens. Pp. 48.
Beet. Pp. 48.
mon Birds. Pp. 48.
Herd. Pp. 30.
it Station Work—I. Pp. 30.
ean as a Forage Crop. Pp. 24.
ng. Pp. 48.
f Curing Tobacco. Pp. 24.
Culture. Pp. 40.
Farm Produce. Pp. 31.
lk on the Farm. Pp. 40.
Geese. Pp. 55.
it Station Work—II. Pp. 32.
and Pastures. Pp. 30.
it Station Work—III. Pp. 32.
in Beef Production. Pp. 24.
ges of the Southwest. Pp. 32.
it Station Work—IV. Pp. 32.
od. Pp. 39.
g of Soils. Pp. 24.
it Station Work—V. Pp. 32.
it Station Work—VI. Pp. 27.
Twig-Borer. Pp. 16.
ure in the South. Pp. 24.
re of Tobacco. Pp. 22.
oils. Pp. 23.
it Station Work—VII. Pp. 32.
od. Pp. 32.
sonous Plants. Pp. 32.
it Station Work—VIII. Pp. 32.
nds. Pp. 23.
eases and Treatment. Pp. 15.
it Station Work—IX. Pp. 30.
'ood. Pp. 31.
ls for Farmers. Pp. 46.
it Station Work—X. Pp. 32.
s to Southern Farmers. Pp. 48.
emies of Shade Trees. Pp. 30.
ng in the South. Pp. 40.
Pp. 30.
Forage Plants. Pp. 48.
it Station Work—XI. Pp. 30.
'rost. Pp. 24.
it Station Work—XII. Pp. 32.
Dairy Cattle. Pp. 48.
it Station Work—XIII. Pp. 32.
. Pp. 20.
re in the United States. Pp. 28.
nterest in Good Seed. Pp. 24.
Bread Making. Pp. 40.
and How to Grow It. Pp. 32.
it Station Work—XIV. Pp. 28.
in Fruit Growing. Pp. 48.
wing in the South. Pp. 32.
it Station Work—XV. Pp. 30.
ecting Tobacco. Pp. 32.
s, and Other Legumes as Food.

122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp. 32.
134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing. Pp. 48.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propagation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.
179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.
183. Meat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
185. Beautifying the Home Grounds. Pp. 24.
186. Experiment Station Work—XXIII. Pp. 32.
187. Drainage of Farm Lands. Pp. 38.
188. Weeds Used in Medicine. Pp. 45.
190. Experiment Station Work—XXIV. Pp. 32.
192. Barnyard Manure. Pp. 32.
193. Experiment Station Work—XXV. Pp. 32.

194. Alfalfa Seed. Pp. 14.
195. Annual Flowering Plants. Pp. 48.
196. Usefulness of the American Toad. Pp. 16.
197. Importation of Game Birds and Eggs for Propagation. Pp. 30.
198. Strawberries. Pp. 24.
199. Corn Growing. Pp. 32.
200. Turkeys. Pp. 40.
201. Cream Separator on Western Farms. Pp. 23.
202. Experiment Station Work—XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work—XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and Their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-Out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. [illegible]
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 1[illegible]
251. Experiment Station Work—XXX[illegible] Pp. [illegible]
252. Maple Sugar and Sirup. Pp. [illegible]
[illegible] The Ge[illegible]
[illegible]
[illegible] The Hom[illegible]
[illegible]

[illegible] Management of Soils to Conserve Moisture. Pp. 30.
267. Experiment Station Work—XXXVII. Pp. 32.
268. Industrial Alcohol: Sources and Manufacture. Pp. 45.
269. Industrial Alcohol: Uses and Statistics. Pp. 29.
270. Modern Conveniences for the Farm Home. Pp. 48.
271. Forage Crop Practices in Western Oregon and Western Washington. Pp. 39.
272. A Successful Hog and Seed-Corn Farm. Pp. 16.
273. Experiment Station Work—XXXVIII. Pp. 32.
274. Flax Culture. Pp. 36.
275. The Gipsy Moth and How to Control It. Pp. 22.
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 40.
278. Leguminous Crops for Green Manuring. Pp. 27.
279. A Method of Eradicating Johnson Grass. Pp. 16.
280. A Profitable Tenant Dairy Farm. Pp. 16.
281. Experiment Station Work—XL. Pp. 32.
282. Celery. Pp. 36.
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. 42.
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. 48.
285. The Advantage of Planting Heavy Cotton Seed. Pp. 16.
286. Comparative Value of Whole Cotton Seed and Cotton-Seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. Pp. 48.
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. Pp. 30.
295. Potatoes and Other Root Crops as Food. Pp. 15.
296. Experiment Station Work—XLI. Pp. 32.
297. Method of Destroying Rats. Pp. 8.
298. The Food Value of Corn and Corn Products. Pp. 40.
299. Diversified Farm[illegible] Under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-Grown Tea. Pp. 16.
302. Sea Island Cot[illegible]ts Culture, Improve[illegible]t, and Disc[illegible]. Pp. 48.
30[illegible] [illegible] Harvesting [illegible]v. Pp. 32.
304. Growing and Cu[illegible] Pp. 39.
305. Experiment Stati[illegible]LII. Pp. 32.
306. Dodder in Relat[illegible]eds. Pp. 27.
307 [illegible] Pp. 16.
30[illegible] [illegible]. 52.
30[illegible] [illegible]ork—XLIII. Pp. 32.
[illegible]ama Diversification Farm.
[illegible]lay [illegible] Burnt-Clay Roads. Pp. 20.
[illegible]ccessful Southern Hay Farm. Pp. 15.
[illegible]vesting and Storing Corn. Pp. 32.
[illegible]thod of Breeding Early Cotton to Es[illegible]pe Boll-Weevil Damage. Pp. 24.
[illegible]ogress in Legume Inoculation. Pp. 20.
[illegible]xperiment Station Work—XLIV. Pp. 32.
[illegible]xperiment Station Work—XLV. Pp. 32.
[illegible]p. 28.
[illegible]n Work in Cooperation with [illegible]. Pp. 23.

Issued Octobe

U. S. DEPARTMENT OF AGRICULTUR

FARMERS' BULLETIN 307.

SELLE: ITS CULTURE AND

BY

P. J. WESTER,

Special Agent, Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., August 4, 1907.

Sir: I have the honor to transmit herewith the manuscript of a paper entitled "Roselle: Its Culture and Uses," by P. J. Wester, Special Agent at our Subtropical Laboratory and Garden, Miami, Fla., and to recommend that it be published as a Farmers' Bulletin.

The roselle plant is adapted for culture in the tropical and subtropical regions of the United States, and should be especially valuable in southern California, Florida, the tropical islands of the United States, and in the Canal Zone. It is used in the South very much as the cranberry is used in the North, and is especially valuable for the making of jellies.

In the preparation of this bulletin the writer has received many valuable suggestions and considerable aid from Dr. Ernst A. Bessey, Pathologist in Charge of the Subtropical Laboratory and Garden, Miami, Fla. Dr. L. O. Howard, Chief of the Bureau of Entomology, identified the soft scale and yellow aphis, and Dr. H. W. Wiley, Chief of the Bureau of Chemistry, made the analyses of the roselle and the cranberry.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

CONTENTS.

Page.
ı.. 5
geographical distribution of the roselle........................... 6
ıaracters and relationships................................. 7
.... 8
and fertilization.. 10
.... 12
ınd marketing the calyces................................. 12
and uses of the fruit..................................... 13
lant for fiber.. 14
.... 14
eases and insect enemies................................. 16
.... 16

ILLUSTRATIONS.

Page.
·lle plant.. 8
ıch of the roselle plant, showing blossoms......................... 9
ıre calyces of the ordinary roselle, somewhat affected by mildew .. 9
ıre calyces of the Victor roselle, somewhat affected by mildew 10
ıre calyces of the Victor roselle................................. 10
·ces of the roselle prepared for cooking by removal of seed pods ... 13

ROSELLE: ITS CULTURE AND USES.

INTRODUCTION.

Fruits and economic plants indigenous to the Tropics are now as ver before attracting the attention of the people of the United ates. Some, such as the avocado and the guava, are natives of e Western Hemisphere; others, like the roselle, are introductions m the Old World.

A strictly tropical plant, the roselle is very sensitive to frosts. is, together with its peculiar habit of blooming late in October gardless of the time when the seed is planted, has restricted the ltivation of the roselle to tropical and subtropical regions. Its tribution, for this reason, has not been so general nor has the plant come so widely known as introduced plants indigenous to the mperate Zone. It is, however, only rational to assume that this jectionable feature could be overcome were persistent efforts made th that end in view and that the roselle, like so many other culti- ted plants which have yielded to changed climatic conditions, uld adapt itself to the shorter summers of a higher latitude.

Introduced several years ago into California and Florida, the selle deserves a wider cultivation than it now enjoys and should ove a valuable acquisition to the tropical islands of the United ates and to the Canal Zone. The cultivation of the roselle is so nple and its requirements so few that in the Tropics and Subtropics should be an indispensable plant in the garden of every family. is fact, in view of its peculiar adaptability for jelly making, should use the roselle to become a plant of considerable importance in the nited States at no distant date. The roselle is probably the only ant in cultivation in which the part utilized for food[a] is the calyx. rather low nutritive value, the thickened calyx possesses excellent alities for the manufacture of jelly and allied products. Prepara- ns made from it closely resemble in color and flavor those made m the cranberry. It is rather singular that its season of maturity so coincides with that of the cranberry.

In Queensland, where the culture of the roselle has in recent years sumed considerable proportions, the fruit is utilized largely in the anufacture of jam. In the United States its principal use would obably be as a substitute for cranberries in the household and in the anufacture of jelly.

---

[a] For analyses showing the food value of the calyx and pod of the roselle, see Farmers' lletin 293, page 14.

HISTORY AND GEOGRAPHICAL DISTRIBUTION OF THE ROSELLE.

The almost total absence of literature relative to the roselle until the last two decades and the lack of cultural varieties would seem to indicate that the culture of this plant is of comparatively recent origin. De Candolle, in his "Origin of Cultivated Plants," 1885, does not mention it.

The writer has examined many of the older works on Indian agriculture without finding more than one referring to the roselle. This work[a] is devoted to fiber-producing plants, which shows that roselle was early cultivated for its fiber. The author says, speaking of roselle, okra, and *Hibiscus abelmoschus:* "The dietical use of these species has been mentioned in order to show that if cultivated on account of their fiber they would also be useful for other purposes"; and it would seem from this quotation that the various uses of the roselle were not generally known at that time. For more than thirty-five years subsequent writers on Indian agriculture maintain absolute silence on the subject, and Duthie[b] mentions the plant only incidentally. Woodrow[c] speaks of its utility for jelly making. In India the plant has been grown chiefly for its fiber. It has apparently not attained much importance for culinary purposes.

The writer has been unable to obtain any data relative to the introduction of the roselle into the British colonies in Australia, where its cultivation evidently is more extensive than anywhere else in the world, as, according to Semler,[d] two large preserving factories utilizing the roselle were in operation in Queensland in 1892. Shinn[e] refers to roselle jam as being shipped to Europe in large quantities.

The Queensland Agricultural Journal, volume 6, page 371, published in 1900, contains the longest treatise on the roselle that has come to the attention of the writer. Its brevity, it being less than five pages in length and containing no references to any previous literature, presupposes the recent development of the industry there. In Queensland the calyces are mainly utilized in the manufacture of jam, but are also, according to the article cited, well adapted for pickles, while the writer also calls attention to the fact that the roselle can be propagated from cuttings and that such plants bear fruit when earlier and more vigorous seedlings bear little or none. The seed is sown in October in Queensland.

The roselle is hardly mentioned in the horticultural literature of the West Indies, indicating that it is an object of indifference there. It was probably introduced from India before 1855, as Royle[a] in a work published that year says that it is there called "red sorrel."

---

[a] Royle, J. F. Fibrous Plants of India, 1855, p. 260.

[b] Duthie, J. F. Field and Garden Crops of Northwestern Provinces and Oudh, 1893.

[c] Woodrow, M. Gardening in India, 1899, p. 183.

[d] Semler, H. Die Tropische Agricultur, 1892, p. 391.

[e] Report of the California Agricultural Experiment Station, 1896–97, p. 382.

In Hawaii the roselle, although introduced long ago, has not ceived much attention.

Eleven or twelve years ago a Mr. Neustadt, of San Francisco, ported seed from Queensland, and the plant was tested and seed bsequently distributed in California by the agricultural experiment ation of that State. The plant received much favorable comment ere from those who tested it at that time.[a] Later literature is lent on the subject.

The name in Florida, "Jamaica sorrel," is evidently an indication at the plant was introduced from Jamaica—at what date the riter has been unable to ascertain—but it was probably not extenvely grown in Florida before 1887, as P. W. Reasoner[b] does not fer to it. Harcourt[c] does not speak of it.

In Florida, as in California, those who have tried the roselle have othing but praise for the plant, and considerable interest in it is anifest, but its culture on a large scale has not yet, to the knowledge f the writer, been undertaken by anyone.

The assumption by Royle[d] that the name roselle is a corruption f the French word "oseille" (the equivalent of the English "sorrel") eems very probable. In the evolutionary stages the name has at lifferent times been spelled "rouselle," "rozelle," and "rosella."

BOTANICAL CHARACTERS AND RELATIONSHIPS.

Roselle (*Hibiscus sabdariffa* L.), or Jamaica sorrel, as it is sometimes called, is an annual from the Tropics of the Old World belonging to the large family Malvaceæ. Itself furnishing the roselle fiber of commerce, it is closely related to several genera containing fiber-producing plants: Sida, Malva, Althea, and Lavatera. Its most important relative is cotton (*Gossypium* sp.). Of vegetables, okra (*Hibiscus esculentus* L.) is related to the roselle. Among related ornamental plants may be mentioned species of Abutilon, Hibiscus, Althea, and Malva.

The habit of the roselle (fig. 1) is similar to that of the cotton plant; the stem is reddish, branching profusely. As usually planted—that is, in February and March—the roselle attains a height of from 5 to 7 feet. The leaves on the young plants are entire; as the plant increases in size the leaves change to palmately five parted; later, the leaves in whose axils the flowers are borne are three parted. The large, almost sessile yellow flowers, each with a red eye, are usually borne singly in the axils of the leaves (fig. 2). They fade before the day is past and the subsequent enlargement of the calyces is then very rapid. In less than three weeks they attain their full size and are ready for picking (figs. 3, 4, and 5). If the "fruit," if we may so call it, is not now picked and the seed is allowed to mature, the plant dies early in January. There are in the axils of the leaves several latent flower buds, and when the calyces are picked as soon as they are full grown these buds develop and the productivity of the plant is greatly increased.

---

[a] Report of the California Agricultural Experiment Station, 1897-98, p. 236.

[b] Bul. 1, Division of Pomology, U. S. Dept. of Agriculture, 1887.

[c] Harcourt, H. Florida Fruits, 1886.

[d] Royle, J. F. Fibrous Plants of India, 1855, p. 260.



Fig. 1.—Roselle plant.

VARIETIES.

The roselle being a plant of recent cultivation and one that only to a slight extent has been exploited for commercial profit except as a fiber plant, it having been grown mostly as a curiosity in the gardens interested individuals without any thought of improving the

, it is only natural that no cultural varieties have developed.[a] out any thought of improving the roselle, the writer during the ner of 1904 obtained a few plants in Cocoanut Grove, Fla., from W. A. H. Hobbs and planted them in the Subtropical Garden, ni, Fla., in order to have the plant under observation.

the plants bloomed and fruited the marked variation in the s on the different plants suggested that there was an excellent rtunity to breed a new and distinct strain of the roselle, and at suggestion of Prof. P. H. Rolfs, at that Pathologist in charge of the Subtropical ratory and Garden, seed was saved the best plants. With this seed for the writer began systematized breed- he next year. A number of the plants ing in the autumn of 1906 had calyces of such large size and exhibited such distinct characters that they were thought worthy of naming as a variety, and the name "Victor" has therefore been given to this sort.



FIG. 2.- Branch of the roselle plant, showing blossoms.

The improvement of these plants over the common kind is best illustrated in figure 5. When it is remembered that these are from plants in the second generation, the improvement is remarkable. As it was thought that these plants might be a special strain, inquiries were made to find out whether the original plants had any previous history, but this inquiry only served to confirm the fact that they were of the ordinary variety grown in Florida. Mr. William A. Taylor, of the Bureau of Plant Industry, suggested to the writer that this capacity for improvement might be due to the fact that the lle has previously been principally grown for fiber, which doubt- is correct. Another attempt to breed the roselle was made by H. J. Webber in the nineties at Eustis, Fla., where the Subtropi- Laboratory was then located. This work was, unfortunately, ninated by the severe freeze of 1895.

—Mature calyces the ordinary ro-, somewhat af- ed by mildew. ree-tenths nat- l size.)

---

[a] ince this article was written O. W. Barrett, of the Bureau of Plant Industry, has med the writer that he has heard of a variety with straw-colored calyces. This t, however, has not been verified.

The plants of the Victor variety are inclined to be a trifle more dwarf than the common kind, but the foliage is similar. The measurements of the calyx of the common variety are, length 33 mm., diameter 22 mm.; in the improved type the measurements are 49 mm. and 28 mm., respectively. The increase in size is thus seen to be rather more in length than in diameter. Calyces of the improved type have in some instances been 60 mm. long and 38 mm. in diameter. (See the two detached calyces in fig. 5.) The improved type is also distinct in being more strongly ribbed longitudinally and in having the calyx not so closely appressed to the seed pod as in the common variety. It is frequently inclined to be convolute at the apex.



FIG. 4.—Mature calyces of the Victor roselle, somewhat affected by mildew. (Three-tenths natural size.)

CULTIVATION AND FERTILIZATION.

The roselle will thrive on any soil that is moderately rich or that is supplied with the necessary plant food in the form of commercial fertilizer. Stable manure should be used sparingly only and should be supplemented by phosphates and fertilizers containing potash, as an excess of ammonia in the soil tends to the development of large plants at the expense of their productiveness. This is particularly true on low-lying land where moisture is abundant, and the high pine lands in Florida are for this reason preferable to the muck and prairie lands. Land that is subjected to inundations and soil insufficiently drained should be avoided. The plant has been found well adapted to the clayey soil of California. Henricksen[a] says that a sandy loam is preferable to other soils.



FIG. 5. Mature calyces of the Victor roselle. (Two-fifths natural size.)

The roots of the roselle descend to greater depths than those of many other crops, and the land should be plowed deep and, when the il is clayey, well pulverized. This plant is very much subject to ot-knot nematodes (*Heterodera radicicola*) and should not be planted land infested with this pest, as that would only result in almost solute failure.

---

[a] Bul. 171, Office of Experiment Stations, p. 38.

The roselle always comes to the market at the same time of the ar, and, as no literature on the subject that had come to the atten-on of the writer mentioned any attempt to grow it successively, veral sowings were made in 1906 at the Subtropical Laboratory at ifferent times of the year, to note the influence on the habits of rowth, the season of maturity, and, possibly, the size of the calyx. hese plantings were made as follows: No 559, April 1; No. 560, ay 1; No. 561, June 1; No. 562, June 23.

Besides these, seeds from large selected pods were sown June 26 (No. 42). Plant No. 542 came into bloom October 26, a few days in dvance of Nos. 560, 561, and 562. A few days later bloom was noted n No. 559. Notes made in 1905 show that plants from seed sown on une 10 bloomed October 25. The plants from the earlier sowings aturally developed into large plants, with greater bearing capacity. his advantage was offset, however, by the fruits being to a marked egree smaller than those from later sowings. A comparison of the ifferent plants in this experiment indicates that to combine high ield with the production of large pods the seed should be planted bout May 15 in south Florida.

Make the seed bed in a place sheltered from high winds and work in horoughly a moderate quantity of stable manure or commercial fer-ilizer. Sow the seed thinly in drills 6 inches apart, covering the eed from ¼ to ½ inch; then firm the soil and, if dry, water thoroughly. he seed will germinate in a few days. If the weather is dry, the oung plants should be watered as occasion requires. When the lants are 3 to 4 inches high they are ready for transplanting to the ield.

The plants should be set out in rows 6 to 10 feet apart and 4 to 8 eet apart in the row, according to the fertility of the land and the upply of moisture. The seedlings are easily transplanted if proper recautions are taken. The work should preferably be performed on cloudy day or late in the afternoon. Where a few plants are esired for home use only it will be found advantageous to sow a few eeds where the plants are to remain permanently and when the lants are well developed to thin out to one plant to a hill.

Experiments with different fertilizers have been started at the Sub-ropical Laboratory, but have not been carried on for a sufficiently ong time to indicate the best form in which the fertilizer should be pplied. Meantime a formula of nitrogen, 4 per cent; potash, 7 per ent, and phosphoric acid, 6 per cent, has given good results. One-third of the actual ammonia is derived from nitrate of soda and the other two-thirds from dried blood. The sources of potash and phosphoric acid are muriate of potash and acid phosphate, respectively.

The fertilizer should be applied at the rate of from 1,000 to 2,000 pounds to the acre, according to the fertility of the land. On lands rich in ammonia the nitrogenous elements should be greatly reduced. It should be understood that this applies to Florida soils and conditions. The amount, and possibly the formula, would probably have to be modified in other sections. In the sandy and leachy soils of Florida it will be found advantageous to make several small applications instead of applying the total quantity at the time of planting. No cultivation is necessary, except to stir in the fertilizer and to keep down the weeds while the plants are small. When the ground is well shaded by the plants cultivation may be discontinued.

YIELD.

During 1906 experiments were well under way to ascertain the total yield of the roselle plant, but a hurricane in October inflicted so much damage on the plants in the experimental area that accurate data were unobtainable. Henricksen[a] quotes the yield as four pounds of fruit to each plant, averaging two pounds of calyces, the useful part, and adds, "Plants observed at Pueblo Viejo in sandy loam were estimated to yield double that amount."

HARVESTING AND MARKETING THE CALYCES.

In less than three weeks from the time of flowering, the calyces are ready for picking. In south Florida the first fruit is gathered about the middle of November.

It has been already pointed out how the yield may be largely increased by picking going over the field every few days to pick the full-grown calyces, which will force the plant to send out new flower buds. By these repeated pickings the plants are forced to fruit continuously until late in February, whereas otherwise they would cease to bear in December. Moreover, the calyces are more brittle and more easily broken from the plants while young and tender, and in the manufacture of jelly make a lighter red and a more transparent product than those from the more mature fruit. On poor land it would be of advantage to make a small application of fertilizer to the plants in December.

The fruit is seen at present in local markets only and is sold by the quart. Its excellent qualities for making a sauce so closely imitating in flavor the cranberry as to deceive the very elect are not well known by the public or it would be a formidable rival in the South to that fruit, on which transportation charges are necessarily high owing to the great distance it must be transported. The crisp

---

[a] Bul. 171, Office of Experiment Stations, p. 38.

 appearance of the roselle is diminished by being too long
ınds of the dealer, but this does not indicate deterioration
ful qualities.

COMPOSITION AND USES OF THE FRUIT.

roselle it is the large, reddish, fleshy calyces surrounding pod that are used for food. As already stated, a considerable has lately been developed in Queensland, where the fruit is to jam and exported. There is no reason why a similar should not grow up in the United States. The usefulness selle as a substitute for cranberry sauce has been emphasized and its qualities for making jelly are unexcelled. In the States it would probably become of greatest importance in ufacture of jelly.

alysis of the calyx was made by the food laboratory of the of Chemistry, which at the same time made an analysis of berry for comparison, the uses of the two fruits being so It will be seen from these analyses (see table below) that the nts of the two fruits occur in nearly the same proportions, lly the only difference being that traces of benzoic acid in some present in the cranberry, while absent from the roselle.

*mparative analyses of the composition of the roselle and the cranberry.**

	Roselle.	Cranberry.
	Per cent.	*Per cent.*
	88.91	88.53
	11.09	11.47
	.89	.25
ble matter)	6.67	4.60
lic)	2.77	2.74
gar as invert	.33	1.90
	.03	.10
	Absent.	Present.
	Absent.	

of fruit of roselle, 6.11 grams; cranberry, 0.94 gram. Percentage of edible portion: Roselle, calyx minus the portion of its base which is cut away in removing the seed pods, 50.22; 00.

paring for cooking, take the pod between the thumb and r of the left hand, stem end up; cut off the stem and the d of the ca- iere the seed mnited with x, when a essure with ers holding will force seed pod. 6.) After g in this calyx may for making sauce, jam, and transparent, bright red jelly. her dishes will suggest themselves to the thrifty housewife.



FIG. 6.—Calyces of the roselle prepared for cooking by removal of seed pod. (Four-fifths natural size.)

The calyces may also be separated from the seed pods and dried in the sun or in an evaporator, and are in this form, according to Mr. O. F. Cook,[a] occasionally seen in the markets of the Tropics. The juice of the calyces could probably be boiled to a sirup and used as a flavoring extract at soda fountains, and the fruit might also be used in coloring jellies, jams, or similar products as a substitute for coal-tar dyes where a bright red color is desired.[b]

USE OF THE PLANT FOR FIBER.

While this paper has been prepared primarily with reference to the utilization of the fruit of the roselle, the plant is, as previously stated, grown in India for its fiber, which is used in the manufacture of cordage and coarser textile products. Considered from this standpoint, the plant without further breeding could be cultivated over a large area in the Southern States, as the crop would be harvested before it was damaged by early frosts. On account of the vigor of the plant and its easy cultivation it is well worth a trial with this end in view. "For this purpose the crop is cut while in flower, dried, made into bundles, and soaked in water for fifteen or twenty days. It is then possible to wash out a strong silky fiber known in commerce as roselle hemp, considered by some to be the equal of jute. The leaves are sometimes used as a salad and the seeds are supposed to have medicinal properties. They are also fed to cattle and poultry."[c]

BREEDING.

The roselle is an annual, and consequently seed must be saved every autumn for planting the next spring. To improve the strain the grower should go over his field repeatedly when the fruit is setting and tag such plants as combine great vigor with large bearing capacity and have calyces large and well formed. To obtain the best results in a comparatively short time it would be expedient to bag and hand-pollinate the flowers. When the seed pods turn yellow they should be gathered from time to time and dried, after which they are easily thrashed out. Keep the seed in a dry place secure from moths and rats.

During a long period of cultivation nearly all of our vegetables have become so domesticated that they may be forced to grow and produce at will where frostless conditions prevail; hence we have fresh tomatoes, eggplants, etc., in midwinter in the South. The selle, not having had this advantage, can at present be cultivated ly where frost is unknown, or nearly so, as its growing period is very ng and its blooming and fruiting season extends late in the year. ould it, however, be found desirable to grow the plant in temperate imates, there is no reason to doubt that the roselle would adapt elf to shorter summers. Its near relative, Sea Island cotton, is a riking illustration of how a plant may adapt itself to entirely new nditions, and the following quotations from Dr. H. J. Webber are, this instance, of timely interest:

---

[a] Contributions from United States National Herbarium, Vol. VIII, pt. 2, p. 160.

[b] After this bulletin was prepared the writer was informed by Mr. W. W. Tracy, sr., of the Bureau of Plant Industry, that he, together with Mr. Coulter, made jelly from the small and tender branches several years ago. He adds that the leaves were picked off before boiling the stems.

[c] Contributions from the United States National Herbarium, Vol. VIII, pt. 2, p. 159.

> According to tradition and the reports of growers, Sea Island cotton when first intro- ced into this country from the West Indies was a perennial unsuited to the duration the seasons of the latitude of the Sea Islands off South Carolina and Georgia, where seldom matured fruit. However, through the selection of seed from early maturing dividual plants and through better methods of culture, there has developed an proved race which now seems to be thoroughly adapted to the conditions of growth the regions referred to. Furthermore, under the continuous and rigorous selection which the plants have been subjected, the fiber has gradually improved, and now at produced along the coast and on the islands lying off South Carolina and Georgia considered superior to that grown in any other part of the world. The custom of refully selecting the seed has grown with the industry, and may be said to be insep- able from it, and it is only by such careful selection that the staple can be kept up its present superior excellence. Several different strains have been developed, d are maintained by different growers selecting with different ideals in view. * * This method and similar ones employed by numerous other growers are plicable, with slight variations, to most of our common crops, such as corn, wheat, c.[a]
>
> About 1,785 seeds of this cotton were brought to Georgia from the Bahamas. Not- ithstanding the good care they received and the mild winter, the plants were killed wn, but they came up again from the roots and with this start succeeded in ripening few seeds before the first frost in the fall. The earliest of these seeds were sown turn and by continuing this process of selection the flowering period became earlier d earlier, until now the plants ripen a large proportion of their seeds before frost, en along the coasts of the Carolinas. Besides striving to obtain earlier maturing rts, very careful selection has for years been made with a view to increasing the ngth, fineness, and strength of the staple. The selection is regularly practiced by l intelligent growers and to-day it may be regarded as one of the necessary cultural ethods. Every year a special patch of cotton is grown from selected seed; the plants this patch are examined very carefully and the seed of the best individuals retained planting a similar patch next year, the seeds of the remaining plants being used plant the general crop. Under such continuous and rigorous selection the length d fineness of the fiber have gradually increased until it is now recognized as superior that grown anywhere else in the world and commands the highest price in the rket.[b]

With the object in mind of breeding an early-ripening variety of e roselle the breeder might find it expedient to harvest some of the ed before it is fully mature, as it has been shown that plants from een seeds—tomatoes, for instance—have a tendency to mature uit earlier than plants from ripe seeds.

---

[a] Yearbook, Department of Agriculture, 1898, p. 358.

[b] Yearbook, Department of Agriculture, 1899, p. 490.

FUNGOUS DISEASES AND INSECT ENEMIES.

The only disease that has so far been noted on the roselle is a mildew (*Oidium* sp.) which attacks all parts of the plant above ground and under favorable conditions appears capable of doing considerable damage in discoloring the fruit and in lessening the vitality of the plant. (See figs. 3 and 4, showing mildew on the calyces.) Where its presence was noted, however, the greater part of the crop was gathered before the mildew made its appearance, making the loss of fruit comparatively small. Experiments have not been made to find a remedy, but sulphuring the plants would probably be found to be effective. Bordeaux mixture would without doubt prove efficacious, but would also in all probability tend to discolor the manufactured product.

The most serious enemy of the roselle is the root-knot nematode (*Heterodera radicicola*). A cheap and effective remedy for this pest has not yet been found and infested lands should not be planted with the roselle.

The soft scale (*Coccus hesperidum*) has been noted on the roselle, but has not yet assumed the character of a pest. Its activity is restricted to the stem and lateral branches close to the ground. The scale is distributed by a small black ant.

The cotton stainer (*Dysdercus suturellus*) has been observed on the plants in limited numbers, but does not appear to be injurious.

The yellow aphis (*Aphis gossypii*) has been known to do considerable damage on individual plants by attacking the leaves and flower buds and causing the calyces to drop. It has not, to the knowledge of the writer, appeared as a serious pest. Remedies for this species, better known as the melon or cotton aphis, are considered in Circular No. 80 of the Bureau of Entomology of this Department.

SUMMARY.

The roselle is an annual from the Old World Tropics.

It is extremely sensitive to frosts, and can at present be grown for its fruit only in tropical and subtropical countries.

Being easily cultivated when the climate is favorable, the roselle should be in the garden of every family, and on account of its excellent qualities for making jellies, jams, etc., it is certain to become an important plant in the manufacture of those products.

The young stems also make good jelly. For such use the plant can be grown almost anywhere in the North or South.

By proper methods of breeding it is possible to obtain strains with larger calyces. Probably earlier bearing races can be obtained by careful selection of the earliest flowering plants.

O

Issued September 7, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 308

GAME LAWS FOR 1907.

A SUMMARY OF THE PROVISIONS RELATING TO SEASONS, SHIPMENT, SALE, AND LICENSES.

BY

T. S. PALMER, HENRY OLDYS, and CHAS. E. BREWSTER
Assistants, Biological Survey.

(Revised edition, October, 1907.)

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Biological Survey,
Washington, D. C., August 27, 1907.

Sir: I have the honor to transmit herewith for publication in the series of Farmers' Bulletins a summary of the game laws for 1907 relating to seasons, shipment, sale, and licenses, prepared by T. S. Palmer, Henry Oldys, and Charles E. Brewster, of the Biological Survey. This bulletin is similar in scope to those issued annually since 1902 and includes changes in the laws made during the present year. The information here given is greatly condensed in order to present the essentials of the laws as compactly as is compatible with clearness. The section relating to legislation includes references for most of the new laws and a summary of the more important bills under consideration which failed to pass—features which are believed to be of special value to those interested in game protection.

Respectfully,

H. W. Henshaw,
Acting Chief, Biological Survey.

Hon. James Wilson,
Secretary of Agriculture.

CONTENTS.

Page.

Introduction 3
- Scope of the bulletin 3

Legislation of 1907 3
- New laws passed in 1907 6
- Bills which failed to pass 9

Close seasons 11
- Close seasons for game in the United States and Canada, 1907 11

Shipment of game 25
- Federal laws 25
- Marking packages 25
- State laws prohibiting export 26

Sale 34
- Sale prohibited all the year 34
- Sale in close season 34
- Sale in open season 35

Licenses for hunting and shipping game 39

Appendix.—Tables showing close seasons for game under county laws 49
- Maryland 49
- North Carolina 51

ILLUSTRATIONS.

Page.

Fig. 1. States and Provinces which prohibit export of game 32
2. States and Provinces which prohibit sale of game throughout the year. 3
3. States and Provinces which require residents to obtain hunting licenses. 3
4. States and Provinces which require nonresidents to obtain hunting licenses ....

GAME LAWS FOR 1907.

INTRODUCTION.

SCOPE OF THE BULLETIN.

object of the present bulletin is to present in convenient form imary of the game laws of the United States and Canada which n seasons, shipment, sale, licenses, and limitations on amount nay be killed. Its purpose is, primarily, to furnish information rning restrictions on trade in game, knowledge of which is nec- in the enforcement of the Federal statute regulating interstate ierce in game, commonly known as the Lacey Act. Hence such sions as relate to methods of capture of game, enforcement of disposition of fines and fees, and such matters as are of special al application are not included. These may be found elsewhere, r in summaries prepared for the use of sportsmen by game asso- ns, railroad companies, and private publishers, or from the laws selves, which in most cases may be had in separate form from game officials[a] or secretaries of state.

e demand for a publication containing a concise summary of exist- ame laws, both Federal and State, apparently increases in direct rtion with interest in game protection, and the need of such a iary constantly grows with the increasing complexity of game ation and the prevalence in some States of county laws. In land and North Carolina the legislatures enact separate laws for ifferent counties; in New York, Oregon, and Washington laws for ent districts or sections of the State are fairly numerous and ecoming more so. In Louisiana the close season for deer must ed by the police jury of each parish, and in Nevada and Virginia y officers are empowered to shorten or shift open seasons. In the ving tables such local laws and regulations are included as fully ssible, but as some are inaccessible and others are likely to be ed at any time an absolutely complete and accurate summary of is impracticable.

LEGISLATION OF 1907.

1907 regular legislative sessions were held in all of the States erritories except seven[b]—Kentucky, Louisana, Maryland, Mis- pi, Ohio, Oklahoma, and Virginia—and also in all the Provinces

---

lirectory of these officers with their addresses and a list of the commissions issue fish and game laws in separate form may be found in Circular No. 62 of ological Survey, U. S. Department of Agriculture, 1907.

the following résumé the acts of Vermont are included, as the session of its ture in 1906 occurred too late in the autumn to incorporate the changes in the law bulletin of that year.

of Canada. Game bills were under consideration in each of these States and Provinces and new laws were passed in all except Arizona, Georgia, Nevada, New Jersey, North Dakota, and British Columbia. Including the 71 local laws passed in North Carolina, the statutes affecting game numbered in all about 180. Several States, including Alabama, Missouri, Texas, and Utah, adopted entire new game laws, and Alabama, South Dakota, and West Virginia passed the American Ornithologists' Union law giving complete protection to nongame birds.

In the number of bills introduced and in the general demand for change of some sort the record of 1907 is second to that of no previous year, although the number of bills actually passed was equaled by the legislation of 1905. In spite of the large number of bills introduced there was a manifest tendency toward conservatism. Most of the changes of season were made with a view of securing greater protection. In several States the seasons were closed entirely for certain kinds of game, and in others measures were allowed to fail rather than pass in an unsatisfactory form. Much attention was given to licenses as a means of providing funds for game protection, and also to legislation extending or strengthening the warden service.

Among the novel or more striking features of the year's legislation were acts prohibiting the use of automatic guns for the hunting of game in Pennsylvania, New Brunswick, and Ontario; establishing an elective office of game commissioner in Alabama; providing for an optional license in Tennessee for a resident hunting with verbal permission on lands where otherwise he would have to obtain written consent; authorizing rewards for information leading to conviction for killing big game in Wyoming, and the increase in such rewards in Minnesota; requiring the State warden of Idaho to investigate means of destroying noxious animals; providing that all heads of big game secured in Alberta must be stamped or branded by the department of agriculture before being sold; requiring that anyone who kills a deer in Vermont must report the fact and exhibit the head to the nearest game warden; limiting hunting and lumber camps in Maine to the use of 6 deer a season; applying the residue over and above expenses of the game-protection fund in Missouri to the improvement of roads; and limiting hunting by able-bodied men in two Florida counties to taxpayers.

Licenses.—The license system was adopted for the first time in Alabama, California, Connecticut, Rhode Island, and Texas. Alien licenses were established in Alabama, California, Connecticut, Maine, New Hampshire, South Carolina, Texas, and Utah; nonresident licenses in Alabama, California, Connecticut, Massachusetts, Rhode Island, and Texas, and resident licenses in Alabama, California, Connecticut, Tennessee, and Utah. Michigan, Vermont, and Wyoming established bird licenses, and Alberta and Nova Scotia guide licenses. Nova Scotia and Ontario made provision for licenses for guests of residents, Missouri changed its State license to a county license, and Tennessee and Alberta provided licenses for game dealers, that of Tennessee being graduated in fee according to the population of the town in which it might be used. Two optional licenses were established, that of Tennessee already mentioned, and a license for hunting deer in New Brunswick, the issue of which was made discretionary by the surveyor-general of the Province. Prince Edward Island provided a special license for nonresidents paying taxes on real estate valued at $325 or more, Massachusetts and Rhode Island adopted identical provisions permitting members of existing fishing and hunting clubs to secure nonresident licenses on payment of a fee of $1. Ontario increased the nonresident fee from $25 to $50, and Saskatchewan increased the fees charged nonresidents for hunting big game and birds from $25 to $100 and from $15 to $50, respectively. Three counties in Florida established special licenses. As a result of the year's legislation, hunting licenses of some sort are now required in all the provinces of Canada and all the States and Territories, except Alaska, Arkansas, District of Columbia, Georgia, Indian Territory, Nevada, New Mexico, and Oklahoma.

Warden service.—In the legislation of the year a notable tendency is observable toward consolidation of the related offices of fish, game, and forestry protection. Michigan added forestry to the duties of the game and fish warden, with an increase of salary from $2,000 to $3,000. Montana made the State warden ex officio fire warden and a member of the board of fish commissioners, increasing the salary from $2,000 to $2,400. Texas extended the duties of the fish and oyster commissioner to include game, with an increase from $1,800 to $2,500 in salary, and with provision for a deputy in charge of game matters at $1,800. Ontario abolished the game commission and combined the work of fish and game protection under the charge of the former chief warden, changing his title to superintendent of game and fisheries. (An attempt was likewise made in Washington to consolidate game, fish, and forestry protection, but the proposed measure failed to pass.) Increases in the number of salaried deputies were also made in several States. In Illinois the district wardens were increased to 16, in New York the protectors from 65 to 75, Montana added 4 district wardens to the force already employed, and Michigan 10 district deputies.

Preserves.—In several States measures were enacted to encourage propagation of game or to provide for the establishment of State or private preserves. In California the State fish commissioners were authorized under certain conditions to set aside private lands as State game preserves. Massachusetts made an appropriation for the acquisition of lands on Marthas Vineyard as a preserve for the heath hen, and authorized the use of a part of the Middlesex Fells for the establishment of a zoological park. Minnesota gave absolute protection to wild animals and birds on State forest reserves, lands, and parks. Pennsylvania prescribed that State game preserves should not exceed 9 miles in circumference, or be located within 25 miles of each other; that there should be a perpetual close season for game and wild birds upon them; and that it should be unlawful to take firearms or dogs upon such preserves at any time, or to enter them during the open season for game. Alberta established two Provincial preserves; and Indiana, Illinois, North Carolina, and Vermont adopted provisions specially exempting from certain restrictions deer raised in private preserves.

Miscellaneous.—Among the miscellaneous provisions adopted should be mentioned the authorization by Pennsylvania and Wisconsin of the confiscation of boats and other appliances used in unlawful hunting and the provision made by New Hampshire, Massachusetts, Rhode Island, and New Brunswick, permitting the use of shotguns in protecting crops from the depredations of deer.

NEW LAWS PASSED IN 1907.

Alabama.—One act: Providing a State game and fish commissioner at $2,500 per annum to be elected every four years, shortening seasons, fixing bag limits, prohibiting all export and sale, requiring $1 and $3 resident and $15 nonresident and alien licenses, and giving complete protection to nongame birds (No. 18).

Alaska. No legislation.

Arizona.—No legislation.

Arkansas.—Laws not received.

California.—Four acts: Establishing $1 resident, $10 nonresident, and $25 alien licenses (ch. 206); altering the deer and dove seasons, opening a season for gray squirrels, placing a bag limit on squirrels and reducing that on ducks, removing protection from all fish-eating birds, encouraging the establishment of private preserves by authorizing the posting of private lands and having them registered with and controlled for 1 to 5 years by the State board of fish commissioners for such purpose (ch. 433); and requiring that artesian wells be kept capped except when used for irrigating purposes, thus restricting use of water by ducking clubs.

Colorado.—Three acts: Providing for a deputy game and fish commissioner, extending close seasons for elk, antelope, mountain sheep, and crested quail, permitting the hunting of does and fawns, giving absolute protection to wild turkeys and wild pigeons and a close season to plover, shortening curlew season, and reducing number of ducks allowed in possession at one time from 100 to 50 (chaps. 185, 186, 187).

Connecticut.—Four acts: Extending prohibition of sale of quail, grouse, and woodcock to 1911 (ch. 70); reducing the bag limit on rail and prohibiting spring shooting of snipe and shore birds (ch. 71); and of waterfowl (ch. 72); providing a hunting license system with fees of $1 for residents, $10 for nonresidents, and $15 for aliens, the proceeds to be used for the preservation and propagation of game (ch. 153).

Delaware.—One act: Prohibiting shooting of ducks on Indian River and Rehoboth Bay from boats not propelled by oars.

District of Columbia.—No legislation.

Florida.— Five local acts: Affecting seasons and hunting licenses in Clay County (ch. 5775), seasons, licenses, bag limits, and warden service in Hernando County (ch. 5776), and licenses and warden service in Sumter County (ch. 5783); and limiting the right to hunt to taxpayers in Taylor (ch. 5783) and Wakulla (ch. 5784) counties.

Georgia.— No legislation.

Hawaii.—One act: Providing for protection of birds beneficial to forests (ch. 104).

Idaho.—Three acts: Strengthening the warden system, providing for capturing game for propagation or scientific purposes, permitting shipment within the State and export of bag limit by resident licensees, restricting cold storage of game, and shortening seasons of practically all game (pp. 112, 475); and providing for the extermination of predatory animals (p. 301).

Illinois. —One act: Strengthening the warden service, adding a number of imported birds to the game list, extending the close seasons for grouse, pheasants, and wild turkeys for several years, shortening the squirrel season, reducing bag limits, and authorizing the trapping of game for propagation or restocking purposes (p. 344).

ndiana.—Three acts: Increasing protection of squirrels (ch. 94), woodcock, doves, ... ducks, removing protection from rabbits, reducing bag limits, permitting resident armers to hunt on their own lands without license, providing for restocking covers rom the proceeds from resident licenses, increasing restrictions on cold storage (ch. 16), and exempting deer raised in private parks from protection (ch. 219).

ndian Territory.—No legislation.

owa.—One act: Giving complete protection to English and Chinese pheasants to .5 (ch. 134).

ansas.— Five acts: Giving complete protection to Hungarian partridges and Eng- [illegible] d Chinese pheasants for six years (ch. 218); increasing protection of prairie [illegible] ns in Butler County (ch. 220) and of quail, grouse, and prairie chickens in Raw- ins County (ch. 221); prohibiting sale of refrigerated undrawn poultry and game [illegible] 187); and providing for extension of the State fish and game hatcheries (ch. 39).

aine.—Four general acts: Giving complete protection to squirrels for four years [illegible] h. 85); extending the duck season (ch. 158); limiting export of deer by residents o one a season, permitting residents to export 6 partridges, 10 woodcock, and 10 ucks under a $5 export license for each species, allowing 6 deer a season to each umber camp (ch. 181); and providing a $15 alien license (ch. 118). Five special [illegible] ts: Increasing protection of de[illegible] n the town of Isle au Haut (ch. 63) and the ounties o[illegible] umberland (ch. 414 [illegible] York (ch. 420) and extending the season for [illegible] [illegible] [illegible] [illegible] 281 and [illegible] ll ducks in Lincoln County

Massachusetts.—Eleven acts: Protecting gulls (ch. 99), loons and eagles (ch. 118), and hawks and owls (ch. 250); abolishing the special seasons in Bristol County (ch. 161); shortening the squirrel season (ch. 166); establishing a $10 nonresident license with exemptions in favor of nonresident owners of real estate and members of existing fishing and hunting clubs (ch. 198); restricting duck hunting in Dukes County (ch. 264); authorizing the protection of crops from deer (ch. 307); providing for establishing a refuge on Marthas Vineyard for the heath hen (ch. 504), and making minor changes (chaps. 299, 300).

Michigan.—Seven acts: Adding forest protection to the duties of the State warden and increasing his salary to $3,000 (No. 264); increasing the warden force (No. 448); protecting European partridges for five years (No. 271); altering arrangements for transporting deer after end of season (No. 468); providing a $10 nonresident small-game license (No. 529); and making minor changes in the season for waterfowl (Nos. 301, 495).

Minnesota.—Three acts: Increasing the salary of the executive agent to $2,500, providing for rewards for convictions for illegal hunting, exempting from license requirement residents not over 21 years old, making resident licenses expire Dec. 15, and altering a few other details of the old law (ch. 469); authorizing arrest without warrant, prohibiting use of firearms within 3 miles of cities with population of 50,000 (ch. 300); and giving absolute protection to wild animals and birds on State forest reserves, lands, and parks (ch. 45).

Missouri.—Two acts: Abolishing regular deputy wardens, prohibiting export of game from county except a limited bag by a sportsman, permitting sale of imported game during open season and of domestic game in county of capture, penalizing the sale of game under a false name, permitting hunting without license in county of residence and providing special $1 licenses for hunting in adjoining counties and $2.50 county licenses for rest of State, restricting the nonresident license to the county of issue, removing protection from does and fawns, changing the squirrel and turkey seasons, closing the season for prairie chickens for three years (p. 277); and providing for calling a grand jury in each county at least once a year to investigate game-law violations (p. 320).

Montana.—Three acts: Making the State warden ex officio fire warden and a member of the board of fish commissioners and increasing his salary to $2,400 (ch. 147); opening a season for antelope with a bag limit of 1 a season (ch. 166), and lengthening the deer season fifteen days (ch. 124).

Nebraska.—One act: Prohibiting sale of all game, shortening seasons, curtailing bag limits, and giving absolute protection to deer and antelope, with a $100 fine for their unlawful killing.

Nevada.—No legislation.

New Hampshire.—Four acts: Giving absolute protection to gray squirrels to 1913 (ch. 76 ; permitting the hunting of deer only with shotguns, opening a season for deer in the southern half of the State, permitting protection of crops from deer (ch. 130); adding woodduck, Bartramian sandpiper, and killdeer to the list of protected game birds (ch. 52); increasing real estate holding necessary for exemption from nonresident license requirement, shortening quail, ruffed grouse, woodcock, and Wilson snipe season, and lengthening those for other upland game, shorebirds, and ducks, and establishing an alien license (ch. 36).

New Jersey.—No legislation.

New Mexico.—One act: Changing seasons for deer, doves, and quail, and authorizing the county commissioners to extend the open season for quail two months in any precinct on petition of 25 resident householders (ch. 105).

New York.—Six acts: Making the deer season two weeks earlier (ch. 668); modifying the transportation season conformably (ch. 666); increasing the number of game protectors from 65 to 75 (ch. 519); and making minor changes relating to rewards (ch. 96) and seasons in Dutchess County (ch. 92) and Lewis County (ch. 48).

North Carolina.—Seventy-one local acts, the most important of which were four prohibiting the hunting of deer and pheasants (ruffed grouse) to November 1, 1910, in 17 counties, with an exemption authorizing the killing, sale, and use of deer raised in preserves (ch. 358); establishing close seasons for deer and ducks in Beaufort County (ch. 384), for deer in Hertford County (ch. 423), and for upland game birds in Columbus County (ch. 505).

North Dakota.—No legislation.

Oregon.—Four acts: Opening the season for male deer one month earlier (ch. 182); protecting quail and Mongolian pheasants until January 1, 1912, in Grant, Harney, Wheeler, Gilliam, and Umatilla counties (ch. 85); repealing the special season for quail, partridges, and pheasants in Douglas County (ch. 98), and giving absolute protection to ringneck pheasants in Jackson County (ch. 23).

Pennsylvania.—Seven acts: Establishing game refuges on State forest reservations (No. 64); extending spring shooting of waterfowl, abolishing the bag limit on waterfowl, and authorizing confiscation of decoys, guns, boats, and all other contrivances used in violation of law (No. 57); lengthening the seasons for rabbits (No. 62) and ruffed grouse (No. 63); giving complete protection to does and fawns (No. 61) and all birds and game within the limits of State preserves (No. 64); increasing protection of nongame birds (No. 149), and prohibiting use of automatic guns (No. 244).

Rhode Island.—Two acts: Establishing a $10 nonresident license with exemptions in favor of nonresident real estate owners and members of existing fishing and hunting clubs (ch. 1456), and permitting protection of crops from deer under permit of the secretary of state (ch. 1455).

South Carolina.—Two acts: Incorporating the Audubon Society of South Carolina with powers of a game commission, providing for wardens, prohibiting export except a limited amount under nonresident license, requiring the marking of packages of game, providing for a game-protection fund, substituting a $10 nonresident State license for the $25 county license and the special license for hunting on navigable waters (ch. 315), and lengthening the deer season in Dorchester County (ch. 228).

South Dakota.—One act: Giving complete protection to nongame birds.

Tennessee.—One act: Extending absolute protection of deer to 1911, shortening the quail season, establishing a $3 resident license for hunting on another's lands under verbal permit, and providing graduated dealers' licenses with fees ranging from $5 to $25, based on population of towns where used (ch. 185).

Texas.—Two acts: Extending the game law, which would have expired in 1908 (ch. 345), enlarging the office of fish and oyster commissioner to cover game, providing a chief deputy commissioner and deputy wardens, establishing a $15 nonresident license and allowing licensee to take one day's bag out of the State, protecting absolutely antelope, mountain sheep, prairie chickens, and Mongolian and English pheasants until 1912, reducing the bag limit on deer and wild turkeys, placing robins and chachalacas on the game list, and changing the dove and turkey seasons (ch. 379).

Utah.—One act: Modifying appointment of wardens, establishing a $1 resident license, reducing the nonresident and alien license from $25 to $10, permitting residents to shoot two deer each in October (nonresidents can not hunt them at any time), altering the seasons for grouse, prairie chickens, sage hens, and doves, and for quail in the Great Salt Lake region, protecting quail in Garfield County, extending absolute protection of elk, antelope, sheep, and introduced game to 1911, permitting limited sale of shore birds and waterfowl, and authorizing scientific collecting of birds and eggs (ch. 118).

Vermont.—Five acts: Strengthening the warden service, requiring any person killing a deer to report the fact and exhibit the head to the nearest deputy game warden, permitting killing at any time of deer in private game preserves, shortening the seasons for upland game and shore-birds, providing a close season for gray squirrels, and making exemption from the nonresident license requirement in favor of real estate owners (No. 152); giving increased financial support to the office of fish and game commissioner (No. 153); establishing a nonresident $5 game bird license (No. 155); providing for payment for damages done by deer (No. 156), and removing sale restrictions from game from private game preserves stocked at the owner's expense (No. 157).

Washington.—One act: Opening a 3-months' season for Chinese pheasants east of the Cascades corresponding with that in effect west of the Cascades, permitting the killing of deer on islands, except game preserves, during October, and protecting bobwhite quail and Chinese pheasants in Okanogan County to 1912 (ch. 222).

West Virginia.—One act: Giving complete protection to nongame birds (ch. 57).

Wisconsin.—Eleven acts. Giving absolute protection to moose throughout the State and to deer in 36 counties, reducing the bag limit on deer for nonresidents to 1 (ch. 259) and the export limit to 1 (ch. 311); prohibiting hounding and forbidding possession of dogs in hunting and lumber camps, in the deer country (ch. 201); increasing protection of quail, grouse, and imported pheasants (ch. 627); providing bag and export limits on grouse, shore birds, and waterfowl, increasing restriction of shipment in or from the State (ch. 586); prohibiting the use of a rifle in hunting waterfowl other than goose or brant, authorizing confiscation of boats (ch. 415); and making minor changes (chaps. 287, 315, 544, 567, 611).

Wyoming.—Four acts: Making head hunting and tusk hunting a felony and authorizing the payment of $300 rewards for detection of violations of the act (ch. 47); limiting absolute protection of quail and Mongolian pheasants to end in 1912 (ch. 35); shortening the seasons for grouse, prairie chickens, and sage chickens, establishing a $1 bird license for residents, extending the $2 big game resident license to cover birds, and reducing the bag and export limits on big game from 2 to 1 (ch. 102); and prescribing details of issuing licenses (ch. 36). The legislature also memorialized the "Benevolent and Protective Order of Elks" to discourage the use of elk tusks.

Alberta.—One act: Closing seasons for elk, sheep, goat, and upland game, and shortening the season for big game; establishing two Provincial game preserves; giving comprehensive protection to nongame birds; providing export permits at $5 for each big game trophy and $1 for 12 game birds; permitting limited export for propagation under $5 permit; requiring that heads of big game be stamped by minister of agriculture before being sold, at fees of $5 for elk, caribou, moose, and sheep, and $2 for deer, antelope, and goat; placing bag limit of 2 on antelope; providing licenses for guides at $5, game dealers and trappers at $10, and residents at $2.50; increasing guest license to $2, and repealing exemption of Indians from the game laws.

British Columbia.—No legislation; a few local restrictions made by orders in council.

Manitoba.—One act: Giving absolute protection to buffalo and to the females of deer, antelope, elk, moose, and caribou (ch. 66).

New Brunswick.—One act: Establishing a $10 bird license, providing for the issue of a $10 deer license at the option of the surveyor-general, prohibiting employment of nonresident guides, reducing from 5 to 2 the number permitted to employ one guide, requiring guides to report the number of game animals of each species killed by their parties, authorizing the return of the license fee for ladies who have accompanied hunting parties but have killed no game, prohibiting the use of automatic guns, and permitting the killing of deer in protection of crops (ch. 40).

Newfoundland.—One act: Prohibiting all hunting of caribou in a certain region on Grand Lake, increasing the fee for a nonresident guide license from $25 to $50, and permitting sale at any time of ptarmigan or willow grouse killed in open season.

Nova Scotia.—One act: Shortening seasons for moose, shore birds, and waterfowl, opening a 6-months' season for upland game birds, including capercailzie, blackcock, and chukar partridge, closing the season for four years for ruffed grouse and spruce partridge on Cape Breton Island, prohibiting sale of deer and caribou to 1910, permitting limited export for propagation, providing a $2 guide license, and requiring moose hunters to report each moose killed to the Game Society (ch. 27).

Ontario.—One act: Substituting a superintendent of game and fisheries for the board of game commissioners and reorganizing the warden service, opening a 3-months' season for pheasants, partridges, and prairie chickens, and making minor changes in other seasons, penalizing the sale of game under a false name, further increasing the discretionary powers of the lieutenant-governor-in-council, prohibiting the use of automatic guns, licensing the carrying of guns by persons engaged in constructing railways or other public works, and further restricting cold storage of game (No. 1371).

Prince Edward Island.—One act: Establishing licenses at $2.50 for nonresident sons and brothers of residents, at $2.25 for guests for a specified number of days, and at $5 for nonresident real estate owners; permitting licensee to export 12 birds, placing wild turkey and curlew on the game list, and extending seasons for woodcock, snipe, and plover.

Quebec.—No legislation.

Saskatchewan.—One act: Providing for a chief game guardian and subordinates, shortening the season for big game, and abolishing the special season in the southeast part of the Province, prohibiting spring shooting of waterfowl and shore birds, increasing the nonresident licenses from $15 and $25 to $50 and $100, respectively, reducing bag limits on big and upland game, and permitting export of game for propagation on application from governments of other Provinces or States (No. 23).

Unorganized Territories.—Laws not received.

Yukon.—Laws not received.

BILLS WHICH FAILED TO PASS.

Among the numerous measures which failed to pass, or to receive the approval of the governor, were some which contained novel features or features of special interest. More than the usual number of game bills were vetoed. In California a bill establishing a game commission and another providing for the celebration of bird day in the schools passed the legislature, but failed to receive the approval of the governor. In New York a dozen or more game bills failed to receive approval of the governor, among them being a bill carrying an appropriation of $20,000 for the establishment of a herd of buffalo in the Adirondack Park, which was vetoed,[a] and a bill protecting gray squirrels throughout the year. In Oregon a bill allowing fruit growers to destroy birds supposed to be injuring their crops at any season was likewise vetoed.

---

[a] See Forest and Stream, July 20, 1907, p. 88.

Practically nothing was accomplished in the way of Federal legislation, as a bill to amend the Alaska game law by providing a system of nonresident licenses passed the House but failed in the Senate a few minutes before adjournment, and none of the bills to establish game refuges on the National forests made substantial progress.

It is obviously impossible to mention more than a few of the numerous measures considered in the State legislatures, but the following were some of the more important ones which failed: Bills to prohibit the use of automatic guns in hunting game were introduced in Connecticut, Georgia, Illinois, Indiana, Iowa, Maine, Michigan, Minnesota, Missouri, Nebraska, New Jersey, New York, Oregon, Pennsylvania, Rhode Island, Texas, and Washington, but failed in all the States except Pennsylvania; in Arkansas a bill removing protection from ducks and other waterfowl was introduced but failed to pass; in California, a bill amending the law for the protection of nongame birds; in Delaware, a bill to establish a State game commission for conducting the work hitherto performed by the Delaware Game Protective Association and increasing the nonresident license from $5 to $10; in Illinois, a bill permitting shooting on submerged lands (Forest and Stream); in Iowa, a bill to establish resident licenses, which passed the house but failed in the senate; in Florida, three bills to establish the office of State game commissioner, to provide a warden system, and to revise the general game laws; in Maine, a measure excluding firearms from the woods during close season; in Michigan, bills extending the close season for quail and licensing private preserves; in Minnesota, a universal license for residents hunting in their own counties; in Montana, three bills, (*a*) abolishing the office of State warden and the special game protection fund, (*b*) abolishing the office of deputy warden and giving State wardens jurisdiction over peace officers, and (*c*) abolishing the office of State warden and providing for an elective office of county game warden and stock inspector; in New Jersey, measures prohibiting spring shooting of waterfowl and summer shooting of woodcock, establishing a resident and alien license system, and prohibiting all sale of game; in New York, a bill authorizing the sale of certain imported game from December to April, inclusive, and a bill providing for a $1 resident and $20 nonresident license; in North Carolina, a bill charging nonresidents $100 for shooting in Currituck Sound; in North Dakota, a general bill amending the game law, stopping spring shooting, establishing licenses, and protecting nongame birds; in Pennsylvania, a bill to establish a resident license; in South Dakota, a law closing the quail season for several years, which passed the legislature but failed to receive the sanction required by its referendum clause; in Washington, a bill to create a State game commission composed of the governor, State fire warden, and the fish commissioner, and a bill (H. 155) to prevent hunting accidents by imposing a penalty of $1,000, or imprisonment not exceeding 10 years, for killing persons accidentally; in West Virginia, amendments to the general game law; in Wisconsin a bill to permit spring shooting of waterfowl; in Wyoming, all efforts to protect the antelope; in Alberta, the establishment of a reserve for goats; and in British Columbia, all game legislation.

CLOSE SEASONS.

All the general close seasons for game prescribed by the various States and by the Provinces of Canada are here brought together in one table. For the sake of simplicity a uniform method is used in both the arrangement of species and statement of seasons. In each case deer and other big game are first considered; then squirrels and rabbits; then upland game birds, such as quail, grouse, pheasants, turkeys, and doves; then shore birds, and finally waterfowl, such as ducks, geese, and swans. In the statement of seasons only close seasons have been given, and in stating these the plan of the Vermont law, to include the first date but not the last, has been followed consistently.[a] The Vermont scheme has the advantage of showing readily both the open and close seasons, since either may be obtained by reversing the dates of the other.

In some States certain days of the week constitute additional close seasons throughout the term in which killing is permitted. Hunting on Sunday is prohibited in all except four of the States east of the Mississippi, and in Iowa, Kansas, Missouri, Minnesota, Nebraska, North Dakota, and Oklahoma, as well as in most of the Canadian Provinces. Mondays constitute a close season for waterfowl in Ohio and other week days for wild fowl in several favorite ducking grounds in Delaware, Maryland, Virginia, and North Carolina. Hunting is prohibited on election day in Baltimore, Frederick, and Harford counties, Maryland. The county laws of Maryland and North Carolina, which are too numerous to be included satisfactorily, are given in detail on pages 49–52, but are not incorporated in the following table, which otherwise may be regarded as a practically complete résumé of the regulations now in force. The difficulty of securing absolute accuracy in a table of this kind is very great, and the absence in the laws of many States of express legislation as to the inclusion or exclusion of the date upon which seasons open and close makes exactness almost an impossibility.

CLOSE SEASONS FOR GAME IN THE UNITED STATES AND CANADA, 1907.

[The close seasons include the first date, but not the last. To find the open seasons *reverse the dates*. Seasons which apply only to special counties are placed to the left of the column containing the close seasons for the State in general.]

	Close seasons.
Alabama (1907):	
Male deer (does protected all the year)	Jan 1–Nov. 1.
Squirrel (black, gray, or fox)	Feb. 1–Sept. 1.
Quail or partridge, dove, rail, coot, mud hen, woodcock, sandpiper, curlew, other shore birds, duck, goose, brant, swan	Mar. 1–Nov. 1.
Wild turkey gobblers (hens protected all the year)	Mar. 1–Dec. 1.
Ruffed grouse (pheasant), imported pheasant or other introduced game birds.	Until Dec. 1, 1912.
Snipe, plover	May 1–Nov. 1.
Alaska [b] (1902–1904):	
Deer	Feb. 1–Aug. 1.
Moose, mountain sheep	Jan. 1–Sept. 1.

---

[a] See discussion of this question in Circular No. 43 of the Biological Survey, U. S. Department of griculture, 1904, entitled "Definitions of the open and close seasons for game."

[b] Game animals or birds may be killed at any time for food or clothing by native Indians or Eskimo, by miners, explorers, or travelers in need of food, but game so killed can not be shipped or sold.

Close Seasons for Game—Continued.

	Close seasons.
Alaska (1902-1904)—Continued.	
Caribou (except on Kenai Peninsula, until Sept. 1, 1908, and in the rest of the Peninsula district[a] Nov. 1-Sept. 1)	Jan. 1-Sept. 1.
Mountain goat	Jan. 1-Aug. 1.
Bear (large brown)	Jan. 1-Apr. 1.
Grouse, shore birds	Dec. 16-Sept. 1.
Ptarmigan, waterfowl	Feb. 1-Sept. 1.
Arizona (1905):	
Male deer	Dec. 1-Sept. 15.
Female deer, spotted fawn, elk, mountain sheep, mountain goat	All the year.
Antelope, 6 years	Until Mar. 1, 1911.
Quail, bobwhite, partridge, grouse, pheasant, snipe, rail	Mar. 1-Oct. 15.
Introduced pheasant (Chinese, Japanese green, golden, ringneck) 6 years	Until Mar. 1, 1911.
Wild turkey	Dec. 1-Sept. 15.
Arkansas (1901-1905):	
Deer	Feb. 1-Sept. 1.
Quail or partridge	Mar. 1-Nov. 1.
Pinnated grouse, prairie chicken	Dec. 1-Oct. 31.
Pheasants (Chinese, English), 10 years	Until Mar. 14, 1913.
Wild turkey	May 1-Sept. 1.
Dove	All the year.
California[b] (1901-1907):	
Male deer	Oct. 1-July 15.
Tree squirrel	Jan. 1-Sept. 1.
Female deer, fawn, elk, antelope, mountain sheep	All the year.
Valley quail, partridge, plover, curlew, ibis, rail, shore birds	Feb. 15-Oct. 15.
Mountain quail	Feb. 15-Sept. 1.
Grouse, sage hen	To Sept. 1, 1909.
Pheasants, bobwhite, imported quail or partridge, swan	All the year.
Dove	Oct. 15-July 15.
Wilson snipe	Apr. 1-Oct. 15.
Duck	Feb. 15-Oct. 1.
Colorado (1899-1907):	
Deer	Oct. 21-Oct. 1.
Elk, 4 years	Until Nov. 1, 1911.
Antelope with horns, mountain sheep with horns, 4 years	Until Oct. 15, 1911.
Antelope and mountain sheep without horns	All the year.
Quail (bobwhite, crested), 13 years	Until 1920.
Wild turkey, pheasant, partridge, ptarmigan, wild pigeon, crane	All the year.
Grouse, prairie chicken	Oct. 2-Aug. 20.
Sage chicken	Oct. 2-Aug. 1.
Dove	Sept. 6-Aug. 15.
Plover, curlew	Oct. 31-Aug. 1.
Snipe, shore birds, duck, goose, brant, swan, waterfowl (see exception)	Apr. 16-Sept. 10.
Exception: Altitudes above 7,000 feet ... May 2-Sept. 15	
Connecticut (1901-1907):	
Deer, 10 years	Until June 1, 191
Gray squirrel, hare, rabbit [illegible]	Dec. 1-Oct. 1.
Quail, ruffed grouse, woodcock [illegible] Mongolian)	Dec. 1-Oct. 1.
Dove [illegible]	All the year.
[illegible], Wilson o[illegible] snipe, shore birds, gallinule, [illegible]	Jan. 1-Sept. 1.
[illegible]	Jan. 1-Sept. 12.
[illegible]	
[illegible] counties), rabbit	Jan. 1-Nov. 15.
[illegible]	Jan. 1-Nov. 15.
[illegible]	All the year.
[illegible]	Feb. 2-Sept. 1.
[illegible]	Apr. 16-Oct. 1.[c]

---

[a] The Territory is divided into three game districts: (1) Sitka district—Southeastern Alaska east of the 141st meridian; (2) Peninsula district—Aleutian Islands, Alaska and Kenai peninsulas and adjacent islands, and that part of Alaska west of the 141st meridian draining into the Pacific Ocean; (3) Yukon district—Remainder of Territory, including the area drained by the Kuskokwim, Tanana, Yukon, and Kowak rivers, and the area which drains into the Arctic Ocean.

[b] Seasons fixed by ordinances of boards of county supervisors are omitted (see explanation on p. 49

[c] Wild fowl on A[illegible]aman Bay and tributaries, Sussex County, May 1-Nov. 1, and on Monday [illegible] days, Saturdays, and Sundays in the open season.

Close Seasons for Game—Continued.

	Close seasons.
Columbia[a] (1899-1901):	
at (sale or possession)	Jan. 1-Sept. 1.
, rabbit (except English rabbit, Belgian hare)	Feb. 1-Nov. 1.
partridge	Mar. 15-Nov. 1.
grouse or pheasant (except English, ringneck, or other imported nts raised in inclosures, sale or possession unrestricted), wild turkey.	Dec. 26-Nov. 1.
hicken or pinnated grouse	Mar. 15-Sept. 1.
	All the year,
k	Jan. 1-July 1.
lover, duck, goose, brant	Apr. 1-Sept. 1.
d, marsh blackbird, rail or ortolan, other game birds not previously oned	Feb. 1-Sept. 1.
1903):	
	Feb. 1-Nov. 1.
partridge, wild turkey	Mar. 1-Nov. 1.
	Apr. 1-Oct. 1.
03-1905):	
	Jan. 1-Sept. 1.
artridge, pheasant, wild turkey	Mar. 15-Nov. 1.
ipe, marsh hen	Mar. 15-Sept. 1.
ck, wood duck or summer duck	Feb. 1-Sept. 1.
05):	
heasant	Mar. 1-Sept. 16.
ve, wild pigeon	Feb. 1-July 1.
d birds	All the year.
lover, turnstone, curlew, stilt, mud hen, migratory duck	May 1-Sept. 16.
wild duck, Hawaiian goose	Feb. 1-Sept. 16.
7):	
k, mountain sheep, mountain goat	Jan. 1-Sept. 15.
aribou, antelope, buffalo	All the year.
	Dec. 1-Nov. 1.
	Dec. 1-Aug. 15.
e, pheasant, turtle dove, prairie chicken	Dec. 1-Sept. 1.
n	Dec. 1-Aug. 1.
an pheasant, Canada grouse or fool hen, swan, 4 years	Until Mar. 14, 1911.
lover, duck, goose	Jan. 1-Sept. 15.
03-1907):	
0 years	Until May 28, 1917.
(gray, red, fox, or black)	Nov. 16-July 1.
	Dec. 20-Nov. 11.
grouse, prairie chicken, Mexican blue quail, California mountain California valley quail, Hungarian partridge, capercailzie, black , 4 years	Until July 1, 1911.
rkey, pheasants (copper or Soemmering, English, golden, green Japa-Mongolian, ringneck, silver, tragopan, Reeves, Elliot, Hungarian, oe, Amherst, melanotte, impeyan, argus), partridge (black Indian, is, chukar), sand grouse, 6 years	Until July 1, 1913.
g dove, woodcock	Dec. 1-Aug. 1.
pe or Wilson snipe, sand or other snipe, golden, upland, or other :	May 2-Sept. 1.
oose, brant, or other waterfowl	Apr. 16-Sept. 1.
905-1907):	
	All the year.
	Nov. 1-July 1.
ck	Jan. 1-July 1.
uffed grouse, prairie chicken, or pinnated grouse	Jan. 1-Nov. 10.

---

prohibited in the District, by act of June 30, 1906, except on the marshes of the Eastern ve the Anacostia Bridge, and on the Virginia shore of the Potomac, provided no birds hin 200 yards of any bridge or dwelling.

wful to kill game or game birds within 1 mile of West Palm Beach; similar regulations at St. Augustine. Special seasons: Clay County, quail, wild turkey, Mar. 1-Nov. 1 and s each week rest of year; Hernando County, deer, quail, Feb. 1-Dec. 1, wild turkey, 1, dove, duck, Mar. 1-Dec. 1.

ed in inclosure for market may be killed at any time.

ed in private preserves may be killed at any time.

Close Seasons for Game—Continued.

	Close season.
Indiana (1905–1907)—Continued.	
Pheasants, wild turkey, dove	All the year.
Duck, goose, brant, or other waterfowl	Apr. 1–Sept. 1.
All game except waterfowl	Oct. 1–Nov. 10.
Iowa (1897–1907):	
Deer, elk	All the year.
Squirrel (gray, timber, or fox)	Jan. 1–Sept. 1.
Quail, ruffed grouse or pheasant, wild turkey	Dec. 15–Nov. 1.
Pinnated grouse or prairie chicken	Dec. 1–Sept. 1.
Pheasants (English, Mongolian, Chinese, ringneck)	Until Oct. 1. 1915.
Turtle dove	All the year.
Woodcock	Jan. 1–July 10.
Sandpiper, plover, rail, marsh or beach birds, duck, goose, brant	Apr. 15–Sept. 1.
Kansas (1903–1907):	
Antelope, 5 years	Until Mar. 13, 1908.
Red squirrel	All the year.
Quail (see exceptions)	Dec. 15–Nov. 15.
Exceptions: Bourbon, Crawford, Decatur, Finney, Grant, Gray, Greeley, Hamilton, Haskell, Hodgeman, Morton, Rooks, Scott, Sherman, Smith Stafford, Stanton, Stevens, and Wichita counties...... Until Mar. 11, 1908.	
Grouse, prairie chicken (see exceptions)	Oct. 15–Sept. 15.
Exceptions: Prairie chicken in same counties as quail..Until Mar. 11, 1908	
Prairie chicken in Butler county, 3 years.............. To Mar. 9, 1910	
Pheasants (English, Mongolian, or Chinese), Hungarian partridge, 6 years	Until Feb. 27, 1913.
Dove	Sept. 15–Aug. 1.
Plover	Sept. 15–July 15.
Duck, goose, brant	Apr. 15–Sept. 1.
Kentucky (1894–19[illegible]	
Deer	Mar. 1–Sept. 1.
Rabbit (except with dogs or in snares)	Sept. 15–Nov. 15.
Squirrel (black, gr[illegible], or fox)	Feb. 1–Nov. 15.[a]
Quail, partridge, pheasant	Jan. 1–Nov. 15.
Pheasants (English, ringneck, Mongolian, or Chinese)	All the year.
Wild turkey	Feb. 1–Sept. 1.
Dove	Feb. 1–Aug. 1.
Woodcock	Feb. 1–June 20.
Wood duck, teal, or other duck, goose	Apr. 1–Aug. 15.
Louisiana (1904–1906):	
Deer (female and young protected all the year)	Local seasons.[b]
Quail, woodcock	Mar. 1–Nov. 1.
Prairie chicken, wood duck, 5 years	Until July, 1909.
Male wild turkey (female protected all the year)	Apr. 1–Dec. 1.
Snipe, papabotte	May 15–Aug. 1.
Dove, grosbec, surf bird, chorook, sandpiper, plover, tatler, curlew, rail (mud hen), gallinule, coot (poule d'eau)	Mar. 1–Aug. 1.
Duck (except wood duck), goose, brant, swan	Apr. 1–Sept. 1.
Maine (1903–1907):	
[illegible] see exceptions)	Dec. 16–Oct. 1.
Exceptions: Androscoggin County .... Nov. 1–Oct. 1	
counties of Cumberland (females to 1909), Kennebec, Knox, Lincoln,	
[illegible] towns of Bath, West Bath, and Phippsburg, all	
[illegible] all the [illegible], and Waldo..... Dec. 1–Nov. 1	
[illegible] of [illegible] Mount Desert, Southwest Harbor,	
[illegible] naut (on islands) until Feb. 13,	
[illegible] otherwise as in State law.	
[illegible]	Dec. 1–Oct. 15.
[illegible]	All the year.
[illegible]	Until Oct. 15. 19[illegible]
Squirrel (gra[illegible]	Until May 1, 191[illegible]
[illegible]	Apr. 1–Sept. 1.
Quail, do[illegible]	All the year.
Ruffed grouse, partridge, woodcock	Dec. 1–Sept. 15.
Pheasant, black game, capercailzie or cock of the woods, 10 years	Until Apr. 28, 191[illegible]

---

[a] Except June 15–Sept. 15.

[b] Close seasons for deer in Louisiana, not less than 7 months in length, to be fixed by police juri [illegible] the [illegible] parishes but north of latitude 31 the period from May 1 to Aug. 15 to be alway [illegible]

Close Seasons for Game—Continued.

	Close seasons.
Maine (1903–1907)—Continued.	
Snipe, sandpiper, plover	May 1–Aug. 1.
Wood duck, dusky or black duck, teal, gadwall or gray duck, mallard, widgeon or baldpate, shoveler, pintail or sprigtail, redhead, scaup or greater bluebill, lesser scaup or lesser bluebill, golden-eye or whistler, bufflehead, ruddy duck or broadbill (see exceptions)	Jan. 1–Sept. 1.
Exceptions: Golden-eye (Hancock Co.); ducks (Lincoln Co.). Feb. 1–Sept. 1	
All ducks on the Kennebec River below Gardiner and in Merrymeeting Bay .... Dec. 1–Sept. 1	
Maryland (1898–1906) (*see county laws, pp. 49–60*):	
Squirrel	Dec. 1–Sept. 1.
Pheasants (English, Mongolian)	Dec. 25–Nov. 1.
Dove	Dec. 25–Aug. 15.
Snipe, plover	May 1–Aug. 15.
Reedbird, sora (water rail or ortolan)	Nov. 1–Sept. 1.
Duck, goose, brant, swan, and other wild fowl	Apr. 10–Nov. 1.
Massachusetts (1902–1907):	
Deer, 5 years	Until Nov. 1, 1908.
Gray squirrel	Dec. 1–Oct. 1.
Hare or rabbit	Mar. 1–Oct. 1.
Quail (see exception)	Dec. 1–Nov. 1.
Exception: Nantucket Island, 3 years .... Until Mar. 1, 1908	
Ruffed grouse or partridge, woodcock	Dec. 1–Oct. 1.
Prairie chicken, dove, wild or passenger pigeon	All the year.
Pheasants (English, golden, Mongolian), males	Dec. 1–Nov. 1.
Heath hen, wood or summer duck, 5 years	Until 1911.
Bartramian sandpiper (upland plover)	Until July 15, 1910.
Snipe, sandpiper, plover (except upland plover), rail, or any "shore," "marsh," or "beach" birds	Mar. 1–July 15.
Black duck, teal	Mar. 1–Sept. 1.
Other ducks	May 20–Sept. 1.
Michigan[a] (1905–1907):	
Deer (see exceptions)	Dec. 1–Nov. 10.
Exceptions: Deer in red coat and fawn in spotted coat	All the year.
Allegan, Clare, Gladwin, Grand Traverse, Huron, Isabella, Lake, Lapeer, Macomb, Manistee, Mason, Mecosta, Missaukee, Newaygo, Oceana, Osceola, Ottawa, St. Clair, Sanilac, Tuscola, and Wexford counties .... Until Jan. 1, 1908	
Deer on Bois Blanc Island .... Until 1918	
Kalkaska County .... Until 1910	
Arenac, Bay, Benzie, Cheboygan, Emmet, and Leelanau counties .... Until 1912.	
Elk (see exception), moose, caribou, 8 years	Until June 16, 1913.
Exception: Elk on Bois Blanc Island .... Until 1918	
Squirrel (black, fox, or gray)	Dec. 1–Oct. 15.
Quail (bobwhite), ruffed grouse (partridge), spruce hen (see exception)	Dec. 1–Oct. 15.
Exception: Upper Peninsula (ruffed grouse, spruce hen) .... Dec. 1–Oct. 1	
Pinnated grouse (prairie chicken), wild turkey, capercailzie, black game, hazel grouse, pheasants (English, Mongolian), wild pigeon	Until 1910.
European partridge	Until 1912.
Dove	All the year.
Snipe, plover, woodcock, duck, goose, brant, or other waterfowl (except that snipe, bluebill, canvasback, widgeon, redhead, pintail, whistler, spoonbill, butterball, and sawbill duck, goose, and brant may be hunted Mar. 2–Apr. 25, and goose and brant in Chippewa County at any time)	Jan. 2–Sept. 1.
Minnesota (1905–1907):	
Deer, male moose	Dec. 1–Nov. 10.
Elk, female moose, caribou, fawn	All the year.
Quail, partridge, ruffed grouse (pheasant)	Dec. 1–Oct. 1.
Sharp-tailed or white-breasted grouse, pinnated grouse or prairie chicken, turtle dove, woodcock, snipe, upland plover, golden plover	Nov. 1–Sept. 1.
Pheasants (Chinese, English, Mongolian, golden, Reeves, Japanese, tragopan, Temminck)	Until Jan. 1, 1910.
Duck, goose, brant, or any aquatic fowl	Dec. 1–Sept. 1.

---

[a] On Grand Island, Alger County, native deer, mule deer, blacktail deer, elk, moose, caribou, (columbian), antelope, buffalo, native partridge, Manitoba grouse, dalripan (European ptarmigan), and ptarmigan are protected to June 7, 1910.

Close Seasons for Game—Continued.

	Close seasons.
Mississippi (1906):	
Deer (spotted fawn all the year), bear	Mar. 1-Nov. 15.
Quail or partridge	Mar. 1-Nov. 1.
Wild turkey (females all the year)	May 1-Jan. 1.
Dove	Mar. 1-Aug. 1.
Plover, tatler, chorook, grosbec, coot, rail (mud hen), duck, swan, goose, brant	Mar. 1-Sept. 1.
Missouri (1907):	
Deer	Jan. 1-Nov. 1.
Squirrels (gray, black, fox)	Jan. 1-June 1.
Quail (bobwhite, partridge)	Jan. 1-Nov. 1.
Ruffed grouse (pheasant), pinnated grouse (prairie chicken), Mongolian, Chinese, and English pheasants, and other imported game birds	Until Dec. 1, 1912.
Wild turkey	Feb. 1-Dec. 1.
Dove, woodcock, plover	Jan. 1-Aug. 1.
Snipe, duck, goose	May 1-Sept. 15.
Montana (1905-1907):	
Deer	Dec. 15-Sept. 1.
Elk, antelope, mountain goat, mountain sheep	Dec. 1-Sept. 1.
Moose, caribou, bison or buffalo	All the year.
Quail, Chinese pheasant	All the year.
Grouse, prairie chicken, fool hen, pheasant, partridge, sage hen, turtledove, duck, goose, brant, swan	Dec. 1-Sept. 1.
Nebraska (1901-1907):	
Deer, antelope, elk, squirrel (gray, red, fox, timber)	All the year.
Quail	Dec. 1-Nov. 15.
Partridge, pheasant, ptarmigan, English partridge, Belgian partridge, English pheasant, Chinese pheasant, English black cock, other imported game birds, wild turkey, curlew	All the year.
Prairie chicken, sage chicken, grouse, dove, wild pigeon, plover	Dec. 1-Sept. 15.
Snipe, yellowlegs, crane, duck, goose, brant, or any game waterfowl	Apr. 11-Sept. 15.
Nevada[a] (1901-1903):	
Deer, antelope (males)	Nov. 15-Sept. 15.
Female deer and antelope, spotted fawn; all elk, caribou, mountain sheep, mountain goat	All the year.
Quail, grouse, prairie chicken, woodcock, snipe, plover, curlew, sandhill crane, duck	Mar. 1-Sept. 15.
Sage hen	Feb. 16-July 15.
Dove	Nov. 2-July 15.
Swan	All the year.
New Hampshire (1901-1907):	
Deer in Carroll and Coos counties	Dec. 1-Oct. 1
Deer in Grafton County	Dec. 15-Nov. 1
Deer in rest of State	Dec. 15-Dec. 1
Elk, moose, caribou	All the year.
Gray squirrel	Until Oct. 1, 1918.
Hare, rabbit	Mar. 1-Oct. 1.
Quail, partridge, ruffed grouse, woodcock, Wilson snipe	Dec. 1-Oct. 1.
Dove	All the year.
Killdeer, upland plover or Bartramian sandpiper, wood duck	Until Mar. 7, 1912.
Sandpiper, yellowlegs, plover, rail, duck (except sheldrake) ("beach birds," teal, coot, may be shot in Rockingham County July 15-Feb. 1)	Feb. 1-Oct. 1.
New Jersey (1903-1906):	
Deer,[b] 3 years	Until Nov. 10, 1909.
Squirrels (gray, black, fox), hare (rabbit)	Jan. 1-Nov. 10.
Quail (partridge), ruffed grouse (partridge or pheasant), prairie chicken, pheasant (English or ringneck pheasant),[c] wild turkey	Jan. 1-Nov. 10.
Dove	All the year.
Woodcock	Jan. 1-Oct. 1.[d]

---

[a] County commissioners may change dates of close seasons (without altering length) for deer, antelope, or sage hens, or lengthen close seasons, for any other game in their respective counties.

[b] Not applicable to deer in game preserves or to possession of imported deer properly tagged.

[c] English or ringneck pheasants in established game preserves may be shot Oct. 1-Jan. 1 by the owners of such preserves or such persons as they may designate.

[d] Except July.

Close Seasons for Game—Continued.

Jersey (1903-1906)—Continued.		*Close seasons.*
English or Wilson snipe (bog or jack snipe)		Jan. 1-Sept. 1.a
Surf or bay snipe, sandpiper, yellowlegs, plover (except upland plover), curlew, all shore birds		Jan. 1-May 1.
Upland plover		Oct. 1-Aug. 1.
Reedbird, rail, marsh hen		Jan. 1-Sept. 1.
Duck, goose, brant, swan, or other wildfowl		May 1-Sept. 1.
Mexico (1905-1907):		
Deer (with horns)		Dec. 1-Oct. 15.
Deer (without horns), elk, mountain sheep		All the year.
Antelope, 5 years		Until Mar. 13, 1910.
Quail (native or crested)		Feb. 1-Oct. 1.b
Mountain grouse, prairie chicken, wild turkey		Jan. 1-Oct. 1.
Bobwhite quail, pheasants, wild pigeon, 5 years		Until Mar. 13, 1910.
Ptarmigan		All the year.
Turtle dove		May 1-July 15.
York (1900-1907) (*see special laws for Long Island on next page*):		
Deer (see exception)		Nov. 1-Sept. 16.
Exception: Orange and Sullivan counties	Nov. 16-Nov. 1	
Fawns, elk, moose, caribou, antelope		All the year.
Black bear (except in Essex and Lewis counties, unprotected)		July 1-Oct. 1.
Squirrel, black or gray (see exceptions)		Dec. 1-Sept. 16.
Exceptions: Chautauqua County	Dec. 1-Oct. 16	
Dutchess, Rensselaer, and Sullivan counties	Dec. 1-Oct. 1	
Greene County	Dec. 16-Oct. 1	
Orange County	Dec. 16-Oct. 16	
Richmond County (gray squirrel only)	All the year	
Saratoga County	Nov. 1-Sept. 16	
Hare, rabbit:		
Albany, Genesee, Monroe, Orleans, and Wyoming counties	Dec. 16-Sept. 16	
Broome and Cortland counties	Dec. 1-Sept. 16	
Dutchess County	Dec. 1-Oct. 16	
Erie, Madison, Rensselaer, Steuben, and Sullivan counties	Feb. 16-Oct. 1	
Fulton, Greene, and Schenectady counties	Feb. 1-Nov. 1	
Herkimer and Oneida counties	Feb. 15-Sept. 16	
Livingston and Ulster counties	Jan. 16-Oct. 1	
Orange County	Dec. 16-Oct. 16	
Richmond County	Dec. 16-Nov. 1	
Rockland County	Dec. 31-Nov. 1	
Westchester County	Dec. 1-Nov. 1	
Quail (see exceptions)		Dec. 1-Nov. 1.
Exceptions: Cattaraugus and Chautauqua counties	Dec. 1-Oct. 16	
Orange and Ulster counties	Dec. 16-Oct. 16	
Rensselaer County	Dec. 1-Oct. 1	
Richmond County, 2 years	Until 1908	
Grouse (see exceptions)		Dec. 1-Sept. 16.
Exceptions: Cattaraugus and Chautauqua counties	Dec. 1-Oct. 16	
Dutchess, Greene, Rensselaer, Sullivan, and Tioga counties	Dec. 1-Oct. 1	
Orange and Ulster counties	Dec. 16-Oct. 16	
Saratoga County	Nov. 1-Sept. 16	
Pheasants (Mongolian, ringneck, English), 6 years (see exception)		Until 1910.
Exception: Dutchess and Suffolk counties	Jan. 1-Nov. 1	
Dove		All the year.
Woodcock (see exceptions)		Dec. 1-Sept. 16.
Exceptions: Cattaraugus and Chautauqua counties	Dec. 1-Oct. 16	
Dutchess, Greene, Rensselaer, Sullivan, and Tioga counties	Dec. 1-Oct. 1	
Orange and Ulster counties	Dec. 16-Oct. 16	
Saratoga County	Nov. 1-Sept. 16	
Plover		Jan. 1-Aug. 16.
Wilson or English snipe, jacksnipe, bay snipe, yellowlegs, surf birds, curlew, rail, water chicken, mud hen, gallinule, shore birds, duck, goose, brant, swan		Jan. 1-Sept. 16.

Except March and April.

County commissioners on petition of 25 resident householders in any precinct may extend season to April 1 in such precinct.

Close Seasons for Game—Continued.

	Close seasons.
Long Island (1900-1906):	
Deer shooting permitted only on first two Wednesdays and Fridays after first Tuesday of November (Nov. 6, 8, 13, and 15 in 1907).	
Squirrel (black or gray), hare, rabbit	Jan. 1-Nov. 1.
Quail (except on Robbins Island, protected all the year, and Gardiners Island, Feb. 1-Oct. 15), grouse	Jan. 1-Nov. 1.
Woodcock	Jan. 1-Aug. 1.
Pheasants (English, Mongolian, ringneck), in Suffolk County	Jan. 1-Nov. 1
Dove	All the year.
Wilson or English snipe, jacksnipe, bay snipe, surf snipe, winter snipe, sandpiper, yellowlegs, willet, dowitcher, shortneck, plover, ringneck, killdeer, oxeye, curlew, rail	Jan. 1-July 16.
Gallinule, meadow hen, mud hen	Dec. 31-Aug. 16.
Duck, goose, swan	Jan. 1-Oct. 1.
Brant	May 1-Oct. 1.
North Carolina (1905) (*see county laws, pp. 51-52*):	
Deer	Feb. 1-Oct. 1
Quail, wild turkey, dove, lark, robin	Mar. 1-Nov. 1.
•**North Dakota** (1901):	
Deer	Dec. 1-Nov. 10.
Elk, moose, caribou, buffalo, mountain sheep	All the year.
Antelope, 10 years	Until Jan. 1, 1911.
Quail, pheasants (English, Chinese), sharp-tailed grouse, ruffed grouse, pinnated grouse, prairie chicken, woodcock, swan	Oct. 15-Sept. 1.
Crane, duck, goose, brant	May 1-Sept. 1.
Ohio (1900-1904):	
Squirrel	Oct. 15-Sept. 1.
Rabbit	Dec. 5-Nov. 15.[a]
Raccoon	Mar. 1-Sept. 1.
Quail	Dec. 5-Nov. 15.
Ruffed grouse, introduced pheasants, 4 years	Until Nov. 10, 1908.
Dove, woodcock	Dec. 1-Sept. 1.
Snipe, plover, shore birds, rail, coot or mud hen, duck, goose, swan	Dec. 1-Sept. 1.[b]
Oklahoma (1899):	
Deer, antelope	All the year.
Quail	Feb. 1-Oct. 15.
Grouse	All the year.
Prairie chicken, wild turkey	Jan. 1-Sept. 1.
Pheasants	Jan. 1-Dec. 1.
Dove, plover	Jan. 1-Aug. 1.
Oregon (1901-1907):	
Male deer (except in Baker, Coos, Curry, Grant, Harney, Malheur, Umatilla, Union and Wallowa counties)	Nov. 1-July 15.
Coos and Curry counties	Oct. 15-July 15
Female deer (except in above counties)	Nov. 1-Sept. 1.
Coos and Curry counties	All the year.
Spotted fawn	All the year.
Elk	Oct. 15-Sept. 15.
Silver gray squirrel (*Sciurus fossor*)	Jan. 1-Oct. 1.
Partridge (English or gray), capercailzie, moor hen, pheasant (silver, golden, copper, green Japanese, and Reeves), wild turkey, woodcock	Dec. 1-Oct. 1.
Prairie chicken (see exceptions)	Until Sept. 15, 1908
Exceptions: Wasco County	Oct. 15-Aug. 1
Umatilla County	Dec. 1-Oct. 1
Dove	All the year.
Upland plover, rail	Jan. 1-Aug. 1.
Duck, goose,[c] swan (except in Lake County, Apr. 1-Aug. 15, and in Coos County, Feb. 1-Aug. 1)	Feb. 1-Sept. 1.

---

[a] Applies to hunting with *gun* only.

[b] Except Mar. 1-Apr. 20; Sundays and Mondays are also closed seasons for ducks and other water fowl.

[c] Unlawful to kill geese at any time on islands or sand bars in the Columbia River east of the Cascades.

Close Seasons for Game—Continued.

gon (1901–1907)—Continued.	*Close seasons.*
West of Cascades:	
Quail, bobwhite, partridge, grouse, native pheasant (ruffed grouse), ringneck (China torquatus) pheasant (see exceptions)	Dec. 1–Oct. 1.
Exceptions:	
Tillamook County: Native pheasant (ruffed grouse), ringneck (China torquatus) pheasant	Dec. 1–Sept. 15
Blue grouse	Oct. 15–Aug. 1
Clatsop, Coos, Curry, and Josephine counties: Ringneck (China torquatus) pheasant	Dec. 1–Sept. 15
Jackson County: Ringneck (China torquatus) pheasant	All the year
East of Cascades:	
uail (except in Wasco County, Oct. 15–Aug. 1, and Gilliam, Grant, Harney Umatilla, and Wheeler counties, to Jan. 1, 1912) hunting permitted only from second Saturday to third Tuesday in September (Sept. 14–17 in 1907)	
Native pheasant (ruffed grouse), grouse, sage hen	Dec. 1–Aug. 15.
heasant	All the year.
Iongolian ringneck (China torquatus) pheasant (see exception)	Until Feb. 15, 1910.
Exception: Gilliam, Grant, Harney, Umatilla, and Wheeler counties	To Jan. 1, 1912
nsylvania (1905–1907):	
)eer (deer without horns protected all the year)	Dec. 1–Nov. 15.
ear	Mar. 1–Oct. 1.
quirrel	Dec. 1–Oct. 1.
Iare, rabbit	Dec. 1–Oct. 15.
uail	Dec. 1–Nov. 1.
uffed grouse (pheasant), woodcock	Dec. 1–Oct. 1.
rairie chicken, imported pheasants (Chinese, English, Mongolian), wild turkey	Dec. 1–Oct. 15.
Vild pigeon	Until Apr. 22, 1915
ove, reedbird, rail, blackbird, sandpiper, tatler, curlew, or any shore bird	Jan. 1–Sept. 1.
Vilson snipe (jacksnipe)	May 1–Sept. 1.
pland or grass plover	Dec. 1–July 15.
oot or mud hen	Jan. 1–Sept. 1. a
Vild waterfowl—duck, goose, brant, swan, grebe	Apr. 10–Sept. 1.
le Island (1900–1907):	
eer, 4 years	Until Jan. 1, 1908. b
ray squirrel, hare, rabbit	Jan. 1–Nov. 1.
uail or bobwhite, ruffed grouse or partridge, woodcock	Jan. 1–Nov. 1.
heasant, 5 years	Until Oct. 15, 1910.
ove	All the year.
lack duck and wood duck	Apr. 1–Aug. 15.
h Carolina (1902–1907):	
eer (see exception)	Jan. 1–Sept. 1.
Exception: Beaufort, Berkeley, Charleston, Clarendon, Colleton, Darlington, Dorchester, Florence, Hampton, Horry, Kershaw, Marion, and Marlboro counties	Feb. 1–Aug. 1
uail, partridge, pheasant, wild turkey, woodcock (see exception)	Mar. 1–Nov. 15.
Exception: Aiken, Barnwell, Beaufort, Berkeley, Charleston, Clarendon, Colleton, Dorchester, Fairfield, Georgetown, Hampton, Lexington, Oconee, and Saluda counties	Apr. 1–Nov. 1
Iongolian pheasant, 3 years	Until Jan. 1, 1910.
h Dakota (1899–1905):	
)eer, elk, buffalo, mountain sheep	Dec. 1–Nov. 1.
ntelope, 10 years	Until Jan. 1, 1911.
uail, ruffed grouse, sharp-tailed grouse, pinnated grouse, prairie chicken, woodcock	Jan. 1–Sept. 1.
)ove	All the year.
lover, curlew	May 15–Sept. 1.
rane, duck, goose, brant	May 1–Sept. 1.

---

xcept Apr. 1–16.

ame deer kept in confinement may be killed by the owner at any time, or any deer injuring by any person on his premises under permit from secretary of state.

Close Seasons for Game—Continued.

	Close seasons.
Tennessee (1903–1907):	
Deer (except Fentress County, Jan. 1–Dec. 1)	Until Oct. 1, 1911.
Squirrel	Mar. 1–June 1.[a]
Quail or partridge	Mar. 1–Nov. 15.
Grouse, pheasant (except English or ringneck pheasants), wild turkey,[b] meadowlark	Mar. 1–Nov. 1.
Pheasant, English or ringneck	Jan. 1–Dec. 1.
Dove (see exception), teal, wood (summer) duck	Apr. 15–Aug. 1
Exception: Dove in Shelby County	Mar. 1–July 15
Robin, woodcock, snipe, sandpiper, plover, tatler, willet, godwit, curlew, avocet, marsh blackbird, rail, coot, mud hen, duck (except teal and wood duck), goose, brant, swan	Apr. 15–Oct. 1.
Texas (1907):	
Deer (female deer and spotted fawn protected all the year)	Jan. 1–Nov. 1.
Antelope, mountain sheep, 5 years	Until July 1, 1912.
Quail or partridge, dove	Feb. 1–Nov. 1.
Prairie chicken or pinnated grouse, pheasants (Mongolian, English), 5 years	Until July 1, 1912.
Wild turkey	Apr. 1–Nov. 1.[c]
Utah (1907):	
Deer with horns (see exception)	Nov. 1–Oct. 1.
Exception: Nonresident not permitted to kill deer.	
Deer without horns, elk, antelope, sheep, any introduced game	Until Mar. 28, 1911
Quail (see exceptions), pinnated grouse, pheasants (English, Mongolian, Chinese)	All the year.
Exceptions: Quail in Garfield, Kane, and Washington counties	Feb. 1–Aug. 1
Quail in Davis, Salt Lake, and Weber counties	Oct. 26–Oct. 14
Partridge, grouse, prairie chicken, sage hen, pheasant, mourning dove	Dec. 1–Aug. 1.
Snipe, shore birds, duck, goose, brant, swan	Jan. 1–Oct. 1.
Vermont (1894–1906):	
Deer	All the year except Oct. 21–27.[d]
Moose, caribou	All the year.
Gray squirrel	Dec. 1–Sept. 15.
Hare, rabbit	May 1–Sept. 15.
Quail, ruffed grouse or partridge, woodcock, English snipe, plover (other than upland)	Dec. 1–Sept. 15.
Pheasant, English partridge	Until Oct. 1, 1909
Dove	All the year.
Upland plover	Dec. 1–Aug. 1.
Duck, goose	Jan. 1–Sept. 1.
Virginia[e] (1903–1906):	
Deer	Jan. 1–Oct. 1.
Squirrel:	
Alexandria County (gray)	Until Sept. 1, 1910
Isle of Wight and Southampton counties (gray or fox)	Jan. 15–Sept. 1
Rabbit:	
Accomac and Northampton counties	Jan. 15–Nov. 15
Alexandria, Fairfax, Fauquier, Loudoun, and Prince William counties.	Jan. 1–Nov. 1

---

[a] *Special squirrel seasons:* Benton, Decatur, Wilson, Jan. 1–June 1; Carroll, Mar. 1–June 15; Carter Mar. 1–July 15; Crockett, Weakley, Feb. 1–July 1; Fayette, Jan. 1–July 15; Gibson Sevier, Feb. 1–June 1 Hardeman, Feb. 15–July 15; Haywood, Jan. 1–May 1; Henderson, Jan. 15–July 15; Lauderdale, Feb. 1–July 1; McNairy, Madison, Mar. 1–July 1; Robertson, Jan. 1–July 1; Shelby, Feb. 1–June 15; Stewart Feb. 1–Aug. 1; Warren, Mar. 1–Oct. 1. Bedford, Blount, Cannon, Clay, Coffee, Cumberland, Dickson Fentress, Giles, Greene, Hickman, Humphreys, Jackson, Knox, Lawrence, Lincoln, London, Marshall Maury, Meigs, Moore, Overton, Perry, Pickett, Putnam, Rhea, Sequatchie, Sullivan, Van Buren. Washington, Wayne, White, Williamson, unprotected.

In Chester, Hardeman, Hardin, and McNairy counties anyone may kill squirrels on his own property at any time for his own use.

[b] *Special wild turkey seasons:* Lauderdale, Jan. 1–Nov. 1; Dyer (gobblers), May 1–Nov. 1, (hens) Feb 1–Nov. 1; Clay, Fentress, Overton, Pickett, May 1–Aug. 1.

[c] *Vide* opinion of assistant attorney-general of Texas dated Sept. 17, 1907.

[d] Deer kept in private game preserves may be killed by the owners at any time.

[e] Boards of supervisors may shorten the open seasons in their counties and make other restrictions not repugnant to law "and may include in such protection other game not specifically mentioned in this section." Code 1904, sec. 2070a as amended in 1906.

Close Seasons for Game—Continued.

		Close seasons.
Virginia (1903-1906)—Continued.		
Rabbit—Continued.		
Amelia,[a] Charlotte,[a] Greenesville, Spottsylvania, and Sussex counties.	Feb. 1-Oct. 1	
Buckingham [a] and Cumberland [a] counties	Feb. 15-Oct. 15	
Caroline, Essex, Hanover, Henrico, and King William counties.	Feb. 1-Nov. 1	
Chesterfield County	Feb. 1-Sept. 1	
Culpeper and Orange counties	Jan. 15-Nov. 1	
Elizabeth City County	Feb. 1-Nov. 15	
Halifax County	Feb. 1-Oct. 15	
James City and York counties, town of Williamsburg	Feb. 15-Nov. 15	
Nottoway County	Jan. 1-Sept. 1	
Shenandoah County	Mar. 1-Nov. 1	
Stafford County	Feb. 1-Sept. 15	
Opossum:		
Halifax County	Feb. 1-Oct. 15	
Quail or partridge, pheasant or grouse, wild turkey, woodcock (see exceptions)		Feb. 1-Nov. 1.
Exceptions: West of the Blue Ridge	Jan. 1-Nov. 1	
Accomac and Northampton counties (pheasant, grouse—5 years).	Until Mar. 14, 1909	
Pheasants (English, Mongolian), 5 years		Until Jan. 1, 1909.
Dove		All the year.
Robin		Mar. 1-Dec. 15.
nipe (except Wilson and robin snipe), sandpiper, plover (except black-breasted green-headed, and white), willet, tatler, rail (except sora), gallinule, mud hen		Jan. 1-July 20.
Summer or wood duck		Jan. 1-Aug. 1.
Winter waterfowl		Apr. 1-Oct. 15.[b]
Washington [c] (1903-1907):		
Deer (see exception)		Dec. 15-Sept. 15.
Exceptions: Deer on islands, except those containing game preserves.	Nov. 1-Oct. 1.	
Spotted fawn	All the year.	
Elk		Until Oct. 1, 1915.
Moose, caribou, antelope, sheep, goat (males)		Nov. 1-Sept. 15.
Moose, caribou, antelope, sheep, goat (females)		All the year.
Quail west of Cascades	Jan. 1-Oct. 1	
Quail east of Cascades, 5 years	Until Sept. 15, 1908	
Bobwhite quail, Chinese or Mongolian pheasants in Okanogan County.	Until Sept. 30, 1912.	
Partridge, grouse, prairie chicken, sage hen, native pheasant, ptarmigan (except east of Cascades, Nov. 15-Aug. 15; prairie chicken in Kittitas County, Oct. 1-Sept. 10)		Jan. 1-Sept. 1.
Pheasants (Chinese, Mongolian or other imported pheasant)		Jan. 1-Oct. 1.
Dove		All the year.
Snipe, sand-hill crane, duck, swan (see exception)		Mar. 1-Sept. 1.
Exception: Goose, brant, or other waterfowl on Columbia and Snake rivers, or within half a mile of their shores, in Columbia, Douglas, Franklin, Garfield, Klickitat, Kittitas, Wallawalla, Whitman, and Yakima counties	All the year.	
Goose, brant (except as above)		May 1-Sept. 1.
Plover, rail		Mar. 1-Aug. 15.
West Virginia (1903):		
Deer (except spotted fawn, protected all the year)		Dec. 16-Oct. 15.
Squirrel, rabbit		Jan. 1-Sept. 15.
Quail or Virginia partridge		Dec. 20-Nov. 1.
Ruffed grouse, pheasant, pinnated grouse or prairie chicken, wild turkey		Dec. 15-Oct. 15.
Dove		All the year.
Woodcock		Nov. 2-July 15.
Snipe		July 1-Mar. 1.
Duck, goose, brant		Apr. 1-Oct. 1.

---

[a] Young rabbits or hares may be killed or captured June 1-Aug. 1 in Amelia and Charlotte counties, and June 1-Oct. 15 in Buckingham and Cumberland counties.

[b] Wildfowl can not be hunted on Wednesdays and Saturdays on Back Bay, Princess Anne C

[c] On Mercer Island, Lake Washington, game animals and birds are protected all the year.

Close Seasons for Game—Continued.

	Close seasons.
Wisconsin (1898–1907):	
Deer (see exceptions)	Dec. 1–Nov. 11.
Exceptions: Door County, 5 years	Until Nov. 11, 1912
Adams, Brown, Calumet, Columbia, Crawford, Dane, Dodge, Fond du Lac, Grant, Green, Green Lake, Iowa, Jefferson, Juneau, Kenosha, Kewaunee, La Crosse, Lafayette, Manitowoc, Marquette, Milwaukee, Monroe, Outagamie, Ozaukee, Racine, Richland, Rock, Sauk, Sheboygan, Vernon, Walworth, Washington, Waukesha, Waushara, and Winnebago counties	All the year
Moose	All the year.
Squirrel (gray, black, fox), rabbit	Mar. 1–Sept. 1.
Quail, pheasants (Chinese, English, Mongolian), 8 years	Until Oct. 1, 1915.
Partridge, woodcock, snipe, plover	Dec. 1–Sept. 1.
Prairie chicken, grouse in Adams, Barron, Burnett, Buffalo, Chippewa, Clark, Crawford, Dodge, Dunn, Eau Claire, Grant, Iowa, Jackson, Juneau, Lafayette, Marquette, Monroe, Pepin, Polk, Portage, Richland, Rusk, Sawyer, St. Croix, Vernon, Washburn, Waushara, and Wood counties	Oct. 15–Oct. 1
Prairie chicken, grouse in rest of State	Until Sept. 2, 1915
Turtle dove, swan	All the year.
Rail or rice hen, duck, coot or mud hen	Jan. 1–Sept. 1.
Goose, brant	May 1–Sept. 1.
Wyoming (1903–1907):	
Deer, elk, antelope, mountain sheep	Nov. 15–Sept. 15.
Moose, 9 years	Until Sept. 15, 1912.
Quail (bobwhite, California, Mexican), Mongolian pheasant, 5 years	Until Sept. 1, 1912.
Partridge, grouse, prairie chicken, sage chicken	Sept. 15–Aug. 1.
Dove, swan	All the year.
Snipe, plover, green-shank, tatler, godwit, curlew, avocet, or other wader, duck, goose, brant	May 1–Sept. 1.
Alberta[a] (1906–7):	
Deer, moose, caribou	Dec. 1–Nov. 1.
Elk or wapiti	Until Nov. 1, 1910.
Antelope	Nov. 1–Oct. 1.
Buffalo	All the year.
Mountain sheep, mountain goat	Until Oct. 1, 1909.
Grouse, partridge, prairie chicken, ptarmigan, pheasant (except English)	Until Sept. 15, 1908.
English pheasant	All the year.
Crane, snipe, sandpiper, plover, curlew, shore bird, rail, coot	Jan. 1–Sept. 1.
Duck, goose, swan	Jan. 1–Aug. 23.
British Columbia[b] (1898–1905):	
Deer (except fawns), sheep (except ewes and lambs), goat	Dec. 15–Sept. 1.
Fawns, ewes, and lambs	All the year.
Bull elk or wapiti, bull moose, bull caribou, hare	Jan. 1–Sept. 1.
Females and young of elk, moose, and caribou	All the year.
Quail, English partridge, pheasant, swan, and all imported game birds	All the year.
Grouse, prairie chicken, ptarmigan (see exception)	Jan. 1–Sept. 1.
Exception: Grouse and ptarmigan north of latitude 55°	Apr. 1–Sept. 15
Snipe, plover, duck (see exception)	Mar. 1–Sept. 1.
Exception: Duck, north of latitude 55°	Apr. 1–Sept. 15

---

[a] Except for elk and buffalo the seasons here given do not apply to that portion of the Province north of latitude 55°.

[b] The lieutenant-governor is empowered to make further restrictions in these seasons. Resident Indians (nonresidents not allowed to hunt) and farmers in "unorganized districts" may kill deer for immediate use as food, but Indians can kill does and fawns only Aug. 1–Feb. 1; free miners while engaged in placer mining or prospecting in unorganized districts, and surveying or engineering parties engaged in their duties may kill any game for food. By proclamation of March 31, 1904, the lieutenant-governor in council declared that "all that portion of the Province not included within any municipality, except the Kamloops, Okanagan, Similkameen, Greenwood, and Grand Forks Electoral Districts, shall be defined as an unorganized district within the meaning of the 'Game Protection Act, 1898.'" The following special seasons have been made by orders in council: In the municipalities of Chilliwack and Kent (Agassiz) no birds may be shot before October 15, 1907; in the Okanagan electoral district prairie chickens, willow grouse, and blue grouse are protected until September 1, 1910; and in the Lillooet and Cariboo electoral districts the open season for mountain sheep closes November 14 in each year.

Close Seasons for Game—Continued.

	Close seasons.
itoba (1902-1907):	
Deer, elk or wapiti, moose, caribou or reindeer, antelope or cabri (males)	Dec. 15-Dec. 1.
Females and young of foregoing species and bison or buffalo	All the year.
Quail, woodcock, snipe, sandpiper, plover (except upland plover)	Jan. 1-Aug. 1.
Grouse, partridge, prairie chicken	Nov. 1-Oct. 1.
Dove	All the year.
Pheasant, 5 years	Until Oct. 1, 1909.
Upland plover	Jan. 1-July 1.
Duck	Dec. 1-Sept. 1.
Brunswick (1899-1905):	
Deer, moose, caribou (cow and calf moose and cow caribou all the year)	Dec. 1-Sept. 15.
Partridge	Dec. 1-Sept. 16.
Pheasant	All the year.
Woodcock, snipe, teal, wood duck, dusky or black duck, goose, brant	Dec. 2-Sept. 1.
Shore or other birds on beaches, islands, or lagoons bordering tidal waters of Northumberland Strait, Gulf of St. Lawrence, and Bay of Chaleur	Jan. 1-Sept. 1.
foundland [a] (1902-1906):	
Elk, moose, 10 years	Until Jan. 1, 1912.
Caribou (except in a special region near Grand Lake, all the year)	Feb. 1-Oct. 21.[b]
Ptarmigan, willow grouse or partridge, any grouse	Jan. 12-Oct. 1.
Snipe, plover, curlew, or "other wild or migratory birds (except wild geese)".	Jan. 12-Aug. 21.
a Scotia (1900-1907):	
Deer, caribou, 5 years	Until Oct. 1, 1910.
Moose (see exception)	Dec. 1-Oct. 1.
Exception: **Cape Breton Island until Oct. 1, 1915. Calf moose under 1 year.. All the year**	
Hare, rabbit	Mar. 1-Nov. 1.
Ruffed grouse or partridge (see exception)	Nov. 1-Oct. 1.
Exception: **Cape Breton Island ruffed grouse and spruce partridge, 4 years. Until Oct. 1, 1911**	
Spruce partridge [see exception above), sharp-tailed grouse, ptarmigan, blackcock, capercailzie, chukar partridge, pheasant, woodcock, snipe, curlew, plover, teal, blue-winged duck (see exception) wood duck	Mar. 1-Sept. 1.
Exception: **Cumberland Co. (blue-winged duck)............ May 1-Sept. 1**	
tario [c] (1907):	
Deer (young protected all the year)	Nov. 16-Nov. 1.[d]
Elk or wapiti	All the year.
Moose, caribou, or reindeer (see exception)	Nov. 16-Oct. 16.[e]
Exception: **Female moose and young moose and caribou..... All the year.**	
Squirrel (black or gray)	Dec. 2-Nov. 1.
Hare [f]	Jan. 1-Oct. 1.
Quail, wild turkey	Dec. 2-Nov. 1.
Grouse, pheasants, prairie fowl, partridge, woodcock	Dec. 16-Sept. 15.
Capercailzie	Until Sept. 15, 1909.
Snipe, plover, rail, other shore birds or "waders"	Dec. 16-Sept. 1.
Dove	All the year.[g]
Goose, swan	May 1-Sept. 15.
Duck and other waterfowl (except goose and swan)	Jan. 1-Sept. 1.
ce Edward Island (1906-1907):	
Hare, rabbit	Mar. 1-Sept. 1.
Partridge	Until Oct. 1, 1908.
Wild turkey, plover, curlew	Jan. 1-July 15.

Stipendiary magistrates may in their respective districts prohibit destruction of hares and rabbits pecified terms.

Except Aug. 1-Oct. 1.

Lieutenant-governor in council may alter close seasons in region north and west of French er, Lake Nipissing, and Mattawa River, and in the vicinity of Rondeau Park, and close for a nite period seasons for any game animal or nonmigratory game bird whose numbers have inished.

Persons who put or breed deer on their own lands, and their licensees, may hunt such deer Oct. ov. 16.

South of the Canadian Pacific R. R., between Mattawa and the Manitoba boundary, Nov. 16-Nov. 1

Cottontail rabbits (wood hares) may be killed during close season when damaging trees or shrubs.

Under act for protection of insectivorous birds, Rev. Stats. 1897, ch. 289, sec. 3.

Close seasons for Game—Continued.

	Close seasons.
Prince Edward Island (1906-1907)—Continued.	
Woodcock, snipe	Jan. 1-Sept. 1.
Yellowlegs, shore and other birds along beaches or tidal marshes, teal, black, or bluewinged duck	Jan. 1-Aug. 20.
Goose	May 10-Sept. 15.
Brant	June 10-Oct. 1.
Quebec (1899-1906):	
Zone 1.[a] Deer, moose (see exceptions)	Jan. 1-Sept. 1.
Exceptions: In Ottawa and Pontiac counties	Dec. 1-Oct. 1
Cow moose and young deer and moose	All the year
Caribou (young protected all the year)	Feb. 1-Sept. 1.
Hare	Feb. 1-Dec. 1.
Bear	July 1-Aug. 20.
Birch or swamp partridge	Dec. 15-Sept. 1.
White partridge or ptarmigan	Feb. 1-Nov. 1.
Woodcock, snipe, sandpiper, plover, tatler, curlew	Feb. 1-Sept. 1.
Widgeon, teal, duck, sheldrake	Mar. 1-Sept. 1.[b]
Zone 2. Close seasons same as in Zone 1, except as follows:	
Caribou	Mar. 1-Sept. 1.
Hare	Mar. 1-Oct. 15.
Birch or swamp partridge	Feb. 1-Sept. 15.
White partridge or ptarmigan	Mar. 1-Nov. 15.
Saskatchewan[c] (1905-7):	
Deer, elk or wapiti, moose, caribou (females and young all the year)	Dec. 15-Dec. 1.
Antelope (young all the year)	Nov. 15-Oct. 1.
Buffalo	All the year.
Grouse, partridge, prairie chicken, ptarmigan	Dec. 1-Sept. 15.
English pheasant	All the year.
Crane	Jan. 1-Aug. 1.
Snipe, sandpiper, plover, curlew, shore birds, rail, coot, duck, goose, swan	Jan. 1-Sept. 1.
Unorganized Territories[d] (Keewatin, etc.), 1894:	
Deer, elk or wapiti, moose, caribou, mountain sheep, mountain goat	Apr. 1-Dec. 1.[e]
Musk ox	Mar. 20-Oct. 15.
Grouse, partridge, prairie chicken, pheasant	Jan. 1-Sept. 1.
Duck, goose, swan	Jan. 15-Sept. 1.
Yukon[f] (1901):	
Deer, elk or wapiti, moose, caribou, mountain sheep, mountain goat, musk ox.	Jan. 1-Oct. 1.
Bison or buffalo	All the year.
Grouse, partridge, prairie chicken, ptarmigan, pheasant	Jan. 15-Oct. 1.
Snipe, sandpiper, crane, duck, goose, swan	June 1-Sept. 1.

---

[a] Zone No. 1 comprises the whole Province, except that part of the counties of Chicoutimi and Saguenay east and north of the river Saguenay. Zone No. 2 comprises the excepted part of said counties.

[b] Inhabitants of Zone 2 and Gaspé County may take these birds for food at any season except June 1-Aug. 1.

[c] Lieutenant-governor-in-council may extend close seasons over current year within limits on petition of 6 game guardians.

[d] Indians, inhabitants, and travelers, explorers, and surveyors in need of food exempt. Governor in-council may alter seasons.

[e] Except July 15-Oct. 1.

[f] Indians, explorers, surveyors, prospectors, miners, and travelers in need of food are exempt. Commissioner-in-council may alter seasons.

SHIPMENT OF GAME.

Shipment is the most important feature of the traffic in game. It has, likewise, a marked effect upon the perpetuation of game, and when permitted without limitation is a great factor in its rapid destruction. A realization of this fact has induced many of the States to prohibit export of all or certain kinds of game and in a few instances all transportation even within the State. The subject may be conveniently considered under the following subheads: "Federal laws," "Marking packages," and "State laws prohibiting export."

FEDERAL LAWS.

Federal laws for the protection of game comprise the statutes regulating interstate commerce in game and the importation of birds from foreign countries and those providing for the protection of birds and game on territory under the immediate jurisdiction of the United States.

They comprise: (1) The Lacey Act, regulating the importation of game and its shipment from one State to another; (2) the tariff act, imposing duties on game, skins, and feathers imported from foreign countries; (3) the act regulating the introduction of eggs of game birds; (4) game laws of the District of Columbia, Alaska, and the Indian Territory, and (5) provisions for protecting birds in the National parks,[a] National forests, and other Government reservations. These laws are more fully discussed in Bulletin No. 16 of the Biological Survey, entitled "Digest of Game Laws for 1901" (pp. 69-79). The full text of several may be found in various circulars published by the Biological Survey: Circular No. 29 (1900) contains the Lacey act, Circular No. 34 (1901), the game laws of the District of Columbia, and Circular No. 42 (1904), the Alaska game law, with regulations for 1904, which are still in force.

MARKING PACKAGES.

Section 4 of the Lacey Act requires every package containing game animals or birds when shipped by interstate commerce to be clearly marked so as to show the name and address of the shipper and the nature of the contents. The laws of Colorado, Connecticut, Louisiana, Michigan, Mississippi, Montana, Nebraska, North Carolina, Ohio, Oregon, South Carolina, Wisconsin, New Brunswick, and Ontario likewise require each package of fish or game to bear a statement indicating the contents. Such general statements as "game" or "birds" are not sufficient to show the nature of the contents; the *kind* of game should be shown, and also the *amount* in the package.

Some of the State laws are very explicit on the subject of marking. Nebraska requires all packages to be labeled with the address of the consignor and the amount of each kind of game contained in the package, and provides a fine of $10 to $50 for omission of these details. Ohio and North Carolina have similar requirements. Michigan requires all packages of game to be plainly marked on the outside with the names of the consignor and consignee, the initial point of billing and destination, and an itemized statement of the quantity of game contained therein. South Carolina requires the names of consignor, consignee, and owner, and a description of the contents. Wisconsin's requirements are similar, and heavy penalties are provided for violation. Mississippi directs that the package bear the names of consignor and consignee and an itemized statement of the species of game, and further provides that the contents must be packed so as to be readily seen. In Louisiana and Ontario packages must also be made so as to show the contents, besides bearing, on the outside, a description of the contents and the names and addresses of owners. Several States require big game and game birds carried by sportsmen to be marked with the owner's name, shipped as baggage, and transported open to view.

---

[a] The law governing the Yellowstone Park prohibits any person, or any stage, express, or railway company from receiving for transportation animals, birds, or fish taken in the park, under a penalty not exceeding $300. (28 Stat. L., ch. 72, sec. 4.)

Railroad and express companies should call the attention of their agents to these provisions, and insist that all packages be properly marked before shipment. In Nebraska, South Carolina, and Wisconsin common carriers are prohibited, under heavy penalties, from receiving consignments of game not properly labeled. In Texas they may examine suspected packages, and in Arkansas they may cause them to be opened when necessary, and may refuse packages supposed to contain fish or game for export. In Michigan and Wisconsin packages of fish or game may be broken open by game wardens, and if not properly marked may be confiscated.

STATE LAWS PROHIBITING EXPORT.

Since the constitutionality of the Connecticut statute prohibiting export of certain game was established by the Supreme Court in 1896[a] nonexport laws have been generally adopted, and at the present tim every State prohibits the export of certain kinds of game. (See fig 1, p. 33.) In some States sportsmen are allowed to carry a limite amount of game out of the State under special restrictions, and exceptions to the laws prohibiting export are also made in the case of bird and animals intended for propagation.

Restrictions on shipment from the State have now become so stringent that all the States and Territories west of the Mississippi River except two prohibit export of all game protected by local laws. Of the two exceptions, Iowa prohibits export of all game but shore birds, and Wyoming export of certain species. East of the Mississippi similar laws are in force in nearly all of the States north of the Ohio and Potomac rivers, and also in Alabama, Mississippi, Tennessee, Virginia, and West Virginia. The export of most if not all protected game taken within the State is prohibited in all these States except Massachusetts, Rhode Island, Connecticut, New Jersey, Delaware, Maryland, and Illinois, and in these export of certain kinds of game is illegal.

Deer can be lawfully exported from only six States—Delaware (where they do not occur), Georgia, Kansas, Kentucky, North Carolina, and Ohio. The export of deer hides is prohibited by specia ovisions in the laws of Alaska, California, Florida, Wyoming, itish Columbia, and Ontario; Wisconsin limits the export of green les to the period from November 13 to December 3 of each year; ashington and British Columbia prohibit killing deer for hides; egon makes all hunting for hides dependent on permission of the ate game and forestry warden; and New Brunswick and Newfound- id allow shipment of green hides only under license.

---

[a] Geer v. Connecticut, 161 U. S., 519.

Among game birds the most general prohibition is that of the port of quail, which is now in force in every State and Territory, th two exceptions. In one of the excepted States, Wyoming, quail not occur; in the other, Maryland, several counties prohibit their port. A number of States permit imported birds to be exported, wever, and Colorado, Illinois, and Montana allow quail to be shipped om the State under permit. Besides these exceptions, 23 States, cluding Oregon (see table), permit nonresident hunters to take a nited number of birds out of the State; Maine, Montana, South akota, Vermont, Virginia, Wyoming, British Columbia, and New runswick grant the same privilege to resident hunters.

Special attention is called to the following table, which contains a st of the game prohibited from export by each State and Territory:

Export of Game Prohibited.

labama:

Deer, squirrel, quail or partridge, ruffed grouse or pheasant, imported pheasant or other imported game bird, wild turkey, dove, rail, coot or mud hen, woodcock, snipe, sandpiper, curlew, shore birds, duck, goose, brant, swan.

Exceptions: Nonresident licensee may take with him or have carried to him, openly, game lawfully killed by him. State game and fish commissioner may issue permit to any person to capture, kill, or export game birds at any time, dead or alive, for scientific or propagating purposes; fee $1.

laska:

Deer, moose, caribou, mountain sheep, mountain goat, wild birds or any parts thereof.

Exception: Specimens and trophies may be exported under restrictions imposed by the Secretary of Agriculture.[a]

izona:

Deer, elk, antelope, sheep, goat, quail, bobwhite, partridge, grouse, pheasant, wild turkey, snipe, rail, duck, goose, brant.

kansas:

All game except rabbits, which must be shipped open to view.

lifornia:

Deer, deerskins, quail, partridge, grouse, prairie chicken, sage hen, pheasant, dove, wild pigeon, shore birds, plover, snipe, rail, curlew, ibis, duck.

lorado:

Deer, elk, antelope, bison, buffalo, sheep, quail, partridge, grouse, ptarmigan, prairie chicken, sage chicken, pheasant, wild turkey, dove, pigeon, snipe, curlew, crane, duck, goose, brant, swan, waterfowl.

Exception: Game may be exported under permit from game commissioner if permit be attached and package plainly marked so as to show nature of contents. The following fees are charged for export permits: Elk, $10; deer, $5; antelope, $5.

nnecticut:

Quail, ruffed grouse, woodcock.

laware:

Rabbit, quail, partridge, woodcock (nonresidents also prohibited from shipping English snipe).

orida:

Deer, deer hides, quail or partridge, wild turkey from county.

orgia:

Quail or partridge.

---

[a] See Circular No. 42, Biological Survey, U. S. Department of Agriculture, 1904.

Export of Game Prohibited—Continued.

Idaho:

Deer, elk, moose, caribou, antelope, buffalo, mountain sheep, mountain goat, quail, partridge grouse, prairie chicken, sage hen, Mongolian pheasant, dove, plover, snipe, duck, goose, swan.

Exception: Any hunter may export, under hunting license, animals lawfully taken; but each shipment must be accompanied by a sworn statement of number and date of license and fact that game was not procured contrary to law.

Illinois:

Squirrel, quail, ruffed grouse, pinnated grouse, prairie chicken, pheasant, wild turkey, duck, goose, brant, taken in the State.

Exception: Game may be exported under license from the State; nonresident may take from State 50 birds killed by himself, if carried openly for inspection.

Indiana:

Deer, quail, grouse, prairie chicken pheasant, wild turkey, woodcock, duck, goose, brant, and other waterfowl.

Exception: Nonresident may take from State 15 birds killed by himself, if carried openly for inspection, together with his license, or 45 if he has hunted for 3 or more days consecutively.

Indian Territory:

"Every person other than an Indian who hunts, traps, takes, or destroys any game *except for subsistence in the Indian country*, shall forfeit all traps, guns, and ammunition in his possession, and shall be liable in addition to a penalty of $500." (Rev. Stat. U. S., 1878, sec. 2137.)

Iowa:

Squirrel, quail, ruffed grouse, pinnated g rouse, prairie chicken, pheasant, wild turkey, woodcock duck, goose, brant.

Exception: Nonresident may take from State not more than 25 game birds or animals killed by himself, if carried openly for inspection.

Kansas:

Quail, partridge, grouse, prairie chicken, pheasant, dove, plover, duck, goose, brant.

Kentucky:

Quail, partridge, grouse, pheasant, wild turkey, killed in the State.

Louisiana:

Deer, squirrel, quail, prairie chicken, wild turkey, dove, grosbec, woodcock. snipe, surf bird, chorook, sandpiper, plover, tatler, curlew, papabotte (upland plover), rail (mud hen), gallinule, coot (poule d'eau), duck, goose, brant, swan, taken in the State.

Exception: A sportsman may carry with him out of the State 1 deer and 12 birds of each kind.

Maine:

Deer, moose, quail, ruffed grouse, pheasant, capercailzie, black game, plover, woodcock, snipe, sandpiper, wood duck, dusky or black duck, teal, gadwall or gray duck, mallard, widgeon or baldpate, shoveler, pintail or sprigtail, redhead, scaup or greater bluebill, lesser scaup or lesser bluebill, golden-eye or whistler, buffle head, ruddy duck or broadbill.

Exceptions: A resident of the State may export 1 deer in a season if open to view, tagged to show name and address of owner and accompanied by him, and under shipping license 1 moose, 6 partridges, 10 woodcock, and 10 ducks lawfully killed by himself. A nonresident may export under hunting license 1 moose and 2 deer lawfully killed by himself; and may take home 10 partridges, 10 ducks, and 10 woodcock. Any person may export a pair of game birds under a special 50-cent license.

Maryland: *County provisions, as follows:*

Allegany—Quail, pheasant, wild turkey, woodcock.

Anne Arundel—Squirrel, rabbit, quail, partridge, pheasant, woodcock, snipe, plover from county.

Baltimore—Partridge, pheasant, woodcock

Calvert—Rabbit, partridge, woodcock from county (for sale, barter, or trade).

Caroline—Rabbit, quail, partridge, woodcock from county.

Dorchester—Squirrel, rabbit, quail, partridge, woodcock, dove.

Exception: Twelve quail or partridges, 6 squirrels, rabbits, woodcock, and doves may taken out of the county as personal baggage, if carried openly and not intended for sale.

Frederick—Squirrel, partridge, pheasant, woodcock from county.

Kent—Squirrel, rabbit, and all birds from county (for sale, except under license).

Montgomery—Partridge, pheasant, wild turkey from county (for sale).

Queen Anne—Rabbit, partridge, woodcock from county (for sale).

Somerset—Squirrel, rabbit, quail or partridge, pheasant, dove, woodcock, duck, goose from county.

Washington—Deer, squirrel, rabbit, partridge, pheasant, wild turkey from county (for sale).

Wicomico and Worcester—Quail or partridge from both counties considered as one territory.

Massachusetts:

Quail, ruffed grouse, woodcock taken in the State; other game illegally taken in the State.

Exception: Nonresident may take 6 birds out of the State under his hunting license.

Export of Game Prohibited—Continued.

Michigan:

Deer, elk, moose, caribou, squirrel, quail, partridge, ruffed grouse, prairie chicken, spruce hen, Manitoba grouse, ptarmigan, Mongolian or English pheasant, wild turkey, dove, pigeon, snipe, plover, woodcock, duck, goose, brant, and other wild waterfowl.

Exceptions: (1) Game consigned to a point within the State may be transported outside the State if necessary to reach destination.

(2) Nonresident licensee may take out 1 deer under permit from State warden.

(3) Landowners and members of clubs owning game preserves may ship during open season under a $10 permit from State warden 50 ducks or other migratory birds lawfully killed by them on their own premises.

Minnesota:

Deer, elk, moose, caribou, hide or horns thereof, quail, partridge, ruffed grouse, prairie chicken, pinnated grouse, sharp-tailed or white-breasted grouse, ringneck or English pheasant, dove, snipe, duck, goose, brant, or any aquatic fowl.

Exception: Nonresident licensee may ship in open season, under his license coupons, to his residence, 1 deer and 25 birds lawfully taken by himself.

Mississippi:

Deer, bear, quail or partridge, wild turkey, dove, plover, tatler, chorook, grosbec, coot (poule d'eau), rail (mud hen), duck, goose, swan, brant.

Missouri:

Deer, squirrel, quail, pinnated grouse, prairie chicken, ruffed grouse, pheasant, wild turkey, dove, woodcock, snipe, plover, duck, goose from county:

Exceptions: Any person may take 1 deer, 2 wild turkeys, 25 quail, and 25 ducks, lawfully killed by him, to his residence by the usual manner of travel. Deer or elk from private preserves may be exported dead or alive under a special 50-cent permit from the county game warden.

Montana:

Deer, elk, moose, buffalo, mountain sheep, mountain goat, quail, pheasant or partridge, prairie chicken, fool hen, sage hen, grouse, Chinese pheasant, duck, goose, brant, swan.

Exception: Game lawfully killed may be exported during the open season if accompanied by the owner, and when shipped by resident of State, by permit from State game and fish warden, or when shipped by nonresident of State, by hunting license; total shipment under one license not to exceed number allowed to be killed in one season; all packages to be plainly labeled to show nature of contents.

ebraska:

Deer, elk, antelope, quail, partridge, pheasant, grouse, ptarmigan, prairie chicken, sage chicken, wild turkey, pigeon, dove, snipe, plover, yellowlegs, curlew, crane, duck, goose, brant, swan.

Exception: Nonresident may ship 50 birds out of State under hunting license, but must give common carrier invoice of number and kind of birds, must have details of shipment marked on license, and must accompany the shipment.

vada:

Deer, elk, antelope, caribou, mountain sheep, mountain goat, quail, grouse, pheasant, sage chicken, prairie chicken, dove, snipe, plover, woodcock, curlew, sandhill crane, duck, goose.

w Hampshire:[a]

Elk, moose, caribou, quail, partridge, ruffed grouse, pheasant, woodcock, Wilson snipe, dove, plover, yellowlegs, sandpiper, rail, duck (except sheldrake), and all "beach" birds.

Exception: Nonresident may export, under his hunting license, 2 deer and 12 birds, carried open to view, on notice of number and kind to the commissioner who issued the license.

w Jersey:

Hare, rabbit, squirrel, quail or partridge, ruffed grouse or pheasant, pinnated grouse, English pheasant, ringneck pheasant, woodcock.

Exception: English or ringneck pheasants killed on preserves established prior to April 15, 1908, may be exported from the State.

w Mexico:

Deer, elk, antelope, mountain sheep, native or crested quail, bobwhite quail, partridge, mountain grouse, prairie chicken, pheasant, ptarmigan, wild turkey, turtle dove, wild pigeon for market.

w York:

Game or birds taken in the State, including deer (excepting head, feet, and skin), elk, antelope, moose, caribou, squirrel, hare, rabbit, quail, grouse, Mongolian and English pheasants, plover, Wilson or English snipe, woodcock, curlew, shore birds, rail, mud hen, gallinule, water chicken, duck, goose, brant, or swan.

---

[a] Blue Mountain Forest Association permitted to ship deer, elk, and moose killed in its preserve.

Export of Game Prohibited—**Continued.**

North Carolina:[a]

Quail, partridge, pheasant, grouse, wild turkey, snipe, shore or beach bird, woodcock, taken in State.

Exception: Nonresident may take out of State under his hunting license 50 quail (partridge), 12 grouse, 2 turkeys, and 50 beach birds or snipe in a season.

North Dakota:

Deer, elk, moose, caribou, antelope, buffalo, mountain sheep, quail, ruffed grouse, prairie chicken, pinnated grouse, sharp-tailed grouse, English or Chinese pheasant, woodcock, crane, duck, goose, brant, swan.

Ohio:

Squirrel, quail, ruffed grouse or pheasant, Mongolian pheasant, English or ringneck pheasant, dove, woodcock, plover, snipe, shore birds, rail, duck, goose, swan, coot, mud hen.

Exception: Nonresident may take with him from State under his hunting license 50 animals and birds.

Oklahoma:

Deer, antelope, quail, grouse, prairie chicken, imported pheasant, wild turkey, dove, plover.

Oregon:

Deer, antelope, elk, moose, mountain sheep (or hides of said animals), quail or bobwhite, English or gray partridge, capercailzie, moor hen, grouse, sage hen, pheasant; Mongolian, silver, golden, copper, green Japanese, and Reeves pheasants; prairie chicken, wild turkey, woodcock, rail, upland plover, duck, goose, swan, or other wildfowl.

Exception: Any citizen of Washington may take one day's bag with him out of the State.

Pennsylvania:

Deer, rabbit, hare, squirrel, quail, partridge, grouse, pheasant; English, Mongolian, or Chine pheasant; wild turkey, reedbird, plover, woodcock, rail, web-footed wildfowl, taken in State.

Rhode Island:

Quail, ruffed grouse, woodcock.

South Carolina:

Deer, quail, partridge, grouse, pheasant, wild turkey, woodcock, snipe, and other game birds animals.

Exception: Licensee may carry openly in his hand 2 deer, 50 partridges, 12 ruffed grou 4 wild turkeys, 50 beach birds, 50 wild ducks and geese in aseason.

South Dakota:

Deer, elk, antelope, buffalo, mountain sheep, quail, ruffed grouse, prairie chicken, pinnat grouse, sharp-tailed grouse, plover, curlew, woodcock, crane, duck, goose, brant.

Exception: Two deer, 1 elk, 1 buffalo, 1 mountain sheep, and not more than 15 birds n intended for commercial purposes may be shipped in open view during open season and days thereafter, when tagged and accompanied by owner; and in the case of big game, certificate—good for 5 days—that such game was lawfully killed must be obtained from justice of the peace and given to the carrier.

Tennessee:

All State game, viz: Deer, squirrel, quail, partridge, grouse, prairie chicken, pheasant, wi turkey, marsh blackbird, dove, meadowlark, robin, plover, snipe, woodcock, sandpiper, tatle willet, curlew, godwit, avocet, rail, coot, mud hen, duck, goose, swan, brant.

Exception: Nonresident may take with him from the State 50 ducks or 30 head of oth game, but must present to some officer or employee of common carrier his hunting licen and sworn statement that his game is not for sale and will not be sold.

Texas:

All wild animals, wild birds, and wild fowl found in the State, including deer, antelope, mou tain sheep, quail or partridge, grouse, pinnated grouse or prairie chicken, Mongolian English pheasant, wild turkey, dove, pigeon, plover, snipe, jacksnipe, curlew, duck, goose.

Exception: Nonresident licensee may take one day's bag out of State.

Utah:

Deer, elk, antelope, mountain sheep, quail, partridge, prairie chicken, sage hen or grouse, pir nated grouse, pheasant, Mongolian, Chinese, or English pheasant, dove, snipe, shore bird, duck goose, brant, swan, or any introduced game animal or bird.

Vermont:

Deer, gray squirrel, quail, ruffed grouse or partridge, plover, English snipe, woodcock, duck, goo

Exception: One deer may be exported during the open season and ten days thereafter by resident, if shipped open to view, properly labeled with the name of the owner and acco panied by him; and by a nonresident when his license, with shipping coupons attached, presented to the transportation company.

---

[a] The following county laws are also in force: Brunswick, Dare, New Hanover—Wild fowl, Mar 10-November 10 from county. Catawba, Iredell, Surry, Swain—Quail from county.

Export of Game Prohibited—Continued.

rginia:

Deer, venison, quail or partridge, pheasant or grouse, wild turkey, woodcock, plover, snipe, sandpiper, surf-bird, curlew, willet, tatler, rail (except sora), mud hen, gallinule, waterfowl.

Exceptions: During open season nonresident may, under his hunting license, take with him out of the State, or as baggage on the same conveyance, 1 deer, 50 quail or partridges, 10 pheasants or grouse, 3 wild turkeys, 30 waterfowl, and 25 of each, or 100 in all, of plover, snipe, sandpipers, willets, tatlers, and curlew, if killed or captured by himself, and shipped open to view and plainly labeled with his name and address. Any citizen of State may ship from the State, as a gift and not for sale (which fact must be stated on shipping tag), 1 deer, 18 quail or partridges, 6 pheasants, 3 wild turkeys, and 12 waterfowl, if open to view and plainly labeled with names and addresses of donor and donee, and number of each kind of bird so shipped.

'ashington:

Deer, elk, moose, caribou, antelope, mountain sheep or goat, quail, partridge, grouse, prairie chicken, sage hen, pheasant, ptarmigan, plover, rail, sandhill crane, snipe, duck, goose, brant, swan or any other game animal or bird of the State, including introduced bobwhite, California valley quail, mountain quail, and Old World pheasants.

Exception: Nonresident may export one season's limit of big game and one day's bag limit of birds under his hunting license, if accompanied by affidavit that the game was killed by him and is not for sale.

est Virginia:

Deer, quail, pheasant, ruffed grouse, wild turkey.

sconsin:

Deer, quail, partridge, grouse, prairie chicken, pheasant, Mongolian, Chinese, or English pheasant, dove, plover, snipe, woodcock, rail, wild duck, goose, brant, swan, or other aquatic fowl.

Exception: During open season nonresident may take out of State under his hunting license, in personal possession or as baggage or express, accompanying same to State line, 1 deer and not more than 30 game animals and birds of all kinds, provided packages are plainly marked so as to show the names and addresses of shipper and consignee and number of each kind of game, and, in case of deer, have proper coupons attached.

oming:

Deer, elk, moose, antelope, mountain sheep, or green hides, teeth, or horns of any of said animals.

Exceptions: Smithsonian Institution or other well-known scientific institutions may export any game animals or birds, under permit of State game warden; mounted heads and stuffed specimens may be shipped out of State.

Export of 1 hide, 1 scalp, 1 head, and 1 pair of tusks of any big game except moose, permitted upon affidavit that they were taken from animals lawfully killed and the payment of 25 cents to the justice of the peace of precinct where affiant lives and attachment of the tag issued by him; and a nonresident (or resident, when necessary to cross territory of another State to reach his home) may export under his hunting license carcasses, heads, antlers, scalps, skins, and teeth of any animals lawfully killed.

berta:

Deer, elk, moose, caribou, buffalo, sheep, goat, antelope, grouse, prairie chicken, pheasant, ptarmigan, snipe, sandpiper, plover, curlew, shore bird, rail coot, crane, duck, goose, swan.

Exceptions: Commissioner of Agriculture may grant permits to export for propagation for public parks, zoological gardens, or scientific purposes one pair of each species of big game and game birds upon payment of $5 fee. The holder of a general nonresident license may take with him out of the Province as trophies, heads, skins, and hoofs of big game legally killed by him.

itish Columbia:

Deer, elk, moose, caribou, mountain sheep, mountain goat, hare, quail, partridge (English), pheasant, grouse, prairie chicken, ptarmigan, snipe, plover, duck, swan.

Exception: Heads, horns, and skins of big game lawfully killed by the shipper may be shipped under his hunting license.

nitoba:

Deer, elk, moose, caribou, antelope, quail, grouse, partridge, prairie chicken, pheasant, plover, snipe, sandpiper, woodcock, duck.

Exception: Minister of agriculture and immigration may issue permit to export heads and skins of 2 of each species of animal and all game, except grouse, prairie chicken, and partridge, and not more than 100 geese and swans, or 50 ducks.

w Brunswick:[a]

Deer, moose, caribou, or any portion thereof; partridge, pheasant, woodcock, snipe, wood duck, dusky (black) duck, teal, goose, brant.

Exception: Surveyor-general may issue special license to export game alive or dead.

---

[a] Except in the case of partridge the prohibition applies only to common carriers.

Export of Game Prohibited—Continued.

Newfoundland:

Caribou (antlers, heads, or skins), or partridge, willow or other grouse for sale.

Exceptions: Minister of marine and fisheries may issue special licenses to export game for breeding or scientific purposes. Nonresident may export 3 stag caribou under hunting license and export permit; resident may export antlers, head, or skin of caribou under export permit; but not, in either case, for sale.

Nova Scotia:

Red deer, American elk, moose, moose skin, caribou, caribou skin, hare, rabbit, quail, Canada grouse (spruce partridge), ruffed grouse (birch partridge), pheasant, blackcock, capercailzie, ptarmigan, sharp-tailed grouse, woodcock, snipe, plover, curlew, yellowlegs, beach birds, all waders and sandpipers, blue-winged duck, teal, wood duck, American scoter (black coot), surf scoter (sea coot), American eider, king-eider, harlequin duck, old squaw, whistler, American scaup duck, lesser scaup duck (bluebill), white-winged coot, American widgeon, gannet, goose, brant, heron, bittern, loon, gull, least tern, stormy petrel.

Exceptions: Holder of general license may take with him, out of Province, the mounted head and remainder of the carcass of any moose lawfully shot by himself; and mounted heads and dressed skins or live mammals or birds for propagation may be exported under permit from Provincial secretary.

Ontario:

All wild game animals and birds.

Exceptions: 1 bull moose and 1 bull caribou or head, skin, or parts thereof, between October 15 and December 1, and 2 deer, head, skin, or part thereof, in November, and 100 ducks may be exported under nonresident hunting license, if shipping coupon and, if required, affidavit of lawful killing, be attached and contents of packages be open to view.

Prince Edward Island:

All game except geese and brant.

Exception: Nonresident licensee may carry out of Province 12 birds killed by himself.

Quebec:

Deer, moose, caribou, or parts thereof, except under permit from minister of colonization, mines, and fisheries (fee not to exceed $5) and under tags attached to nonresident licenses.

Saskatchewan:

Deer, elk, moose, caribou, buffalo, sheep, goat, antelope, grouse, prairie chicken, pheasant, ptarmigan, snipe, sandpiper, plover, curlew, shore bird, rail, coot, crane, duck, goose, swan.

Exceptions: Commissioner of agriculture may grant permits to export for propagation for public parks and zoological gardens or scientific purposes 1 pair of each species of big game and game birds upon payment of $5, or a specified number on application of another Province or State. The holder of a general nonresident license may take with him out of the Province as trophies heads, skins, and hoofs of big game which he has legally killed.

Canada also has a general law prohibiting export of deer (except those raised on private preserves), wild turkeys, quail, partridges, prairie fowl, and woodcock, and permitting each nonresident to export two deer in a year at certain ports within fifteen days after the close of the open season, under permit of the collector of customs of the port from which export is made. The ports of export are: Halifax and [illegible] Scotia; Macadam Junction, New Brunswick; Quebec, [illegible] Ottawa, Quebec; Kingston, Niagara Falls, Fort Erie, [illegible] Marie, and Port Arthur, Ontario; and such others [illegible] customs may designate.

[illegible] camp, etc., must deposit with the [illegible] an amount equal to the duty (30 [illegible] guns, canoes, tents, cooking [illegible] are taken out within six [illegible] returned. But members [illegible] reserves in Canada and ha[illegible] Canadian commissioner of customs may [illegible] certificates in lieu of making the deposit. The [illegible] ammunition and provisions.



FIG. 1.—States and Provinces which prohibit export of game. Ruled areas indicate States whi prohibit export of any game; dotted areas, States which prohibit export of certain kinds of gan Inclosed names indicate special exceptions permitting nonresident hunters to take out a limit amount of game. The letter *a* indicates prohibition of export for sale only. (For details, pp. 27-32.)



FIG. 2.—States and Provinces which prohibit sale of game throughout the year. Ruled areas in cate States prohibiting sale (resale in Nevada) of all protected game; crossed areas, States prohibiti sale of all protected game taken in the State; dotted areas, States prohibiting sale (resale in De ware) of certain game; and blank areas, States that have no special sale prohibitions (except a f local provisions in North Carolina and Virginia). (For details, see pp. 35-39.)

MAPS SHOWING RESTRICTIONS ON EXPORT AND SALE IN 1907.

SALE.

Legislation restricting the sale of game is passing through a transition stage. Some States prohibit the sale of game throughout the year, others only in close season, and between these extremes may be found all gradations and exceptions, such as restrictions prohibiting sale of game outside the State or for export, and exemptions allowing sale for a few days in the close season. The difficulty of tabulating such regulations is increased by the fact that in addition to the special sale laws, close seasons, and provisions regarding possession must be taken into consideration. In consulting the following summary, therefore, it will be necessary to bear in mind three different classes of restrictions: "Sale prohibited all the year," "Sale in close season," and "Sale in open season."

SALE PROHIBITED ALL THE YEAR.

Forty-three States and Territories[a] and most of the Provinces of Canada now prohibit sale of all or certain kinds of game at all seasons. (See fig. 2, p. 33.) In Alabama, Arizona, Arkansas, Hawaii, Idaho, Kansas, Michigan, Minnesota, Mississippi, Montana, Nebraska, New Mexico, and Texas the sale, and in Nevada the resale, of all game protected by the State law is prohibited; in South Dakota, of all big game; in Wisconsin, of all game except rabbits and squirrels; in California, Utah, Washington, and Manitoba, of all big game and upland game. In a few instances prohibitions against the sale of certain game are so general as to afford protection over a considerable area in adjoining States. Thus, ruffed grouse can not be sold in any State or Province along the Canadian border except Vermont, New York, Pennsylvania, Ohio, New Brunswick, and Quebec, nor in the States of Massachusetts, Rhode Island, Connecticut, Arkansas, Kansas, Nebraska, or Wisconsin. Practically every State in which prairie chickens occur now prohibits their sale or export. Hence exposure of these birds for sale in any State where they do not occur, as in any city east of Indianapolis, is strong indication of violation of law.

SALE IN CLOSE SEASON.

In general, the sale of game is prohibited during the close season but a brief additional open period is sometimes provided in order t permit dealers to close out stock on hand at the end of the huntin season. In Colorado, Illinois, Iowa, Nebraska, New York, Tennessee and British Columbia the sale season includes the open season and th following five days for all or certain kinds of game. An extension o ten days for sale is added to the open season in New Brunswick; fifteen days in Alaska, New Jersey, Pennsylvania, and Quebec; thirt days (for imported ruffed grouse) in Pennsylvania; sixty days i Yukon; three months (for goose and brant) in New Brunswick; an until the following 1st of January in Ontario.

---

[a] Including Hawaii, but omitting Tennessee and Virginia, which prohibit sale only a few of their counties, and Alaska, which prohibits sale of only heads, ski and trophies.

SALE IN OPEN SEASON.

rder to counteract a tendency on the part of market hunters to
pate the opening of the season, the sale of certain game is some-
prohibited at the beginning of the open season, as during the
wo days in Illinois, the first three in Nova Scotia and Quebec, and
st month in British Columbia. Washington permits the sale of
and wildfowl (which may be killed from September 1 to March
y during November and then not more than 25 in a day.
following table shows the kinds of game sale of which is *pro-*
d throughout the year. The sale of all other game is so generally
bited during the close season as to render a detailed enumeration
essary, but when an extension of a few days is added to the open
or a special season is provided for either possession or sale,
ion is called to this exemption under the heading "Permitted."

Sale of Game Prohibited throughout the Year.

na:
game protected by the State.

:
ds, hides, and skins of all protected game.
Permitted: Carcasses of all game may be sold during the open season and 15 days thereafter.

a:
, elk, antelope, sheep, goat (or meat, hide, head, or horns of said animals), quail, bobwhite,
rtridge, grouse, pheasant, wild turkey, dove, snipe, rail, duck, goose, brant.

as:
"game, wild fowl, or birds whatsoever," except bears, rabbits, opossums, raccoons, and
uirrels.[a]

nia:
meat and hides of female deer, or those from which evidence of sex has been removed,
ail, partridge, grouse, pheasant, sage hen, dove, ibis, snipe, plover, rail, or shore birds.

lo:
ame taken in the State.
ermitted: Domestic game may be sold by hotels, restaurants, etc., during the open season
d five days thereafter, or during the limits of a storage permit. Imported game (under
ense) and game taken from licensed private parks and lakes may be sold at any time if
ompanied by an invoice.

ticut:
l, ruffed grouse, woodcock, until October 1, 1911.

re:
l, partridge, pheasant; buying for sale prohibited.

:
, deer hides, quail or partridge, wild turkey.

ame protected by the Territory.

ame protected by the State.

, squirrel (gray, red, fox, black), quail, Mexican blue quail, California mountain quail, Cali-
nia valley quail, ruffed grouse (pheasant), pinnated grouse (prairie chicken), pheasant
glish ringneck, Chinese ringneck, green (Japanese), copper (Soemmering), tropogan [trago-
], silver, golden, Reeves, Elliot, Hungarian, Swinhoe, Amherst, melanotte, impeyan, argus);
tridge (Hungarian, black Indian, caccabis, chukar), sand grouse; capercailzie, heath grouse
ack grouse), wild turkey, duck, goose, brant, coot, rail.
ermitted: Deer bred in inclosures for market may be sold at any time; cock pheasants may be
d by breeders (under permit of State game commissioner) from November 1 to January 1,
ves, woodcock, snipe, plover, coot, and rail may be sold from the third day of the open season
the fifth day of the close season, and squirrels, quail, ruffed grouse (partridges), pinnated
use (prairie chickens), Mexican blue quail, California mountain quail, California valley
ail, Hungarian partridges, capercailzie, heath grouse (black grouse), wild turkey, duck
se, and brant imported from other States from October 1 to February 1.

---

[a] Squirrels killed in Ouachita and Union counties can not be sold therein.

Sale of Game Prohibited throughout the Year—Continued.

Indiana:

Quail.

Iowa:

Permitted: All game may be sold during the open season and five days thereafter.

Kansas:

Red squirrel, quail, partridge, grouse, pinnated grouse (prairie chicken), pheasant, dove, plover, duck, goose, brant (buying also prohibited).

Kentucky:

Quail, partridge, grouse, pheasant, wild turkey, killed in the State.

Maine:

Deer, moose, or game birds for export. Ruffed grouse, woodcock, all protected ducks, for any purpose.

Permitted: Deer may be sold by local dealers under license.

Maryland:

Anne Arundel—Quail, partridge, pheasant, woodcock, snipe, plover.

Frederick—Squirrel, partridge, pheasant, woodcock, taken in county.

Montgomery—Partridge, pheasant, wild turkey, for export.

Somerset—Rabbit, quail or partridge, woodcock, dead or alive, for export from the county, or for any other purpose than as food within the county, or for propagating purposes.

Washington—Deer, squirrel, rabbit, partridge, pheasant, wild turkey, taken in county.

Wicomico, Worcester—Quail or partridge for export (both counties considered as one territory).

Permitted: Baltimore City—Ruffed grouse, may be sold October 1-December 25.

Massachusetts:

Deer and quail taken in the State, ruffed grouse, heath hen, prairie chicken, sharp-tailed grouse, woodcock, and wood duck.

Permitted: Dealers or persons in the cold-storage business may sell quail lawfully imported, during November and December.

Michigan:

All game protected by the State.

Minnesota:

All game protected by the State.

Mississippi:

All game protected by the State.

Missouri:

All game protected by the State.

Permitted: Game lawfully secured may be sold in county of capture. Imported game may be sold during open season.

Montana:

All game protected by the State.

Nebraska:

All game protected by the State.

Nevada:

Resale of all game.

New Hampshire:

Ruffed grouse or partridge, woodcock.

New Jersey:

Deer taken in the State until November 10, 1909.

Permitted: All other game may be sold during the open season and fifteen days thereafter.

New Mexico:

Deer, elk, antelope, mountain sheep, native or crested and bobwhite quail, partridge, grouse, pheasant, ptarmigan, wild turkey, turtle dove, wild pigeon, killed in the Territory.

New York:

Grouse and woodcock taken in the State, and quail taken in Delaware, Greene, Orange, Schoharie, Sullivan, and Ulster counties.

Permitted: Deer may be sold from October 1 to November 25. Elk, caribou, and antelope imported or killed in a private park by the owner may be sold during the open season for deer; and quail, grouse, and woodcock (except as noted above) during the open season and until January 1. Pheasants bred or liberated in Dutchess and Suffolk counties may be possessed at any season in Greater New York for consumption but not for sale. Ducks, geese, brant, and swans may be possessed during the open season and until March 1. On Long Island ducks, geese, and swans may be possessed from October 1 to March 1, and brant until May 1. Squirrels, hares and rabbits, quail, grouse, and woodcock lawfully taken on Long Island may be possessed in the city of New York during the open season in the State at large.

North Dakota:

Deer, ruffed grouse, pinnated grouse, prairie chicken, sharp-tailed grouse, woodcock.

Ohio:

Squirrel, quail, ruffed grouse, Mongolian, English, or ringneck pheasant, dove, woodcock, snipe, plover, rail, shore bird, duck, goose, swan, coot, mud hen, killed in the State for sale.

ahoma:

Deer, antelope, quail, grouse, prairie chicken, wild turkey, dove.

Sale of Game Prohibited throughout the Year—Continued.

on:

eer, elk, moose, mountain sheep, silver-gray squirrel, quail, bobwhite quail, partridge, grouse, ruffed grouse, capercailzie, moor hen, pheasant (silver, golden, copper, green Japanese, Reeves, and ringneck), wild turkey, woodcock, upland plover, rail, duck, swan.

Permitted: Five deerskins, properly tagged, may be sold in a season by the hunter who originally secured them. Tags not issued after first five days of close season.

ısylvania:

eer, quail, partridge, grouse, pheasant, taken in the State; wild turkey and woodcock (wherever taken).

Permitted: Squirrel, rabbit or hare, bear, dove, reedbird, blackbird, upland plover, Wilson or jack snipe, sandpiper, tatler, curlew, or any other shore bird, rail, coot or mud hen, duck, goose, brant, and swan taken in the State may be sold during the open season and fifteen days thereafter; ruffed grouse taken outside of the State may be sold during the open season and thirty days thereafter.

de Island:

uail, ruffed grouse, pheasant, woodcock.

h Carolina:

eer until February 23, 1908; quail or partridge, pheasant, wild turkey, and woodcock, taken in the State, until March 1, 1911.

h Dakota:

eer, elk, buffalo, mountain sheep.

Permitted: Skins, heads, and antlers of animals lawfully killed may be sold at any time.

ıessee:

yer County—Wild turkey.

Permitted: All game may be sold in the State during the open season and five days thereafter.

s:

ll game animals, hides and horns, wild birds, and wildfowl found in the State.

:

eer, elk, antelope, mountain sheep, quail, partridge, grouse, prairie chicken, sage hen, pheasant Mongolian, Chinese, and English pheasant, dove.

Permitted: 25 in all of shorebirds and waterfowl may be sold in a day to private parties.

ıont:

uail, ruffed grouse, pheasant or English partridge, English snipe, plover, woodcock, duck, goose, except for consumption as food in the State.[a]

nia:

nglish or Mongolian pheasant (except for propagation) until January 1, 1909.

arroll, Grayson, Greenesville, Patrick, Sussex counties—Quail or partridge taken in county.

larke county—Quail, rabbit, squirrel, pheasant, wild turkey (outside of county).

rederick, Shenandoah counties—Quail, ruffed grouse, wild turkey, woodcock (prohibition applies only to nonresidents of Virginia).

age county—Quail (for export).

hington:

eer, elk, moose, caribou, mountain sheep, mountain goat, quail, partridge, grouse, prairie chicken, sage hen, ptarmigan, pheasant, Chinese or Mongolian pheasant, sandhill crane, plover, rail, swan, and all other game birds except ducks, geese, and brant.

Permitted: Ducks, geese, and brant may be sold during November, but only 25 in a day.

onsin:

enison, quail, partridge, grouse, prairie chicken, pheasant, Mongolian, Chinese, or English pheasant, snipe, plover, woodcock, duck, goose, brant, or other aquatic bird.

ming:

eer, elk, moose, antelope, mountain sheep, or skins, heads, antlers, or teeth thereof.

Permitted: Sale of 1 hide, 1 scalp, and 1 head of any big game, except moose, and 1 pair of elk tusks, on affidavit that they were taken from animals lawfully killed.

rta:

ountain sheep, mountain goat, or prairie chicken, grouse, pheasant, ptarmigan, or other member of the Gallinæ, unless captured by owner. Heads of big game before they can be sold must be stamped by minister of agriculture at fees of $5 for elk, caribou, moose, and sheep, and $2 for deer, antelope, and goat.

sh Columbia:

lk, quail, grouse, ptarmigan, prairie chicken, English partridge, pheasant, swan, female and young of deer, moose, caribou, or mountain sheep, heads of moose, caribou, and sheep; also male deer on Vancouver Island.

Permitted: Male deer after September 1; male moose, caribou, mountain sheep, mountain goats, and hares after October 1; and snipe, plover, and ducks may be sold during the open season and five days thereafter.

itoba:

eer, elk, moose, caribou, antelope (except heads and hides), quail, grouse, pheasant, partridge, prairie chicken, woodcock, plover, snipe, sandpiper.

---

[a] Game from private game preserves stocked at owner's expense may be sold at any ti



FIG. 3.- States and Provinces which require residents to obtain hunting licenses.



FIG. 4.— States and Provinces which require nonresidents to obtain hunting licenses.

Inclosed names indicate that special privileges are granted for taking a limited amount of game out of the State. Arkansas does not permit hunting by nonresidents; Kentucky has no definite fee. (For details, see pp. 41–48.)

MAPS SHOWING LICENSE LAWS IN 1907.

Sale of Game Prohibited throughout the Year—Continued.

r Brunswick:

Permitted: Geese and brant may be sold during the open season and until March 1, and all other game during the open season and (under license from game warden) ten days thereafter.

wfoundland:

Permitted: Caribou may be sold from August 1 to January 1.

'a Scotia:

Deer, caribou to 1910, pheasant, blackcock, capercailzie, Canada grouse (spruce partridge), chukar partridge.

Permitted: Moose may be sold from October 1 to December 20. Any game bird other than those above mentioned during the open season with the exception of the first three days.

ario:

Quail, partridge, woodcock, snipe, subject to regulations of lieutenant-governor in council.

Permitted: All other game may be sold during the open season[a] and until the following January 1 under license.

nce Edward Island:

Partridge until October 1, 1908.

bec:

Birch or swamp partridge, woodcock, until October 1, 1908.

Permitted: All other game may be sold after the third day of the open season and fifteen days after the close thereof. Hotels, restaurants, and clubs may serve, under license, all game lawfully taken, except birch or swamp partridge and woodcock. Skins and heads of animals lawfully taken and animals kept alive may be sold.

katchewan:

Mountain sheep, mountain goat, or prairie chicken, grouse, pheasant, ptarmigan, or other member of the Gallinæ, unless captured by the owner.

kon:

Permitted: Deer, elk, moose, caribou, bison, musk oxen, sheep, and goats may be sold during the open season and sixty days thereafter.

LICENSES FOR HUNTING AND SHIPPING GAME.

In Arkansas nonresidents are not permitted to hunt, except on their 'n premises, and in 43 States and Territories[b] and throughout Canada enses must be secured before nonresidents can hunt any or certain nds of game (see fig. 4). In 21 States and 4 Canadian Provinces like restriction is imposed on residents, but the fees are usually ry much smaller, and often are merely nominal (see fig. 3). The es for nonresident licenses for both big and small game range from 10 in a number of States to $50 in Wyoming, British Columbia, New runswick, and Newfoundland, and $100 in Saskatchewan; those for sident licenses from 75 cents in North Dakota to $5 in Washington, d $7 ($5 for moose and caribou and $2 for deer) in Ontario.

A new kind of hunting license, often known as the "alien" license, s recently been adopted by several States to restrict hunting by perns who are not citizens of the country. Thus Alabama, Florida, ew Hampshire, Pennsylvania, Louisiana, South Carolina, Texas, Utah, d Wyoming provide that all hunters who are unnaturalized resints of the State must obtain the same license required of nonresints; Massachusetts has a special $15 license for resident aliens, Conecticut and Maine a $15, and Washington a $50 license for nonresint aliens, California a $25 license for all aliens, and Manitoba a $100 cense for all who are not British subjects.

Licenses are generally issued only for the open season, and thus xpire at fixed dates. Some are necessarily very brief in duration. lichigan issues a $25 nonresident deer license good only for twenty ys in November; Vermont, a $15 nonresident deer license good only r the last six consecutive week days of October. In a few instances censes are issued at reduced rates for a week or for a few days. Of is character are the $5 nonresident bird license, good for one week, sued by British Columbia; the guest licenses, good for five days, issued by Alberta and Saskatchewan, and the daily licenses issued for hunting birds in Colorado and any game in Lafayette County, Fla.

---

[a] Seasons depend on regulations of game commission.

[b] Not including Georgia, in which a license must be secured to hunt for marl

Eleven States issue licenses good only in the county named therein—Alabama, Colorado, Florida, Georgia (market hunting), Iowa, Maryland, Mississippi, Missouri, South Carolina, South Dakota, and Washington—with fees ranging from $1 for residents of Alabama and Washington, to $50 for residents hunting ducks for market in South Carolina.

Twenty-eight States and 8 Canadian Provinces allow nonresident licensees to carry or ship out of the State or Province a limited amount of game, while this privilege is denied by 15 States and Territories and 1 Canadian Province. Maine, Michigan, and Montana issue export permits additional to the hunting license.

Nonresident landowners or taxpayers are not required to pay the usual fee in Maryland (most counties),[a] Massachusetts, New Hampshire, New Jersey, North Dakota, Tennessee, Nova Scotia, and Prince Edward Island. But to secure this exemption in Massachusetts and New Hampshire the nonresident hunter must own land to the value of $500 and $1,000, respectively; in Tennessee, Nova Scotia, and Prince Edward Island he must pay a tax of at least $100, $30, or $25 per annum, respectively, and in North Dakota must own or cultivate a quarter section of land. Similar exemptions are made in the case of resident landowners and, in some instances, their tenants hunting on their land in Alabama, California, Colorado (farming or grazing lands only), Connecticut, Illinois, Indiana, Kansas, Montana, North Dakota, and Oregon, and no license is required of those hunting within their own county in Minnesota, Missouri, or Nebraska. Special exemptions are made in favor of nonresident members of fish and game clubs by Kansas, Massachusetts, Rhode Island, and Quebec. In Virginia no license is required of bona fide guests of residents, and in Ontario no fee is charged for a guest license.

In Maine,[b] South Dakota, Wyoming, New Brunswick (on wild lands), and Nova Scotia nonresidents are not permitted to hunt big game unless accompanied by qualified guides, and in Colorado, Maine, Montana, Wyoming, Alberta, New Brunswick, Newfoundland, Nova Scotia, and Ontario guides are licensed. Maine, Alberta, and New Brunswick also license camp help. Nearly every State requires licensees to have their licenses in personal possession while hunting and to exhibi them on demand of any warden (in New Hampshire of any person).[c]

Details in regard to hunting licenses are given in the following table. In every case the statement regarding the fee includes th amount charged for issuing the license by the county clerk or othe officer.

---

[a] All the counties of Maryland allow nonresidents to hunt without license on invitation of landowners, except Allegany, Caroline, Dorchester (unless relatives), Garrett, Kent, Somerset, Talbot, Wicomico (unless accompanied by a resident), an Worcester.

[b] On wild lands of the State, except from December 1 to 15.

[c] The following counties in North Carolina require hunters to obtain written permission for hunting on lands other than their own: Anson (Lanesboro Township) Cherokee, Clay, Craven, Currituck, Davidson, Henderson, Hertford, Jones, Madison Martin, (Cross Roads, New Hope, Goose Nest, Hamilton, and Poplar Point townships), Montgomery, Nash, Randolph (townships of Back Creek, Franklinsvill [quail], and part of Columbia), Richmond (Mineral Springs and Wolfpit townships) Robeson (south of the Carolina Central Railroad and east of the Carolina Norther ailroad), Rowan, Rutherford (Rutherford Township), Union, Wayne, and Yadkin

State.	Kind of license.	Fee.	By whom issued.	Details of license.	Bag limit.	Export limit.
bama	Nonresident	$15.00	Probate judge of the county.	Expires Dec. 31.	1 deer, 2 turkeys, 25 of each other kind of birds a day.	Nonresident licensee may carry out of State or have carried to him game lawfully killed by him.
	Alien	15.00	do	do		
	Resident	3.00	do	State license; required to hunt outside of county of residence, except on lands owned or leased by hunter. Expires Dec. 31.		
	Resident	1.00	do	County license; required to hunt outside of voting precinct, ward, or beat of hunter, except on lands owned or leased by him. Expires Dec. 31.		
ska					2 moose, 4 each of caribou, sheep, goats, large brown bears, 8 deer a year; 10 grouse or ptarmigan, 25 shore birds or waterfowl a day.	In discretion of Secretary of Agriculture, who issues permit in each case.
zona	Nonresident	10.00	Fish and game commissioner or county recorder.	Deer only.	3 deer a season, 25 quail a day.	No export.
tansas				Nonresidents not permitted to hunt.[a]		Do.
lfornia	Nonresident	10.00	Board of fish commissioners, county clerks.	Expires not later than June 30. Land owners hunting on their own lands exempt.	2 deer a season; 25 each of quail, partridges, snipe, plover, curlew, shore-birds, rail, ibises, and doves, and 35 ducks a day.	Do.
	Alien	25.00	do	do		
	Resident	1.00	do	do		
orado	Nonresident	25.00	Commissioner of game	Expires Dec. 31	1 deer a season; 25 ducks a day, 50 in possession at once; 25 other birds a day, 50 in possession at once.	Permit from commissioner required.
	do	2.00	do	County license for birds, $2 first day; each subsequent day $1. Expires Dec. 31.		
	Resident	1.00	Commissioner of game or county clerk.	Expires Dec. 31. Owners of farms or grazing lands hunting on their premises exempt.		
	Guide	5.00	Commissioner of game	Expires Dec. 31. Must have in addition a State license.		
necticut [b]	Nonresident	10.25	Town city, or borough clerk.	Good for 1 year from date of issue.	5 ruffed grouse a day, 36 a year; 35 rail, 50 each of plover, snipe, shore-birds a day.	No quail, ruffed grouse, or woodcock.
	Alien	15.25	do	do		
	Resident	1.10	do	do		

[a] But see State *v.* Mallory, 88 S. W. 955, deciding that nonresidents may hunt on their own land.

[b] No license is required of a bona fide resident of Connecticut, or his lineal descendants, hunting on land occupied by him and used for agricultural purposes.

Details of hunting licenses, with bag limits, and export regulations—Continued.

State.	Kind of license.	Fee.	By whom issued.	Details of license.	Bag limit.	Export limit.
Delaware	Nonresident	$5.00	Delaware Game Protective Association.	$2 for each subsequent year.		No rabbit, quail, partridge, robin, woodcock, Wilson snipe.
Florida	Noncitizen	10.00	Clerk of circuit court	County license. Expires Mar. 1.[a]	5 deer, 5 turkeys a year; 20 quail, 2 turkeys by individual or 40 quail, 4 turkeys by party a day.	No deer, quail, or wild turkeys.
Georgia	Market hunting.	25.00	Ordinary of county	County license; permits killing for sale. Expires Dec. 31.	40 doves a day	No quail.
Idaho	Nonresident	25.00	State warden, deputy probate judge, or justice of the peace.	Expires Jan. 31	2 deer, 1 ibex, 1 goat, 1 sheep, 1 elk a season; 18 quail, 12 each of sage hens, partridges, pheasants, grouse, prairie chickens, 24 ducks, 3 geese a day.	2 deer, 1 ibex, 1 mountain goat, 1 mountain sheep, 1 elk. No birds.
	Nonresident	5.00	do	Birds only. Expires Jan. 31.		
	Resident	1.00	do	Expires Jan. 31. Not required of females.		
Illinois	Nonresident	15.50	City, village, or county clerk.	Expires June 1	15 squirrels; 20 rail, ducks, geese, brant, coots, or other waterfowl and 15 other birds a day.	50 birds of all kinds.
	Resident	1.00	do	Expires June 1. Not required of owners and tenants of farms hunting on their lands.		
Indiana	Nonresident	15.50	Clerk of circuit court	Good for 1 year.	15 quail; 15 ducks or other waterfowl a day; 45 birds in possession as result of 3 or more days' consecutive hunting.	15 birds of all kinds, or 45 in case of 3 or more days' consecutive hunting.
	Resident	1.00	Commissioner of fisheries and game, clerk of circuit court.	Good for 1 year. Not required of landowners hunting on their own lands, nor of their children or tenants, nor for hunting rabbits in township of residence.		
Iowa	Nonresident	10.50	County auditor	County license. Expires Jan. 1.	25 each of quail, prairie chickens, ruffed grouse or pheasants, woodcock, wild turkeys, ducks, geese, brant a day.	25 of all kinds of game.
Kansas	Nonresident	15.00	Secretary of state	Expires June 30. Not required of owners of land and members of hunting club hunting on their own premises.	20 each of quail, plover, duck; 15 each of grouse, prairie chickens; 10 each of geese, brant a day.	No export.
	Resident	1.00	County clerk	do		
Kentucky	Nonresident		do	Expires 1 year from date of issue. Same fee as resident of Kentucky is subject to in State of nonresident.		Do.
Louisiana	Nonresident	10.00	Sheriff	Required of nonresidents and unnaturalized residents.	6 deer a season; 75 snipe and ducks, 25 other birds a day.	1 deer, 12 birds.
	Market hunting	25.00	do			
Maine	Nonresident	15.00	Commissioners of inland fisheries and game.	All game during October, November, and December.	1 moose, 2 deer a season (except in Cumberland, Knox, Kennebec, Lincoln, Sagadahoc, Waldo, and York counties, limit 1, and in lumber	1 moose, 2 deer, 10 each of partridges, ducks, and woodcock.
	Nonresident	5.00	do	Game that may be shot before Oct. 1. Licensee may procure moose and deer license		

				law or pay taxes in State.	sandpipers a day.	
	Camp keeper	5.00	do			
	Guide (nonresident).	20.00	do	Expires Dec. 31. Guide to be registered, and to guide not more than 5 persons at a time.		
	Guide (resident)	1.00	do	do		
	Shipment		do	Moose, $5; deer, $2; pair of game birds, 50 cents. Permits shipping home or to hospital in State.		
Maryland	Nonresident	5.00 25.50	Clerk of circuit court	Separate county laws[b]		Local laws.
Massachusetts	Alien	15.00	City and town clerk	Required of unnaturalized foreign-born residents. Nonresident aliens not permitted to hunt.		6 birds.
	Nonresident	[c]10.00	Commissioner of fisheries and game.	Expires Dec. 31. Not required of owners of real estate to value of $500.		
Michigan	Nonresident	25.00	County clerk	Deer. Good for season	2 deer a year; 12 each of quail, grouse, spruce hen a day, 50 in possession at a time; 25 ducks, waterfowl, snipe, plover, woodcock a day, 75 in possession at a time.	1 deer under license and shipping permit.
	Nonresident	10.00	do	Small game only. Good for season. Not required of persons hunting on their own land.		
	Resident	1.50	do	Deer. Good for season		
	Export	10.00	State game and fish warden.			Nonresident landowner and member of a club maintaining a game preserve may export 50 ducks or migratory birds killed by him on said premises.
Minnesota	Nonresident	25.00	Board of game and fish commissioners.	Game animals. Expires Dec. 31.	1 deer (nonresident), 2 deer (resident), 1 moose a season, 15 birds a day.	1 deer, 25 birds.
	Nonresident	10.00	do	Game birds. Expires Dec. 31		
	Resident	1.00	County auditor	Not required for county of residence. Expires Dec. 15.		

---

[a] Not applicable to counties having special game laws. Nonresidents of Lafayette and Sumter counties required to secure license of game warden and pay therefor $1 per day. Hernando County issues a $10 nonresident and a $1 resident license, both good for the season, and Clay County issues a $10 guide license; while no one is permitted to hunt in Taylor County who is between the ages of 18 and 60 and does not pay taxes or work on the roads in the county, nor in Wakulla County if between the ages of 21 and 55 and not a taxpayer of the State.

[b] County and local licenses are issued at the following rates, including clerk fees: Allegany, $10.50; Baltimore, $5.25; Calvert, $10.50; Caroline, $5; Carroll, $10.50; Cecil (upland game and shore birds), $5.50; Charles (rabbit, quail, and woodcock), $20.50; Dorchester, $5; Frederick, $15.50; Garrett, $25.50; Harford, $10.50; Howard, $8; Kent, $15.50 (if invited by landowner, $5.50); Montgomery, $15.50; Patuxent River, $11; Prince George, $20.50; Queen Anne, $5; St. Mary, $20.50; Somerset, $5.25, nonresident of the State, $10.50; Talbot, $10; Washington, $10.50 (not required of residents of Maryland or the District of Columbia); Wicomico, $10.50; Worcester (wildfowl), $10. Guests of landowners require no licenses, except in Allegany, Caroline, Dorchester, Garrett, Kent, Talbot, and Worcester counties. Nonresident taxpayers are usually exempt. In Somerset County residents are required to take out a $1.25 license, except to hunt on their own land, and in several other counties residents pay fowling licenses as follows: Anne Arundel, pusher, $2; booby and brush blind, $5; Cecil, Elk, and Bohemia rivers, sneak boat, $5.50, sink box, $10.50; Susquehanna Flats, sneak boat, $5.75, sink $20.75; Harford, sneak boat, $5.75, sink box, $20.75; Patuxent River, pusher, $2.50.

[c] Members of incorporated game clubs owning real estate to the value of $1,000 and organized prior to passage of law pay a fee of only $1.

Details of hunting licenses, with bag limits, and export regulations—Continued.

State.	Kind of license.	Fee.	By whom issued.	Details of license.	Bag limit.	Export limit.
Mississippi	Nonresident	$20.00	Sheriff	County license. Good for season. Landowners and their nonresident relatives and friends, hunting on their lands exempt.	1 deer a day, 5 in a season; 20 each of quail, wild turkeys, plover, tatlers, choroooks, grosbecs, coots, poule d'eau, rails, ducks, swan, geese, brant a day.	No export.
Missouri	Nonresident	15.00	Circuit court clerk or license collector.	County license. Good for 1 year.		
	Resident	1.00	do	Good for 1 year. Required for hunting in counties adjoining county or city of residence.	1 deer, 2 turkeys, 25 of any other species a day; or 2 deer, 4 turkeys, 50 of any other species in possession at a time.	1 deer, 2 turkeys, 25 quail, 25 ducks.
	Resident	2.50	do	County license. Good for 1 year. Required for hunting in counties not adjoining residence.		
Montana	Nonresident	25.00	State game and fish warden or deputy.	Expires Dec. 31	3 deer, 1 elk, 1 antelope, 1 goat, 1 sheep a season; 10 each of grouse, prairie chickens, fool hens, pheasants, sage hens, partridges, turtle doves a day.	Number permitted to be killed under hunting license.
	Nonresident	10.00	do	Birds only. Expires Dec. 31		
	Resident *a*	1.00	State game and fish warden, or deputy, or justice of the peace.	Expires Dec. 31. Not required of landowners hunting on their own premises.		
	Guide	10.00	State game and fish warden.	Good for 1 year		
	Shipping	.50	do	Permits limited export in open season.		
Nebraska	Nonresident	10.00	Game and fish commissioner or county clerk.	Expires Dec. 31	10 geese or brant, 25 other birds (in Sept. only 10 prairie chickens or grouse) a day; 10 geese or brant, 50 other birds in possession at a time.	50 birds.
	Resident	1.00	do	Necessary outside of county of domicile. Expires Dec. 31.		
Nevada					3 deer, 3 antelope a season; 20 quail, 20 ducks, 20 sage hens, 6 grouse, 5 plover, and 15 snipe a day.	No export.
New Hampshire	Nonresident	10.00	Fish and game commissioners.	Expires Dec. 31. Not required of owners of real estate to value of $1,000.	2 deer a season	Nonresident licensee may carry from the State 2 deer, 12 birds.
	Alien	10.00	do			
New Jersey	Nonresident	10.50	County clerk	All game except wild waterfowl, snipe, and mud hens. Expires 1 year from date of issue. Nonresident owners of freehold estate and their sons exempt from fee.	30 marsh hens a day	No upland game except wild turkeys.
New Mexico					1 deer a season	No export for sale.

						grouse, 2 turkeys, 50 beach birds or snipe.
North Dakota	Nonresident	25.00	County auditor	**Expires Dec. 31. Nonresident owning or cultivating a quarter section of land may take out resident license in county where land lies.**	**5 deer a season; 25 birds a day**	No export.
	Resident [c]	.75	....do	Expires Dec. 31. Citizen hunting on his own land exempt.		
Ohio	Nonresident	15.25	County clerk	Expires Dec. 15	10 squirrels; 18 each of quail, doves, woodcock, snipe, plover, rail, shore birds, geese; 25 ducks; 6 each of pheasants, prairie chickens, or grouse a day.	**50 animals and birds.**
Oklahoma						No export.
Oregon	Nonresident	10.00	County clerk	Good for one year. Not required of landowners hunting on their own premises.	5 deer a season; 10 each of quail (east of Cascades, 6 a day, 12 a week), grouse, prairie chickens, ring-neck pheasants a day; 50 ducks a week.	No export allowed, except by Washington hunters, who may take one day's bag.
	Market hunting.	10.00	Game and forestry warden.	Nonresident. Expires Dec. 31.		
	Resident	1.00	County clerk	Good for one year. Not required of landowners hunting on their own premises.		
Pennsylvania	Nonresident	10.00	County treasurer	Required of nonresidents and unnaturalized residents. Good for year of issue.	1 deer a season, 6 squirrels a day; 5 each of ruffed grouse, introduced pheasants, 10 woodcock a day, 20 a week, 50 a season; 10 quail a day, 40 a week, 75 a season; 1 wild turkey a day, 4 a season.	No export.
Rhode Island	Nonresident	[d]10.00	Secretary of State	Expires Dec. 31.		No quail, ruffed grouse, or woodcock.
South Carolina	Nonresident	10.25	County clerk	Required of nonresidents and aliens. Good for season.		Licensee may carry from the State openly in hand 2 deer, 4 wild turkeys, 12 ruffed grouse, 50 each of partridges (quail), beach birds, ducks, geese.
	Market hunting	50.00	County treasurer	**County license for residents hunting wild fowl on public lands and navigable waters. Expires Dec. 31.**		

[a] United States soldiers stationed in the State and officers of the United States forest service classed with residents.

[b] A $25 license is required for shooting wildfowl from blind, battery, box, float, or raft in waters of Dare County lying north of an east-and-west line passing through northern end of Roanoke Island; south of said line 2 nonresidents may shoot from such devices belonging to a resident if a $5 tax has been paid upon same.

[c] Residents of the State under 16 years may hunt without license, but must have written consent of their parents.

[d] Members of incorporated game clubs owning real estate to the value of $1,000 and organized prior to passage of law pay a fee of only $1.

Details of hunting licenses, with bag limits, and export regulations—Continued.

State.	Kind of license.	Fee.	By whom issued.	Details of license.	Bag limit.	Export limit.
South Dakota	Nonresident	$25.00	County treasurer	County license for big game. Issued Nov. 1. Expires Dec. 31. Nonresident licensee must be in charge of guide.	2 deer, 1 elk, 1 buffalo, 1 sheep a year; 15 birds a day.	2 deer, 1 elk, 1 buffalo, 1 sheep, 15 birds.
	Resident	2.50	do			
	Nonresident	10.00	do	State license (birds) for season.		
Tennessee	Nonresident	10.25	State game warden	Expires Dec. 31. Not required of property owners who pay $100 in taxes.	50 ducks; 30 of all other birds in aggregate a day.	50 ducks; 30 of all other birds in aggregate.
	Resident	3.00	do	Required when hunting on lands with verbal permission of owner. Expires Dec. 31.		
	Market hunting.	25.00	do	Annual license; $200 bond required.		
Texas	Noncitizen	15.00	Game, fish, and oyster commissioner.	Expires Dec. 31	3 deer a season; 25 birds a day. (3 wild turkeys Dec. to Feb.).	Nonresident licensee may take out 3 deer, 75 ducks, 25 other birds.
Utah	Nonresident	10.00	State fish and game commissioner or deputy.	Required also of aliens; good to Jan. 31.	2 deer a season (residents only), 12 quail a day (in Davis, Salt Lake, Utah, and Weber counties); 8 each of partridges, pheasants, prairie chickens, sage hens, grouse, doves, and 25 in all of snipe, shorebirds, ducks, geese, brant, swans, a day.	No export.
	Resident	1.00	State fish and game commissioner or depury; justice of the peace.	Not required of females; good to Jan. 31.		
Vermont	Nonresident	[a]15.00	State fish and game commissioner.	Deer only [b]	1 deer and 35 ruffed grouse or woodcock a season; 5 each of gray squirrels, quail, ruffed grouse, pheasants, woodcock, plover, English snipe, geese, and 20 ducks a day.	1 deer; no birds.
	Nonresident	5.00	Town clerk	Birds only [b]		
Virginia[c]	Nonresident	10.00	County clerk	Good in open season in the 6 months following issue.	....	1 deer, 50 quail, 10 pheasants or grouse, 3 wild turkeys, 30 waterfowl, 25 of each or 100 in all, plover, snipe, sandpipers, willets, and tatlers.
Washington	Nonresident	10.00	State auditor	State license. Good for 1 year.	4 deer, 1 moose, 1 antelope, 1 caribou, 2 sheep, 2 goats a season; 10 each of partridges, Chinese pheasants, ptarmigan, grouse, prairie chickens, sage hens; 15 quail; 25 each of plover, rail, cranes, snipe, ducks, or other waterfowl a day.	A season's limit of big game and a day's limit of birds.
	Nonresident	5.00	State or county auditor	County license. Good for 1 year.		
	Alien	50.00	do	State or county license. Nonresident. Good for 1 year.		
	Resident	5.00	State auditor	State license. Good for 1 year.		
	Resident	1.00	State or county auditor	County license. Good for 1 year.		
West Virginia	Nonresident	16.00	State game warden	Good for 1 year. Not required of landowners hunting on own property.	2 deer a season; 12 quail a day.	No deer, quail, ruffed grouse, pheasants, wild turkeys.

oming	Nonresident	50.00	Justice of the peace	Expires Dec. 31. Required also of aliens. Each licensee must employ guide.	2 deer, 1 elk, 1 antelope, 1 sheep a season; 12 birds a day.	2 deer, 1 elk, 1 antelope, 1 sheep.
	Nonresident	5.00	do	Birds only. Expires Dec. 31		
	Resident [e]	2.00	do	Expires Dec. 31		
	Resident	1.00	do	Birds only. Expires Dec. 31		
	Guide [f]	10.00	do	Good for one year.		
erta	Nonresident	25.00	Game guardian	Expires Dec. 31	1 deer, 1 elk, 1 moose, 1 caribou, 2 antelope a season; 20 grouse, partridges, pheasants, prairie chickens, ptarmigan a day, or 200 a season.	Under general license, trophies of big game legally killed.
	Nonresident	15.00	do	Birds only. Expires Dec. 31		
	Guest	2.00	do	Guests of residents hunting with them. Good for 5 days.		
	Guide, camp help.	5.00	do	Maximum fee. Expires Dec. 31.		
	Resident	2.50	do	Big game. Expires Dec. 31 [g]		
tish Columbia	Nonresident	50.00	Game warden or any government agent.	Members of army or navy or Canadian militia in actual service exempt.	5 deer, 2 elk, 2 moose, 5 caribou, 5 goats, 3 sheep, 250 ducks and snipe a season.	Heads, hides, and horns of animals legally killed by nonresident licensees.
	Nonresident	5.00	do	Birds only. Good for 1 week		
nitoba	Alien	100.00	Minister of agriculture and immigration.	Nonresident. Good for season.	1 deer, 1 elk, 1 moose, 1 caribou, 1 antelope a season; 20 in all of grouse, partridges, prairie chickens a day, 100 a season; 50 ducks a day in September.	No export. But see p. 31.
	Nonresideut	25.00	do	British subject		
	Resident	2.00	do	Animals only		
w Brunswick	Nonresident	50.00	Surveyor-general; chief game commissioner; any game warden.	Moose, caribou, and deer [h]	2 deer, 1 moose, 1 caribou a season.	No partridge; other game under permit.
	Nonresident	10.00	Surveyor-general	Deer only. Discretionary with surveyor-general.		
	Nonresident	50.00	Surveyor-general; chief game commissioner; any game warden.	In Westmoreland County		
	Resident	2.00	do	Moose, caribou, and deer		
	Resident	.25	do	In Westmoreland County		
	Guide	2.00	do	Resident accompanying anyone hunting big game.		

[a] A nonresident holding a bird license may secure a deer license by paying $10 additional.
[b] Not required of anyone owning real estate in Vermont, occupying the same as a domicile at least three months in the year, and paying taxes thereon.
[c] Guests not required to procure license to hunt on land of host, provided the host receives no compensation, directly or indirectly, from such guest.
[d] Bona fide settlers who have not resided in the State 1 year may take out a special resident license.
[e] Applicant must be an elector of the State; child or ward, over 14 years, of an elector; or a soldier or sailor of the United States and an elector thereof, stationed 1 year post in the State. Soldier and sailor must employ guide.
[f] Guide must be citizen and qualified elector of State, must act as assistant game warden, and is equally responsible with employer for violation of law.
[g] Not required in Northern Alberta.
[h] Nonresidents hunting big game on wild lands must be in charge of registered guide.

Details of hunting licenses, with bag limits, and export regulations—Continued.

State.	Kind of license.	Fee.	By whom issued.	Details of license.	Bag limit.	Export limit.
New Brunswick	Camp help	$1.00	Surveyor-general; chief game commissioner; any game warden.	Resident		
	Camp help	50.00	do	Nonresident		
Newfoundland[a]	Nonresident	51.00	Stipendiary magistrate; justice of the peace; minister of marine.	Good for season. Licensee can not employ unlicensed guide.	3 caribou	3 caribou under license and permit.
	Guide	50.00	do	Nonresident. Resident guide licenses free.		
Nova Scotia[b]	Nonresident	30.00	Provincial secretary, clerk of municipality, or agent of game society.	Expires Aug. 1. Must employ licensed guide.	1 moose a season; 5 ruffed grouse, 10 woodcock a day.	Mounted head and rest of carcass of any moose lawfully killed by licensee.
	Guide	2.00	Provincial secretary or agent, agent of game society.	Resident. Expires Aug. 1.		
Ontario	Nonresident[c]	25.00	Superintendent of game and fisheries.		2 deer, 1 bull moose, 1 bull caribou a season.	2 deer, 1 bull moose, 1 bull caribou, 100 ducks.
	Resident	5.00	do	Moose and caribou		
	Resident	2.00	do	Deer		
	Guest		do	No fee required		
	Guide	2.00?	do	Optional with chief warden and game commissioners.		
Prince Edward Island.	Nonresident[d]	15.00	Game inspector	All game. Expires 1 year after date.		12 birds, (except geese and brant, on which no limit is placed.)
Quebec	Nonresident[e]	25.00	Minister of colonization, mines, and fisheries or his agents.	All game	Zone 1: 2 deer, 2 caribou, 1 moose a season. Zone 2: 2 deer, 1 moose, 4 caribou a season.	
	Resident	5.00	do	3 deer and 3 caribou additional to bag limit.		
Saskatchewan	Nonresident	100.00	Game guardian	Expires Dec. 31	2 deer, 2 elk, 2 moose, 2 caribou a season; [f] 10 grouse, partridges, pheasants, prairie chickens, ptarmigan a day, or 100 a season.	Under general license, trophies of big game legally killed.
	Nonresident	50.00	do	Birds only. Expires Dec. 31.		
	Guest	1.00	do	Guests of residents hunting with them. Good for 5 days.		
Yukon					6 deer, 6 moose, 2 elk, 2 musk oxen a season.	

---

[a] Any officer of a British war ship stationed on the coast of Newfoundland for fisheries protection may obtain a free hunting license good for six weeks of open season and may employ an unlicensed guide.

[b] Former residents, in Government employ, who are members of the game society, require no license. Nonresident landowners paying $30 or more annual taxes require licenses, but pay no fee. Officers of the army or navy stationed in Nova Scotia pay $5 fee, unless members of the game society, in which case they are exempt.

[c] Lieutenant-governor-in-council authorized to increase nonresident license fee as to deer, moose, and caribou to $50, and to provide licenses for residents of other Provinces corresponding with those required by such Provinces of residents of Ontario.

[d] Nonresidents paying taxes on real estate in Prince Edward Island to value of $325 pay a fee of only $5.

[e] Active members of incorporated fish and game clubs pay a fee of $10.

[f] Two each of these animals in southeastern part of Province (formerly southeastern Assiniboia).

.—TABLES SHOWING CLOSE SEASONS FOR GAME UNDER COUNTY LAWS.

al States local laws prevail to such an extent as to require
bles. The county laws of Virginia and Tennessee were
n 1903 and those of Alabama in 1907, but local laws are still
ı Maryland and North Carolina. In California, under the
vernment act of April 1, 1897, boards of supervisors were
l to shorten the open seasons for game, and this privilege was
so generally that the seasons fixed by the State law were mate
ified. In July, 1905, the district court of appeal of the second
district, in passing on the constitutionality of the dove ordi-
os Angeles County (Ex parte Prindle, 1 Cal. App. Dec., 280),
his authority abrogated by an amendment to the constitution
sec. 25½) adopted in 1902, and in July, 1906, the superior court
ernardino County held the game ordinance of that county
ı the same grounds. Consequently these local seasons are
ncluded.

ollowing table the season for each kind of game under the
(if any) is first given, after which the local exceptions are
counties:

MARYLAND.

Close seasons for game under county laws.[a]

f game.	Close seasons.	Kinds of game.	Close seasons.
		Rabbit—Continued.	
	Jan. 1-Oct. 15.	Carroll, Howard	Dec. 25-Nov. 10.
	Jan. 1-Oct. 1.	Charles	Jan. 15-Oct. 15.
n	Jan. 1-Nov. 1.	Dorchester, Talbot	Jan. 1-Nov. 1.
1-Sept. 1 (ex-		Garrett	Feb. 1-Nov. 1.
ws):		Harford	Dec. 1-Nov. 1.
Cecil	Jan. 1-Sept. 1.	Montgomery [b]	Dec. 20-Nov. 1.
ndel	Dec. 24-Sept. 1.	Prince George	Dec. 26-Nov. 9.
	Nov. 2-Sept. 15.	St. Mary	Jan. 16-Nov. 1.
	Jan. 16-Sept. 1.	Somerset	Jan. 1-Nov. 15.
(gray or fox)	Nov. 15-Sept 1.	Wicomico, Worcester	Jan. 15-Nov. 15.
	Dec. 1-Sept. 1.	Quail (or partridge):	
	All the year.	Baltimore, Baltimore City, Charles, Frederick, Kent, St. Mary, Washington.	Dec. 25-Nov. 1.
ry (gray)	Dec. 15-Aug. 1.		
n	Dec. 25-Sept. 15.		
	Feb. 15-Sept. 1.		
ince George	Unprotected.	Allegany	Dec. 1-Nov. 1.
		Anne Arundel. Cecil, Queen Anne.	Dec. 25-Nov. 15.
e, Baltimore le), Calvert, k, Kent, Wash-	Dec. 25-Nov. 1.		
		Calvert	Jan. 11-Nov. 1.
		Caroline	Jan. 16-Nov. 15.
		Carroll, Howard	Dec. 25-Nov. 10.
	Dec. 1-Nov. 1.	Dorchester, Talbot	Jan. 1-Nov. 1.
ndel, Cecil, nne.	Dec. 25-Nov. 15.	Garrett	Until Oct. 1, 1908.
		Harford	Dec. 1-Nov. 1.
	Jan. 16-Nov. 15.	Montgomery	Dec. 20-Nov. 1.

ful to hunt on election day in Baltimore, Frederick, or Harford counties, and in Fred-
t is unlawful to hunt with gun or rifle Oct. 10-Nov. 1.
other means than shooting prohibited Nov. 1-Jan. 15.

MARYLAND—Continued.

Close seasons for game under county laws—Continued.

Kinds of game.	Close season.
Quail (or partridge)—Cont'd.	
Prince George	Dec. 26-Nov. 9.
Somerset, Wicomico, Worcester.	Jan. 15-Nov. 15.
Ruffed grouse (or pheasant):	
Baltimore, Calvert, Caroline, Charles, Frederick, Kent, Talbot.	Dec. 25-Nov. 1.
Allegany	Dec. 1-Nov. 1.
Anne Arundel, Cecil	Dec. 25-Nov. 15.
Carroll, Howard, Queen Anne, St. Mary.	Dec. 25-Nov. 10.
Baltimore City (sale)	Dec. 25-Oct. 1.
Dorchester, Wicomico, Worcester.	Feb. 1-Nov. 10.
Garrett	To Oct. 1, 1908.
Harford	Dec. 1-Nov. 1.
Montgomery	Jan. 1-Sept. 1.
Prince George	Dec. 26-Nov. 9.
Washington	Dec. 25-Aug. 12.
Somerset	Unprotected.
English pheasant, Mongolian pheasant, Dec. 25-Nov. 1 (except as follows):	
Anne Arundel	Dec. 25-Nov. 15.
Howard	Dec. 25-Nov. 10.
Dorchester	Feb. 1-Nov. 10.
Garrett	Until Oct. 1, 1908.
Prince George	Dec. 26-Nov. 10.
Wicomico, Worcester	Feb. 1-Nov. 10.
Wild turkey:	
Baltimore, Baltimore City (sale), Calvert, Caroline, Charles, Prince George, Talbot.	Dec. 25-Nov. 1.
Allegany	Dec. 1-Nov. 1.
Dorchester, Wicomico, Worcester.[a]	Feb. 1-Nov. 10.
Frederick	Jan. 15-Nov. 15.
Garrett	Until Oct. 1, 1908.
Howard	Dec. 25-Nov. 10.
Kent	All the year.
Montgomery	Mar. 1-Nov. 1.
Washington	Jan. 1-Nov. 1.
Anne Arundel, Carroll, Cecil, Harford, Queen Anne, St. Mary, Somerset.	Unprotected.
Dove, Dec. 25-Aug. 15 (except as follows):	
Carroll, Frederick, Wicomico.	All the year.
Dorchester	Jan. 1-Aug. 1.
Kent	Dec. 25-Aug. 1.
Somerset	Jan. 1-Aug. 10.
Washington	Dec. 25-Aug. 12.
Wild pigeon, Kent County	Dec. 25-Aug. 1.
Woodcock:	
Baltimore, Baltimore City (sale), Calvert, Frederick, Howard, Kent.	Dec. 25-Nov. 1.[b]
Allegany	Dec. 1-Nov. 1.
Anne Arundel	Aug. 16-June 14.
Caroline	Jan. 16-July 4.
Carroll	Dec. 25-July 15.
Cecil	Dec. 25-Nov. 15.
Charles	Feb. 24-July 5.
Dorchester, Montgomery	Jan. 1-July 1.
Garrett	Dec. 1-Oct. 1.
Harford	Dec. 1-July 1.
Woodcock—Continued.	
Prince George	Dec. 26-June 30.
Queen Anne	Feb. 1-July 5.
St. Mary	Feb. 25-July 4.
Somerset	Jan. 1-June 15.
Talbot	Jan. 1-July 5.
Washington	Dec. 25-July 12.
Wicomico	Feb. 1-July 10.
Worcester	Feb. 1-Nov. 10.[b]
Plover, May 1-Aug. 15 (except as follows):	
Anne Arundel	Aug. 16-Mar. 2.
Carroll	May 1-Sept. 1.
Kent	Dec. 25-Aug. 1.
Prince George	May 1-Sept. 2.
Somerset	May 1-Dec. 1.
Wicomico	Jan. 15-Nov. 15.
Worcester	Unprotected.
Snipe, May 1-Aug. 15 (except as follows):	
Anne Arundel	Aug. 16-May 2.
Carroll	May 1-Sept. 1.
Kent	Jnne 1-Mar. 15.
Prince George	May 1-Sept. 2.
Somerset	May 1-Dec. 1.
Wicomico	Jan. 15-Nov. 15.
Worcester	Unprotected.
Sora rail or ortolan, Nov. 1-Sept. 1 (except as follows):	
Anne Arundel and Prince George—	
Patapsco or Potomac	Nov. 1-Sept. 5.[c]
Patuxent River	Jan. 1-Sept. 2.
Caroline, Kent	Jan. 16-Sept. 15.
Cecil	Dec. 25-Nov. 15.
Harford	Dec. 1-Sept. 1.
Talbot	Jan. 1-Sept. 10.
Somerset	Unprotected.
Reedbird, Nov. 1-Sept. 1 (except as follows):	
Cecil	Dec. 25-Nov. 15.
Harford	Dec. 1-Sept. 1.
Patuxent River	Jan. 1-Sept. 2.
Somerset	Unprotected.
Duck (except wood duck), goose, brant, swan, and other wildfowl, Apr. 10-Nov. 1 (except as follows):	
Anne Arundel (on Magothy, Rhode, Severn, and West rivers).	May 1-Oct. 1.[c,d]
Caroline (duck)	Apr. 2-Sept. 15.[c]
Cecil, Harford	Special provisions.[d]
Kent	Apr. 25-Nov. 1.[d]
Patuxent River (duck and goose).	Apr. 15-Nov. 2.[d]
Somerset (duck)	Apr. 1-Oct. 1.
Goose	Apr. 1-Nov. 1.
Talbot (wild fowl) on Great Choptank River.	May 1-Oct. 10.[c]
Allegany	Unprotected.
Wood or summer duck, Apr. 10-Nov. 1 (except as follows):	
Charles (acorn duck)	Apr. 10-Oct. 1.
Dorchester	Jan. 1-Aug. 1.
Somerset	Jan. 1-Sept. 1.
Talbot, Wicomico	Jan. 1-Sept. 10.
Worcester	Mar. 1-Sept. 1.

---

[a] It is not clear whether or not the law protects the wild turkey in these counties.

[b] Except July in Baltimore City, Calvert, Frederick, Howard, and Worcester.

[c] Otherwise as stated in State law.

[d] Wildfowl shooting is also prohibited on Bohemia, Elk, and Sassafras rivers Apr. 1-Nov. 1, and Tuesdays, Thursdays, and Sundays; on Magothy River, Mondays, Wednesdays, Fridays, and Sundays; on the Patuxent River, Sundays; on Rhode and West rivers, Tuesdays, Thursdays, Saturdays, and Sundays; on Severn River, Tuesdays, Thursdays, Fridays, and Sundays; and on the Susquehanna Flats r. 1-Nov. 1, and Tuesdays. Thursdays, and Sundays, also Saturdays in November and December.

NORTH CAROLINA.

Close season for game under county laws—Continued.

of game.	Close seasons.
-Oct. 1 (except ws):	
atham, David- rsyth, Guilford, mery, Moore, ph,[b] Richmond, gham,Scotland, Stokes, Surry, a, Wilkes, Yad-	To Nov. 1, 1910.[a]
Northampton..	Feb. 1-Aug. 15
Yancy	Dec. 1-Nov. 1.
k	Feb. 1-Sept. 1.
Cleveland, Co- [d]	Jan. 1-Oct. 1.
Jones	Feb. 1-Aug. 1.
	To Feb. 23, 1911.
	To Feb. 28, 1917.
Halifax, New er, Warren	Jan. 1-Sept. 1.
[e]	Mar. 1-Sept. 20.
xcept Hatteras to Mar. 4, 1908).	Mar. 1-Oct. 15.
, Person, Vance.	Jan. 15-Sept. 1.
	Oct. 1-Feb. 1.
ll	To Feb. 4, 1917.
	Jan. 1-Dec. 1.
[f]	Nov. 1-Oct. 15.
	Nov. 1-Sept. 1.
	All the year.
	Feb. 1-July 15.
	Jan. 1-Nov. 1.
ania	Dec. 15-Oct. 15.
	Feb. 1-Oct. 15.
Chowan, Cum- l, Duplin, Edge- Gates, Greene, t, Hyde, John- enoir, Martin, tank, Perqui- Pitt, Washing- ayne, Wilson.	Unprotected.
,Chowan,Cleve- Dare (except quirrel on Hat- anks to Mar. 4, lates, Hertford, , Mecklenburg, mans, Pitt.	Mar. 1-Nov. 1.
arteret, Craven, Martin, Pam- squotank, Tyr-	Mar. 1-Oct. 1.
be	Nov. 1-Jan. 15.
	Mar. 1-Sept. 1.
	Feb. 1-Oct. 1.
	Jan. 1-Dec. 1.
	Feb. 15-Oct. 1.
nery, Transyl-	Apr. 1-Sept. 1.
	Apr. 1-Oct. 1.

Kinds of game.	Close seasons.
Opossum: [b]	
Alamance, Caswell, Chatham, Durham, Franklin, Graham, Guilford, Halifax, Mecklenburg, Moore, Orange, Pamlico, Wake, Warren.	Feb. 1-Oct. 1.
Clay	Apr. 1-Nov. 1.
Greene	Feb. 1-Oct. 1.
Harnett, Lincoln	Jan. 1-Oct. 1.
McDowell	Mar. 1-Oct. 15.
Mitchell	Feb. 15-Oct. 1.
Quail or partridge, Mar. 1-Nov. 1 (except as follows):	
Alexander	Jan. 15-Dec. 1.
Anson [i]	Jan. 20-Nov. 20
Buncombe	Feb. 1-Nov. 14.
Burke, Catawba, Edgecombe, Forsyth, Nash.	Feb. 15-Nov. 15.
Cabarrus, Davidson, Duplin, Franklin, Guilford, Macon, Montgomery, Randolph,[b] [j] Swain, Wilson.	Mar. 1-Nov. 15.
Camden, Cherokee, Clay, Currituck, Davie, Iredell, Pasquotank, Perquimans, Rowan.	Mar. 1-Dec. 1.
Cleveland, Lincoln, Stokes, Surry, Yadkin.	Feb. 1-Dec. 1.
Columbus, Richmond	Apr. 1-Nov. 1.
Dare, Tyrrell, Vance	Mar. 1-Oct. 15.
Durham, Madison	Feb. 1-Nov. 15.
Gaston	Jan. 15-Nov. 28.[k]
Henderson	Apr. 1-Nov. 15.
Hyde	Mar. 20-Oct. 15.
Mecklenburg	Jan. 10-Dec. 1.
Mitchell	Feb. 15-Oct. 1.
Northampton	Feb. 1-Nov. 1.
Union	Jan. 15-Dec. 15.
Watauga [l]	Mar. 1-Sept. 1.
Graham, Onslow	Unprotected.
Pheasant:	
Ashe, Chatham, Davidson, Forsyth, Guilford, Montgomery, Moore, Randolph,[b] Richmond, Rockingham, Scotland, Stanly, Stokes, Surry, Watauga, Wilkes, Yadkin.	To Nov. 1, 1910.
Buncombe	Feb. 1-Nov. 14.
Burke	Feb. 15-Nov. 15.
Cherokee	To Feb. 28, 1912.
Edgecombe	Mar. 1-Nov. 15.
Clay	Mar. 1-Dec. 1.
Granville, Macon	Mar. 1-Nov. 1.
Henderson	Apr. 1-Nov. 1.
McDowell	To Jan. 1, 1912.
Madison	Feb. 1-Nov. 15.
Mitchell	Feb. 15-Oct. 1.
Rowan	Feb. 1-Dec. 1.

ed in private preserves may be killed, sold, or used at any time.
ng is prohibited in part of Columbia Township, Randolph County, Jan. 15-Nov. 15, and
art hunting by landowners and tenants is prohibited Mar. 1-Nov. 15.
Creek and White Creek townships.
alf mile of Lake Waccamaw.
side of Poplar Branch Township.
hout horns protected all the year.
iver or within 100 yards thereof.
region between Alligator River and county line Feb. 15-Aug. 1.
oro township only.
insville Township Jan. 15-Nov. 15.
on extends to last Thursday in November.
reek Township all the year.

NORTH CAROLINA.

Close seasons for game under county laws—**Continued.**

Kinds of game.	Close seasons.
Pheasant—Continued.	
Rutherford (English, Mongolian).	To Mar. 8, 1918.
Stokes	Feb. 1–Dec. 1.
Swain	Jan. 1–Nov. 20.
Transylvania (English, Mongolian, California, to Nov. 1, 1910).	Mar. 1–Nov. 1.
Watauga	To Jan. 1, 1911.
Wild Turkey, Mar. 1-Nov. 1 (except as follows):	
Anson[a]	Jan. 20–Nov. 20.
Buncombe	Feb. 1–Nov. 14.
Burke	Feb. 15–Nov. 15.
Cabarrus, Cherokee, Davidson, Edgecombe, Guilford, Macon, Wilson.	Mar. 1–Nov. 15.
Clay, Randolph,[b] Rowan, Stokes.	Feb. 1–Dec. 1.
Columbus	Apr. 1–Nov. 1.
Davie	To Mar. 1, 1908.
Henderson	Apr. 1–Nov. 15.
Madison	Feb. 1–Nov. 15.
Mitchell	Feb. 15–Oct. 1.
Northampton	Feb. 1–Nov. 1.
Pamlico	Mar. 1–Oct. 1.
Pender	Feb. 1–Oct. 1.
Richmond	Jan. 1–Oct. 1.
Union	Jan. 15–Dec. 15.
Carteret, Dare, Graham, Onslow, Stanly, Swain, Tyrrell.	Unprotected.
Dove, lark, robin, Mar. 1–Nov. 1[b] (except as follows):	
Buncombe (dove)	Feb. 1–Nov. 14.
Burke	Feb. 15–Nov. 15.
Cabarrus, Cherokee, Edgecombe (except dove, Oct. 1–Aug. 1), Guilford, Macon (dove).	Mar. 1–Nov. 15.
Columbus (dove)	Apr. 1–Nov. 1.
Davidson, Richmond	Apr. 1–Oct. 15.
Davie, Rowan	Mar. 1–Dec. 1.
Halifax (dove)	Feb. 1–Aug. 1.
Henderson	Apr. 1–Nov. 15.
Hyde	Mar. 15–Nov. 1.
Madison (except dove, Feb. 1–Nov. 15)	Jan. 1–Dec. 1.
Mecklenburg	Feb. 1–Nov. 15.
Mitchell	Feb. 15–Oct. 1.
Dove, lark, etc—Continued.	
Northampton (except dove, Feb. 15–Nov. 1)	Feb. 1–Nov. 1.
Stokes	Feb. 1–Dec. 1.
Union	Jan. 15–Dec. 15.
Vance	Mar. 15–Oct. 15.
Warren (dove)	Feb. 1–Aug. 1.
Carteret, Duplin, Graham, Moore, Onslow, Swain, Wilson.	Unprotected.
Woodcock:	
Brunswick, New Hanover	Jan. 1–Sept. 1.
Cherokee, Granville, Randolph[b]	Mar. 1–Nov. 1.
Craven, Jones	Feb. 1–Nov. 1.
Edgecombe	Mar. 1–Nov. 15.
Henderson	All the year.
Madison	Jan. 1–Dec. 1.
Mitchell	Feb. 15–Oct. 1.
Rowan	Feb. 1–Dec. 1.
Stokes	Feb. 1–Dec. 1.
Snipe:[b]	
Anson[a]	Jan. 20–Nov. 20.
Brunswick, New Hanover	Mar. 1–Sept. 1.
Cherokee, Edgecombe	Mar. 1–Nov. 15.
Granville	Mar. 1–Nov. 1.
Halifax, Warren	May 1–Feb. 1.
Madison	Jan. 1–Dec. 1.
Mitchell	Feb. 15–Oct. 1.
Marsh hen, curlew, and other shore birds:[b]	
Anson[a]	Jan. 20–Nov. 20.
Carteret	Apr. 1–Aug. 15.
Cherokee, Edgecombe	Mar. 1–Nov. 15.
Granville	Mar. 1–Nov. 1.
Henderson	All the year.
Madison	Jan. 1–Dec. 1.
Stokes	Feb. 1–Dec. 1.
Wildfowl:[b]	
Anson	Jan. 20–Nov. 20.
Beaufort (summer duck)	Feb. 1–Sept. 15.
Brunswick, New Hanover	Mar. 1–Sept. 1.[c]
Carteret[d]	Apr. 1–Nov. 25.
Craven, Granville, Jones.	Mar. 1–Nov. 1.
Currituck[e]	Apr. 1–Nov. 1.
Dare[f]	Mar. 10–Nov. 10.
Edgecombe, Guilford	Mar. 1–Nov. 15.
Henderson	All the year.
Hyde[g]	
Madison	Jan. 1–Dec. 1.
Stokes	Feb. 1–Dec. 1.

---

[a] In Lanesboro Township only.

[b] All hunting is prohibited in part of Columbia Township, Randolph County, Jan. 15–Nov. 15, and in another part hunting by landowners and tenants is prohibited Mar. 1–Nov. 15.

[c] Ducks only.

[d] Applies to shooting from batteries and sneak boats.

[e] Applies to hunting over decoys. In addition to this close season, Wednesdays, Saturdays, and Sundays are closed for all hunting. Ring shooting is prohibited Apr. 1–Feb. 15.

[f] Applies only to hunting for sale.

[g] Battery shooting prohibited on Wednesdays, Saturdays, and Sundays on Pamlico Sound.

○

1068 Issued October 19, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 309.

Experiment Station Work,

XLIII.

Compiled from the Publications of the Agricultural Experiment Stations.

ICE FOR HOUSEHOLD USE.
CULTURE AND VARIETIES OF ROOT CROPS.
COWPEAS AND SOY BEANS.
SILAGE FROM FROSTED CORN.
COOPERATION IN MARKETING CROPS.
INCUBATION OF EGGS.
CAUSES OF DEATH OF YOUNG CHICKS.
SNOW FOR POULTRY.
ERADICATION OF CATTLE TICKS.
BACTERIA IN CREAM.

SEPTEMBER, 1907.

PREPARED IN THE OFFICE OF EXPERIMENT STATIONS.
A. C. TRUE, Director.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

THE AGRICULTURAL EXPERIMENT STATIONS.

ALABAMA—
- College Station: *Auburn;* J. F. Duggar.[a]
- Canebrake Station: *Uniontown;* J. M. Richeson.[b]
- Tuskegee Station: *Tuskegee;* G. W. Carver.[a]

ALASKA—*Sitka:* C. C. Georgeson.[c]

ARIZONA—*Tucson:* R. H. Forbes.[a]

ARKANSAS—*Fayetteville:* W. G. Vincenheller.[a]

CALIFORNIA—*Berkeley:* E. J. Wickson.[a]

COLORADO—*Fort Collins:* L. G. Carpenter.[a]

CONNECTICUT—
- State Station: *New Haven;* E. H. Jenkins.[a]
- Storrs Station: *Storrs;* L. A. Clinton.[a]

DELAWARE—*Newark:* Harry Hayward.[a]

FLORIDA—*Gainesville:* P. H. Rolfs.[a]

GEORGIA—*Experiment:* Martin V. Calvin.[a]

HAWAII—
- Federal Station: *Honolulu;* J. G. Smith.[c]
- Sugar Planters' Station: *Honolulu;* C. F. Eckart.[a]

IDAHO—*Moscow:* H. T. French.[a]

ILLINOIS—*Urbana:* E. Davenport.[a]

INDIANA—*Lafayette:* A. Goss.[a]

IOWA—*Ames:* C. F. Curtiss.[a]

KANSAS—*Manhattan:* C. W. Burkett.[a]

KENTUCKY—*Lexington:* M. A. Scovell.[a]

LOUISIANA—
- State Station: *Baton Rouge.*
- Sugar Station: *Audubon Park, New Orleans.*
- North Louisiana Station: *Calhoun:* W. R. Dodson (*Baton Rouge*).[a]

MAINE—*Orono:* C. D. Woods.[a]

MARYLAND—*College Park:* H. J. Patterson.[a]

MASSACHUSETTS—*Amherst:* W. P. Brooks.[a]

MICHIGAN—*Agricultural College:* C. D. Smith.[a]

MINNESOTA—*St. Anthony Park, St. Paul:* E. W. Randall.[a]

MISSISSIPPI—*Agricultural College:* W. L. Hutchinson.[a]

MISSOURI—
- College Station: *Columbia;* H. J. Waters.[a]
- Fruit Station: *Mountain Grove;* P. Evans.[a]

MONTANA—*Bozeman:* F. B. Linfield.[a]

NEBRASKA—*Lincoln:* E. A. Burnett.[a]

NEVADA—*Reno:* J. E. Stubbs.[a]

NEW HAMPSHIRE—*Durham:* E. D. Sanderson.[a]

NEW JERSEY—*New Brunswick:* E. B. Voorhees.[a]

NEW MEXICO—*Agricultural College:* L. Foster.[a]

NEW YORK—
- State Station: *Geneva;* W. H. Jordan.[a]
- Cornell Station: *Ithaca;* L. H. Bailey.[a]

NORTH CAROLINA—
- College Station: *Raleigh;* C. B. Williams.[a]
- State Station: *Raleigh;* B. W. Kilgore.[a]

NORTH DAKOTA—*Agricultural College:* J. H. Worst.[a]

OHIO—*Wooster:* C. E. Thorne.[a]

OKLAHOMA—*Stillwater:* W. L. English.[a]

OREGON—*Corvallis:* J. Withycombe.[a]

PENNSYLVANIA—*State College:* T. F. Hunt.[a]

PORTO RICO—*Mayaguez:* D. W. May.[c]

RHODE ISLAND—*Kingston:* H. J. Wheeler.[a]

SOUTH CAROLINA—*Clemson College:* J. N. Harper.[a]

SOUTH DAKOTA—*Brookings:* J. W. Wilson.[a]

TENNESSEE—*Knoxville:* H. A. Morgan.[a]

TEXAS—*College Station:* H. H. Harrington.[a]

UTAH—*Logan:* E. D. Ball.[a]

VERMONT—*Burlington:* J. L. Hills.[a]

VIRGINIA—*Blacksburg.*

WASHINGTON—*Pullman:* R. W. Thatcher.[a]

WEST VIRGINIA—*Morgantown:* J. H. Stewart.[a]

WISCONSIN—*Madison:* H. L. Russell.[a]

WYOMING—*Laramie:* J. D. Towar.[a]

---

[a] Director.
[b] Assistant director.
[c] Special agent in charge.

XPERIMENT STATION WORK.

d by W. H. BEAL and the Staff of the Experiment Station Record.

---

ient Station Work is a subseries of brief popular bulletins compiled ɔublished reports of the agricultural experiment stations and kindred s in this and other countries. The chief object of these publications ıminate throughout the country information regarding experiments at ɜnt experiment stations, and thus to acquaint farmers in a general the progress of agricultural investigation on its practical side. The rein reported should for the most part be regarded as tentative and rather than conclusive. Further experiments may modify them, and alone can show how far they will be useful in actual practice. The ıe stations must not be depended upon to produce "rules for farming." ıply the results of experiments to his own conditions will ever remain m of the individual farmer.—A. C. TRUE, Director, Office of Experiions.

CONTENTS OF NO. XLIII.

Page.
usehold use 5
ıd varieties of root crops 7
and seeding 8
al cultural considerations 9
l-wurzels 10
ɔs 12
abi 14
s 14
nd soy beans 15
in rotation 15
nd manuring 16
ng 17
sting 17
ıing 18
ies 18
on to soil fertility 18
n frosted corn 19
n in marketing fruit and truck crops 20
ın of eggs and other factors which affect incubation 24
death of young chicks 27
ıg snow for water for poultry 28
n of cattle ticks 29
ı cream 31

EXPERIMENT STATION WORK.[a]

ICE FOR HOUSEHOLD USE.[b]

ıe matter of ice and ice supplies has been briefly referred to in a ıssion of water for table use in an earlier bulletin of this series.[c] ıe purity and wholesomeness of the ice supply has heretofore ıed to be a matter of much less concern to both sanitary engineers consumers than the quality of the water supply. Yet in view of increasing uses of ice its purity is rapidly becoming a matter ut slightly less importance than that of water. While the chemcomposition and the factors which affect the purity of water have ived a large amount of attention by the agricultural experiment ions, little study has been made of ice supplies in station labora-ɜs.

he consensus of opinion is that natural ice formed to a reasonable :h is comparatively pure under usual circumstances, but that it is ' likely to be contaminated if it freezes to the full depth of a low pond or stream, or if it is flooded, particularly with surface ɜr. The Vermont Experiment Station found that of a small ber of samples of pond ice examined all were unfit for household

ıe following extracts from a recent publication of the New York e department of health regarding ice and ice supplies bear :tly upon this question:

> general there are a great many conceivable ways that ice and ice supplies become infected. The danger from many of these causes of infection may, ver, be so remote or so infrequent as to hardly merit notice. There are, ver, a few dangers associated with the formation of natural ice and the ɜsting of ice supplies, as now generally practiced, which do merit considon.

---

progress record of experimental inquiries, published without assumption of ınsibility by the Department for the correctness of the facts and conclusions ted by the stations.

ompiled from Vermont Sta. Rpt. 1898, p. 177; Mo. Bul. N. Y. Dept. Health, 907), No. 2, pp. 2-6.

. S. Dept. Agr., Farmers' Bul. 262, p. 5.

The first of these dangers is the one due to the harvesting of ice from polluted sources. This ice may be taken from ponds or rivers which have been polluted by sewage and may contain the germs of typhoid fever and other diseases.

Secondly, ice may become contaminated during the period and operations of harvesting by filth which may have come from infected sources. The hands and feet of laborers or the hoofs of horses may be the channels by which infection may be transmitted to the ice even after it has been taken from the water, and notwithstanding the purity of the water.

Thirdly, ice may become infected from surface drainage from the adjacent lands during thaws. The water which has thus flowed over infected fields that may have been fertilized or otherwise infected may be carried onto the ice and settle and be frozen into it.

Finally, ice may become infected from the exposure and handling incident to distribution of it in our cities and even within our homes. This may be by far the most serious mode of infection, for it leaves the time interval between infection and transmission too short for any counteracting influence of cold to be exerted.

The opportunities afforded for infection during the distribution of our ice supply are many. They start with the infection by the icemen in handling the ice and include infection from the air of our cities, the dirt and filth gathered while the ice is deposited upon pavements and sometimes in streets, the dirty ice broom, the water with which it is washed, and, finally, the handling just prior to placing in coolers or ice chests. To be sure, these sources may be largely avoided and wholly eliminated by final and careful washing, but here, as in all our daily habits in the preparation of food, sanitary precautions are not always observed, and the dangers may often be more real than apparent.

Notwithstanding the many possibilities of ice infection, examination of the literature of the subject shows that the number of epidemics of disease attributable to ice is small. The reason for the small mortality from ice infection "of which we have authentic record, is due to a series of natural agencies or safeguards * * * which tend, by a process of successive elimination, to reduce or entirely destroy the bacterial or germ life that may have been originally present in the polluted water or have infected the ice after its formation, or even after harvesting."

The first safeguard or influence which is active in the reduction of bacterial life is the well-established phenomenon of subsidence and oxidation upon suspended matters, including bacteria in bodies of quiescent or slowly flowing water. This action, of course, will effect in the greatest degree the purification of ice harvested from ponds and lakes. It affects in a large measure, however, ice collected from rivers and especially those in which the velocities are slow enough to admit of formation of ice of sufficient thickness to warrant harvesting.

The second agent in the self-purification of ice is the removal of suspended and dissolved matters which is brought about during the action of freezing. It is commonly known as the "filtration process of freezing," and it affects not only the suspended matters, such as particles of dirt and bacteria, but also chemicals that are in solution. * * *

Of perhaps the greatest influence in the self-purification of ice is the effect of low temperature upon the vitality and life of the bacteria themselves. It has been found by nearly all observers that bacteria exposed to low temperatures near the freezing point very soon lose their vitality, and if exposed for sufficient length of time are either killed or become so attenuated as to be nonpathogenic, i. e., their vitality has been so lowered that they are unable to be sufficiently revived to produce disease.

This effect of low temperature upon the vitality of bacteria is proportional in a measure to the degree of cold, but of much more importance is the effect of the time of exposure. * * * The few that are not killed after exposure for say one month have become so attenuated as to be unable to produce disease.

There is still another influence depending upon time of exposure that must not be confounded with the phenomenon of cold alone. This is the influence or destruction of pathogenic [or disease producing] bacteria when exposed or disseminated through a body of water. It has been found that without special relation to temperature, pathogenic bacteria are slowly killed when discharged into a body of water. This is probably due partially to the fact that water is not a favorable environment to most species of pathogenic bacteria accustomed to environment in a human being, and partially to the fact that when exposed to the ravages of other water bacteria they are soon destroyed. * * *

These facts, while emphasizing the great immunity bestowed by nature, point, however, to the real dangers of ice infection with renewed force. There still remain, for instance, the infection due to handling and distribution; to surface pollution due to the pernicious practice of flooding ice to get a thicker crop; to surface pollution due to rains and melting snow washing pollution from side slopes onto ice that has already formed, and finally to the dangers of artificial ice when this has been manufactured from contaminated water and delivered to consumers before the natural processes of purification have had an opportunity to become active or effective.

It is for the removal of some of these possible or residual dangers, notwithstanding the high efficiency of natural purification, that regulations looking to the conservation of our ice supplies become desirable if not necessary. * * * It needs no proof to show that ice harvested from the vicinity of sewer outlets would be loathsome if not dangerous. In fact, even if there were no danger from such a procedure there would still be an æsthetic objection to organic and other filth associated with polluted waters that make incumbent the forming of laws for the protection of our ice supplies.

With the growth of population and manufacturing industries the pollution of streams, ponds, and lakes is becoming so general as to render it more and more difficult to find unpolluted bodies of water from which to harvest natural ice. It therefore becomes increasingly important to guard against this source of danger to the public health, particularly as the demand for ice is steadily growing and its uses rapidly multiplying.

CULTURE AND VARIETIES OF ROOT CROPS.[a]

As explained in an earlier number of this series,[b] root crops are a valuable feed for stock, especially during the winter when they supplement the rations of grain and other dry feed stuffs. They thrive best in regions having moist and cool weather, but, nevertheless, enough heat and sunshine to promote rapid growth during the growing season. In many sections of the Northern States root crops may be grown with profit, but the fact that their culture is not so generally understood as it should be is probably the reason that they are not grown so extensively in the United States as in Canada and parts of Europe.

---

[a] Compiled from New York Cornell Sta. Buls. 243 and 244.

[b] U. S. Dept. Agr., Farmers' Bul. 305, p. 19.

The New York Cornell Station has recently published the results of investigations as to the best methods of growing mangels, half-sugar mangels, sugar beets, ruta-bagas, kohl-rabi, hybrid turnips, turnips, and carrots in order that this information might serve as a guide to those wishing to raise any of these crops under similar conditions. The culture of these roots is explained as the experience of the station has determined it, and the leading varieties are described.

SEEDS AND SEEDING.

In discussing seeds and seeding it is pointed out that the commercial "seed" of mangels, half-sugar mangels, sugar beets, and carrots is really the fruit, of which each individual fruit may contain from 1 to 7 seeds. The fruit of the carrot, however, bears only one seed. The commercial seeds of ruta-bagas, turnips, and kohl-rabi are true seeds. Almost all of the seed samples received at the station contained dust, and in some of them the dust and pieces of stem reached 7 per cent of the total weight. The following table gives a comparison of the different kinds of seed studied at the station.

Comparison of root-crop seeds.

Crop.	Seeds per pound.	Germination.
		Per cent.
Mangels	32,000 to 185,000	73 to 185
Half-sugar mangels	24,000 to 36,000	100 to 136
Sugar beets	22,000 to 24,000	102 to 132
Ruta-bagas	161,000 to 188,000	83 to 92
Hybrid turnips	183,000 to 266,000	71 to 94
Common turnips	200,000 to 260,000	89 to 92
Kohl-rabies	114,000 to 129,000	48 to 96
Carrots	440,000 to 460,000	15 to 83

In the case of carrots, with a germination power of only 15 per cent, the cost of a pound of seed which would grow, based on the ordinary price of the seed, or 60 cents per pound, would be $4 per pound. This seed was sown at the station, and a good stand was secured, but for each carrot grown over 80 seeds were required. These figures need no comment to show the value and the necessity of good seed.

Sowing from May 6 to 9 proved better at the station for all roots than sowing as late as June 12. Planting early in May generally promotes yield, dry matter content, and keeping quality. On clay loam soil the carrot seed failed to grow when sown one-fourth inch deep, while it grew well in sand sown five-eighths inch deep. Mangels, half-sugar mangels, and sugar beets were all sown three-fourths inch deep and all others between one-fourth and one-half inch distance of 30 inches between rows is advised, in order to adm horse culture for a longer period of time than when the rows are nearer together. With this distance between rows the largest per acre may not be realized, but by all possible elimination of labor roots are produced at the lowest cost per ton.

GENERAL CULTURAL CONSIDERATIONS.

Mangels were ready for thinning thirty to thirty-five days sowing, ruta-bagas twenty-five to thirty days, turnips sixtee twenty-five days, and carrots and parsnips about thirty-five to days. Clean culture was given and an application of 100 pounc nitrate of soda per acre was made when the crop was found t making insufficient growth. Common turnips, some of the hy turnips, and cabbages were used from the beginning of Septer until November, and the other crops were harvested and store October and early in November. Cabbages, common turnips, some of the early hybrid turnips may be used in September, Oct and November, the later hybrid turnips and ruta-bagas in Nover and December, and mangels and half-sugar mangels the rest of winter. These crops are all well adapted to feeding cattle and sl but ruta-bagas are especially good for hogs, and carrots for fee horses.

A proper rotation, early sowing, and a uniform stand are rega as essentials for a high yield. Mangels grown continuously on same land for four years yielded 9.6 tons of roots, containing 1 of dry matter, while on land under rotation they yielded 34 ton roots and 4 tons of dry matter per acre. From 25,000 to 30,000 pl of mangels, ruta-bagas, and hybrid turnips, and from 40,000 to 6(plants of carrots per acre are suggested as proper stands.

Two half-sugar mangels, Vilmorin Half-Sugar Rosy and C Half-Sugar, are recommended as suitable stock for breeding purp Carter Holborn Elephant, Kangaroo, and Garton Superlative bagas are comparatively free from fibrous roots and have a uni and good shape. The Yellow Aberdeen hybrid turnip proved for early fall use, while Garton Pioneer is later and can be st as well as ruta-bagas. Of the different varieties of turnips for e fall use, Mammoth Improved Green Globe and White Egg are gested. Carter 100-ton carrot was the best variety for clay loam Lobberich Agricultural carrot did equally well on clay loam gravel loam, and Giant Wiltshire and Orange Giant gave good y on heavy clay loam. The two last mentioned varieties, however, difficult to harvest because they broke off so readily, thus indica that they are better adapted to deep friable loams. White Vi and Carter Model kohl-rabi gave about equally good yields.

MANGEL-WURZELS.

In a closer consideration of the principal root crops it is pointed out that the five different shapes of mangels grown in this country are the long, half-long, ovoid, tankard, and globe types. In addition to these a long curved type, known as the cow-horn mangel, is grown in Europe. The color of the skin may be white, pink, red, orange, yellow, golden, purple, or black. The flesh, which consists of concentrate rings of firm tissue alternating with rings of softer tissue, is seldom uniform in color. The juice of the softer rings is often colored and may be crimson in the Long Red, golden in the Golden Tankard, or white in the half-sugar mangel and the sugar beet. The long varieties are three to four times as long as their greatest diameter and frequently taper to the crown and the tip of the root. From one-half to two-thirds of the root is below the surface of the ground, which indicates that varieties of this type should be cultivated on deep friable soils worked to a good depth. The half-long varieties are shorter than the long sorts, and they taper from the shoulders to the taproot.

The ovoid form is about two to three times as long as it is broad and tapers to the crown and the tip of the root. The color of the skin is most commonly yellow or orange. About one-half the root may be below ground, and owing to its short length this form is much better fitted for shallow soils than the long forms. The tankard is about two to three times as long as broad and carries its width almost uniformly throughout its entire length. The Golden Tankard, with a deep yellow colored flesh, and the Crimson Tankard, with a crimson or rose colored skin and with crimson rings in the flesh, are perhaps the best known varieties of this form. Four inches in diameter and 10 to 11 inches in length is a common proportion, and generally but 5 inches of the root is below the surface. The globe varieties attain a size of from 4 to 7 inches in diameter and are spherical, or nearly so, in form. This type is particularly well adapted to shallow soils, as frequently from two-thirds to four-fifths of the root forms above ground. The Yellow Globe is the variety most commonly grown.

In order that the descriptions of root crops may be better understood, the different parts are briefly defined. The neck or part that bears the leaves may be long, medium, or short. This part should be as small as possible, as it is of little value for feeding purposes. The shoulders, more prominent in some varieties than in others, consist of the upper part of the stem and do not bear leaves. The shoulders and the neck together constitute the crown, which is removed from sugar beets before using them for the manufacture of sugar. The stem or hypocotyl is the thick fleshy part between the neck and the tapering primary root. It is rich in nutrients and varies in length in different varieties. The primary root appears as a continuation of the stem. It should terminate in a single small taproot, as secondary roots, prongs, or forks are undesirable, not only increasing the cost of harvesting, but also indicating a coarse and fibrous nature. Well-formed roots are described as smooth, while those lacking the proper shape are referred to as forked or rough. The two depressions running lengthwise down the primary root on opposite sides are known as the dimples. The lateral roots should be fine, fibrous, and fairly abundant, and spring from the dimples. This fibrous root system breaks off in harvesting.

While mangels may be grown on almost all productive soils, deep loams are considered best and are necessary for the production of heavy yields of the long varieties. Mangels and sugar beets need considerable sunshine for the development of the root and the elaboration of sugar. With a good supply of moisture in the soil after the plants have become established they will grow in a warm, dry climate and withstand drought far better than most other crops. In the rotation mangels may be grown between two grain crops or after another intertilled crop which has been heavily manured, as cabbages. Good success is also secured in growing them after clover which has been down for a year, and as they are not harvested until late in the fall, the grain crops best suited to succeed them are oats and corn. If oats follow, the tops should be spread uniformly over the land and plowed under in the fall, because the leaves are a valuable manure, and if left unspread the grain crop will be uneven.

In preparing the soil for mangels it is advised to plow deeply in the fall and to cross-plow or to give a deep disk harrowing in the spring. Ten to 12 tons per acre of barnyard manure should be applied previous to plowing, and this may be supplemented in the spring with fertilizers. The seed bed should be put into fine condition with disk and spike-tooth harrow, and previous to the last two harrowings from 240 to 280 pounds of acid phosphate, 100 to 120 pounds of nitrate of soda, and 100 to 120 pounds of muriate of potash should be mixed together and applied immediately. This treatment will stimulate the young plants into vigorous growth. In some cases 400 to 500 pounds of salt per acre are applied. If the land needs lime, the use of 1,500 to 2,000 pounds per acre will often be found profitable.

Owing to the smallness of the seed it is easy to sow it too deep. From 6 to 8 pounds of good seed are required per acre, and the sowing may be done with a grain drill. A 7-inch 11-hoe drill may be used to sow the seed in either 28 or 35 inch rows. In order to facilitate the use of a 2-horse cultivator the rows should not be less than 30 inches apart. As soon as the plants have four leaves all the plants except little bunches every 6, 8, or 10 inches apart are chopped out with a hoe 5 or 6 inches wide, and after this has been done the remaining plants are thinned to but one plant every 6 to 10 inches. The globe and tankards require rather a greater width in the row than the long varieties. The bunching and thinning must be done at this stage, for if done later the development of the plants is checked. As soon as the rows can be seen, shallow cultivation is given to keep the land at all times free from weeds and from a hard or crusted surface. If the plants appear stunted when they are thinned, a top dressing of 50 pounds of nitrate of soda per acre mixed with 50 pounds of acid phosphate, or with salt or sand to give it bulk, may be used with profit. The mangels should be harvested before severe frosts occur and may be taken up at any time when the outer leaves have withered. The roots should be pulled up with as little injury as possible and the tops twisted off. If stored in a root cellar, the place should be dry and well ventilated. The average yield is generally from 16 to 29 tons, although at the station during the past three years several varieties have yielded at the rate of 40 tons per acre. The average yield of dry matter per acre during the past three years was between 2.4 and 3 tons. In the case of sugar beets 20 tons of beets contained about 4 to 4.5 tons of dry matter, while the yields of half-sugar mangels ranged between the yields of mangels and sugar beets. The amount of dry matter in mangels usually varies between 7 and 14 per cent. In 1904, on the University farm, the dry matter varied between 9.56 and 16.01 per cent in nine varieties. About half of the dry matter is sugar, the percentage often varying between 3 and 8 per cent. It is pointed out that the average composition of the mangel to-day is practically the same as it was fifty years ago, while the sugar beet has been increased 50 per cent in its value for sugar production during the past forty years.

TURNIPS.

The turnip also consists of a thickened stem and root. The best known types are the common turnip (*Brassica rapa*), the hybrid turnip, and the ruta-baga, Swedish turnip, or Swede (*Brassica campestris* or *Brassica rutabaga*). The common turnip and the ruta-baga are thought by some to be of distinct primary origin, while hybrid turnips are said to be a cross between these two. In the turnip the color of the leaves is a grass green, while the ruta-baga has leaves of bluish green or covered with a bluish white bloom. The turnip
s its growth in from sixty to ninety days, while the ruta-baga
from ninety to one hundred and eighty days. The flesh of
nip is soft, usually white to yellow, more often white, while
the ruta baga is firmer, white, yellow, or orange, but more
yellow. Turnip seed is small, only 2 to 3 pounds being sown
acre, while of the larger and darker ruta-baga seed 4 to 5 pounds
uired.

Turnips are classified commercially according to their shape, form f the upper part of the root, color of the upper part of the root, and olor of the flesh. The principal shapes are long, tankard, round or lobe, and flat, but there is considerable variation between these dif-erent forms. Some taper toward the tap root, while others are airly uniform in width. The long type, three or more times as long s broad, generally tapers toward the tap root. The tankard form orresponds to the tankard form of the mangel. A large proportion f the root of this type is above ground and the part underground apers abruptly toward the tap root. All roots nearly spherical elong to the round or globe form and the flat-shaped turnips are reater in width than in length. The round or globe turnips tend to row deep in the soil and are better suited to deeper soils than the ankard or flat types. The roots are flat-topped or round-topped, ccording to the shape of the upper part of the root and the character f the shoulders. The crown should be convex to avoid holding water. The roots are called white, yellow, green, bronze, purple, or red tops, nd graystones, according to the color of the part of the root exposed o the light. The roots known as graystones have the upper part mottled with transverse green and purple streaks. The flesh of turnips s generally either white or yellow. The yellow flesh varieties of common turnips are considered of superior quality, and most of the hybrid turnips introduced on account of their superior merit have yellow flesh. The crown should be single; that is, only one shoot or neck should arise from it, as roots with multiple crowns or those hav-ng several shoots are generally coarser, more fibrous, and considered of lower feeding value.

The best soils for this crop are free-working lands, rich in organic matter and in good tilth. Common turnips will do better on lighter oams than ruta-bagas, and these will give a better yield than turnips pon heavy to medium loams. Climate is apparently of more impor-ance than soil for this crop. A damp and rather dull climate, with well-distributed rainfall throughout the growing season, seems to e best. To prepare the land it is recommended that an application f about 10 tons of barnyard manure per acre be plowed under in all and the land be put in good tilth the next spring. Lime slaked o a very fine powder may be applied at the rate of 1,000 pounds of uicklime per acre and harrowed in with 400 to 600 pounds of acid hosphate and 50 pounds of nitrate of soda. This application must e well incorporated with the soil before sowing and the seed bed made as fine as possible. From 2½ to 5 pounds of seed are usually own in the case of ruta-bagas and hybrid turnips and from 2 to 4 ounds, or an average of 3 pounds, per acre in the case of common urnips when the rows are 27 to 30 inches apart. It was found at the station that ruta-bagas and Garton Pioneer hybrid turnips, when sown early, lost in quality by the production of long necks. It is considered best to plant in rows 30 inches apart, which will admit of easy cultivation, and to place the plants 7 to 8 inches apart in the row. With this rate of planting an acre will contain about 28,000 plants. The cultivation consists in keeping the land free from weeds by means of frequent, shallow tillage. As the crop grows quickly, only three or four cultivations can be given, with intervals of seven to ten days, before the leaves meet in the rows. A top dressing of 50 pounds of nitrate of soda is sometimes very advantageous. In 1905 the station secured from 20 to 25 tons per acre from such varieties as the Improved Green Globe and the Carter Mammoth. In 1906 White Egg gave the largest yield. During two years hybrid turnips sown on May 11 yielded at the rate of 23 tons, while those sown June 12 yielded only about 14 tons per acre. Garton Pioneer showed considerable resistance to soft rot, being the only one not attacked, and yielding for the two years at the rate of nearly 28 tons per acre.

The average yield of ruta-bagas from the early sowing for two years was at the rate of 21 tons. The common turnips are harvested as soon as they are large enough and often used for feed in the fall. The hybrid turnips may be used a little later and may even be stored, Garton Pioneer being a good variety for this purpose. Ruta-bagas are usually stored after mangels, but before serious frost has occurred.

KOHL-RABI.

Kohl-rabi (*Brassica caulorapa*) is grown for its thickened stem instead of for its leaves. The crop succeeds wherever ruta-baga succeed, the cultural treatment of the crop being the same. The crop is not so subject to disease as ruta-bagas, withstands drought better can be grown on heavier soils, and thrives well on muck land. It further advantages are that it stands well out of the ground and car be readily pastured by sheep; that it does not seem to cause tainte milk when fed to dairy cows, and that it is also better than the ruta-baga in withstanding frosts and developing in warm climates. Its leaves are as valuable for feed as the stem. Among the well-known varieties are the White and Purple Vienna, Short-top White, Goliath, and Carter Model.

CARROTS.

The carrot, like the mangel and turnip, is made up of thickened stem and root, the proportions of the two parts varying in different ies. The carrot is composed of a well-defined outer layer, ed or scarlet in the red varieties, and an inner layer or core, yellow or dull white. The outer layer is considered to be feeding value than the pith; hence those containing the

ıallest percentage of core should always be selected. This crop re-
ıires deep, well-pulverized, sandy loam soil, fitted and cultivated
e same as for mangels. The manure should be applied to the pre-
ous crop or else be well rotted before being plowed under. The
ed germinates very slowly and from 6 to 7 pounds should be sown
›r acre, although if it is of good germination power 4 or 5 pounds
sufficient. Carrots should be sown in rows about 30 inches apart
ıd the plants left about 3 inches apart in the rows. This gives from
›,000 to 60,000 plants per acre. The crop is usually harvested before
ɪvere frost sets in and stored as other roots. At the station the yields
ıried from 7 to 25 tons per acre, although it is stated that much
igher yields are sometimes reported. The leaves of carrots appear
› be of higher feeding value than the leaves of mangels or ruta-bagas.
'arrots are considered of high value for all classes of stock, but
ɜpecially of great value for feeding horses.

COWPEAS AND SOY BEANS.[a]

The great importance of cowpeas and soy beans to our agriculture
ɪ more and more recognized, and the culture of these crops is spread-
ıg from year to year, not only in all sections of the Southern States,
ut even to unexpected northern latitudes. The two crops were
ɜcently grown in comparison by the Indiana and Oklahoma experi-
ıent stations, and several points worthy of attention were brought
ɪt for the benefit of growers. The plants are similar in many
ɜspects, while they differ in others, and a comparison of their charac-
ɪristics leads to a better knowledge of their adaptations and value.

PLACE IN ROTATION.

On most, if not all, farms where cowpeas and soy beans can be
rown successfully either one or both can profitably be given a per-
ıanent place in the crop rotation. In some localities both crops
ıcceed well, but the one is perhaps better known than the other.
'or this reason a larger acreage may be devoted to it. In Oklahoma,
ɔr instance, where the cowpea is quite extensively grown, the soy
ean has not come into such general use as a forage or a grain crop,
lthough it is considered by many a good substitute for the cowpea in
he rotation. Both the cowpea and soy bean are well adapted to
ɪreceding a crop of wheat. When planted early and well cultivated,
: is possible to harvest the crops in August in Oklahoma, leaving
mple time to prepare the land for winter wheat.

For the corn and wheat producing sections of the State a three-year
otation, consisting of corn the first, oats the second, and wheat, fol-
ɔwed by either cowpeas or soy beans, the third year, is recommended.

---

[a] Compiled from Indiana Sta. Bul. 120; Oklahoma Sta. Bul. 74.

For a more extended rotation the following succession of crops is suggested: Corn, Kafir corn, cotton, oats, and wheat, followed by cowpeas or soy beans the same year. In the sections of the State where broom corn is grown a rotation consisting of broom corn the first year, cowpeas or soy beans the second, and durum wheat the third year, is considered profitable. Many farmers sow cowpeas between the corn rows at the last cultivation, and this practice makes it possible to use the crop twice in a three-year rotation, as, for instance, when oats followed by cowpeas are grown the first year, cotton the second, and corn the third. In addition to increasing the fertility of the soil through their power of using the free nitrogen of the air and storing a considerable quantity of it in their roots, both crops have a beneficial effect upon the physical condition of the soil by making it loose and mellow.

SOIL AND MANURING.

Although cowpeas and soy beans, like other leguminous crops, increase soil fertility, they are not successful on thin and badly worn lands. The influence of barnyard manure on the two crops was shown in an experiment made by the Oklahoma Station. Two crop rotations, one including the cowpea and the other the soy bean, were grown on manured and unmanured ground. In the first corn, oats, wheat, and cowpeas in the order given occupied the soil during a period of three years. Cowpeas were grown in 1902 and 1905, but the latest crop had a poor stand and the yields were low. The plats which had been manured at varying intervals gave an average yield of 3.23 bushels of grain and 0.35 ton of straw per acre, while the unmanured plats yielded 2.88 bushels of grain and 0.29 ton of straw. The second rotation, consisting of castor beans, Kafir corn, cotton, oats, wheat, and soy beans, was completed in five years, necessitating the removal of both wheat and soy beans the last year. The manured plats in this experiment received 14 tons of manure per acre in 1902, but no manurial treatment was given afterwards. In 1904, after the wheat was harvested, the land was disked with a disk harrow several times, and 30 pounds of soy bean seed per acre was put in with a disk drill July 12. This crop required seventy-nine days to mature, and was harvested October 1. The unmanured land produced on an average 11.6 bushels of grain and 0.68 ton of straw and the manured 17.6 bushels of grain and 1.02 tons of straw per acre.

In 1904 cowpeas and soy beans were compared in general farm work on bottom and upland soil. The bottom land was seeded May 5 and the upland June 30. In both trials cowpeas gave much the heavier yields of cured hay per acre. This has also been the experience of the Indiana Station, where the cowpea produced about

›e as much hay and not half as much grain as the soy ›vy rains interfered with the crops on the bottom land, and late planting on the upland soil gave the better results, espe grain production. The soy bean stood the excessively mois ons better than the cowpea. Both crops are also quite dr stant, the power of endurance being a little greater in tl ns than in the cowpea.

PLANTING.

Both crops are generally drilled in rows 24 to 36 inches apart Indiana Station the common wheat drill was found the mos iient and most satisfactory machine for doing this work. ommended that for the medium-sized varieties the drill be bushels per acre on the wheat scale, and using the first, fiftl ith holes, thus making the drills 32 inches apart for soy bea first, fourth, seventh, and tenth holes, making the drills 24 rt for cowpeas. The 32-inch drills require about 23 pour d per acre and the 24-inch drills about 30 pounds. For the sı ds the drills should be set at about 2 pecks less and for the ds at about 10 or 12 pecks per acre on the wheat scale. In 1 Oklahoma Station soy beans in rows 24 inches apart ga erage yield of 8.6 bushels of grain and 0.77 ton of straw per ile a 32-inch planting produced 10 bushels of seed and 0.89 aw. The average results for three years of experiments in me planting soy beans for seed production at the Indiana Station t drills 32 inches apart and cultivated produced the best sts at different stations indicate that both crops are sensiti wding. In this particular experiment at the Indiana Static h drills with cultivation gave an average yield of 21.3 bushe e, 24-inch drills with cultivation 20.4 bushels, 8-inch drills w tivation 15.6 bushels, and broadcasted plats 10.7 bushels.

HARVESTING.

Directions for harvesting given by the Indiana Station state ien the soy bean is desired for hay the crop should be cut whe ds are about half filled and dried and then handled much as e hay. It was found, however, that the soy bean is not commended for haymaking, being more distinctively a grain d that the cowpea is much more satisfactory for this pu hen grown for the grain the soy bean should be harvested as three-fourths of the leaves have fallen and the majority o ls have attained a brownish color. The crop must not be all ripen too thoroughly, as the pods then have a tendency to en and to scatter their seeds. The Medium Green, the Very I

Brown, and the Ogema soy bean were found to be particularly given to shattering, while the Ito San, Early Brown, and Medium Early Yellow were less liable to loss in this way.

The cowpea should be cut for hay or for soiling when the first pods begin to ripen. This subject is discussed in a previous bulletin of this series.[a]

THRESHING.

The Oklahoma Station found that the use of a machine for threshing the cowpeas, even after blank concaves had been put in and some of the teeth of the cylinder removed and the speed of the machine reduced, was not very successful, a large percentage of the grain being broken and spoiled for planting. It is suggested that threshing the seed with a flail will give better results and will cost approximately from 6 to 8 cents per bushel as compared with 4 to 5 cents for machine threshing. The soy bean is not so brittle as the cowpea and can be readily threshed with the machine, provided the precautions above mentioned are taken.

VARIETIES.

With reference to varieties, the Oklahoma Station states that Medium Green, Early White, Ito San, Medium Yellow, and Black soy bean varieties ripen early and mature even in sections where the growing period is much shorter than in Oklahoma. Of the different varieties of soy beans tested at the Indiana Station, the most productive varieties were Medium Green, with an average yield for four years of 22.2 bushels; Early Brown, with 21.5 bushels; Ito San, with 21 bushels, and Medium Early Yellow, with 20.2 bushels per acre. Tests of several varieties of cowpeas made by this station showed that the California Blackeye ranked first in earliness, requiring only one hundred and twelve days to ripen as compared with one hundred and forty-two days for other sorts in the test. The White Era and Whippoorwill gave the largest yields of grain and the Iron was the best producer of forage. A number of varieties of cowpeas were grown for two years at the Indiana Station, and of these the leading varieties with their average yields of hay per acre annually were as follows: Clay, 7,600 pounds; Iron, 7,400 pounds; Warren, 6,500 pounds, and New Era, 6,450 pounds.

RELATION TO SOIL FERTILITY.

The complaint is sometimes made that the soy bean does not enrich the soil to the same extent as does the culture of the cowpea. Judging from the chemical composition of the two crops it seems possible at when both crops are removed from the soil the soy bean carries vay a greater quantity of fertility because the grain is so much cher in nitrogen than the grain of the cowpea. If, however, both ops are used for green manuring their chemical composition can t produce a wide difference in soil improvement. The higher trogen content of the soy bean seed is offset by heavier yields of een material in case of the cowpea.

---

[a] U. S. Dept. Agr., Farmers' Bul. 222.

SILAGE FROM FROSTED CORN.[a]

In view of the difference of opinion among farmers as to whether rn is seriously damaged for silage making by frosting, the Vermont xperiment Station undertook experiments in which different secons of the same field of corn were ensiled in unfrosted condition nd after different degrees of frosting.

A little more than half of it was cut into the silo on October 7, immature nd just barely touched by an extremely light frost. A hard frost seemed mminent that night, but did not occur. Indeed, the first hard frost was delayed wo weeks, occuring on the night of October 21. Half of the remainder was cut n that date prior to the frost, mature, ears glazed; the remainder two days ater, on Monday, mature, ears glazed, hard frosted or even frozen, with leaves adly whitened.

The feeding value of the different lots of silage was determined y feeding experiments with 21 milch cows for from fifteen to twenty-five weeks. It was found that—

(1) In every case more dry matter was eaten when the mature silage ration was fed, as was to have been expected: (2) the quality of the milk made when the silage from the frozen corn was fed was depressed slightly; (3) the total solid and fat yields were slightly depressed when the ration containing the frozen corn silage was fed; and (4) the products per unit of consumption were depressed when the more mature silages were fed, owing to the greater consumption but smaller production.

The general outcome of the experiments, therefore, was that "the effect of frosting corn, and yet more of freezing it, appears very slightly to have been to depress its feeding value when made into silage."

In view, however, of the fact that from 6 to 15 per cent more total dry matter was harvested as a result of the two weeks' longer growth of the crop, and in view of the presumption that the proportion of digestible dry matter was similarly augmented, a 1 per cent depression resulting from the feeding of frozen silage is a negligible quantity. No ill result on the butter product was observed. It is reported that silage made from frozen corn keeps well in a good silo. It would appear, therefore, that the testimony of this trial is, on the whole, in favor of running frost risks to gain a greater maturation.

---

[a] Compiled from Vermont Sta. Bul. 129, p. 132.

COOPERATION IN MARKETING FRUIT AND TRUCK CROPS.[a]

The cooperative idea among fruit and truck growers, having passed the experimental stage, has become an important factor in present-day marketing. Scarcely any well-developed horticultural sections are without their associations in one form or other. New fruit and truck regions are being constantly developed, however, and a brief study of cooperative methods may be of value. The benefits to be derived from such organizations are many. Small producers can make combined shipments in car lots, which is now considered the economic unit of shipment. Organizations, through the volume of their business, can secure minimum transportation rates. They can afford to maintain daily telegraphic communications with all of the important markets and are thereby enabled to divert cars already en route to places where the demand is greatest. Growers are advised when to hold and when to ship. Uniform grades and packs are secured. Organizations are in a position to know the actual supply of their respective communities; hence managers, working in harmony, can regulate prices to a considerable extent. Through the association the members can procure packing material, fruit-picking baskets, spraying materials, and pumps, potato bags, etc., at a greatly reduced cost. Successful associations require choice products. By an interchange of ideas and experience members are in position to eliminate unprofitable varieties of fruits or vegetables from the community and to develop thorough and economic systems of cultivation. These and many other advantages might be noted.

Cooperative associations have developed rapidly in the West. Over thirty fruit and produce organizations of various kinds are now doing business in Colorado. In a recent publication of the Colorado Station, W. Paddock describes the workings of these associations, which in a general way are similar to those of other sections.

> There are two methods of packing and grading fruit; in one instance the association does all the packing, the growers delivering the fruit to the packing house just as it is taken from the trees. Here the packers, under the direction of a superintendent, sort the fruit into the various grades, and at the same time pack it into boxes or crates. Should there be any culls they are returned to the grower and are at his disposal.
>
> Each grower is given a number, which is used to designate his fruit throughout the season. As each box is packed it is marked with his number and the grade. When the boxes are loaded into the cars the number of boxes, the varieties, and the various grades which belong to any grower are kept account of and duly recorded. In this way the price for each box of fruit in any car is easily determined.

---

[a] Compiled from Colorado Sta. Bul. 122; Maryland Sta. Bul. 116; Oregon Sta. Bul. 94. See also Transactions Wisconsin State Hort. Soc. 1907; Canada Dept. Agr., Dairy, and Cold Storage Comr. Bul. 18.

But where there is a very large amount of fruit to be handled it is impossible r the association to do the packing, consequently the growers assume this rk. With this arrangement the association employs an inspector, whose duty is to inspect each load as it is delivered. This he does by opening the boxes on e side in the case of apples, when a good estimate of the contents may be de. If the pack is satisfactory not more than two boxes may be opened. If satisfactory, several may be examined, and if all run under the inspector's ndard, the entire load must either be placed in a lower grade or else be packed.

It will be seen that a great deal depends on the inspector, and that it is a dif- ult position to fill. Upon him depends the reputation of the association, so he ust be entirely free to do the work as he sees fit.

Each man's fruit is kept track of by numbers, as in the former case.

The association charges a commission on all sales, usually 5 per cent, to fray expenses. Then, in case the packing is done by the association, an addi- nal charge is made to cover the cost of the box and packing. Any surplus , of course, distributed as premiums. Any fruit grower may become a member the association so long as there is stock for sale, and the owner of one share entitled to all of its privileges. The number of shares one individual may n is limited.

The growers are generally asked and, in many instances, required to furnish estimate of their crop. In the smaller associations the manager sometimes cures this information by visiting the orchards in person. This estimate is ade early in the fall, or not until damage by worms and other causes is prac- ally over and the crop is secure. With this knowledge in hand, the manager n enter into contracts for delivering certain amounts of various varieties grades.

The system of selling has been radically changed within the past few years. rmerly practically all of the fruit was consigned to commission men, who, a class, it may be truthfully said, are inclined to do the best they can by their nstituents. But too often the experience has been otherwise. Not infre- ently has it happened that shipments consigned to a distant city have been ported as not being up to grade, or not in good condition, so the market ice could not be realized. In such cases, though the manager may be certain at his fruit is as he represented, he is often unable to help himself, so must ke what he can get. But of late years the plan of selling f. o. b. is being acticed more and more, and this is largely due to the organized efforts of the sociations. Consignments are only made to well-known firms, and much of s fruit is sold at auction.

But even with this arrangement difficulties arise, so in order to protect them- ves the larger associations have an agent at the more important distributing ints. It is the duty of the agent, or broker, to inspect all cars which come o his territory, as near the destination as possible, and thus protect the sociation from dishonest buyers. He also is on hand to adjust the differences ich arise when the fruit actually reaches the buyer in poor condition.

Express shipments are only made to comparatively near-by points, and with h shipments the growers receive exactly what the fruit brings, less the ex- ssage and the association's commission. It is usually the early fruits that are ressed, but prohibitive rates prevent any very large amount of business ng done in this way.

Such associations often fail in their purpose. The prime causes failure are well summed up by Waugh,[a] on the following page:

---

[a] Fruit harvesting, storing, marketing.

All classes of farmers are constitutionally and proverbally distrustful of other people and of one another. In a fruit association there arise (such is the experience) the most inveterate jealousies. Each man thinks he is furnishing a better grade of fruit than his neighbor, though all share alike in the profits. Each one fears the other will reap some special advantage somehow. In particular, the appointment of managers, superintendents, supervisors of grading, shipping agents, and all other officials of the company offers a sufficient opportunity for the elaboration of all sorts of neighborhood quarrels. Each man thinks he ought to be manager, and when one man is finally chosen he is usually suspected of all sorts of favoritism. In any case, he is apt to be hampered in his business relations by committees, boards of directors, and various kinds of red-tape and foolishness. Often he has to consult a committee before taking any important action. * * *

Another difficulty which arises from the same cause is that subscribers to such an association never want to pay a manager's wages. Two or three dollars a day is considered good pay. Yet such a man is compelled at times to handle thousands of dollars' worth of business. The position is such as in ordinary business life would command a salary of $5,000 a year or more.

Where such conditions exist there is little chance of success. They may be avoided to a great extent if inexperienced shippers will limit the size of their organization until the minor details connected therewith have been thrashed out. A few selected growers are sufficient to demonstrate to the community the advantages of cooperation, and a healthy expansion will soon take place. When the volume of business is sufficient to warrant such action, the management should be turned over to a man who is especially equipped with a knowledge of the details of marketing, and who has no crop interests of his own. He should receive the confidence of the members and be given a chance to work out his own ideas. The manager's salary should be adequate for the work and responsibility involved. It is sometimes the custom to give him a percentage on the total amount of business transacted. Well-established associations, however, can afford to pay a good manager a straight salary and thus feel more certain of retaining his services from year to year. The Colorado bulletin, previously referred to, contains a report of the Grand Junction Fruit Growers' Association, which "is the oldest and is doing the largest business of any in the State."

This association was started in 1891, when a few growers combined and appointed one of their number salesman of their fruit for the season. This arrangement continued with varying degrees of success up to 1897, when it became apparent that the increased business, if no other cause, would necessitate employing a manager by the year, who should devote his entire time to the association. Accordingly, this was done, and the business has increased year by year, as shown below. That the majority of the stockholders are satisfied with the workings of the association is proven by their loyalty and by the fact that the capital stock has recently been increased to $100,000 for the purpose of accommodating the increasing number of members.[a]

---

[a] Number of stockholders January, 1907, was 666; number of shares of stock sold to January, 1907, was 14,169.

The Grand Junction Fruit Growers' Association—Growth of business.

Year.	Paid growers.	Total business.	Cars shipped.	Year.	Paid growers.	Total business.	Cars shipped.
7	$54,065.00	$88,987.00	167	1902	$195,975.15	$287,887.15	618
8	21,785.00	43,750.00	89	1903	247,188.45	339,305.41	682
9	21,346.00	56,591.00	82	1904	437,154.33	557,291.11	1,282
0	68,323.00	114,590.00	202	1905	475,763.00	608,408.30	797
1	98,972.90	153,380.00	256	1906	555,813.44	814,278.62	1,086

Cooperative associations are especially well developed in the Pacific ast region. According to C. I. Lewis, of the Oregon Station, the ood River Apple Growers' Union has met with great success.

The Hood River organization now has a membership of over 100 and controls proximately 90 per cent of the fruit of the valley. In four years it has been le to raise the price from 85 cents to $3.15 for the best grade of Spitzenbergs, d $2.50 for the best Yellow Newtowns. The prices range somewhat as regards e and quality. As an experiment this past fall the association sent 9 carads of fall apples to England. These apples were selling here at approximately cents a box. After all expenses were paid they netted the Hood River owers $1.32 per box.

As a type of a well organized and managed association in the East, . N. Hutt, of the Maryland Station, gives the following description the Peninsula Produce Exchange of the eastern shore of Maryland:

This exchange operates along the lines of the New York, Philadelphia and rfolk and the Baltimore, Chesapeake and Atlantic railroads. It has 25 local ipping points at each of which is an agent who inspects and brands the grade produce, and reports to the head office at Olney the amounts and grades of uit and truck received. The general manager in the head office is in touch by ire with prices in all the large markets, and as soon as the daily reports of ceipts and grades are wired in from his local agents is in a position to make s sales and place his consignments where the demand is greatest. The change spends over $10,000 annually in telegrams regarding crops, markets, d prices. The capital stock of the exchange was reported in 1905 at $31,000. his was owned by the 2,500 farmers who sell through the exchange. In 1905 dividend of 7 per cent was declared and in 1906 a 10 per cent dividend. In dition to this a surplus was laid by for emergencies. The exchange forwards nually thousands of cars of both sweet and Irish potatoes in addition to other uck and fruit. It is reported as doing an annual business in the neighborhood $2,000,000.

Instances of successful organizations might be noted from every rominent horticultural region in the United States. The above xamples, however, are sufficient to demonstrate the possibilities of uch institutions. The details of organization will vary more or less n their solution, depending greatly on the nature of the region and rops to be handled and the volume of business conducted. In the ublications of the Oregon and Colorado stations herein mentioned he text is given of the articles of incorporation and by-laws of cerain associations, together with instructions to growers and packers. uch information can usually be procured in printed form from any ell-established organization.

EVAPORATION OF EGGS AND OTHER FACTORS WHICH AFFECT INCUBATION.[a]

During incubation the egg loses water by evaporation, and the amount lost has an effect upon the number of eggs which hatch. C. A. Whiting, who recently studied this question of evaporation, found that during incubation a fertile egg lost a little over 20 per cent in weight, while a sterile egg receiving like treatment lost 15.5 per cent. Another fertile egg, weighing 2.22 ounces, lost during incubation 21.64 per cent in weight. The chick hatched from the egg weighed 1.55 ounces, or 29.65 per cent less than the egg before incubation. A fertile egg shaken vigorously to destroy the germ lost 17 per cent during incubation.

In tests carried on at the Ontario Agricultural College and Experimental Farm to secure data regarding the evaporation of eggs under different conditions with reference to the number which hatched, it was found that when eggs were hatched by hens in nests in the open, the average evaporation of those which hatched was 10.9 per cent. The same figures were obtained with eggs hatched in a nest lined with rubber cloth and placed inside a building, and a slightly higher value, 11.9 per cent, with nests containing a layer of moist earth and kept inside a building. The highest evaporation of eggs which hatched, 15.15 per cent, was observed with nests containing chaff and kept inside a building. In the case of incubators the average percentage of evaporation of eggs that hatched ranged, under different conditions, from 9.1 to 16.3 per cent. Considering both natural and artificial incubation, the range was from 5.9 to 27 per cent. With outdoor nests 87 per cent of the fertile eggs hatched; with indoor nests containing moist earth, 85 per cent: with indoor nests made of chaff, 77 per cent, and with an indoor nest lined with rubber cloth 100 per cent. In the incubator tests 65 to 76 per cent of the fertile eggs hatched. From the recorded data, W. R. Graham, who conducted the investigations, believes that the best results will be obtained when the evaporation is controlled so that it is about that of eggs hatched by hens with nests out of doors on the ground.

Tests made at the University of St. Louis, by A. C. Eycleshymer, showed that during natural incubation the loss by evaporation was 13 per cent of the original weight of the egg and that this loss could be lessened to 9 per cent and still the egg would give a healthy chick. When increased, experimentally, to 20 per cent, perfect chicks were so obtained. These results are, in general, much the same as those tained at the Ontario Experimental Farm, and if average values re considered it seems fair to conclude as did Eycleshymer that in rtificial incubation "the moisture in the incubator should be so ntrolled that it will allow the evaporation of about 13 per cent of e original egg."

---

[a] Compiled from Bul. South. Cal. Acad. Sci., 5 (1906), No. 3, p. 50; Ann. Rpt. Ontario Agr. Col. and Expt. Farm, 32 (1906), p. 202; Biol. Bul. Mar. Biol. Lab. Woods Hole, 12 (1907), No. 6, p. 360. See also U. S. Dept. Agr., Farmers' Buls. 186, p. 28; 281, p. 24.

In the experiments at St. Louis University the effect of a number of ther conditions on the incubation of eggs was also studied.

As regards the turning of eggs, Eycleshymer points out that—

> The hen turns the egg in two ways. If a sitting hen be watched as she returns rom feeding to sitting, it will be seen that she moves her body rapidly from side o side. Whether the object be to turn the eggs is uncertain. Probably the rst object is to bring the surface of the body in the closest possible contact ith the growing embryos. Accidentally or purposely, she also turns the eggs. his is not only true of the hen returning from feeding, but also when on the est, for she is frequently observed moving about and settling down with the ame characteristic lateral movements. Sometimes there are so many eggs in he nest or they are so widely scattered that the hen fails to properly cover hem. When such conditions occur, the hen invariably uses her beak to bring he outlying eggs in contact with her body. Not only does she frequently thus urn the eggs, but also she very often reaches beneath her body and turns the ggs lying near the center of the nest. Why she does this, is a question which waits an answer.

H. F. Prince, who studied this question at the Agricultural College f Cornell University,[a] with a number of hens, found that in every nstance the eggs were moved every day and did not remain in the ame part of the nest for more than three days. "The thorough manner in which the hen turns the eggs may well furnish us a clue to the most natural and proper treatment of the eggs when under the artificial conditions of the incubator."

Eycleshymer's experiments with an incubator showed that the best results were obtained when eggs were turned frequently, at least five times. The embryos in unturned eggs not infrequently die, the principal cause of death being attributed to the allantois, a membranous sac essential to the normal development of the embryo, growing fast to the yolk, which causes the rupture of the membrane inclosing he yolk and allows it to escape, so that it can not be taken into the ody of the embryo. When the eggs are turned it is probable that he position of the allantois is shifted and thus adhesion to the yolk s prevented. "It should be remarked that during the early days of ncubation it is also necessary to turn the eggs frequently; otherwise, he embryo grows fast to the shell membrane."

In a study of the effect of temperature a great many observations ere made of the temperature of the eggs directly under the hen, of the hen's body, and of the eggs during incubation. Special thermometers were used and precautions taken to secure accuracy. Under natural conditions, in the author's opinion, his observations show that the proper temperature of eggs during the first week is about 100° F., 101° F. for the second week, and 102–103° F. for the final week. In the case of artificial incubation the experimental data reported led to the conclusion that the most favorable temperature within the egg chamber is close to 102–103° F., the first half of the incubating period, and 103–104° F. for the latter half.

---

[a] Cornell Countryman, 3 (1906), p. 139.

In any consideration of temperature, the fact must be kept in mind that as the chick grows it gives off more and more heat, so that if an incubator of 200-egg capacity were entirely without artificial heating, the temperature would be much higher than that of the surrounding atmosphere; it consequently follows that less artificial heat is necessary during the later stages of incubation. The 102–103° F. in the earlier stages is largely artificial heat, while the 103–104° F. in the later stages would be the combined animal heat given off by the egg and the artificial heat supplied by the heat radiator.

Under natural conditions eggs are cooled somewhat at intervals during incubation when the hen leaves the nest.

It may be stated with a fair degree of certainty that the cooling of the eggs is due to the necessity of obtaining food, and in no way fundamentally affects the growth of the chick when there is an abundant supply of fresh air. There is not the least doubt, however, but what it has a beneficial influence in cases of poor ventilation, and since no incubator is supplied with too much, it probably is best to adopt the common practice of cooling the eggs. In so doing it would not seem advisable to cool the eggs for more than twenty to thirty minutes each day for the first fifteen or eighteen days.

In natural incubation under usual conditions eggs are well ventilated, as fresh air can always reach them by diffusing through the feathers which cover them and foul air pass off in the same way. As might be supposed, it has been found that the degree of ventilation has a decided effect upon the percentage of eggs which hatch in incubators. In the tests made at the University of St. Louis 85.7 per cent of the fertile eggs hatched in an incubator provided with special ventilation, while only 44.3 per cent hatched in an incubator without ventilation.

When a perfect ventilation has been obtained it has produced certain deleterious effects which must be corrected. It is commonplace to say that when evaporation goes on in still air this air soon becomes saturated and evaporation, if not stopped, goes on very slowly. If, however, the saturated air is constantly removed and dry air takes its place, the rate of evaporation is increased. It is thus evident that any discussion of ventilation must take into consideration the question of moisture.

CAUSES OF DEATH OF YOUNG CHICKS.[a]

It has been often noted that a large number of incubator chicks die during the first ten days in the brooder from a looseness of the bowels, which is commonly known among poultry men as white diarrhea. This trouble has been assigned to a variety of causes, among them being irregular temperature, lack of vitality of breeding stock, improper feeding, and poor ventilation not only of brooders but also of the rooms in which the incubators are kept. A committee of Ontario poultry experts after investigating the cause of this mortality among chicks in Ontario and New York concluded that the lack of ventilation was perhaps the most important of the determining factors.[b]

The Connecticut Storrs Experiment Station has recently studied this question, being led thereto by the fact that nearly every chick died of 400 hatched in February in different incubators, while large numbers of chicks hatched before and after this date did not exhibit any of the fatal symptoms. Believing that food was an important factor in the problem, C. K. Graham, who carried on the work, fed several lots of chicks with different kinds of feed and noted that the mortality was high in whichever lot received one of the grain mixtures. Careful examination showed that this feed contained a fairly large percentage of musty grain, particularly corn. The young chicks ate all the grains indiscriminately, and their lack of ability to detect wholesome from unwholesome foods was further tested by giving them rations which contained such substances as sawdust, coarse salt, and granulated sugar. These materials were eaten as readily as the grains with which they were mixed. Indeed, "the salt and sugar were always selected first, apparently owing to their bright appearance; but as a rule the chicks did not appear to relish them."

When older chicks hatched by hens, and also those taken from the incubators and given to the hens, were offered these same mixtures, it was exceptional to find a chick that took over a grain or two of salt, sugar, or sawdust.

When musty feed was given to the older incubator chicks it was noticed that those which were eight or nine days old showed considerable discrimination in selecting the grain, while still older chicks refused even larger proportions of the musty kernels.

This forces the conclusion that many of the deaths among young chicks are caused by musty food, although there is no doubt that faulty brooders, chills, overheating, improper ventilation, and lack of vitality in the parent stock should all receive proper credit for their share.

---

[a] Compiled from Conn. Storrs Sta. Bul. 44.

[b] Ontario Agr. Col. and Expt. Farms Rpt. 1905, p. 230.

SUBSTITUTING SNOW FOR WATER FOR POULTRY.[a]

Unnecessary labor is one of the chief factors which lessens profits in poultry feeding. To provide 500 to 1,000 hens with water, particularly if they are kept in colony houses, requires considerable time, and if the water is warmed and given to the poultry twice a day the labor will be more than doubled. An abundant supply of water is generally conceded to be an essential feature in successful poultry raising; nevertheless cases have been known where a hen had no water for long periods, except that furnished by dew, and still produced a reasonable number of eggs.

The possibility of lessening the labor of caring for poultry by supplying snow instead of water has been studied at the Connecticut Storrs Experiment Station by C. K. Graham. When pullets and hens were fed wheat screenings and beef scrap from hoppers in colony houses on low ground frozen during most of the experimental period and covered with snow during part of the time, the old hens did not furnish as many eggs or appear to be in as good condition as the younger birds.

The old hens were apparently affected by the snow, the egg production being smaller on the days when snow was on the ground and also considerably less when the ground was frozen; that is, on the cold days when water was not accessible. These conditions do not seem to have affected the younger birds, and they show an increase in eggs immediatey after each snow storm, gradually dropping back as the snow disappears.

In the case of other lots kept under much the same conditions in houses on higher and drier ground, the cold weather did not affect the egg production materially, " but there was a noticeable increase in the amount of grain eaten during the cold weeks, when comparison is made with the very mild ones. This, however, may have been caused by the birds foraging more during the milder periods. These birds did not appear to mind the cold, and there was not the slightest sign of frosted combs among them, nor were there any colds."

Similar tests were made with a number of other lots and in general it was noted that although there were many variations, on an average the egg yield of poultry supplied with cold water was slightly greater than that of the birds depending upon snow. However, the time saved by using snow and dry meshes amounted to nearly half that ordinarily required for tending the fowls.

Snow was given to young chicks, but the results were disastrous; although chicks that were reared in out-door brooders were let run on the snow crust during bright days when 3 weeks old or over, and no serious results followed.

When warm water was compared with cold water the egg production was somewhat increased, but not enough to pay for the extra labor involved.

---

[a] Compiled from Connecticut Storrs Sta. Bul. 44.

ERADICATION OF CATTLE TICKS.[a]

'he enormous handicap which the presence of Texas fever has ced upon the beef and dairy industries of the Southern States has g been familiar to all who have engaged in these lines of work, as .l as to the reading public. The Bureau of Animal Industry made ≀as fever one of its important lines of investigation, and solved problem of the cause of the disease and the means by which it is nsmitted. Following upon its preliminary work came the anıncement of a satisfactory method for the immunization of northı cattle to Texas fever by the use of the blood of immune southern tle. This method, first devised by the Bureau of Animal Industry, l later tested on a large scale and perfected in certain details by rious experiment stations, has furnished safe means for the introction of high-grade cattle into the South. This made possible the eat improvement of existing beef and dairy cattle in that section of e country.

The ticks, however, still remain. They are recognized as the only eans by which the disease may spread from one animal to another, ıd, in addition to transmitting the disease, they cause other almost ually serious financial losses. Badly infested cattle are kept in or flesh, and in many instances fail to reach the size which they herwise would, or fail to mature as early as they normally should. me animals are killed outright by excessive infestation with ticks. ıe total annual loss attributable to cattle ticks in the Southern ates has been estimated at $40,000,000. This loss is represented not ly by the animals which die of Texas fever and of excessive tick in'tation, but by the loss in weight and condition and the depreciation price of all tick-infested animals, due to the fact that they come m south of the quarantine line. One of the most serious economic ults from the presence of cattle ticks in the Southern States is the noyance, additional expense, and business complications due to the sence of the quarantine line running across the country from ocean ocean.

For years the idea has been gaining ground that the only satis:tory way to solve the problem of Texas fever is to eradicate the ks and thus prevent the perpetuation of the disease. A large num: of investigators have been engaged in a careful study of the life story of the cattle tick in order to determine whether its exterminan is a feasible proposition and the methods by which this result ıy be most economically brought about. As a result of this investition three general methods of tick eradication have been perfected, any or all of which may be set in operation in a given locality. These methods are direct insecticide treatment of cattle with oils and other substances, rotation of pastures, and starvation of the ticks by the removal of all animals from certain fenced areas.

---

[a] Compiled from Georgia Sta. Buls. 49, 64; Louisiana Stas. Buls. 82, 84; South rolina Sta. Bul. 130; Tennessee Sta. Bul., Vol. XVIII, No. 1; U. S. Dept. Agr., r. Anim. Indus. Buls. 1, 78, 97; Circ. 110; U. S. Dept. Agr., Farmers' Buls. 3, 261, and other sources.

When the suggestion of tick eradication was first made many of those who were most familiar with the life history and habits of the tick considered it as an impractical proposition. Certain others, however, were more hopeful and began practical tests to determine the efficiency of the method. Without going into details of the organization of these methods it may be stated that the results thus far obtained are so encouraging that even the most skeptical have become convinced of the possibility of final tick eradication. Liberal appropriations have been secured from Congress for the use of the Bureau of Animal Industry in cooperation with State officials in eradicating ticks in the various tick-infested States so that the quarantine line may be gradually pushed farther south. In a conference of Federal and State representatives engaged in this work, held at Nashville, Tenn., on December 5, 1906, the work accomplished during the first five months was presented from a number of standpoints by a number of workers in different sections of the tick-infested States. As stated by Doctor Melvin, the reports received from various inspectors indicate that as a result of five months' work about 50,000 square miles of infested territory had been freed from ticks and might therefore be placed north of the quarantine line. The work is being pushed vigorously in Virginia, North Carolina, Tennessee, Arkansas, Oklahoma, and in other localities within the tick-infested area, and in all localities the methods of starvation, pasture rotation, and direct treatment of cattle with insecticides have yielded the desired results at a comparatively slight expense. In fact, it is at present estimated that the total expense of the complete eradication of the cattle tick from the United States will probably not exceed the amount of annual loss caused to the cattle industry by the presence of the cattle ticks.

A great amount of this work on the part of Federal and State inspectors and veterinary officials must be of an educational nature. It has been found necessary, in the first place, to convince the farmers of the practicability of freeing their farms from ticks and of the desirability of cooperating to the fullest extent in accomplishing these results. The educational propaganda of tick eradication has been carried on largely through farmers' institutes and less formal gatherings of farmers in tick-infested localities and through the personal appeals of inspectors on their tour of inspection from farm to farm. The results of this work are everywhere encouraging, and it seems reasonable to believe that in the future the quarantine line will be gradually pushed southward toward the Gulf.

BACTERIA IN CREAM.[a]

n a recent bulletin of the Oklahoma Station, L. L. Lewis and R. Wright report that last year many farmers living in the inity of the station made butter until the hot days of June, and n gave up the work because they were unable to make a product good quality. The cream was then delivered to the college cream- ·, where, with ice at hand, " it was successfully manufactured into ;ood grade of butter. Most of the butter made on the farms and ered for sale in the local market during the summer months was of :h poor quality that it seemed imperative that the experiment sta- n should make investigations along these lines to determine, if ssible, the various causes operating to produce such a low-grade oduct. As the improvement of the butter must be brought about the improvement of the cream and the conditions under which it kept, it was decided to determine the condition of the cream as de- ered at our creamery," which are considered representative of those the average creamery in the Territory.

To determine the quality of the cream delivered during the summer months, sts were made beginning with the last of June, 1906, and extending to the st of September of that year. This period included the hottest, and conse- ently the most unfavorable months for the handling of cream. As a check these conditions a series of tests was made during the months of December, nuary, and February following, the coldest season of the year. The reason r selecting the summer and winter seasons for this work was to show by mparison the great influence of a low temperature on the quality of cream.

The results show that cream delivered in summer at an age of 3.3 ays contained an average of 462,600,000 bacteria in a cubic centi- eter (0.06 cubic inch), while cream delivered in winter at an age of days contained an average of only 134,800,000 bacteria in a cubic entimeter, or less than one-third that of the 3-day-old samples in ummer. It thus appears that while age has an influence on the umber of bacteria in cream, temperature exercises the greatest con- rol, and that to prevent excessive development of bacteria, cream ust be kept cold, and should be delivered frequently at the creamery.

The bacteria were found to increase in cream for a period of three ays in summer and four days in winter, after which there was a teady decrease; but it is not to be assumed that old cream is better han fresh cream because it has fewer bacteria, for samples of eight- ay cream had an old, unpleasant odor.

As an indication of the care exercised in securing and handling the ream and the milk from which it was obtained, tests were made of e gas-producing and curd-digesting bacteria in the cream delivered. t was found that the combined numbers of gas and digesting germs in cream ranged from a fraction of 1 per cent to 2 per cent in summer and from a smaller fraction to a little more than 1 per cent in winter. As gas-producing bacteria are much more troublesome in summer than in winter because a high temperature favors their growth, there is need of greater care in performing dairy operations at that season of the year. Since large numbers of curd-digesting bacteria are found in hay and straw, these feeding materials should not be handled during the milking period.

---

[a] Compiled from Oklahoma Sta. Bul. 75.

The ordinary souring of milk is due to the action of lactic bacteria on milk sugar, changing it to lactic acid. Now, since rich cream contains a smaller amount of milk sugar than thin cream, it is evident that the lactic bacteria will produce less acid in the rich than in the thin cream.

Cream becomes more sour with age, though the number of bacteria is less after the third or fourth day, and it was found in these experiments that the average cream more than two days old in summer was too sour to be handled at a creamery with good results.

The results as a whole indicate as essentials of successful butter making in Oklahoma, as elsewhere, (1) clean milk, producing rich cream; (2) cleanly handling of the cream at low temperatures and its prompt conversion into butter.

309

O

Issued

U. S. DEPARTMENT OF AGRICUL

FARMERS' BULLETIN No. 310.

A SUCCESSFUL ALABAMA DI FICATION FARM.

BY

M. A. CROSBY,
Assistant Agriculturist, Farm Management Investiga
Bureau of Plant Industry,

J. F. DUGGAR,
Director, Agricultural Experiment Station of the
Alabama Polytechnic Institute,

AND

W. J. SPILLMAN,
Agriculturist in Charge of Farm Management Investig
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., September 4, 1907.

Sir: I have the honor to transmit herewith a paper entitled "A Successful Alabama Diversification Farm," in which an account is given of the work done jointly by Mr. M. A. Crosby, Assistant Agriculturist, Farm Management Investigations, Bureau of Plant Industry, Prof. J. F. Duggar, Director of the Agricultural Experiment Station of the Alabama Polytechnic Institute, and Prof. W. J. Spillman, Agriculturist in Charge of Farm Management Investigations. The paper gives an account of the first three years' work on the diversification farm on the plantation of Gen. T. T. Munford. I respectfully recommend that it be issued as a Farmers' Bulletin.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

CCESSFUL ALABAMA DIVERSIFICATION FARM.

INTRODUCTION.

bulletin is given the record of a 65-acre hog farm in the
rie region of Alabama. The method of farming described is
to the entire area in which corn, alfalfa, and Bermuda
be grown. This area includes the black lands of Texas,
bottoms of Missouri, Arkansas, Louisiana, and Mississippi,
alluvial soils generally in all the Southern States. This
s especially adapted to the large area in Alabama and
i known as the "black belt," in which the soil is peculiarly
alfalfa, and with only slight modification it is applicable to the
a over which alfalfa or clover may be grown in this country.
ary object in the work of this farm was to demonstrate that
ng is practicable in this territory, and three years' expe-
led us to the conclusion that the production of alfalfa hay
ion can also be made highly profitable.

is not only adapted to the territory named, but succeeds
l soils throughout the Southern States. The contents of
in should therefore be of special interest to farmers in the
oms.

tem of farming established on the diversification farm at
n, Ala., was planned with the special view of increasing the
f the soil and reducing the cost of tillage by doing away
ide ditches and adopting improved methods of cultivation.
on an average only 55 acres have been devoted to culti-
ps, the remainder being a worn-out hill, about 6 acres of
n Bermuda grass, the farm has yielded in the three years
fit of $2,320.39, or $773.46 a year. This is an average
fit of $11.90 an acre on land valued at $20 an acre.

m, designated as Diversification Farm No. 3, is located in
nown as the canebrake or black-prairie region of central
It is a portion of the 2,300-acre plantation of Gen. Thomas
d. For several years this plantation has been under the
nt of Mr. William Munford, being devoted chiefly to the

production of cotton. Mr. Munford has also had active charge of the diversification farm, and any success that has been met with is largely due to his good management and faithfulness in carrying out plans.

SOIL.

In contour the land of the black prairie belt varies from level to quite rolling. The soil is a brown, reddish brown, black, or gray limestone clay.[a] It is classified by the Bureau of Soils as Houston clay and Houston black clay, the former occurring on the rolling, hilly portions and the latter in the valleys and level areas. The Houston black clay is deeper and much more productive than the Houston clay.

When wet this soil becomes very plastic and sticky. When very dry it cracks, some of the fissures being 1 or 2 inches across and from 2 to 3 feet deep. If plowed when dry, the soil breaks up into huge clods. With the first rains, however, these clods disintegrate like slaking lime.

This is naturally a very productive soil, but a continual cropping for seventy-five or eighty years with cotton, and occasionally a little corn, has greatly exhausted the humus or vegetable matter on the more rolling land and correspondingly reduced its producing capacity. For this reason there is great need of a more diversified system of farming—one which will add humus to the soil and restore the land to its original state of fertility.

In selecting the site for this farm care was taken to choose an area which would fairly represent the average land of the surrounding country, so that any results obtained could not be credited to peculiar soil or other abnormal conditions.

The soil on this diversification farm, with the exception of about 2 acres of Houston black clay in the northeast corner, practically all belongs to the Houston clay type. It is locally known as poor hill land to distinguish it from the richer and more productive bottom lands. Four years ago one-third of a bale of cotton and from 15 to 18 bushels of corn to the acre would have been considered an average yield.

TYPE OF FARMING.

The farm described in this bulletin was established to determine whether pork could be produced on the plantation at a profit to the owner. Throughout the cotton-growing sections of the Southern States rk is the chief article of food consumed by the colored laborer, but as e bulk of it comes from the great corn belt of the North and West the nount required on a large plantation represents a considerable outy of cash each year. The production of this meat on the plantation here it is consumed means not only a saving in actual cash outlay, it also necessitates the growing and feeding of a large quantity of rage, the surest and quickest way of increasing the fertility of the nd.

---

[a] It is said that this soil owes its origin to a cretaceous sediment laid down in a rapidly deepening sea. It is known as the rotten limestone or Selma chalk formation, practically the whole area being underlaid at varying depths with a rotten limestone. Ledges of a more resistant lime rock outcrop on many of the ridges. The soil is full of shells and sharks' teeth and of vertebræ and other fossil remains of marine life.

Owing to the deficiency of humus in the soil, it was necessary to lopt a cropping system which would supply this essential constituent id at the same time furnish the feed required by the hogs. A rotan was planned with the view of building up the soil rather than of curing the maximum yields of any crops other than those necessary r the maintenance and fattening of the hogs.

ROTATION.

A four-year rotation with alfalfa two years and corn and cowpeas o years in succession was decided upon. The alfalfa is sown early the spring, cut for hay the first year, pastured by the hogs the secd year, and then broken up for corn, the corn to be followed each me with cowpeas, the latter being sown broadcast ahead of the cultiators at the last working of the corn and grazed off by hogs after the rn has been harvested. In addition a few acres were set aside for ich crops as sorghum and peanuts for soiling and pasture. This tation provides for the turning under of a leguminous crop each me the land is broken; first the alfalfa, then the cowpeas, which llow the corn. Ten acres of cotton were grown the first year for a oney crop to offset any loss that might occur from the change of stem.

Alfalfa is not generally considered a suitable crop to utilize in a ort rotation, and ordinarily it would not be recommended for such se, particularly when a maximum yield of hay is one of the objects ought. But in this case, where the yield of hay was a secondary onsideration as compared to the production of hog feed and the uilding up of the soil, alfalfa suited the purpose admirably. The esults obtained the past year (1906) from plowing up a 2-year-old tand of alfalfa for corn indicate quite clearly that, in this section at ast, alfalfa can be utilized to good advantage in a comparatively hort rotation.

It is planned to continue this rotation only until each field has had ne crop of alfalfa plowed under. By that time the soil should be ufficiently rich in humus to permit the paying of more attention to lfalfa hay production. A rotation will then be planned which will llow the alfalfa to remain for several years, and the production of hay ill become one of the prime factors.

ARRANGEMENT OF FIELDS.

At the beginning of the work in 1904 the land was divided by the driveway and old hillside ditches into irregular fields of various sizes. As the work was not started until late in the season, it was impossible to change the arrangement of the fields. This would have delayed the planting, and thus materially interfered with the year's work. Consequently, part of the area now included in the farm was not used at all the first year and part of that used extended beyond the limits of the farm as it stands to-day. In fact, it was not until the third year that it was possible to get the farm laid out into fields of nearly equal size as originally planned and start the regular rotation.



FIG. 1. Diagram of farm, showing arrangement of fields in 1904.

Figure 1 shows the general layout of the farm for the first year. The solid lines show the boundaries of the fields that were cropped in 1904. The broken lines show the rearrangement of the fields and the boundaries of the total area included in the farm since the first year.

Fields *A*, *B*, *C*, and *D* are to be devoted to the rotation previously mentioned. On field *E* will be grown sorghum and other crops to be used for soiling or pasture, while field *F* is a permanent Bermuda pasture, where the hogs can be grazed during wet weather, when their trampling might injure the alfalfa fields. Field *G* was only included in the farm the first year. None of the fields is permanently fenced except field *A*. When a field is to be pastured, it is inclosed by a temporary 26-inch woven wire fence.

Figure 2 shows the arrangement of the hillside ditches at the beginning of this work and during the summer of 1904. These ditches (*a*, *a*, *a*) had been constructed several years before to keep the soil from washing during the heavy rains. They cut the fields up into irregular patches and occupied considerable valuable land that should have been in crops. They were also infested with Johnson grass, and consequently were a source of constant annoyance. In the fall of 1904 it was decided to do away with these hillside ditches and depend upon deep plowing and getting enough humus in the soil to prevent washing. The results of this experiment have so far been highly satisfactory. During the summer of 1905 no washing occurred, although some very heavy rainfalls were recorded. During the torrential rains which occurred in 1906 there were some slight washings, but not enough to do any material damage, while many other lands in the vicinity, even when protected by the hillside ditches, were badly gullied.



FIG. 2. Diagram of farm, showing the location of hillside ditches in 1904.

MANAGEMENT OF HOGS.

At the beginning of the work Mr. Munford had on hand 66 head of hogs, ranging in age from 2 weeks to 2 years. These were for the most part grade Berkshires, but a registered Berkshire boar headed the herd. Since that time several pure-bred sows have been added to the herd and the grades gradually killed off, so that now all the animals on hand are pure bred, and the majority are eligible to registry.

The original plan of management was to keep from 12 to 16 brood sows, have the pigs dropped in the early spring, push them through the summer months, and dispose of them when they were 8 or 9 months old. This would undoubtedly have been the most economical practice, as the high price of grain which prevails throughout the Southern States makes it very expensive to carry through the winter any animals except those wanted for breeding purposes. Unfortunately, however, several of the young sows were permitted to get with pig late in the season, so that each winter there has been quite a number of fall pigs to carry over. This added expense has materially lessened the profits.

PASTURE.

The hogs are pastured to some extent every month in the year, alfalfa furnishing most of the pasture. This pasturage is supplemented during part of the summer months with daily feeds of green sorghum, and later, after the corn has been harvested, the hogs have the run of the corn and pea fields and derive considerable nutritious feed from that source. During wet weather, when their trampling might injure the alfalfa plants, they are run on a Bermuda pasture containing some white clover. This Bermuda grass, not being closely grazed during the summer, makes a matted growth which does not all kill down with the early freezes, and therefore furnishes some roughage for the animals during the winter months, though by no means as much as they need.

WATER SUPPLY.

The water supply comes from a deep well. The water is raised by means of a hot-air pump and is piped to the troughs in the feeding lots. An automatic device regulates the flow so that the troughs are kept full all the time. Figure 3 shows the arrangement of the temporary lanes which lead from the feeding lots to the different fields, thus permitting the hogs to have ready access to the water at all times. Lane *a*–*b* leads from the feeding lots to the lane *c*–*d*. Field *A* reached by a runway under a drive at *c*; *B*, by a similar runway under the lane *c*–*d*, and fields *C*, *D*, and *E* by the lanes *c*–*d* and *d*–*e*. This [illegible] proved a very satisfactory arrangement. During the long, hot summer days the animals consume an enormous quantity of water, and to attempt to carry this to them, instead of letting them come to the water, would be a very expensive process. Then, again,



FIG. 3. Diagram of farm, showing arrangement of fields in 1906.

hen the days are long and hot the hogs graze only during the cool ours of the morning and evening, spending the heated portion of he day in the shade furnished by the trees and sheds in the feeding ots.

GRAIN FED AND METHODS OF FATTENING.

Grain is fed during the entire year, not in sufficient quantity to keep the animals fat, but just enough to keep them in a good, thrifty, growing condition. During the winter months they are fed on corn, with occasionally some oats, mill stuff, rice polish, etc. While on alfalfa pasture they receive very little grain, generally not over 1 pound of grain to each hundred pounds the animal weighs. As the time for fattening approaches, the hogs that are to be killed have their allowance increased until they are on nearly a full grain ration. They are then taken from the pasture and kept in the feeding pens and fed all the corn they will consume without waste.

When ready to kill, the hogs are sold alive to the plantation. As the quantity of meat produced has never exceeded that required for the rations supplied to the plantation labor, all the finished animals have each year been turned over to the plantation and the farm credited with the amount they would have brought in the open market.

In discussing the methods of growing and handling the crops each year's work has been dealt with separately. This was thought best to bring out to better advantage the difficulties attending the work at the beginning, the development of better practices of tillage, and the comparative cost of producing crops under the old and newer methods. The tables following the discussion of each year's crops represent actual costs based on daily records kept by Mr. Munford.

In computing the cost of production of the different crops the customary wages paid to day labor has been used as the basis. This is 50 cents a day for a man and the same amount for a mule. A man, two-horse team, and plow or harrow cost $1.50 a day. This may appear a very low rate to some, but this is the usual rate in this section for this grade of labor. While most of the work was performed by day labor, part was done by farm hands who were getting $10 a month. The computations, however, were all based on the rate paid to day laborers and no reduction was made for the cheaper month hands. Since all the work was done by labor and tools hired from the plantation, no allowance has been made for depreciation in value of the tools.

In determining the cost of keeping the hogs, all crops fed (pasture excepted) have been charged against their feed bill at the regular market prices. In the case of the sorghum, where there was no market price by which to be guided, a charge of $2 per ton for the green forage was made. The cost of producing the cowpeas and peanuts which were grazed off by the hogs was not charged against them but to the field crop account, as it was estimated that the manurial value of these crops would offset what it cost to produce them.

OPERATIONS FOR 1904.

The acreage of crops grown during 1904 is as follows: Alfalfa, 17 acres; corn and cowpeas, 24 acres; cotton, 10 acres; sorghum, 2 acres; and melilotus, 10 acres. All the land had been in cotton the previous year and, with the exception of that planted to cotton and sorghum and a small area of the corn land which was too wet to plow early, had been plowed during the early winter. This, together with the fact that the work was not started until planting time, prevented the giving of any special attention to the breaking of the land.

ALFALFA.

The alfalfa was sown in two fields (*A* and *B*, fig. 1), of 7 and 10 acres, respectively. In preparing for planting, the land previously plowed was disked each way and then harrowed with a smoothing harrow. The seed was sown broadcast at the rate of 25 pounds to the acre and lightly covered with a smoothing harrow. Previous to sowing the seed an application of 200 pounds of cotton-seed meal and 160 pounds of acid phosphate to the acre was made. Field *A* was sown March 19 and field *B* March 24. In both fields an almost perfect stand was secured.

The alfalfa grew rapidly and was cut on June 13, field *A* yielding a total of 7,000 pounds of cured hay, or 1,000 pounds to the acre. This field was then fenced off and from July 14 to September 1 furnished pasturage for 57 head of hogs. This number of animals was not sufficient to keep down the growth, however, so it was necessary to cut the alfalfa again on August 17, when a yield of 1,061 pounds of hay to the acre was secured. Field *B* was cut three times during the season. The first cutting, June 13, gave a yield of 700 pounds of hay to the acre; the second, August 4, 2,374 pounds; and the third, September 19, 1,112 pounds, a total yield of 4,186 pounds of hay to the acre, all secured within five months after sowing the seed.

CORN.

The corn land (fields *A′* and *C′*, fig. 1), with the exception of a small, w, wet area in *A′* (*a*, fig. 4), had been bedded into rows 3½ feet art in the manner customary to the region. These beds were run ver with a smoothing harrow and the corn planted April 6 with a one-horse planter. The low, wet area in *A′* was broken with a two-horse turn plow early in April, disked once each way, thoroughly hared with a smoothing harrow, and planted April 24. The variety nted in both cases was Cocke's Prolific. The first week in May ton-seed meal at the rate of 200 pounds to the acre was applied at side of each row with a one-horse fertilizer distributer. Four shallow cultivations with sweeps were given—one in April, two in May, and one in June. At the last cultivation cowpeas were sown ahead of the cultivators at the rate of 1½ bushels to the acre.



IG. 4.--Diagram of farm, showing arrangement of fields in 1905.

The corn was cut by hand August 16 to 26 and set up in shocks containing about seventy hills h. In October the ears were snapped from the stalks, and both ain and stover were hauled to the barn and stored. The total yield the 24 acres was 490 bushels, or a fraction over 20 bushels to the re.

Forty bushels of the peas were picked and saved for the next year's ed, and the rest were grazed off by the hogs.

COTTON.

The cotton land (field *G*, fig. 1) was plowed into 4-foot beds the ter part of February, harrowed with a smoothing harrow, and anted March 30 to April 4. The soil on this field averaged a little tter than the rest of the farm, as it contained more bottom land. e variety planted was Culpeper, and only a fair stand was secured. ve cultivations and three hoeings were given during the season. ne cultivation was with a weeder, the rest with 12 and 24 inch eeps. An application of 200 pounds of cotton-seed meal and 100 unds of acid phosphate to the acre was made at the side of each w the latter part of May. The picking began September 22 and sted until November 30. The total yield of lint was 2,650 pounds, 265 pounds to the acre, and the total yield of seed was 8,350 pounds, 835 pounds to the acre. Considering the stand secured this was a y good yield.

MELILOTUS.

The melilotus was sown primarily as a soil renovator. The land ld *D*, fig. 1), which had been plowed in December of the previous year, was run over once with a disk harrow and then with a smoothing harrow. Seed of *Melilotus alba* in the hull was sown March 27 at the rate of 2 bushels to the acre and covered lightly with a smoothing harrow. An excellent stand was secured. The crop was mowed twice during the season. The first cutting, April 22, made a yield of 1 ton of cured hay to the acre, and the second cutting, August 19, made a yield of almost 1¼ tons to the acre. This hay was of fine quality and was relished by horses and mules.

SORGHUM.

Field *E*, figure 1, which was devoted to sorghum, was plowed April 20, disked once each way, thoroughly harrowed with a smoothing harrow, and planted April 24, 1 peck of seed to the acre being sown in drills 2 feet apart. The variety was Early Amber cane. Two cultivations were given with 15-inch sweeps. The sorghum was utilized as a soiling crop for hogs from September 1 to October 15. The total yield of green forage was estimated at 16 tons.

RECEIPTS AND EXPENDITURES FOR 1904.

The following tables (Tables 1, 2, 3, and 4) show the cost of production, receipts, and net profit for each crop grown in 1904. Each field is considered separately.

TABLE 1.—*Cost per acre of producing and harvesting crops, 1904.*

Field.	Area, in acres.	Crop.	Cost of preparing land.	Cost of seed, planting, and replanting.	Cost of fertilizer and applying same.	Cost of cultivation and hoeing.	Cost of harvesting.	Total cost per acre.
A	7	Alfalfa (pasture)	$1.39	$4.11	$2.47		$1.03	$9.00
B	10	Alfalfa (meadow)	1.05	3.30	2.04		1.24	7.63
A′ and C	24	Corn	1.17	.76	2.15	$2.08	1.16	7.32
A′ and C	24	Cowpeas		2.05			.37	2.42
D	10	Melilotus	1.30	1.20			1.30	3.80
E	2	Sorghum	2.50	.92		3.25	4.00	10.67
G	10	Cotton	1.20	1.96	3.36	[a] 4.35	3.00	13.87

[a] Includes ginning, baling, and marketing.

TABLE 2.—*Crop yield, cost, and returns per acre, 1904.*

Field.	Area, in acres.	Crop.	Yield.	Price.	Gross returns.	Cost.	Net returns.
A	7	Alfalfa (pasture)	1.03 tons	$12.00 ton	$12.36	$9.00	[a] $3.36
B	10	Alfalfa (meadow)	2.08 tons	12.00 ton	24.96	7.63	17.33
A′ and C	24	Corn	20.4 bu. grain 10.58 ton stover	.50 bu 2.00 ton	10.20 1.16	7.32	4.04
A′ and C	24	Cowpeas	[b] 40 bu			2.42	
D	10	Melilotus	2.23 tons	8.00 ton	17.84	3.80	14.04
E	2	Sorghum	8 tons	2.00 ton	16.00	10.67	5.33
G	10	Cotton	265 lbs. lint 835 lbs. seed	$.07\frac{9}{16}$ lb 15.00 ton	20.04 6.27	13.87	12.44

[a] In addition to pasture.

[b] Not sold; kept for seed.

TABLE 3.—*Hog record for 1904.*

	Dr.	Cr.
d January 1, 1904:		
pigs, and shoats, average weight 75 pounds, at 5 cents	$247.50	
	25.00	
ought in August, at $20	40.00	
ought in September	40.00	
ought in October, at $20	40.00	
	392.50	
or the year	539.60	
hogs sold		$559.86
over for 1905		502.50
	932.10	1,062.36
ofit		130.26

TABLE 4.—*Summary of receipts and expenditures for 1904.*

Crop.	Area, in acres.	Dr.	Cr.	Net profits.
Alfalfa (pasture)	7	$63.00	[a] $86.52	
Alfalfa (meadow)	10	76.30	249.60	
Corn	24	175.68	272.64	
Cowpeas		58.08		
Melilotus	10	38.00	178.40	
Sorghum	2	21.34	32.00	
Cotton	10	138.70	263.10	
		571.10	1,082.26	
ofit from crops on 63 acres				$511.16
Hog record.				
d January 1, and expenses		932.10		
d December 31, and sales			1,062.36	
ofit from hogs				130.26
net profit for year				641.42
ofit per acre (including Bermuda pasture)				8.44

[a] In addition to pasture.

OPERATIONS FOR 1905.

beginning of the year 1905 several changes were made in the nent of the fields. (See fig. 4.) While it was still impossible nto full operation the rotation decided upon, the arrange- the fields was more in conformity with the original plans. rations this year were confined to the 52 acres (exclusive ermuda pasture), but as there were some thin, galled por- this in melilotus (fig. 4, *a*, *a*,), which was used only as a soil or, the total area devoted to crops was only 50½ acres, of acres were in alfalfa pasture, 10 acres in alfalfa meadow, 22 corn and peas, 3½ acres in sorghum, and 8 acres in cowpeas.

ALFALFA.

The alfalfa in the 7-acre field, *A*, was again utilized for pasture. On March 28, 115 head of hogs were turned on this field, and on August 2, 8 more animals were added. The pasturing was continued until about the 1st of October.

In the meantime it was found necessary to mow a portion of the alfalfa at two different times, for, as in the previous year, the number of animals was not sufficient to keep the crop grazed down. The entrance to the pasture being at the northwest corner of the field the hogs kept that portion grazed much closer than the rest, and it only required one mowing. The east half of the field was mowed May 12, and yielded at the rate of 2,066 pounds of hay to the acre for the area that was cut over. The second cutting was made on June 20, and a yield of 1,035 pounds to the acre was secured. The west half of the field was cut June 12, the yield being only about 143 pounds to the acre.

In straightening out the lines between the different fields, portions of what were included in *C* and *D* in 1904 were added to *B*. These areas were plowed up and seeded to alfalfa in March, 1905. On the area *B''*, fig. 4, a fine stand was secured, but for some reason it made but little growth during the season. This may have resulted from the fact that the land was broken deeply with a disk plow and had not settled and become firm before the alfalfa was sown. The area *B'* was too wet for alfalfa, and as the land was badly infested with Johnson grass the young seeding was practically all killed out.

Five cuttings in field *B* were secured during the season from the seeding of the previous year, the first and second being much heavier than the other three. The total yield of hay for the year was 4.7 tons to the acre.

WINTER BARLEY.

After the corn stover had been removed from fields *A'* and *C* in 1904 the land was broken to an average depth of 8 inches with a disk plow and was sown to winter barley in November. The plan was to utilize this crop as a winter pasture for the hogs. Owing to the lateness of sowing and the very dry weather which prevailed during November and December, the crop never made a satisfactory growth and was of little or no use as a pasture. Could it have been sown a month or so earlier there is no doubt that a large amount of grazing would have been secured, as it made a very rapid growth in the spring after the weather moderated. In March this barley was plowed under with a two-horse turn plow and the land prepared for corn.

CORN.

The method followed in preparing the land for corn differed materially from that of the previous year. This year the land in field *D* was thoroughly broken with a disk plow to an average depth of 8 inches, that in fields *A′* and *C* having been thus broken in preparation for the barley. The hillside ditches (fig. 2) were all plowed and harrowed down until little evidence of them remained. After breaking, the land was thoroughly harrowed with a smoothing harrow. Instead of running the rows with the contour of the land, as is the usual practice in this section, the fields were marked off in rows 3 feet apart each way and the corn planted in the check. The dates of planting ranged from April 3 to 11, the variety planted being Tennessee Red Cob. Cutworms greatly damaged the stand in field *A′*, making several replantings necessary, and completely ruined that in field *C*, so that the latter field had to be disked, harrowed, and replanted on May 30 and 31. These pests gave no trouble except on the land where the barley was plowed under. Owing to the lateness of this second planting in field *C* a large early-maturing variety of corn known as Mexican June was used.

Four cultivations were given. The first was with a weeder, the second and third with 12-inch sweeps, and the last with double sweeps. The latter implement consists of a double stock to which are attached two sweeps, one 10 and the other 14 inches in width. This is a great improvement over the old-fashioned wide sweep in that it is easier to handle and leaves the ground nearly level.

On the poorer portions of fields *A′* and *D′* nitrate of soda at the rate of 80 pounds to the acre was applied at the side of the row about the middle of May. The first week in June cotton-seed meal at the rate of 100 pounds to the acre was applied in a similar manner to the entire crop on these fields. Field *C* received an application of 200 pounds of cotton-seed meal to the acre the first week in July.

The corn was harvested in the same manner as was the 1904 crop. The yields of corn (all preceded by cowpeas or melilotus) for the different fields were as follows: *A′*, 112 bushels, or 24.89 bushels to the acre; *C*, 137 bushels, or 19.42 bushels to the acre; and *D′*, 331 bushels, or 31.52 bushels to the acre. The uneven stand in field *A′*, resulting from the frequent replantings, and the fact that the Mexican June variety proved to be a comparatively light producer account for the relatively low yield from fields *A′* and *C*.

COWPEAS.

The latter part of June field *D* was thoroughly pulverized with a disk harrow, and it was sown to cowpeas on July 5, 1¾ bushels of seed being used to the acre. Four acres of these cowpeas were for hay August 23, and a yield of 4.49 tons was secured. The remainder of the peas was grazed off by hogs and plowed under for fertilizer.

SORGHUM.

Field *E* was somewhat enlarged in 1905 and again sown to Early Amber sorghum. The method of preparing the land for planting, the cultivation, and the harvesting were the same as practiced in 1904. The yield was rather light, being only 13.12 tons of green forage for the entire field, or 3.76 tons to the acre. This light yield was undoubtedly the result of planting sorghum after sorghum, a practice which will be guarded against in the future.

RECEIPTS AND EXPENDITURES FOR 1905.

Tables 5, 6, 7, and 8 show the cost of production, receipts, and net profit for each crop grown in 1905, each field being considered separately.

TABLE 5.—*Cost per acre of producing and harvesting crops, 1905.*

Field.	Area, in acres.	Crop.	Cost of preparing land.	Cost of seed, planting, and replanting.	Cost of fertilizer and applying same.	Cost of cultivation and hoeing.	Cost of harvesting.	Total cost.
A	7	Alfalfa (pasture)		[a] $0.62			$0.41	$1.03
B	10	Alfalfa (meadow)		[a] .59			3.90	4.49
A′ and C	11½	Winter barley	$1.48	1.29				2.77
A′	4½	Corn	3.52	1.75	$3.73	$1.50	2.71	13.21
A′	4½	Cowpeas		[b] .11				.11
C	7	June corn	1.78	.82	2.41	1.45	2.04	8.47
C	7	Cowpeas		1.25				1.25
D′	10½	Corn	2.21	.70	3.85	1.33	3.08	11.17
D′	10½	Cowpeas		.11				.11
D	8	do	1.12	.24			.48	1.84
E	3½	Sorghum	2.21	1.26		1.12	3.39	7.98

[a] Cost of resowing thin spots. [b] Cost of labor in sowing seed.

TABLE 6.—*Crop yield, cost, and returns per acre, 1905.*

Field.	Area, in acres.	Crop.	Yield.	Price.	Gross returns.	Cost.	Net returns.
A	7	Alfalfa (pasture)	0.813 ton	$12.00 ton	$9.75	$1.03	[a] $8.72
B	10	Alfalfa (meadow)	4.697 tons	12.00 ton	56.36	4.49	51.87
A′ and C	11½	Winter barley				2.77	
A′	4½	Corn	24.89 bu. grain 1 ton stover	.50 bu 2.00 ton	12.45 2.00	13.21	1.24
A′	4½	Cowpeas				.11	
C	7	June corn	19.58 bu	.50 bu	9.79	8.47	1.32
C	7	Cowpeas				1.25	
D′	10½	Corn	31.52 bu. grain 1 ton stover	.50 bu 2.00 ton	15.76 2.00	11.17	6.59
D′	10½	Cowpeas				.11	
D	8	do.[b]	.56 ton	12.00 ton	6.72	1.84	4.88
E	3½	Sorghum	3.74 tons	2.00 ton	7.48	7.98	[c] .50

[a] In addition to pasture.
[b] Only 4 acres cut for hay, the remainder being pastured and plowed under.
[c] Loss.

TABLE 7.—*Hog record for 1905.*

	Dr.	Cr.
s on hand January 1, 1905:		
1 boar	$25.00	
9 sows, at $25	225.00	
5 gilts, at $10	50.00	
1 shoats and pigs, average weight 50 pounds, at 5 cents	202.50	
1 sow bought in February	133.00	
1 sow bought in November	40.00	
1 sow bought in November	20.00	
99	695.50	
t of feed for the year	551.44	
eipts for hogs sold		$772.78
hogs kept over for 1906		690.50
Total	1,246.94	1,463.28
Net profit		216.34

TABLE 8.—*Summary of receipts and expenditures for 1905.*

Field.	Crops.	Area in acres.	Dr.	Cr.	Net profits.
	Alfalfa (pasture)	7	$7.21	[a] $68.32	
	Alfalfa (meadow)	10	44.90	561.60	
nd C	Winter barley [b]	11½	31.86		
	Corn	4½	59.44	65.02	
	Cowpeas (pastured)		.50		
	June corn	7	59.29	68.32	
	Cowpeas (pastured)		8.75		
	Corn	10½	117.28	186.48	
	Cowpeas (pastured)		1.15		
	Cowpeas (hay and pasture)	8	14.72	53.76	
	Sorghum	3½	27.93	26.18	
			373.03	1,029.68	
Net profit from crops on 50½ acres					$656.65
Hog record.					
s on hand January 1, and expenses			1,246.94		
s on hand December 31, and sales				1,463.28	
Net profit from hogs					216.34
Total net profit for year					872.99
Net profit per acre (including Bermuda pasture)					13.75

[a] In addition to pasture.

[b] Winter barley was followed by corn same year.

OPERATIONS FOR 1906.

n 1906 it was possible for the first time to divide the farm into manent fields and get the regular rotation of alfalfa, corn, and peas rted. Fields *A*, *B*, *C*, and *D*, figure 3, will now be devoted to this ation until each field has been in alfalfa for two years. The cropg system will then be changed in order to leave the alfalfa for a ger period before breaking it up. The acreage of the crops this r was alfalfa pasture, 10 acres; alfalfa meadow, 10 acres; corn d peas, 24½ acres; sorghum, 4½ acres; and peanuts, 3 acres.

CORN.

Figure 3 shows the arrangement of the fields for 1906. Fields *A* and *D* were planted in corn. Part of field *A* was in corn and peas in 1905, while the rest had been in alfalfa pasture two years. That portion of field *A* which had been in alfalfa pasture for two years was broken with a disk plow to an average depth of 8 inches in November, 1905. The continued pasturing had packed the ground so that it was very hard in places and exceedingly difficult to break; consequently, portions of the field were not plowed satisfactorily. Early in April the land was rebroken to a depth of 5 inches with two-horse turn plows and harrowed twice with a smoothing harrow. The remainder of field *A* and all of field *D* were broken with a disk plow.

The corn was planted April 12 to 18 with a check-row planter. The rows were 4 feet apart each way, and from 3 to 4 grains were dropped to the hill. Tennessee Red Cob was the variety planted. The corn was thinned to two stalks in the hill. The stand in field *A* was quite badly injured by cutworms, which made several replantings necessary. This, together with the extra breaking, greatly increased the cost of production.

The east end of field *A*, which was in corn in 1905, was given a dressing of about 4,225 pounds of stable manure to the acre previous to the breaking of the land. Early in June the whole of field *A* received an application of 75 pounds of nitrate of soda to the acre. Later, 125 pounds to the acre of a mixture of 400 pounds of acid phosphate, 25 pounds of kainit, and 100 pounds of cotton-seed meal were applied. Field *D* received a similar quantity of this mixture and 50 pounds of nitrate of soda to the acre.

In harvesting, the yields on the two different portions of field *A* were kept separate in order to note the fertilizing effect of the alfalfa on the crop. The east portion of the field, which had been in corn and peas the year previous and had received a good application of stable manure this year, made a yield of 32$\frac{9}{10}$ bushels to the acre. The rest of the field, which had been in alfalfa for two years, made a yield of 45 bushels to the acre—a fraction over 12 bushels per acre in favor of the alfalfa land. Field *D* yielded at the rate of 33$\frac{7}{10}$ bushels to the acre.

ALFALFA.

Field *B*, which had been in alfalfa meadow for two years, was utilized for hog pasture in 1906. Ninety-three head of hogs were pastured on the field from March 30 until November 4. The west end of the field was cut for hay twice during the season and the east end three times. The yield from these cuttings was 24,285 pounds, — 1⅛ tons per acre.

Field *C* was sown to alfalfa this year. The land was broken eeply with a disk plow in November, turning under the corn stubble and cowpeas that had been grazed off, and then put in fine condition with a smoothing harrow early in February. Previous to the breakng of the land, stable manure at the rate of 7 tons to the acre was applied on the poorer parts of the field. The seed was sown broadcast at the rate of 20 pounds to the acre the 1st of March and lightly covered with a smoothing harrow. A perfect stand was secured. Three cuttings were made during the season. The total yield of cured hay secured was 43,750 pounds, or 2¼ tons to the acre.

SORGHUM.

Field *E′*, figure 3, formerly a part of field *D*, which was in melilotus and cowpeas in 1905, was this year planted to sorghum. The land was prepared as for corn the latter part of January. The seed was drilled in rows 3 feet apart May 9, 1 peck of Amber cane seed to the acre being used. Thorough cultivation with double sweeps was given. The feeding of the green sorghum to the hogs began July 7 and continued until September 19. The total yield of green forage was a little less than 34 tons, or more than 7½ tons to the acre.

PEANUTS.

Peanuts were planted on field *E*. The land was broken with a disk plow the latter part of March and thoroughly harrowed with both disk and smoothing harrows. Planting was done May 10 to 14, 1½ bushels of nuts in hulls being used to the acre. The rows were 3 feet apart. The stand secured was poor, and the crop does not seem to do well on the type of soil in this field (Houston black clay). As the hogs were allowed to do the harvesting, none of the nuts were saved; consequently, no record of the yield was obtained.

RECEIPTS AND EXPENDITURES FOR 1906.

Tables 9, 10, 11, and 12 show the cost of production, receipts, and net profit for each crop grown in 1906, each field being considered separately.

TABLE 9.—*Cost per acre of producing and harvesting crops, 1906.*

Field.	Area, in acres.	Crop.	Cost of preparing land.	Cost of seed, planting, and replanting.	Cost of fertilizers and applying same.	Cost of cultivation and hoeing.	Cost of harvesting.	Total cost.
A	12	Corn	$4.63	$1.34	$3.48	$1.16	$0.97	$11.58
A	12	Cowpeas		2.91				2.91
B	10	Alfalfa (pasture)					1.29	1.29
	10	Alfalfa	2.40	4.68	2.57		1.58	11.23
	12½	Corn	1.79	.51	2.54	2.03	.63	7.50
	12½	Cowpeas		2.68				2.68
	4½	Sorghum	3.53	.52		.92	2.80	7.77
	3	Peanuts	1.25	3.00		5.06		9.31

TABLE 10.—*Crop yield, cost, and returns per acre, 1906.*

Field.	Area, in acres.	Crop.	Yield.	Price.	Gross returns.	Cost.	Net returns.
A	12	Corn	39.67 bu	$0.50 bu	$19.83	$11.58	$8.25
A	12	Cowpeas				2.91	
B	10	Alfalfa (pasture)	1.214 tons	12.00 ton	14.57	1.29	a 13.28
C	10	Alfalfa (meadow)	2.187 tons	12.00 ton	26.24	11.23	b 15.01
D	12½	Corn	33.72 bu	.50 bu	16.86	7.51	9.35
D	12½	Cowpeas				2.68	
E	4½	Sorghum	7.55 tons	2.00 ton	15.10	7.77	7.33
E′	3	Peanuts				9.31	

a In addition to pasture. b Seeded in March, 1906.

TABLE 11.—*Hog record for 1906.*

	Dr.	Cr.
Hogs on hand January 1, 1906:		
1 boar	$25.00	
1 sow (pure-bred Berkshire)	133.00	
9 sows, at $25	225.00	
5 sows, at $15	75.00	
93 shoats and pigs, average weight 50 pounds, at 5 cents	232.50	
109	690.50	
Cost of feed for the year (estimated)	954.85	
96 hogs kept over for 1907		$777.25
Receipts for hogs sold		1,239.50
Total	1,645.35	2,016.75
Net profit		371.40

TABLE 12.—*Summary of receipts and expenditures for 1906.*

Field.	Crop.	Area, in acres.	Dr.	Cr.	Net profits.
A	Corn	12	$138.96	$237.96	
	Cowpeas (pastured)		34.92		
B	Alfalfa (pasture)	10	12.90	a 145.70	
C	Alfalfa (meadow)	10	112.30	b 262.40	
D	Corn	12½	93.87	210.75	
	Cowpeas (pastured)		33.50		
E	Sorghum	4½	34.96	67.95	
E′	Peanuts	3	27.93		
			489.34	924.76	
Net profit from crops on 52 acres					$435.42
Hog record.					
Hogs on hand January 1, and expenses			1,645.35		
Hogs on hand December 31, and sales				2,016.75	
Net profit from hogs					371.40
Total net profits for year					806.82
Net profit per acre (including Bermuda pasture)					12.41

a In addition to value of pasture. b Seeded in March, 1906.

FUTURE PLANS.

As previously mentioned, the present rotation will be run only til a crop of alfalfa has been plowed under on each field. After ıt a cropping system will be planned which will allow the alfalfa remain three or four years before it is broken up. This will probly necessitate bringing field *E* into the regular rotation and taking an additional field for growing sorghum, etc. A five-year rotan of alfalfa, corn, and cowpeas can then be adopted. The alfalfa ı be left on the field three years, two years for meadow and one ır for pasture. It will then be broken up and put in corn and wpeas for two years.

One of the greatest drawbacks to the present system is the lack of abundance of pasturage from the middle of December to the ddle of March. Plenty of grazing at this time of the year would atly lessen the quantity of grain required for wintering the anils that are kept over, and this would correspondingly reduce the t of pork production. To meet this demand for winter grazing an litional area of 10 acres was added to the farm in the fall of 1906. is was very poor worn-out land which had not been cropped for eral years. It will be used almost exclusively for growing annual ture crops. Rye was sown on this field in September. This will be d for pasture until spring, then plowed under, and the land planted cowpeas and peanuts. Part of the cowpeas will be harvested for d, and the remainder, together with the peanuts, will be grazed by the hogs. Vetch was sown with the rye on 1 acre of this d. If this crop succeeds it will be sown with the rye in the ire field in the autumn. This plan of cropping will be continued il the land becomes sufficiently fertile to grow a greater variety of ps.

CONCLUSION.

The results of the three years' work indicate quite clearly that this thod of diversified farming can be made profitable throughout the ıthern States in regions where alfalfa can be grown successfully.

The average net profit per acre for the three years is $11.37. This or the whole farm, including the Bermuda pasture, which was used y little. This, however, does not allow for any rent of land. If an acre were deducted for rental, the profit would be cut to $8.37 acre. While this might seem rather low on land valued at $150 $200 an acre, still it is over 41 per cent on the $20 an acre valuaı placed on the land described. It must also be remembered that ing these three years more attention was given to increasing the ility of the land and getting it in a good state of cultivation than ecuring large yields. The work of increasing the depth to which the land is broken, plowing down the hillside ditches, etc., added materially to the cost of production and correspondingly reduced the profits. For example, alfalfa has been used in a short rotation, which allows it to stand only two years. While this suits the purpose so far as soil improvement is concerned, it does not show to best advantage the possibilities of alfalfa as a profitable hay crop. The returns from field *B* in 1905, when a net profit of over $51 per acre was realized from this field, give some idea of what may be expected when the production of alfalfa hay becomes one of the features of the farm. This was only the second year for the alfalfa on that field, and it would no doubt have given even better returns the third and fourth years.

In connection with the alfalfa work, it has developed that the brown and reddish brown soils are not nearly so well adapted to this crop as the black and gray soils. As a rule, no trouble is experienced in getting a stand on the latter soils, while it is frequently very difficult to secure a perfect stand on the former. This is due in part to the fact that crab-grass is persistent on the brown and reddish brown soils.

It is to be regretted that weights could not have been taken to show the actual gains made by the hogs while on the alfalfa pasture. While they throve and made good gains on this pasture, there are no data to determine its actual value as a meat producer. The results for 1906, however, show that a well-set alfalfa field the second year from sowing will furnish pasture for 12 to 15 head of hogs to the acre for six months—say, from the 1st of April to the 1st of October—and at the same time produce 1½ tons of hay to the acre. Of course, if no hay were cut a few more animals might be grazed, but as the mowing improves the pasture this plan is to be preferred to pasturing enough hogs to keep the alfalfa grazed close all the time.

One of the most interesting things brought out in the records of the corn production is the difference in the cost of cultivation and hoeing under the different methods practiced. The first year, when the rows were laid out with the contour of the land and cultivated only one way, the cost of cultivation averaged $1.38 per acre and the cost of hoeing 70 cents per acre. In 1905 and 1906, when the corn was check-rowed and cultivated both ways, the average cost of cultivation and hoeing was reduced to $1.10 and 21 cents, respectively, a saving of 20 per cent in the cost of cultivation and 70 per cent in the cost of hoeing. Practically all the hoeing necessary under the eck-row method was where the old hillside ditches had been. re the Johnson grass had gained a foothold and gave considerle trouble.

O

Issued December

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 311.

SAND-CLAY AND BURNT-CLAY RO

BY

WILLIAM L. SPOON,

Road Expert, Office of Public Roads.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

LETTER OF TRANSMITTAL.

U. S. DEPARTMENT OF AGRICULTURE,
OFFICE OF PUBLIC ROADS,
Washington, D. C., September 27, 1907.

SIR: I have the honor to transmit for your approval a manuscript containing the results of investigations made by this Office on the mixture of sand and clay for the improvement of roads, and upon the utilization of clay for road construction by burning. Most of the material contained therein has already been published in Bulletin No. 27 of this Office, but the great increase in the demand for reliable information upon the construction of sand-clay and burnt-clay roads makes the publication of a bulletin for wide distribution advisable. I respectfully recommend, therefore, that this manuscript be published as a Farmers' Bulletin.

Respectfully,

LOGAN WALLER PAGE,
Director.

HON. JAMES WILSON,
Secretary of Agriculture.

SAND-CLAY AND BURNT-CLAY ROADS.

INTRODUCTION.

Natural sand-clay roads may frequently be found in localities where the soil contains the right proportions of sand and clay. In sections of the country where the prevailing subsoil is composed entirely of clay, or, on the other hand, is of an extremely sandy character, these materials may be properly mixed so as to overcome as far as possible the objectionable features of each. The mixing of sand and clay as a form of road construction has received careful study and is of great importance, especially to the Atlantic and Gulf States, where throughout large areas sand and clay are practically the only materials available for road building.

One of the objects of this bulletin is to give some account of the commonly observed physical characteristics of clays and sands as an aid to the use of these materials for constructing roads. It must be remembered, however, that the great variation in the physical properties of clay makes it difficult to give definite rules, which shall be general in their nature, for the mixing and application of this material.

It may safely be said that the construction of sand-clay roads in the Southern States has passed the experimental stage. It has been proved that they are well adapted for light traffic, and are less noisy, less dusty, and more resilient than the average macadam road. Even under heavy traffic they have proved to a great extent satisfactory. There are sand-clay roads in the South Atlantic and Gulf States over which heavy loads of cotton and other farm products are hauled throughout the year, with but little resulting damage. When the cheapness of this kind of construction is considered, it will be seen that for certain localities, at least, it is preferable to macadam. In all cases a mixture of sand and clay is better than either material alone, except perhaps where it is impossible to drain a sandy road, and, in consequence, it is always wet. Very little, if any, clay should be used in this case, for the water acts as a binder and the sand remains firm.

In some sections of the country the only available material from which roads can be constructed is clay. To meet this condition the Office of Public Roads has made experiments in the so-called "gumbo" district of the lower Mississippi Valley, in burning the clay along the entire length of the road. By burning clay, even at a moderate heat, its well-known sticky or plastic quality is destroyed, so that even in the wettest weather it will bear traffic. If the clay is fired along the entire length of the road, the cost of hauling it is avoided, and at the same time the advantage is gained of burning the foundation of the road as well as the material to be placed upon it.

PHYSICAL PROPERTIES OF SAND AND OF CLAY.

The mineral known as quartz, which is composed of silica, is found abundantly in all parts of the earth. When consolidated by heat and pressure into great masses of rock it is known as quartzite, and it also appears as an important constituent of many different kinds of rock. When quartzite is disintegrated by the action of the elements and is found in great loose masses, composed of fine and more or less uniform grains, it is known as sand. It is a well-recognized fact that sand lacks binding power, and on drying out is of a loose and unstable nature.

Clay, on the other hand, is formed by the decomposition of other minerals which go to make up the structure of rocks. The origin of all clay is the mineral feldspar, which, under the action of water, has been gradually leached out and changed into clay. The particles of clay are usually much finer than those of sand and are frequently carried by running water some distance from the point at which they were originally formed, where, having settled as a sediment on the bottom, they form deposits which are known as sedimentary clays. In some cases where huge deposits of feldspathic rock have been disintegrated and changed by the action of water in place, the deposits are known as residual clays.

It will be seen from this that clays must vary both in texture and composition. Some will be found to contain as much as 75 per cent of sand, while others are extremely fine in texture and entirely without grit. As would be expected, the sedimentary clays are usually finer and more sticky and plastic than the so-called residual clays.

The two properties of clays which are of the greatest importance from the standpoint of road building are, first, plasticity, and, second, the property of slaking when they first become wet after having been uncovered. A clay is called plastic which becomes sticky or dough-like when mixed with a certain amount of water, so that it can be molded or pressed into various shapes which it will retain even after it has been dried. The most plastic of these materials are known technically as "ball clays." If a lump of such a clay as this is immersed in water it will usually preserve its form for a long time.

There are other clays, however, which will immediately fall to pieces, as a lump of quicklime will do under similar conditions. This is known to be due to the very rapid absorption of water into the porous structure of the clay. It will easily be seen that this characteristic is an important one from the standpoint of the road builder, for any sort of agitation will cause a large percentage of a slaking clay to pass into suspension in water and form a thick mud. Non-slaking clays, although they are very sticky when wet, do not so readily mix with water. It stands to reason that the slaking clays are usually " deep seated," that is to say, they will be found below the surface of the ground. Slaking clays are more easily mixed with other materials than the more plastic ball clays, and this is, of course, to their advantage for road building. On the other hand, they are often of inferior binding power.

There is still another physical characteristic of clay that is of great importance from the standpoint of road building. Some clays shrink when dried, which leads to the cracking and breaking up of their surfaces. This shrinkage is the measure of their expansion, and expansion renders the sand-clay composition unstable. Shrinkage would do no harm if the clay would stay in this condition, but this it does not do. When water, removed by evaporation, is restored to the sand-clay mixture, its entrance is accompanied by a simultaneous expansion which causes the grains of sand to be separated. This property can not be overcome, for it is inherent in the clay, but we can in some measure modify its effect by using less clay in the composition. This, however, will weaken the road and dispose it to break up in dry weather.

Before attempting to construct a sand-clay road it is best to test the material in the neighborhood in order to secure a clay having the least possible shrinkage. There is no better way than to examine the traveled roadways. In almost every community there are short sections of natural sand-clay road which may be examined.

THE MIXING OF SAND AND CLAY.

The best sand-clay road is one in which the wearing surface is composed of grains of sand in contact in such a way that the voids or angular spaces between the grains are entirely filled with clay, which acts as a binder. Any excess of clay above the amount necessary to fill the voids in the sand is detrimental. If a small section taken from the surface of any well-constructed sand-clay road is examined with a magnifying glass, the condition of contact which exists between the grains of sand and the small proportion of clay which is required to fill the voids may be seen. Wherever this proper condition of contact exists for a few inches in thickness upon the surface of a road, it will bear comparatively heavy traffic for a long time, even when the subsoil is sand or clay. The proper mixture or saturation point of clay and sand can easily be seen by referring to figure 1.

All the experiments that have been made by this Office indicate that the materials should not be mixed in a dry state, but that they should be thoroughly mixed and puddled with water. It makes little difference by what method the stirring or mixing is done, so long as it is thorough and proper proportions of the materials are obtained. If an excess of clay is used in the mixture, as shown in figure 2, the grains of sand which are not in contact are free to move among and upon each other, so that no particle exerts more resistance to pressure than if the entire mass consisted of clay alone. On the other hand, if an insufficient amount of clay is used, the mixture will lack binding power and will soon disintegrate.



FIG. 1.—Clay mixed with sand to the point of saturation, with the angular sand grains in contact.

We may now outline the methods which have been used to obtain the proper contact mixture, although it will be necessary to discuss separately the methods of treating slaking and non-slaking varieties of clay. It will readily be seen that it is less economical to haul sticky or plastic clay and spread it upon sand than it is to haul sand and spread it upon clay. The clay is difficult to dig and handle and usually comes out in lumps, which, if placed upon the roadbed and covered with sand, are apt to remain unbroken unless great care is taken in the mixing. The bad effects of lumps of clay in a sandy subsoil and the effects of traffic on such a mixture are illustrated in figures 3 and 4.



FIG. 2.—Sand-clay mixture with an insufficient amount of sand, the grains not being in contact.

Figure 3 shows a cross section of a road into which lumps of clay have been worked. Figure 4 shows the displacement of these lumps when subjected to the prolonged action of traffic, and the resulting formation of deep ruts and general disintegration of the surface.

It has been pointed out that thorough stirring and puddling are absolutely essential to successful sand-clay construction. This is most easily brought about immediately after a hard or prolonged rain, the clay having been previously spread and the larger lumps broken up as completely as possible. The surface should then be covered with a few inches of sand and plowed and harrowed thoroughly by means of a turning plow and a cutaway or disk harrow. This stage of the work will of course be found somewhat disagreeable, leading, as it does, to the formation of a thick, pasty mud; but it is the only practicable way in which the necessary mixing can be accomplished. Many experiments have been tried with dry mixing of the clay and sand, but all have been more or less unsuccessful. In cases where the plowing and harrowing are considered too expensive the mixing may be left to traffic. This, however, inevitably leads to a muddy road surface for a long time, although finally it is possible, by a proper distribution of the sand upon the clay, to bring about a fairly good result, even by this simple method.



FIG. 3.—Cross section of road, showing lumps of clay placed on a sand subsoil and covered with sand.

In case a slaking clay is used, very much less puddling is required, as there are practically no lumps to be broken up and the mixing can easily be done with a harrow after a rain. Slaking clays do not usually make as effective binders as the more plastic clays; therefore in dry weather the road surface becomes more dusty. It will be seen that the best clay for this kind of construction is one which slakes sufficiently easily to enable the lumps to be readily broken up, and which at the same time, without being too plastic, has sufficient binding power to cement the grains of sand and form a smooth, impervious surface on the road. Clays of this nature which have given excellent results are found in abundance in many of the Southern States and doubtless exist elsewhere. Their color is usually red or mottled red and white. Occasionally clays are found sufficiently sandy to be suitable for use without further mixing. When this is the case it is only necessary to spread the material on the road and allow it to pack under traffic. It s obvious that it is necessary to pay careful attention to the physical



FIG. 4.—Cross section of road, showing displacement of lumps of clay when subjected to travel.

properties of the available clay in the neighborhood of the road, as it will frequently be found economical to haul good material for some distance rather than to use an inferior material which is close at hand. The qualities to be considered, as has been pointed out, are the greatest binding power obtainable, together with the least amount of labor necessary for disintegrating and mixing.

APPROXIMATE METHOD FOR ESTIMATING THE PROPER PROPORTIONS OF SAND AND CLAY.

It has already been shown that the best mixture for sand-clay construction is one in which there is just enough clay to fill the voids in the sand, thus producing the proper cementing bond in the road surface. No exact rules can be laid down for calculating in advance the best mixture. It must be remembered that the relation of weight and volume will vary widely in different clays, according to the amount of water which they contain. Some clays, especially the more plastic varieties, even after they are as thoroughly dried as they can be by the hottest summer sun, will still hold as much as 20 per cent of water. This water is known to chemists as " water of combination," because it seems to be either combined with or held in the structure of the clay particles in such a way that it can only be driven out at a high temperature. It is apparent from this that in handling a clay of this kind, even when it seems quite dry, each ton will contain 400 pounds of water which does not enter into the consideration of volume. The amount of clay necessary to fill the voids in any given sand will therefore be found to vary.

An easy method for making a rough or approximate estimate of the volume of the clay filler required for any unit quantity of a given sand is as follows: Two ordinary glass tumblers of the same size are filled to the brim, one with the dry sand to be tested and the other with water. The water is then poured carefully from the one glass into the sand in the other until it reaches the point of overflowing. The volume of water removed from the glass which was originally full of water can be taken as an approximate measure of the voids in the unit volume of sand contained in the tumbler. A simple calculation will reduce this to percentage volume.

Practical experience has shown that the tendency is to calculate too little rather than too much sand for given amounts of clay, and almost variably a second and even a third application of sand is necessary and above the calculated amount. It often happens that clay work up to the surface under the action of traffic, in which case xtra top dressing of sand should be added when required.

METHODS OF CONSTRUCTING A SAND-CLAY ROAD.

In passing to a detailed description of methods of construction, it must first be stated that there are two distinct conditions which are likely to be met. In the first case the road may have a sandy subsoil, ordinarily spoken of as "deep" sand, the objectionable features of which must be overcome by the addition of clay. On the other hand, the subsoil may be of clay, and in this case sand must be added to it. Since there is a radical difference in the methods of construction in these two cases, each will be treated separately.

DRAINAGE.

In all forms of road construction the most important consideration is that of drainage. If natural drainage does not exist, artificial methods must be used. The best natural drainage is usually found upon a loose gravel or a sandy soil, especially when the grade of the road is somewhat above the surrounding country. If the land is dry and the sand deep enough to absorb quickly even the heaviest rains, no special attention need be given to drainage other than to provide the proper crown to the surface of the finished road to divert the water from it. Frequently, in tide-water regions, the country is so low and level that the surface of the road is likely to be kept continually wet from seepage. If this condition has to be met, it is necessary to dig wide ditches on each side of the roadbed and raise the grade so that the crown of the road will be sufficiently high to shed water thoroughly before hauling any clay upon it.



FIG. 5.—Cross section of road, showing clay cover on "deep" sand subsoil.

It is very important that no stumps or branches of trees or other matter subject to decay should be overlooked and left in the roadbed, as at such points weak places are sure to be developed in the course of time. Although natural drainage is much better on sandy subsoils than on clay, in clay districts the conformation of the country is more likely to be of an undulating or rolling character, thus furnishing a natural watershed. Temporary or so-called "wet-weather" springs are not so likely to occur in sandy soils as in clay soils, and therefore need not be so carefully guarded against. Nevertheless, if any indications of these springs are found, precautions should be taken to conduct the water to the side ditches by some form of underdrainage.

SAND-CLAY CONSTRUCTION UPON A SANDY SUBSOIL.

When the drainage has been properly provided, the roadbed should be brought to a crown. It has been found more economical to crown first a section of the road nearest the source of the clay. The first load of clay is dumped on this prepared section at the point nearest the clay bed, each succeeding load thus being hauled over the preceding. Care should be taken to spread each separately and evenly as soon as it has been deposited and before it is driven over. The clay cover spread upon the subsoil is shown in figure 5.

After spreading the clay it should be covered with a layer of clean sand. When the road has been opened to traffic a sufficient amount of sand should be added from time to time to keep the surface smooth and prevent the formation of mud. Both the thickness and the width of the layer of clay to be spread are determined by the volume and character of traffic which the road is to sustain. If a narrow, single-track roadway is to be built, it has been found best to spread the clay to a width of about 12 feet and to a depth of 6 to 8 inches in the center, tapering the layer to a thin edge at the sides. In some cases it may be necessary to modify these directions to accord with the quality of the clay and the amount of sand which it contains. The "leaner" or more sandy the clay, the greater will be the amount required.

After the clay layer is completed and covered with sand, as already stated, if the clay is of a plastic and lumpy character it will probably be necessary to plow and harrow it alternately until the lumps are thoroughly disintegrated. Advantage should be taken of rains in order to puddle the road surface with a harrow. As long as the surface shows a tendency to "ball" and cake, more sand must be added until this trouble is overcome. If, on the other hand, the surface loosens in dry weather, it is due to an insufficient quantity of clay or else because the clay lacks binding power. It must be borne in mind that the construction of a sand-clay road is not a quick operation, but a process of rather slow development. In the course of the work there is time to determine what proportions of the two materials will finally lead to the best results.

If the materials are especially adapted to the purpose it is possible to construct very excellent sand-clay roads without the use of plow, harrow, or roller. The mixing can be left, after the materials have been properly spread, entirely to the action of traffic. In all construction, however, the best results are hastened by the use of plow and harrow. In all cases it is advisable to use a road machine or other similar implement to crown and smooth the surface, after which a light coat of sand may be added.

The quantity of clay required to build a mile of road will vary of course with the width and depth of the clay layer. A roadway 12 feet wide with an average depth of 6 inches of clay will require a cubic yard of clay to cover 4½ feet of road length; that is to say, each cubic yard of clay will make 1½ " running " yards of clay road. Since there are 1,760 yards to the mile, it will be seen that 1,173⅓ cubic yards of clay will be required for 1 mile of construction. From this data the cost may be readily calculated, when the rate of wages and distance of haul are known. The average load has been found to be about two-thirds to three-fourths of a cubic yard, when the hauling is done over sand, and about 1 cubic yard when the hauling is done over a dry clay road. It may be said after rough calculation that a 2-horse load of clay will cover 1 linear yard of 12-foot surface, making 1,760 loads to the mile. The cost of shoveling sand upon the clay is the same, whether the mixing is to be done with a plow and harrow or left to traffic, and should therefore in each case be added to the cost of hauling.

SAND-CLAY CONSTRUCTION UPON A CLAY SUBSOIL.

After proper drainage has been provided the roadbed should first be crowned as nearly as possible to the form desired in the finished road. The road surface should slope from the center to the sides at least one-half inch per foot. It should be noted that it is much more important to form this foundation crown first where the subsoil is of clay than it is with a sandy subsoil.

The foundation having been properly prepared, the surface should be plowed and harrowed to a depth of about 4 inches until it is pulverized as completely as possible. It is then covered with 6 to 8 inches of clean, angular sand. The sand should be spread so that the layer is thickest at the center of the road, following in general the same plan as was outlined for spreading clay upon a sandy foundation. The materials should then be mixed while they are in a comparatively dry state, contrary to the usual practice of doing the entire mixing and puddling when the materials are wet. It has been found that the clay foundation can be more evenly disintegrated when comparatively dry, and it is also a difficult matter to mix the sand evenly with the clay if the latter is soft and cut into ruts by travel. This preliminary mixing should be done if possible, but often conditions do not allow it and the sand has to be mixed on the wet clay road. After this first mixing has been finished the road is finally puddled with a harrow after a rain. In case an excess of clay works to the surface and tends to make the mixture sticky, sand should be applied until this trouble is overcome.

Upon the completion of the mixing and puddling, the road should be shaped while it is still soft enough to be properly finished with a scraper and at the same time stiff enough to pack well under the roller or under the action of traffic. In case it is impossible to obtain the proper consistency of the surface material, it is better to shape the road when somewhat too wet than when it is too dry, even if it is necessary to stop traffic upon it for a few days. The road should be opened to traffic as soon as practicable after completion, as this will be found to have a beneficial effect upon it.

After sand-clay roads are constructed, they should be cared for until the proper condition is established and the road is resistant to traffic. This care is extremely important and is deserving of special mention. No sand-clay road is in proper condition when first constructed, and this attention afterwards is as much a part of the road construction as the hauling of the first load of sand or clay.

COST OF SAND-CLAY CONSTRUCTION.

It is of course impossible to state definitely the cost of this form of construction, as it will be found to vary with the price of labor, the length of haul, the width of roadway, and depth and nature of material. If we assume, however, that the clay can be procured within a mile of the road which is to be improved, and that the cost of labor is about $1 per day and teams $3 per day, the cost of constructing a 12-foot sand-clay road on a sand foundation, covered with clay to an average depth of 6 inches, would be approximately as follows for a distance of 1 mile:

Crowning and shaping road with road machine, using 2 teams at $3 and 1 operator at $1.50 per day for 1 day	$7.50
Loosening 1,173⅓ cubic yards of clay with pick and shoveling into wagons, at 15 cents per cubic yard	176.00
Hauling 1,173⅓ cubic yards of clay, at 23 cents per cubic yard	269.86
Spreading clay with road machine, using 2 teams at $3 and expert operator at $1.50 per day for 3 days	22.50
Shoveling sand on clay, estimated at ½ cent per square yard	35.20
Plowing, using 1 team at $3 per day for 4 days	12.00
Harrowing, using 1 team at $3 per day for 2 days	6.00
Shaping and dressing with road machine, using 2 teams at $3 and expert operator at $1.50 per day for 2 days	15.00
Rolling, estimated at ½ cent per square yard	35.20
Total	579.26

The estimated cost per square yard of road surface, therefore, when computed on the basis of this table, would be about 8 cents, or at the rate of $579.26 per mile.

The cost of building a sand-clay road on a clay foundation would not vary much from the figures given. The latter form of construction would probably be slightly cheaper by reason of the fact that sand can be handled more economically than clay.

According to the experience of this Office, the cost of sand-clay construction in the South has been found to range from $200 to $1,200 per mile, in most cases running from $300 to $800. A sand-clay road constructed under the direction of the Office at Gainesville, Fla., 1 mile in length, 14 feet wide, and having a 9-inch sand-clay surface, cost $881.25 per mile, or 10 cents per square yard. Another sand-clay road built under the direction of the Office at Tallahassee, Fla., 16 feet wide and surfaced with about 7 inches of sand-clay mixture, cost $470 per mile, or about 5 cents per square yard. In case changes of grade have to be made with consequent cuts and fills, the cost would be proportionately greater than the figures given above. There can be no question, however, that under all circumstances this form of construction is cheaper than macadam.

THE USE OF SAND-CLAY ROADS IN THIS COUNTRY.

The possibilities of the sand-clay road may not be fully realized by the public for a long time to come, still the progress being made in this form of road building in nearly every part of the country is encouraging. Such benefits as have come to Richland County, S. C., Pike County, Ala., Dallas County, Ala., Cumberland County, N. C., and many other sections throughout the Atlantic and Gulf States from the use of sand-clay roads should be a sufficient incentive for a general study of the subject in those parts of the country where these materials exist in adequate quantities.

Sand and clay had always been abundant in Pike County, Ala., still a combination of the two for road purposes was not thought of until four years ago. At the present time there are nearly 120 miles of sand-clay road in this county, which for all practical purposes, are as useful as macadam roads, and which have cost about one-sixth of the amount standard macadam of the same or less width would cost in this section. With this system the remotest section of the county may be reached, which would not be the case had fewer and more expensive roads been attempted. At the present rate of improvement every important public road in this county will soon be a serviceable highway, over which a wagon loaded with six bales of cotton may be drawn easily and quickly, whereas, before the improvement began, only small loads were possible. It is important that success like this should be given wide publicity because it carries with it method as well as encouragement. The first thing done in this locality was to find out which of the clays accessible would make a good road. After this important matter had been decided, bonds were issued to raise money to buy equipment. This comprised eight outfits of fourteen to sixteen mules each, wagons, plows, scrapers, and hand tools.

The extent to which this form of road construction can be used in public road improvement throughout the country can hardly be overestimated. In making small repairs to roads, if, instead of filling mudholes with brush, a few loads of sand or gravel from sand bars and gravel beds found along the streams in hilly portions of the country were hauled to the road, permanent improvement would result.

It has been found that this kind of road is admirably suited to the northwestern part of the country as well as to the southern, and it is believed that it will be found worthy of more general study than it has ever received heretofore. Its study should be of interest to the public schools in the rural districts of the country. If school boys were encouraged to make a sand-clay walk to the schoolhouse, the teacher's task of keeping a clean school building would be sufficiently lessened to make up for the time taken to interest the boys. Besides this actual improvement, a lasting benefit would be given to that community from this simple study of a valuable process. For a large part of the country, the sand-clay road is the only road possible or within the reach of the rural districts. It requires less money to build than any other type of road except the earth road and less money to repair. It is simpler in its construction than any other except the earth road, and lasts longer with the same amount of repair.

THE CONSTRUCTION OF BURNT-CLAY ROADS.

In large areas in the South, particularly in the valleys of the Mississippi and its tributaries, sedimentary clays are found very generally. In these areas there is little or no sand, and the clays are of a particularly plastic and sticky variety. These sticky clays are locally known as "gumbo" and "buckshot." In such localities traffic is absolutely impossible during the wet season, as the wheels of heavy vehicles will sink to the hub. In order to overcome this difficulty the Office of Public Roads undertook an investigation of the matter. Special experiments were carried on in the laboratory to see what could be done in the way of burning or clinkering these clays so as not only to destroy their plastic qualities, but also, as far as possible, to form hard, brick-like lumps which should be capable of sustaining traffic. Samples of the material were sent from the Yazoo district in Mississippi to the laboratory, and the clinkering point of the clay was found to be sufficiently low to indicate that simple burning of the lumpy clays upon the road surface by means of open wood fires would accomplish the desired result. Following these laboratory experiments it was decided to make experiments on a road, and it can be stated that this experimental road is proving highly satisfactory.

Gumbo clay is black, owing to the high percentage of organic or vegetable matter it contains. It is particularly sticky in its nature, and is almost wholly free from sand and grit. After it has been burned, however, the plasticity is entirely destroyed, and a light clinker is formed which, though not particularly hard, when pulverized forms a smooth surface and seems to wear well. It should be understood that not all of the clay out of which the road is to be constructed is to be clinkered, but only a sufficient amount should be rendered nonplastic to neutralize the too sticky character of the native clay. Fortunately the gumbo district is plentifully covered with heavy timber, thus affording an abundance of fuel. Work should be done in a dry season of the year.

While the only experimental burnt-clay roads constructed by the Office are in Mississippi, the same methods might be applied with equally good results in the sections of the prairie States that have no other material available for road building and have sufficient timber for this purpose.

FUEL.

Good sound wood, as dry and well seasoned as it is possible to procure, should be provided before beginning the work, and stacked at convenient intervals along the side of the road. About 1 cord of wood has been found necessary for 8 linear feet of roadbed 12 feet wide. The wood may be cut to 4, 8, or 12-foot lengths. Brushwood, if it is dry, or chips, bark, old fence rails and discarded railroad ties, coal slack—in fact any sort of fuel that can be easily and economically obtained—may be used to advantage with the cord wood.

PREPARATION OF THE ROADBED.

After grading the road to an even width between ditches, it is plowed up as deeply as practicable. It will be found necessary to use four horses or mules, as the extremely heavy nature of the clay makes the work of deep plowing difficult. After the plowing has been completed, furrows are dug across the road from ditch to ditch, extending through and beyond the width to be burned. If it is intended to burn 12 feet of roadway, the transverse furrows should be 16 feet long, so as to extend 2 feet on each side beyond the width of the final roadway. Across the ridges formed between these furrows—which should be about 4 feet apart—the first course of cord wood is laid longitudinally so as to form a series of flues in which the firing is started.

The best and soundest cord wood is selected for this first course and should be laid so that the pieces will touch, thus forming a floor. Another layer of wood is thrown irregularly across this floor, in crib formation, with spaces left between in which the lumps of clay are piled. Care should be taken that the clay placed on this cribbed floor is in lumps coarse enough to allow a draft for easy combustion.

After the lumps of clay have been heaped upon this floor, a third course of wood is laid parallel to the first. This third course is laid in exactly the same manner as the first, and each opening and crack should be filled with brush, chips, bark, small sticks, or any other combustible material. The top layer of clay is placed over all a the finer portions of the material are heaped over the whole structure. A careful arrangement of this cord-wood cribbing to separate the clay is important, and the directions should be carefully followed.

The deep covering of clay which is thrown over all should be taken from the side ditches, and may be in lumps of all sizes, including the very finest material. It is spread as evenly as possible over the top in a layer of not less than 6 to 12 inches. Finally the whole is tamped and rounded off so that the heat will be held within the flues as long as possible. When coal slack is available the two top layers of wood may be omitted and the coal slack thoroughly mixed with the mass of clay.

It is necessary to get the fires well under way in the flues before the first layer of wood is burned through. The first action of the fire is to drive out the water contained in the clay before the actual burning and clinkering can begin. In burning the gumbo clays a great advantage is gained from the organic and vegetable matter which is contained in the clay, as that in itself aids combustion.

FIRING.

When the roadbed has been carefully prepared according to the foregoing directions, the firing should begin. In our practice 15 or 20 flues are prepared for firing in one section. If, however, a large force of laborers is available for the work, a greater number of flues can be fired at one time. It is always possible to divide the firing into sections by omitting the charge of wood in one transverse furrow, which may then be covered later and burned in the same way as the rest.

The best results are obtained by firing all the flues of a section simultaneously and maintaining the combustion as evenly as possible. A supply of light, dry, kindling wood, or any easily inflammable material, should be at hand to prevent the fire from dying down in any one place. The firing should invariably be begun on the windward side, in order to obtain the maximum draft. In case the combustion is too rapid in any flue it may be regulated by banking the mouth of the flue with clay.

If the burning is entirely successful, not only the portion of clay which forms the top of the kiln but the ridges between the flues will be burned thoroughly, so as to form a covering of burnt clay 10 to 12 inches in depth, which, when rolled down and compacted, forms a road surface of from 6 to 8 inches in thickness. If properly burned, the material should be entirely changed in character, and when it is wet it should have no tendency to form mud.

When the material is sufficiently cooled the roadbed should be brought to a high crown before rolling, in order to allow for the compacting of the material. This can best be done with a plow or a grader. After this the rolling should be begun and continued until the roadbed is smooth and hard. The finished crown should have a slope of at least one-half inch to the foot.

The main advantages of this method of burning a road over its entire length are, first, that the cost of transporting the clay is avoided; second, that the subgrade of the road is burned as well as the material above.

COST OF BURNT-CLAY CONSTRUCTION.

It is, of course, impossible to give the cost of a burnt-clay road which will apply to the same work in all sections of the country. Although this form of construction in the South up to the present time has been successful, it can not as yet be said to have passed the experimental stage. The items of cost of the experimental road 300 feet long, as constructed at Clarksdale, Miss., are as follows:

30½ cords of wood, at $1.30 per cord	$39.65
20 loads of bark, chips, etc	6.00
Labor, at $1.25 per day, and teams, at $3 per day	38.30
Total cost of 300 feet	83.95
Total cost per mile at this rate	1,478.40

In view of the success of the experiments so far made and the comparative cheapness of this form of construction, it is hoped that the localities which have no hard material available will continue the experiments with burnt clay. Although it can not be denied that the gumbo and buckshot clays of the South are particularly adapted for burning on account of the high percentage of organic matter which they contain, it is none the less probable that many of the surface clays and soils of the States farther north could be treated in the same way, and in fact any soil or clay which bricks or clinkers at a comparatively low temperature should be suitable for the work.

Since the experiment made by this Office at Clarksdale, Miss.,[a] numerous sections of burnt-clay road have been built in that locality, and up to the present time only favorable reports regarding them have been received. Experimental burnt-clay roads are now (1907) being constructed under the supervision of this Office at Indianola, Miss., and at Greenville, Miss., but since the work at these places is still incomplete no report upon it can be given.

---

[a] For reports concerning this road, see Annual Report, Office of Public Roads, 1905.

FARMERS' BULLETINS.

ng is a list, by number, of the Farmers' Bulletins available for distribution. entitled "Experiment Station Work" give in brief the results of experimed by the State experiment stations. Titles of other bulletins are ry. Bulletins in this list will be sent free to any address in the United lication to a Senator, Representative, or Delegate in Congress, or to the Agriculture, Washington, D. C. Numbers omitted have been discontinperseded by later bulletins.

g of Farm Animals. Pp. 40.
a and Swine Plague. Pp. 16.
ulture and Uses. Pp. 24.
d and Fiber. Pp. 16.
d How to Kill Them. Pp. 30.
l Other Changes in Milk. Pp. 22.
ases on the Pacific Coast. Pp. 15.
lage. Pp. 30.
ing for Market. Pp. 24.
position and Cooking. Pp. 31.
ure. Pp. 24.
l and Its Products. Pp. 16.
re. Pp. 30.
t Milk. Pp. 32.
Fertilizers. Pp. 38.
n Humid Climates. Pp. 27.
cting the Cotton Plant. Pp. 32.
ng of Cotton. Pp. 16.
ng. Pp. 24.
arieties of Chickens. Pp. 48.
Beet. Pp. 48.
on Birds. Pp. 48.
Herd. Pp. 30.
Station Work—I. Pp. 30.
an as a Forage Crop. Pp. 24.
g. Pp. 48.
Curing Tobacco. Pp. 24.
Culture. Pp. 40.
Farm Produce. Pp. 31.
on the Farm. Pp. 40.
Geese. Pp. 55.
Station Work—II. Pp. 32.
d Pastures. Pp. 30.
Station Work—III. Pp. 32.
n Beef Production. Pp. 24.
es of the Southwest. Pp. 32.
Station Work—IV. Pp. 32.
d. Pp. 39.
of Soils. Pp. 24.
Station Work—V. Pp. 32.
Station Work—VI. Pp. 27.
Twig-borer. Pp. 16.
e in the South. Pp. 24.
of Tobacco. Pp. 22.
ils. Pp. 23.
Station Work—VII. Pp. 32.
d. Pp. 32.
onous Plants. Pp. 32.
Station Work—VIII. Pp. 32.
ls. Pp. 23.
ases and Treatment. Pp. 15.
Station Work—IX. Pp. 30.
od. Pp. 31.
s for Farmers. Pp. 46.
ep for Mutton. Pp. 48.
Station Work—X. Pp. 32.
to Southern Farmers. Pp. 48.
nies of Shade Trees. Pp. 30.
g in the South. Pp. 40.
. 30.
orage Plants. Pp. 48.
Station Work—XI. Pp. 30.
ost. Pp. 24.
Station Work—XII. Pp. 32.
airy Cattle. Pp. 48.
t Station Work—XIII. Pp. 32.
Pp. 20.
eading Courses. Pp. 20.
e in the United States. Pp. 28.
terest in Good Seed. Pp. 24.
Bread Making. Pp. 40.
nd How to Grow It. Pp. 32.

114. Experiment Station Work—XIV. Pp. 28.
115. Hop Culture in California. Pp. 28.
116. Irrigation in Fruit Growing. Pp. 48.
118. Grape Growing in the South. Pp. 32.
119. Experiment Station Work—XV. Pp. 30.
120. Insects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp. 32.
134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
136. Earth Roads. Pp. 24.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing. Pp. 48.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
143. Conformation of Beef and Dairy Cattle. Pp. 44.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
146. Insecticides and Fungicides. Pp. 16.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propagation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.

179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.
183. Meat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
184. Marketing Live Stock. Pp. 40.
185. Beautifying the Home Grounds. Pp. 24.
186. Experiment Station Work—XXIII. Pp. 32.
187. Drainage of Farm Lands. Pp. 38.
188. Weeds Used in Medicine. Pp. 45.
190. Experiment Station Work—XXIV. Pp. 32.
192. Barnyard Manure. Pp. 32.
193. Experiment Station Work—XXV. Pp. 32.
194. Alfalfa Seed. Pp. 14.
195. Annual Flowering Plants. Pp. 48.
196. Usefulness of the American Toad. Pp. 16.
197. Importation of Game Birds and Eggs for Propagation. Pp. 30.
198. Strawberries. Pp. 24.
199. Corn Growing. Pp. 32.
200. Turkeys. Pp. 40.
201. Cream Separator on Western Farms. Pp. 23.
202. Experiment Station Work—XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
205. Pig Management. Pp. 40.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
216. The Control of the Boll Weevil. Pp. 32.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work--XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
240. Inoculation of Legumes. Pp. 8.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work--XXXIII. Pp. 32.
245. Renovation of Worn-out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. 36.
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
251. Experiment Station Work—XXXIV. Pp. 32.
252. Maple Sugar and Sirup. Pp. 36.
253. The Germination of Seed Corn. Pp. 16.
254. Cucumbers. Pp. 30.
255. The Home Vegetable Garden. Pp. 47.
256. Preparation of Vegetables for the Table. Pp. 48.
257. Soil Fertility. Pp. 39.
258. Texas or Tick Fever and Its Prevention. Pp. 45.
259. Experiment Station Work—XXXV. Pp. 32.
260. Seed of Red Clover and Its Impurities. Pp. 24.
261. The Cattle Tick. Pp. 22.
262. Experiment Station Work—XXXVI. Pp. 32.
263. Practical Information for Beginners in Irrigation. Pp. 40.
264. The Brown-tail Moth and How to Control It. Pp. 22.
265. Game Laws for 1906. Pp. 54.
266. Management of Soils to Conserve Moisture. Pp. 30.
267. Experiment Station Work—XXXVII. Pp. 32.
268. Industrial Alcohol: Sources and Manufacture. Pp. 45.
269. Industrial Alcohol: Uses and Statistics. Pp. 29.
270. Modern Conveniences for the Farm Home. Pp. 48.
271. Forage Crop Practices in Western Oregon and Western Washington. Pp. 39.
272. A Successful Hog and Seed-Corn Farm. Pp. 16.
273. Experiment Station Work—XXXVIII. Pp. 32.
274. Flax Culture. Pp. 36.
275. The Gipsy Moth and How to Control It. Pp. 22.
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 40.
278. Leguminous Crops for Green Manuring. Pp. 27.
279. A Method of Eradicating Johnson Grass. Pp. 16.
280. A Profitable Tenant Dairy Farm. Pp. 16.
281. Experiment Station Work—XL. Pp. 32.
282. Celery. Pp. 36.
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. 42.
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. 48.
285. The Advantage of Planting Heavy Cotton Seed. Pp. 16.
286. Comparative Value of Whole Cootn Seed and Cotton-seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. (In press.)
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. (In press.)
295. Potatoes and Other Root Crops as Food. (In press.)
296. Experiment Station Work—XLI. (In press.)
297. Method of Destroying Rats. (In press.)
298. The Food Value of Indian Corn and Corn Products. (In press.)
299. Diversified Farming under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-grown Tea. Pp. 16.
302. Sea Island Cotton: Its Culture, Improvement, and Diseases. Pp. 48.
303. Corn Harvesting Machinery. Pp. 32.
304. Growing and Curing Hops. Pp. 39.
305. Experiment Station Work—XLII. Pp. 32
306. Dodder in Relation to Farm Seeds. Pp. 27
307. Roselle: Its Culture and Uses. Pp. 16.
308. Game Laws for 1907. Pp. 52.
309. Experiment Station Work--XLIII. Pp. 32
310. A Successful Alabama Diversification Farm. Pp. 24.
311. Sand-clay and Burnt-clay Roads. Pp. 19.

O

Issued November 29, 1907.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 312.

A SUCCESSFUL SOUTHERN HAY FARM.

BY

HARMON BENTON,

Assistant Agriculturist, Farm Management Investigations,
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.

LETTER OF TRANSMITTAL

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., October 23, 1907.

Sir: I have the honor to transmit herewith a paper entitled "A Successful Southern Hay Farm," by Mr. Harmon Benton, Assistant Agriculturist, prepared under the direction of the Agriculturist in Charge of Farm Management Investigations of this Bureau.

While this paper is an exceedingly interesting one as showing the possibilities of a small area of land in the South, it should be understood that the conditions under which the farm in question was managed were unusual. As pointed out in the paper, it would not be possible to duplicate in many places the prices for hay received by the owner of the farm in question. There are many sections of the South, however, where hay would sell at a handsome profit, and the adoption of the systems of management set forth in these pages would be of material advantage in building up the soil. The suggestions and recommendations made are certainly worthy of consideration, and I therefore recommend that the paper be published as a Farmers' Bulletin.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

B. P. I.—316.

A SUCCESSFUL SOUTHERN HAY FARM.

INTRODUCTION.

In localities where a one-crop system has prevailed for a number of years farms which deviate from this system are of special interest, because they show what types of farming are possible in the section in which they are located. In the cotton-growing States such farms are of unusual interest for the reason that so few of them exist. Much of the hay consumed on Southern farms and plantations is shipped from the North. As a result, hay is high priced in the South. There is room for a considerable number of hay farms in that section. That such farms can be made to pay handsomely is demonstrated by the experience of the farmer whose work is described in these pages.

Not every hay grower can follow the methods here described. It is not necessary, however, that a farmer should feed steers for their manure, as is done on this farm, in order to be able to grow hay. While nothing else is quite equal to manure, land can be kept in good heart by plowing under an occasional green crop and then using lime and commercial fertilizers.

A brief discussion of hay growing under more usual conditions on southern farms will be found at the end of this bulletin.

LOCATION.

Eight years ago Dr. D. S. Ramseur, of Cherokee County, S. C., purchased a run-down cotton farm in the Piedmont region, 25 acres of which he has placed under the mangement described below. At that time the land would not produce more than one-fourth bale of cotton to the acre, with 250 pounds of fertilizer. Now the land is yielding more than $50 an acre annually, with less labor than cotton would require. Besides, it is improving in fertility.

The soil varies from a pebbly clay to a sandy loam.

MANAGEMENT.

Under the present management the value of the farm has been greatly enhanced. To illustrate: Doctor Ramseur purchased a few acres of land from an adjoining neighbor in 1906 at $16.66 per acre. At the same time the neighbor offered $100 per acre for the adjoining portion of Doctor Ramseur's farm. It is interesting to note that the difference in value of these two farms has been brought about by difference in soil treatment in eight years' time; besides, profitable crops of hay have been removed from the land every year.

The management of this farm is of interest to every cotton grower and every tobacco grower. At the time the farm was purchased it was terraced according to the usual custom in cotton fields in that section. By the plan followed the objectionable terraces have been removed and the soil has been greatly increased in fertility and in value. The effect of torrential rains is not so great in washing out gullies, owing largely to the fact that the land is covered with some growing crop all the time and to the addition of organic matter to the soil. The methods used by Doctor Ramseur can be applied to at least a small portion of many southern farms and plantations.

For the first few years the crops on the farm here described consisted of oats in winter, cowpeas in summer for hay, and a sufficient acreage of corn to supply the farm. The application of barnyard manure and the turning under of oat and cowpea stubble made it possible to grow crimson clover, and that crop now occupies an important place in the cropping system and has proved to be most valuable.

No commercial fertilizers have been used on the farm since the present owner bought it. A dressing of 6 to 8 tons of barnyard manure per acre is applied annually. This manure is obtained from feeding beef cattle at the owner's home, one-fourth mile from the farm. The beef cattle are natives, fattened for the local market on cotton seed meal and hulls. The feed is mixed in the proportion of 1 pound of meal to 5 of hulls. Twenty-five pounds of the mixture are fed per day per 1,000 pounds live weight. An average of 25 animals is kept constantly on hand; these are sold to butchers as demanded by the local market.

No accurate accounts are kept of the feeding operations, but it is estimated that the increase in live weight and the advance in price of fat cattle over poor ones pay for the food and the time consumed in feeding, leaving the manure as profit.

The animals are fed the same summer and winter under a large shed surrounding the main barn. Feed and water are placed in separate troughs, and the animals eat and drink at will.

The principal part of the work on this farm is performed by one n and one horse. Additional help in the way of teams and men is ed during the harvest season. The owner informed the writer that the horse and man did enough "outside work" to pay for the extra help during the harvest season.

During the winter of 1905 the crops consisted of 18 acres of oats and 7 acres of crimson clover. In the spring of 1906, 3 acres of the land that was in crimson clover the preceding fall were planted in corn, the remaining 4 acres of clover land and the 18 acres of oat land being sown broadcast to cowpeas. No regular rotation of crops has been practiced, owing to the fact that the acreage of corn has been decreased as the land increased in yield and that variation of seasons causes the area of crimson clover planted to be variable. The idea is to get over the entire farm with crimson clover as often as possible.

Corn follows a portion of the clover in the rotation, neither being planted two years in succession on the same land, except in the case of crimson clover following corn. By this system corn and clover gradually rotate over the entire farm. More years are required for corn than clover, as it occupies less than one-half the land now planted in clover. Corn always follows early plantings of crimson clover after cowpeas. This system enables the owner to secure two crops a year from the land: Fall crops, clover and oats; spring crops, corn and cowpeas.

It is quite probable that if vetch seed were sown with the oats better results would be secured. The land is now in condition to produce good vetch. This plant would add to the quality and quantity of oat hay produced and at the same time supply a winter legume. This combination was tried in a small way in the fall of 1906. At the suggestion of the writer the same combination will be tested on a larger scale in the autumn of 1907. By planting vetch with oats two crops of leguminous plants can be secured from the same land every year—oats and vetch and crimson clover in winter and cowpeas in summer.

Cotton is never grown on this farm, as it costs too much in proportion to the amount received for the product.

German millet has been successfully tried, but it is not a satisfactory crop on this farm. Its season is not quite the same as that of cowpeas and it does not fit into the system of growing two crops a year. Farther north, where it can be sown later, it would do this.

Doctor Ramseur does not like sorghum as a hay crop. He considers the yield satisfactory, but it can not be baled and put on the market in a satisfactory condition because it is impossible to dry it sufficiently to prevent the juice from breaking out of the stems when it is baled. This objection would not hold on farms where the sorghum hay is fed at home and where, consequently, it does not need to be baled.

CULTURAL METHODS.

CRIMSON CLOVER.

Crimson clover always follows corn and as much of the cowpea land used for early cutting as can be properly prepared for planting before November 1. Clover seed is sown in the corn at the last plowing and on cowpea land as soon as possible after the removal of the earlier cutting of cowpeas for hay. On corn land the clover is sown at the rate of 20 pounds per acre and cultivated in at the last working of corn. After the cowpeas are harvested the land is plowed as well as possible with a one-horse turning plow. Afterwards it is harrowed into good condition. On cowpea land also the crimson clover seed is sown at the rate of 20 pounds to the acre, but is harrowed in lightly.

Doctor Ramseur prefers to plant crimson clover in August and September. He never plants it after November 1, because the young plants are frequently injured by winter freezing, and besides the growth is unprofitable when planted later. After sowing all the crimson clover possible the remainder of the land is sown to oats.

The earlier plantings of crimson clover are ready to cut for hay about May 10. The hay is allowed to remain in the swath until thoroughly wilted. It is then raked into windrows and allowed to remain until quite well cured, after which the hay is thrown into small, tall cocks, where it remains until thoroughly cured. After being cured the hay is drawn to a large shed in the field, where it is allowed to remain until the owner is ready to put it into bales.

From practical experience extending over a period of about four years Doctor Ramseur states that crimson clover should not be cut for hay while too green. He lets about two-thirds of the flowers dry on the seed head before cutting. He states that he practically lost one crop by cutting too green. "If cut when in full bloom it takes much longer and is more difficult to cure." On the other hand, this crop should not be cut too ripe. If allowed to stand much longer than the early flowering stage, the beards of the calyx form "witch balls" in the stomachs of stock eating the hay, sometimes with fatal results.

Doctor Ramseur considers the stubble of a good crop of crimson clover, when turned under, far superior to cowpea stubble.

The yield of crimson clover in 1906 was 3,500 pounds (1¾ tons) of cured hay per acre.

OATS.

After November 1 the portion of the farm that can not be planted to crimson clover is gradually prepared as well as possible with a one-horse plow, and a variety of oats known as the Appler is drilled in at the rate of 2 bushels to the acre. The open-furrow system is practiced in planting oats, i. e., rather deep furrows are laid off 15 to 18 inches apart, and the oats are planted with a one-horse planter in the bottom of these furrows. In this section oats frequently "heave" during the winter when planted on the level, but if planted in these furrows particles of soil from the sides of the furrows are loosened by freezing and recover the roots of the oats as hey are "heaved" out of the soil.

Oats are planted, as previously stated, over the whole area not planted in crimson clover. In 1906 the 18 acres planted averaged 3,000 pounds of cured hay per acre. The oats are cut for hay while in the dough stage. Doctor Ramseur states that it pays him better to convert oats into hay than to grow them for grain. Oat hay is handled in all respects like crimson clover hay.

CORN.

In 1906, 3 acres of the land that had grown crimson clover was well prepared with a one-horse plow and planted to corn about June 1. The corn rows were 4 feet apart, single plants being left 15 to 18 inches apart in the row. The crop was cultivated shallow and level, so that the crimson clover sown at the last plowing could be cut for hay the following spring.

The corn was cut close to the ground about eight days after the fodder-pulling stage had passed, and it was shocked where it was and left for six weeks or two months. It was then shredded. The corn measured 66⅔ bushels per acre. The stover yielded 2 tons per acre. This is baled and finds ready sale on the local market.

Doctor Ramseur has no shredder, but employs the owner of one to come to his farm and shred his corn. It may not be out of place to state that in this section of the country owners of shredders move around from one farm to another for the purpose of shredding the farmers' corn stover. Doctor Ramseur considers good corn stover equal in food value to cotton-seed hulls.

COWPEAS.

In summer the portion of the farm not needed for corn is planted in cowpeas. The land is plowed as well as possible with a one-horse plow, then harrowed and peas sown broadcast at the rate of 1½ bushels per acre from May 1 to June 25. The seed is harrowed in. The vines are cut for hay after about one-half of the pods are ripe. At this stage they are much more easily cured into hay than if cut earlier. The vines are allowed to remain in the swath until well wilted and the leaves are dry. The hay is then raked into windrows, where it is allowed to remain until the smaller vines are dry. Then it is placed in tall, small cocks until it passes through a sweat. After it has sweated sufficiently it is carried to the field shed, where it is stacked in a large mow for about six weeks before baling. All hay treated thus passes through a heat, but not enough to cause decay.

Mixed varieties of cowpeas are never sown on this farm, for the reason that different varieties ripen at different times. The owner of this farm buys all his cowpea seed, because he thinks it pays better to sell hay than to save seed. When possible, different varieties of unmixed seed are purchased, as early, medium, and late varieties give him a better opportunity to cut the hay at the proper time.

FIELD SHED.

The field shed is cheaply constructed by erecting four posts on a square 24 feet apart; two of these are 22 feet high and two are 20 feet high. These posts are well braced, and a single pitch roof 26 feet square forms the cover. The hay is drawn to this shed after being field cured, and it remains there for six weeks, or until the manager is ready to put it into bales. It should be noted that hay sells better when baled. When this shed is filled it holds 600 bales of hay, weighing from 80 to 100 pounds each. The mow covers a ground space of 50 by 37½ feet. The hay is allowed to project 12½ feet on the front and two sides, but does not extend beyond the roof at the back, as otherwise water falling on the roof would run off on the hay.

EQUIPMENT OF THE FARM AND ITS COST.

A statement of the equipment used on the farm and its cost follows:

One one-horse Georgia plow stock, with attachments	$5.00
One one-horse smoothing harrow	10.00
One one-horse weeder	7.00
One one-horse curved-tooth slicing and smoothing harrow	10.00
One two-horse mower	35.00
One one-horse hayrake	15.00
One one-horse wagon	30.00
One one-horse hay press	90.00
One one-horse wooden roller	7.50
Total	209.50

EXPENSES AND RECEIPTS OF THE FARM.

The expenses of conducting the farm and the receipts from products sold for 1906 are as follows:

Cost of labor.

One man, twelve months, at $15	$180.00
One horse, use of, and feed	100.00

Miscellaneous expenses.

terest on 25 acres of land, valued at $100 per acre, at 8 per cent	$200.00
terest and depreciation on machinery, at 20 per cent	41.90
Total	521.90

Receipts.

acres crimson clover hay, 3,500 pounds per acre, at $1.25 per hundredweight	$306.25
acres oat hay, 3,000 pounds per acre, at $1.25 per hundredweight	675.00
acres cowpea hay, 3,000 pounds per acre, at $1.25 per hundredweight	825.00
acres corn, 66.66 bushels per acre, at 75 cents per bushel	150.00
acres corn stover, 2 tons per acre, at $15 per ton	90.00
Total income	2,046.25
Total cost	521.90
Net income	1,524.35

These figures indicate very clearly the importance of growing hay the cotton farms of the South, where a large proportion of the hay quired is brought from other States. Doctor Ramseur sold all of is hay at his barn, and could have sold more.

When it was suggested that by the use of two horses and two-horse lows, wagons, and implements, one man would be able to work twice s much land, and do especially the plowing better, the owner of this rm informed the writer that his object was to show what could be one with a one-horse farm.

Doctor Ramseur paid $15 a month for labor in 1906. For the year 907, owing to the advance in the price of labor it was necessary to ay the same man $20 per month. This man furnishes his own house nd boards himself.

APPLICATION TO OTHER FARMS OF THE SYSTEM DESCRIBED.

Comparatively few farms in the South have the supply of manure ecessary to duplicate Doctor Ramseur's methods, but even where the anure from cattle is not available it would pay to grow at least nough hay for home consumption, and in many parts of the South y substituting commercial fertilizers for barnyard manure the ethods described could be followed with somewhat similar results. n nearly every farm or plantation some manure is available. But ven where there is no manure hay could still be grown to advantage. n some cases it would undoubtedly pay to plow under an occasional rop of rye or cowpeas to put humus into the soil; but where one is rowing legumes, and especially where there is a crop of stubble to low under every spring and every fall, there will usually be enough umus in the soil so that commercial fertilizers will make good crops f hay.

Of course it would not be possible in all parts of the South to duplicate the prices for hay received by Doctor Ramseur, but there is not a Southern State where good hay like that grown on the farm here described would not sell at a handsome profit over the cost of its production. But while very few farmers would be able to make a profit of $60 an acre on a hay farm, it would be a poor hay grower indeed, with hay at such a price as now prevails in the South, who could not make $20 an acre above expenses.

A word of caution should be inserted here concerning crimson clover. This crop has become important only in a limited section along the Middle Atlantic coast. Elsewhere results with it have been very irregular. It would therefore be wise for the prospective hay grower to experiment with crimson clover on a small scale until he is sure he has learned how to grow it and has gotten his land well inoculated for it. Practically the same remarks apply to vetch, except that the region in which vetch succeeds is considerably larger than the corresponding region for crimson clover. Vetch usually does not thrive when first sown on a piece of land, and the trouble seems to be due to the lack of the proper bacteria in the soil. By persistent effort, however—that is, by continuing to sow a little vetch on the same piece of land for two or three years in succession—the land will become inoculated, and then vetch may be readily grown; and it is doubtful if there is any hay superior to that made by vetch. A very good plan would be to sow for winter hay crops a mixture of oats, vetch, and crimson clover, or any two of these; then for summer sow cowpeas, using two or three varieties having different lengths of growing season in order to extend the period of hay harvest.

Where manure is not available commercial fertilizers should be used unless the ground is known to be rich. The fertilizers required will depend largely upon the character of the crop grown and upon the soil. In the coastal plains region there is no question that both phosphoric acid and potash should be added even to a leguminous hay crop, and for crops other than legumes some nitrogenous fertilizer should be added. One of the most successful hay growers in the South uses for cowpeas, vetch, crimson clover, and other legumes 300 pounds per acre of a fertilizer containing 10 per cent of phosphoric acid and 4 per cent of potash. This is in the coastal plains region. For crops other than legumes—such, for instance, as Johnson grass and oats—he adds about 200 pounds of cotton-seed meal. In the Piedmont region, where the soils contain more clay, the potash could probably be omitted from the fertilizer without greatly affecting the yield of hay.

There should be no difficulty anywhere in the South in getting a winter hay crop that would yield 1 ton per acre, to be followed by summer crop of cowpeas that would yield from 1 to 2 tons per acre. onsidering the price of hay in the South and the considerable come from a hay farm, the cost of the necessary equipment is not o large.

In sections where Johnson grass is well established a very good stem of hay growing is to sow vetch or crimson clover, or both, ith a small amount of oats as a winter crop on Johnson-grass land. here the land is plowed early in the fall and put in good condition r the winter hay crop, two or three good crops of Johnson grass n be cut the next summer. This system will then give a crop of inter hay and two or three cuttings of Johnson-grass hay every year.

A very good modification of this system would be to grow cowpea ay every other year as the summer crop, alternating with Johnson rass, and growing a crop of winter hay each year. The system ould then be, say, oats and vetch, followed by cowpeas, the land eing plowed and put in good condition before sowing the cowpeas. fter the cowpeas are off, disk in the winter hay crop; then the next ummer, after taking off the winter hay crop, let the Johnson grass ome on.

One very successful hay grower in Mississippi sows bur clover on ohnson-grass sod in the fall and pastures the bur clover during the vinter, allowing it to make just enough seed in the spring to reseed he land. This treatment has increased the yield of Johnson-grass ay prodigiously. This farmer cuts Johnson grass before it heads ut, or about the time it is heading, and thus avoids scattering the eed of this serious pest.

It is hoped that a description of Doctor Ramseur's work, showing he possibilities in the production of hay in the South and pointing the way to a satisfactory method, will result in more hay being grown in that section. The farmer or planter who buys hay, even at $15 a ton, when he could grow it, is wasting money. The cost of growing hay under ordinary farm conditions in the South is from $3 to $6 a ton. It is easily seen that where a farmer must pay $15 or $20—and sometimes even $25—a ton for hay, he would save a large part of his expenses by growing his own hay.

On account of the difference in the crops adapted to various soils nd climatic conditions, it is manifestly impossible to lay out a cropping system for a hay farm that will suit all sections. If, however, ny farmer who reads this bulletin desires to do similar work on his wn farm, the Office of Farm Management Investigations, of the Bureau of Plant Industry, United States Department of Agriculture, vill gladly assist in arranging a cropping system suited to local conlitions.

FARMERS' BULLETINS.

[illegible] Representative, or Delegate in Congress, [illegible]

[illegible] and Trees. No. [illegible] Forage Crop. [illegible] Station Work—II. [illegible] Experiment Station [illegible] Feed. [illegible] Lands. [illegible] No. 244. No. 220. Tomatoes. [illegible] Work—XXVIII. [illegible] No. 225. Experiment Station Work— [illegible] Experiment Station Work— [illegible] The Production of Good Seed Corn. [illegible] Diseases. No. 232. Okra: its [illegible] Work—XXX. No. 234. The Guinea Fowl and its [illegible] and Incubators. No. 237. [illegible] States. [illegible] Butter Making on the Farm. No. [illegible] Preventing Diseases of [illegible] of Worn-out Soils. No. 246. [illegible] and Apple Scab. No. 248. [illegible] of Stinking Smut of Wheat [illegible] XXXIV. No. 252. Maple Sugar and [illegible] No. 255. The Home Vegetable [illegible] No. 257. Soil Fertility. No. 258. Texas [illegible] Work—XXXV. No. 260. Seed of [illegible] Southern Agriculture [illegible] Information for Beginners in Irrigation [illegible] Game Laws for 1906. [illegible] Experiment Station Work—XXXVII. [illegible] Industrial Alcohol: Uses and Statistics.

O

Issued December

U. S. DEPARTMENT OF AGRICULTUR

FARMERS' BULLETIN 313.

HARVESTING AND STORING C

BY

C. P. HARTLEY,
Physiologist in Charge of Corn Investigations,
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1907.

CONTENTS.

Page.
troduction 7
he silo 7
orn as a forage crop 8
tripping the blades 8
opping 8
utting and shocking compared with husking from the standing stalks 9
ime of cutting 10
ethods of cutting 10
  Hand cutters 11
  Horse-power cutters 12
  Binders 13
  Shockers 14
hocking 14
  Building and tying the shock 15
  Size of shocks 16
  Spacing of shock rows 17
erking and storing the ears unhusked 17
usking from the shock 17
usking from standing stalks 19
auling to the crib 20
se of corn-picking machines 21
se of huskers and shredders 22
toring the stover 22
toring the ears 23
onvenient cribs 24
rotecting the crop from insects, mice, and rats 26
ethods of harvesting in relation to soil fertility 27
hat constitutes a bushel of corn 28
rinkage 28

B. P. I.—314.

HARVESTING AND STORING CORN.[a]

INTRODUCTION.

The production of a large crop is of course the subject of most importance in corn growing, but there is need of much care and labor in harvesting and storing the crop after it is produced in order to obtain its maximum value.

THE SILO.

On most well-managed farms the work of harvesting and storing the corn crop begins with the filling of the silo. Corn is one of the best crops for this purpose, if not the very best. Sorghum stands dry weather much better than corn and for dry regions is a surer crop, but it is more inclined to fall down and become tangled than corn, thus making it somewhat more difficult to place in the silo. This difficulty is overcome to a large extent by growing the two crops together, and the ensilage made from these two crops grown together is usually superior to that from either crop grown separately.

When the silo first came into use it was thought necessary to fill it with very green succulent growth. This is now known to be an erroneous idea, and the silo is regarded much as a storeroom or food preserver, the value of the ensilage depending to a very great extent on the nutritive value of the crop with which the silo is filled. To this end it is advisable that the corn shall have reached a degree of ripeness indicated by rather hard, well-dented or glazed kernels and partially dried husks before it is placed in the silo. There is a week or ten days when the ears are in this condition and the stalks still contain sufficient sap to cause the silage to pack well in the silo. It is even better to add a little water to accomplish the latter purpose than to cut the crop before it has attained its full feeding value.

---

[a] The following Farmers' Bulletins in reference to Indian corn (maize), its culture, harvesting, storage, etc., will be sent without cost upon the receipt of a request therefor addressed to the Secretary of Agriculture, Washington, D. C.: No. 32, Silos and Silage; No. 81, Corn Culture in the South; No. 199, Corn Growing; No. 229, The Production of Good Seed Corn; No. 253, The Germination of Seed Corn; No. 292, Cost of Filling Silos; No. 303, Corn-Harvesting Machinery.

Many of the State agricultural experiment stations have published valuable bulletins treating of ensilage and the silo, and Farmers' Bulletins 32 and 292 of the Department of Agriculture treat especially of this subject. This publication will, therefore, deal more especially with other methods of harvesting and storing the corn crop.

CORN AS A FORAGE CROP.

Unless to be used for ensilage or cut green and fed directly to stock, it is very seldom profitable to grow corn exclusively for forage. Even when grown for the purpose of filling a silo, the feeding value of the crop is very greatly increased by the amount of grain put in the silo. If hay or forage alone is desired, independent of grain, it can usually be more satisfactorily produced by growing alfalfa, clover, cowpeas, or sorghum than by growing corn. In addition to having a higher feeding value than corn stover, alfalfa, clover, or cowpeas will enrich the soil on which they are grown. The removal year after year of crops of corn or sorghum will rapidly impoverish a soil unless an equivalent amount of humus and fertility is returned to it.

STRIPPING THE BLADES.

In some sections, especially in the Southern States, the practice of stripping the blades by hand from the standing stalks has for years been one of the established operations in connection with harvesting the corn crop. There is no question that the blades when thus gathered and well stored furnish an excellent forage, but there are cheaper methods of obtaining forage of as good or better quality.

Experiments and calculations as to cost and value have been made by the Georgia Experiment Station[a] and other stations in the Southern States, and the conclusion has been reached that the stripping of corn blades is unprofitable and should be discontinued.

TOPPING.

[illegible] practice in some localities to top the stalks
[illegible] By this method the portion of
[illegible] readily and with least waste is
[illegible] late in maturing or wet fall
[illegible] of the [illegible] ening ears, the topping
[illegible] have become hard,
[illegible] fore the topping is
[illegible] heavy growth of cow-
[illegible] acticable and war-

[illegible] p. 208. 1906.

rant the topping of the crop. If the corn is desired for seed, topping will facilitate the drying of the ears and thus make it possible to select the seed before it is injured by freezing. Ordinarily, however, it is found more expensive to top a corn crop than to cut and shock the entire plant.

Experiments conducted by the agricultural experiment station at Auburn, Ala., indicate that a greater profit is obtained by cutting and shocking the entire plant than by topping.

CUTTING AND SHOCKING COMPARED WITH HUSKING FROM THE STANDING STALKS.

Over large areas in the principal corn-growing States corn is grown primarily for the grain, and each farmer decides for himself how much of the crop will be cut. This is usually determined by cutting just enough to feed the animals maintained on the farm. The chief objection to this method is that many farmers do not maintain enough animals to consume all of the corn stover produced. If the ears are gathered from the standing stalks and no use is made of the stover, fully one-third of the crop is wasted. The term " fodder " is applied to the entire plants as ordinarily cut and shocked, while the term " stover " is applied to the portion remaining after the ears have been pulled or husked.

Generally speaking, there is little difference in cost between husking and cribbing corn from the shock and husking and cribbing it from the standing stalk. In some sections men will husk from standing stalks at a lower price than from shocks, but the cost of teams, although they are not usually very busy with other work during corn-husking season, must be taken into consideration. Considering the expense of husking from the standing stalk and from the shock as equal, it is evident that the stover has been obtained for the money paid for having the corn cut and shocked. This cost of cutting and shocking is very much less than the value of the stover if it be properly stored and fed. If left in the field until February or March exposed to the winds and rains of winter, it is questionable whether its feeding value is equal to the cost of cutting and shocking.

There are sections in the Central and Southern States where the soil is rich and the growing season long, causing the corn to make a large, tall growth of stalk which does not furnish a good quality of stover. In such sections it may be better to obtain the necessary quantity of forage by cutting several hay crops each year than by saving the corn stover. This is especially true in localities where warm, damp weather causes the corn stover to lose its feeding value rapidly.

TIME OF CUTTING.

In the sections where corn is grown extensively and primarily for the grain, but where it is cut and the stover fed, the time of cutting is governed by the effect which the cutting will have on the ears. When grown for grain it is not advisable to cut until the kernels have become well dented and hard and the husks partly or entirely dried. From the time the corn reaches this condition there is ordinarily a period of about ten days or two weeks in which the stover has a high feeding value and the production of grain per acre is not materially decreased by cutting. After heavy frosts, or after the leaves become brown and the stalks dry, the expense of cutting is greater than the feeding value of the stover obtained. When cut during the period above mentioned, corn stover has approximately the same value as timothy hay and can accordingly be valued at $6, $8, or $10 a ton. If cutting is delayed until the corn is mature enough to husk and crib or if small shocks of stover are left standing in the field till spring, the feeding value of the product is scarcely worth the expense of feeding it and returning the stalks to the land. There are all kinds of corn stover, and the principal factors governing the quality of any particular kind are time of cutting and care in storing.

The above statements apply to cases in which the corn is grown for grain. The cutting of corn when the ears are in the roasting-ear condition or as they are beginning to glaze makes a more palatable stover, but the full feeding value of the crop is not obtained by such early cutting.

METHODS OF CUTTING.*

Several methods of cutting are now generally followed: By hand; with a horse cutter drawn as a sled or on wheels between the rows; with a corn binder; and with a corn shocker. In the Northern States the corn binder is very widely used. The stalks attain a height of [illegible] feet [illegible] cut and bound very satisfactorily by means of [illegible] north, where the stalks are but 5 feet [illegible] used in cutting and binding the [illegible] this purpose, however, [illegible] built for such heavy [illegible] Southern States, [illegible] 2 or more feet, with [illegible] binder does not meet [illegible] ted for just such

---

[illegible] implements and machinery [illegible] Bulletin 303, entitled "Corn-crops as these would meet with greater favor than the binders designed for corn of average height.

The method of cutting is governed not only by the height of the stalks but also by the quantity of corn to be cut. Where farms are small and the area to be cut is less than 20 acres, cutting by hand or by such a cutter as is shown in figure 1 is found more profitable than maintaining expensive machinery for the purpose. Where a large acreage is to be cut during the limited time within which it is most profitable to cut corn, corn binders or corn shockers are necessary and are the most economical means of harvesting.

HAND CUTTERS.

Although there are circumstances under which the cutting of corn by hand is advisable, there are still cut by this laborious method many acres which could more profitably be cut by corn-harvesting machinery.

Various localities have their peculiarities in regard to methods of cutting corn by hand, kinds of knives used, etc. Figure 2 shows forms of knives that give most general satisfaction. In the hand of the man shown in figure 3 is another form of knife that is very generally used. The same figure shows a shocking horse that is very convenient where the corn is cut by hand and one shock is completed before beginning another. A shocking horse is also very serviceable for shocking after a corn binder, especially when but one man is shocking. Some cutters prefer to tie down supports by twisting together, at proper intervals through the field, four adjoining hills. The tying together of these four hills forms what is known in some localities as gallowses, which support the stalks in beginning a shock. By tying down a row entirely through the field a very



FIG. 1.—Corn harvester with automatic knife guards.

convenient system of cutting can be pursued by cutting from one shock to the next, up one side of the shock row and down the other. A very great deal of hard labor might be saved and more corn cut per day if everyone when cutting corn would adopt a definite system of procedure in cutting and building a shock.

Figure 1 explains a good method of cutting small shocks eight hills square, and can be employed by the use of the shocking horse or by tying down the four central hills as indicated in the illustration. For the first armload, hills 1, 2, 3, 4, 5, 6, 7, and 8 should be cut in the order given, and the armload stood at the point indicated by the letter *a*. The numbers and letters in the figure indicate the order in which the hills are cut and the location in which the fodder is placed. By cutting each shock after this definite system very many unnecessary steps can be saved. Other systems of equal merit can be adopted for cutting shocks of different sizes. Without a definite system of procedure much time is lost and many unnecessary steps are taken.



[illegible] Four types of corn [illegible]

HORSE-POWER CUTTERS.

There are many inexpensive forms of corn cutters similar to the one shown in figure 1 which by the use of a horse, or two horses hitched one in front of the other, will enable two men to cut and shock corn more rapidly and with less fatigue than by hand. In some cases the cutter is drawn on runners as a sled, but the saving in draft warrants the use of wheels. A man on each side catches the stalks as they are cut, and when [illegible] horse is stopped and the fodder placed [illegible] skill can construct such a cutter [illegible] at the points at which [illegible] elevated or lowered to [illegible] attachment of other [illegible] the stubs may be cut [illegible] power is used for cutting [illegible] twine or repairs and [illegible] the cheapest methods

BINDERS.

The corn binder with bundle carrier, as shown in figure 5, is satsfactorily used in cutting corn of average or small size on land that s not very steep or stumpy. On the comparatively level prairie land of the North Central States the corn binder is very generally used in cutting and shocking corn. In light corn or on level land two horses will suffice, but for faster work or heavy corn the use of three or four horses is much more satisfactory. Three men, one to run the binder and two to shock, and two teams can cut and shock about 7 acres of corn a day. However, conditions vary to such an extent regarding the weight of the corn crop, the lay of the land, etc., that it is impossible to give figures that will apply to all cases. Under normal conditions and with an average corn crop the cost of cutting and shocking by means of the corn binder is about $1.50 per acre. In sections where the corn binder is successfully used the principal objections to its use are the cost of twine, which remains upon the fodder but a short time, and the knocking off of ears in the process of binding. In almost all cases the quantity of corn knocked off by the binder is great enough to warrant driving a wagon over the field and gathering the ears from the ground after the corn is cut and shocked. This is necessary because the presence of the shocks in the field prevents the turning in of hogs or cattle to gather up the ears knocked off by the binder.



FIG. 3.—A corn-shocking horse.

The use of a binder with a bundle carrier saves very much of the hard labor of cutting and shocking, and the greater ease of handling the fodder when bound into bundles of convenient size saves labor enough to compensate for the twine used.

The stubble cutter should be attached to the corn binder whenever possible, as the early cutting of the stubs hastens their decay and puts the ground in a better condition for the following crop.

SHOCKERS.[a]

The corn shocker has not as yet met with as much favor as the corn binder, though it is now used extensively in some localities, especially in Ohio. The principal point in favor of using the corn shocker is the saving of hard manual labor. Almost all of the hard work is performed by the teams. The cost of twine is not as great as in the case of the binder, but much more difficulty is experienced in handling the fodder when the shocks are made by the shocker. The variety of movements necessary in stopping the [illegible] unloading the shocks, and preparing the shocker for cutting [illegible] next [illegible] against the use of this machine by all [illegible] further simplification the shocker may [illegible]



Fig. 4. Diagram showing a method of cutting shocks eight hills square.

SH[illegible]KIN[illegible]

[illegible] the corn, it is very [illegible] a manner that will [illegible] dry. Everyone who [illegible] or hauled in shocked corn knows the annoyance and great loss due to poor shocking. It would seem as though anyone would know how to shock corn fodder, and especially anyone raised on a farm. Perhaps everyone does know how, but the large proportion of twisted and fallen shocks seen in every locality where corn is grown, especially where it is grown extensively, is conclusive evidence that many do not properly shock their fodder. To this carelessness is due the loss of millions of dollars' worth of stover, to say nothing of the grain that is also ruined.

---

[a] [illegible] shocker, see Farmers' Bul-

BUILDING AND TYING THE SHOCK.

The stalks should be stood evenly about the shocks, with just enough slant to make them stand well against the shock. The slight slant they have should in all cases be toward the center of the shock. Too much slant is very objectionable, because in settling the slant increases and causes the shock to take water. The shocks should be tied as soon as they are made. This will prevent them from twisting or allowing the stalks to blow down before they have settled in place. Some prefer to wait until the fodder has cured a few days before tying, so that they may be tied tighter. A much better method is to tie them when first made and in about ten days tighten the ties. For tying the shocks, binder twine is the most satisfactory. A half-inch rope some 9 or 12 feet long, depending upon the size of the shocks, with a small well-curved hook made of one-half inch iron rod



FIG. 5.—Corn binder with bundle carrier in operation.

tied in one end of the rope, is of great assistance both in tying and in tightening the ties around the shocks. The rope is placed around the shock near the top and the ring hooked over, and the rope is then drawn tightly and the loose end placed under in order to hold it securely while the binder twine is being placed in position and tied. If the corn is quite tall there is an inclination to tie the shocks too low. The tying should always be done within 2 or 3 feet of the top of the shock.

SIZE OF SHOCKS.

In dry climates and where the corn becomes well ripened about the time cool fall weather sets in, the corn shocks should be large—14, 16,



[illegible] shocks placed well apart to facilitate drilling wheat.

[illegible] in the right stage of maturity and [illegible] these large shocks will not heat or [illegible] exposed [illegible] rains and wind, will [illegible] portion of the shocks. [illegible] umns it is necessary to [illegible] the fodder should not [illegible] essary for it to become [illegible] the stalks are exposed [illegible] ed out and the stover [illegible] hauled to the barn [illegible] o remain in the small shocks, rains will leach from the fodder the soluble and most palatable and nutritious food elements and render the stover dry, brittle, tasteless, and of little feeding value.

SPACING OF SHOCK ROWS.

It is always best to have the shock rows straight across the field, and if the corn has been checked the shock rows can be made straight in two directions. This is very essential when the ground is to be sown to fall wheat. In this case wide shock rows are advisable, and by means of the corn binder and bundle carrier this result can be easily accomplished (fig. 6).

JERKING AND STORING THE EARS UNHUSKED.

Jerking the ears and storing them unhusked is a method of harvesting employed in some sections, especially in the South, where the argument usually given in its favor is that if the husks are on the ears they are more protected from the grain weevil. The destruction of corn by this insect is one of the drawbacks to more extensive corn culture in the South, and it is hoped that tests will be made having as their object the determination of practical methods whereby large quantities of corn can be kept free from destruction by this grain weevil. As soon as the corn becomes dry enough to crib, weevils are frequently found working under the husks on the kernels of the ears, sometimes to the number of twenty or more to the ear. It is a question worthy of careful experimentation to determine whether the corn is more seriously injured by transferring the weevil with the unhusked ears to the crib than would result were the corn husked in the field, causing the weevils to drop to the ground and thereby leaving most of them in the field.

The total amount of work required to jerk the corn and afterward husk it is considerably greater than that required to husk it directly from the standing stalk, and the quantity of forage obtained by gathering the husks is not sufficient to pay for the extra work. Much better forage could be obtained more cheaply by other methods. If the husks are sold advantageously for mattress making it is well to perform the two operations of jerking the ears and afterward husking them in a manner that will furnish husks of good quality. The proportion of husk varies greatly among the different kinds of corn, but it is sufficient to say that it requires fully one-half more room to store the ears unhusked than husked.

HUSKING FROM THE SHOCK.

In sections where the farms range in area from 80 to 160 acres and diversified farming is followed so that all of the stover is fed, husking from the shock is a common method of harvesting the ears. Figures 7 and 8 show some of the forms of husking pegs, gloves, and hooks in general use. Such gloves are too clumsy to be used except when very cold weather makes the use of gloves necessary. For



FIG. 7. Four forms of husking pegs.

keeping the ears clean and to facilitate loading the piles of corn into the wagon, sheets of ducking 6 or 7 feet square are of very great assistance and should be universally used rather than to throw the ears upon the ground, where they may become damp or even muddy and from whence it is necessary to pick them by hand. As the corn should be hauled and stored soon after it is husked, a great supply of these sheets is not necessary, for as soon as the pile of corn from one shock is loaded the sheets are ready for use at other shocks.



Where the shocks yield 4 or 5 bushels of corn it will be necessary to throw some of the ears into the wagon by means of a basket: the remaining ears can then be [illegible] into the wagon [illegible] corners of the canvas [illegible] into the wagon. [illegible] in place of sheets, but [illegible] satisfactory. During very dry and windy weather corn should not be husked from the shock, as the loss of stover is too great. Calm days when the fodder is slightly damp are ideal for husking shocked corn.

The mistake is sometimes made of husking shocked corn for animals which have plenty of time and would enjoy husking it for themselves. This is true of animals carried through the winter that need no more grain than is found on the quantity of fodder they will eat without waste. This method of feeding can not be followed with animals on full feed, as they would waste the larger quantity of stover in their endeavors to get a full feed of grain and would not obtain as much grain as fattening cattle should eat.



FIG. 9.—Wagon equipped with throw board for catching the ears and with platform end gate for ease in scooping out the load.

HUSKING FROM STANDING STALKS.

Figure 9 illustrates the usual method in the Central States of gathering corn from the standing stalks when it has become dry enough to crib. As there is ordinarily not much work for the teams at this time of the year it is quite customary for each husker to have a team and wagon, or two men can accompany each wagon. In husking from the standing stalks the pegs, hooks, and gloves and peg shown in figures 7 and 8 are quite generally used, but many who prefer "hooks" for husking shocked corn find husking pegs preferable for husking standing corn. In husking from standing stalks it is customary to have on one side of the wagon a very high throw-board, against which the ears can be tossed and caused to drop into the wagon without the necessity of the husker looking up to see whether the ear has been thrown over the wagon; the noise made by the ear when it strikes against the throw-board is sufficient.

"Lands" are laid out and driven around in husking by this method so that the husker is always on the same side of the wagon and there are no down rows to husk except one for each new land started. When there are more men than teams available it is customary to have a number of men husk into the same wagon and one man haul the corn to the crib and unload. Upon his return to the field he will leave the empty wagon to be filled and take the other to the crib.



FIG. 10.—Shredder and husker in operation. The shredded stover is blown to the center of the feed shed.

With the proper number of huskers to suit the distance the corn must be hauled the work can usually be arranged so as to avoid any waiting [illegible]

[illegible] CRIB.

[illegible] ling the corn crop [illegible] it will not be neces- [illegible] vise, ears will be lost [illegible] he cribs are equipped [illegible] grain elevators, for [illegible] ls of the wagon and [illegible] have a rear end gate and a high shoveling board which can be lowered on reaching the crib and the scooping of the load begun at once. A wagon thus equipped is shown in figure 9. Without an end gate that will permit of the immediate use of the scoop shovel, about twice the time is required to unload.

Most successful farmers during corn-harvesting time have each load of corn that comes from the various fields passed over the wagon scales and a record made, so that at the end of the harvest the yield of each field and the quantity of grain stored will be known.

USE OF CORN-PICKING MACHINES.

At the present time much interest is being manifested in machines designed to gather the ears from the standing stalks and deliver them into a wagon driven by the side of the machine. To the man who has spent many cold disagreeable days, with sore hands, husking corn, the use of such a machine is very attractive. These machines are in their experimental stage and to their use at present there are some objections, the principal ones being that the corn is not as well husked as when husked by hand. Some ears are skipped and others are knocked off and left in the field. If the machine is equipped with a husking attachment considerable corn will be shelled in the husking and lost in the field. If the husking attachment is removed and the machine used as a corn picker, the ears can be run through a husker at the crib and the shelled corn saved. For extensive use in large fields that contain few gullies or obstacles corn pickers and huskers can be successfully employed and the crop more quickly harvested, but for the general farmer who with the aid of his regular farm help can husk by hand during the early winter what corn has not been cut for stover these machines are not profitable investments in their present state.


FIG. 11.—Rack for hauling corn fodder.

The proper planning of farm work so as to supply to the hired help steady employment throughout the year is the best method of maintaining sufficient competent labor upon the farm. Each farmer should so plan his work that he can employ his help by the year. It is only by so doing that competent help can be prevented from flocking to the factories and cities, where steady employment can be obtained. Corn husking can be performed at a time when other farm duties are not pressing.

USE OF HUSKERS AND SHREDDERS.

The use of shredding machines is becoming quite general in many corn-growing sections. Sometimes the machines are used for shredding the stover after the ears have been husked from the shocks by hand and in other cases both the husking and shredding are done by the machine. The shredding of the stover puts it in a more compact form for storing and a more convenient form for feeding and avoids the troublesome work of handling manure in which there are long coarse corn stalks. Shredded stover is fed with much less waste than stover in any other condition. It has been estimated that shredded stover will go 40 per cent farther in feeding cattle than the whole stalks and considerably farther than when the stalks are put through a feed cutter. As there are shredders of varying capacities, a farmer can own a machine suited to the amount of work to be performed. Shredding fodder by the acre and shredding and husking by the bushel are practices that are gaining favor in many sections, where crews operate huskers and shredders and travel from farm to farm. The blowing of the shredded stover from the shredder and husker to the center of a feed shed (fig. 10), so that shredded stover can be fed in racks around the general supply is a very economical way of using corn stover.



FIG. 12.- Rail pens without covers sometimes used for storing corn.

STORING THE STOVER.

[illegible] it is of great importance that [illegible] the weather. The mis- [illegible] p in sheds and barns [illegible] ield. The reverse is [illegible] epreciate so rapidly [illegible] and ricks than corn [illegible] should be fed in the [illegible] bruary or March it [illegible] abor connected with he hauling and storing of corn stover and racks and wagons should be rranged to avoid any unnecessary labor. Figure 11 illustrates a ack that can be made on the farm and attached to the running gear f the farm wagon. In hauling the fodder or stover from 20 acres of orn this rack will save labor enough each year to pay for its cost.

In the principal corn-producing States the autumns are usually ry, and corn fodder dries thoroughly in the shocks and is shredded nd stored in barns or feed sheds with little danger of heating or olding. The fodder should not be wet when shredded and stored, ut damp days are preferable for doing the hauling and shredding ecause the blades are more pliable and the fodder is therefore hanled with less waste. But in some sections, especially in northern tates, where the corn is full of sap when cut and where damp fall eather prevails, much care is necessary in storing corn fodder or tover to prevent heating and molding. In such localities it should e placed under cover in ricks not more than 6 or 8 feet in thickness, r, if shredded, layers of dry straw several inches deep should alterate with layers of the shredded stover. The depth of the layers of tover can vary from several inches to a foot or more, according to ts dryness when stored. The dry straw will take up some of the moisture from the stover and prevent heating.

STORING THE EARS.

There was a time in the history of the corn-producing belt when rail pens (fig. 12) were about the only available means of storing the corn crop. Much to the discredit of some corn growers this method of storing is still in vogue, even in sections where good means of storage could be afforded at little expense. It is no uncommon sight to see rail pen after rail pen filled with ears of corn and without any cover, exposed to all the rains and snows of winter, and these in sections of the country that produce the most corn and are consequently most interested in higher-priced corn. This corn remains in apparently good condition during the cold weather and is usually placed upon the market in early spring. Filled with water, it is not long after it is loaded into box cars or vessels until it heats and spoils. The installation of elevators where such corn can be kiln dried has been brought about by this poor manner of storing the corn crop. There is now a general prejudice against kiln-dried corn resulting from the fact that kiln drying was first employed and is at present employed to a very large extent to prevent further heating and fermentation of corn that was not allowed to dry properly or was poorly stored before being placed upon the market. This state of affairs, which results from allowing the corn to remain wet during winter and necessitates the removal of the water by expensive means, keeps the price of corn lower than it would be if the corn were allowed to dry in the fields and kept dry until placed upon the market. Grain buyers would pay a better price if the general supply of corn reached them in a condition that would insure its preservation without drying and the resulting shrinkage.



Fig. 13. Double cribs, 240 feet long, divided into bins 6 by 8 feet to facilitate drying of the corn.

Less than 4 per cent of the corn crop of the United States is shipped from this country either as corn or as corn meal, and there is in some of the European countries a strong prejudice against American corn, due to the fact that much of it reaches these foreign countries in a condition unfit for human food. It is clearly not profitable to transport a low grade of corn such distances to be sold as poor food for stock. This state of affairs can be entirely overcome by allowing the corn to dry thoroughly in the field and then keeping it well stored until it is transported. The proper method of treating the corn crop can be quickly brought into general practice if farmers, grain buyers, boards of trade, shippers, [illegible]

[illegible] arranged for both loading and unload- [illegible] way. The eaves should extend [illegible]

[illegible] of the corn.

[illegible]

[illegible] ion to the stored grain [illegible] should be constructed in such a manner that they can be filled and emptied with the least possible labor. For level ground, double cribs with an elevated driveway and approaches that will enable the loads to be driven through the cribs and dumped or scooped out of the wagons without any high pitching are very satisfactory. A crib of this kind which is filled from the central driveway is shown in figure 13. The compartments of this crib are emptied from doors near the ground on the outside. The bins of which these double cribs are composed are of small size, 6 by 8 feet and 13 feet deep, thus affording the stored grain considerable ventilation. Figure 14 shows a similar crib which is both filled and emptied from the central driveway. This arrangement puts the laborers under shelter while filling the wagons in removing the crop from the crib, but it necessitates somewhat higher pitching of the corn in unloading the wagons. Figure 15 is an interior view of one side of the cribs shown in figure 14. On sloping ground equally convenient cribs can be constructed at less expense by extending the crib in such a manner that it can be filled from the upper side and emptied from the lower side. This is a very convenient arrangement, and if the slope of the hill is considerable a driveway can be made below the crib so that with properly constructed chutes the ears can be allowed to roll into the wagons, avoiding the labor of scooping. Such a side-hill crib is shown in figure 16. As the sides should be left as open as possible to permit of a good circulation of air, it is quite necessary



FIG. 15.—Interior view of corncribs shown in figure 14.

that the eaves extend well down over the sides of the crib so as to protect the corn from driving rains and snows.

PROTECTING THE CROP FROM INSECTS, MICE, AND RATS.

In sections where insects are destructive to stored grain, cleanliness is of value in preventing injury from this source. Small quantities of grain should not be left in the cribs during the summer, as they tend to harbor these pests. Where insects are destructive to the stored grain, it is a good practice to dispose of the entire crop as early as possible and clean the cribs thoroughly, so that there



FIG. 16.—Convenient side-hill crib easily filled from upper side and very easily emptied from lower side.

are left few hiding places and no food to carry the insects through the summer. In southern localities, where the weather is warm [illegible] these pests to work throughout the entire year. [illegible] the cr[illegible] that they can be made practically [illegible] some insecticide such as [illegible]

[illegible] injurious to stored grain is [illegible] Insecticide, in which [illegible] injury or doubt as to the [illegible] to the Bureau of Ento- [illegible] of advice as to the best [illegible]

As a protection against rats, mice, and sparrows, galvanized wire netting of about one-fourth-inch mesh can be successfully used in the construction of corncribs. This wire netting can be tacked to the inside of the uprights of the crib, and the strips which constitute the sides of the crib can also be nailed on the inside of the uprights, thus holding the wire netting in place. As a floor, which should be 18 inches or more from the ground, so as not to afford a hiding place for rats, the wire netting can be tacked to the sleepers and the flooring nailed over to hold the wire in place. For overhead protection the wire netting is simply tacked to the joists.

If cribs are built upon solid concrete foundations through which rats can not burrow, no netting will be needed for the floor and the structure can be kept near the ground. With ample roof projection and upper ventilation no danger from dampness need be feared.

METHODS OF HARVESTING IN RELATION TO SOIL FERTILITY.



FIG. 17.—Three-horse stalk cutter which cuts two rows.

The tendency of the present times is to find use for every part of the corn plant. There are more than 40 distinct products made from various parts of this plant, and the effect of the removal of all these products from the farm is to deplete its fertility. Those who expect to continue the production of good crops of corn must keep the fertility of the land in view and have as much as possible of the corn plant consumed on the farm, selling only the completed and finished products. Stalks left standing in the field should be cut as soon as the crop is removed, so that the stalks may decay rapidly and not interfere with the following crops. Early cutting not only allows more time for decay, but early-cut stalks decay more rapidly and completely. Stalk cutters are very effective and inexpensive implements. They are made for two horses and cut one row every time they are driven across the field, or for three horses and cut two rows every time the field is crossed. Figure 17 shows one designed for cutting two rows. Wherever possible, corn should be shelled on the farm and the cobs returned to the soil.

WHAT CONSTITUTES A BUSHEL OF CORN.[a]

The laws of the majority of States recognize 70 pounds of ears as a bushel of corn. Some few States specify that previous to January a bushel of ears shall weigh 72 pounds. Almost without exception the State laws specify that 56 pounds of shelled corn shall constitute a legal bushel. Unless the strain of corn has exceedingly large cobs and short kernels the legal bushel of 70 pounds of ears will yield when shelled 56 pounds of grain, or the legal bushel of shelled corn. A struck bushel of kernels of different strains of corn will vary in weight from 50 to 64 pounds.

SHRINKAGE.

The shrinkage that will take place in a crib of corn from the time it is cribbed in the fall until it is sold varies so greatly in accordance with the amount of moisture the corn contains when placed in the crib, and also the ventilation of the crib, that it is impossible to state a percentage of shrinkage that will apply with certainty to any particular crib of stored corn. Some carefully conducted tests in Illinois[b] showed that during a period of twenty-one months the shrinkage was but 9 per cent of the original weight of the corn cribbed. Other tests show that during the first year the shrinkage in cribbed corn from December to June varies from 8 to 18 per cent, with an average of 14½ per cent for the first year and an average of 20 per cent for two years.

For the ten years from 1896 to 1905 the Chicago price of corn for the month of May has averaged 3.8 cents per bushel, or 8.9 per cent, higher than the December price. As the average price in May is 3.8 cents higher than in December, a shrinkage of 8.58 per cent of the fall weight will equalize the increase in price, so that the same amount would be received whether the crop be sold in December or in May.

Estimating interest on the value of the corn at 6 per cent, a shrinkage [illegible] 84 per cent will make it immaterial whether the selling be [illegible] ember or in May.

[illegible] 2 pounds are sold as a bushel in December and 70 [illegible] imating interest at 6 per cent, a shrinkage of 8.45 [illegible] the selling be done in [illegible]

---

[a] [illegible] stry, entitled "Legal and [illegible]

[b] [illegible] 3, The Shrinkage of Ear [illegible]

FARMERS' BULLETINS.

The following is a list of the Farmers' Bulletins available for distribution, showing the number, title, and size in pages of each. Copies will be sent free to any address in the United States on application to a Senator, Representative, or Delegate in Congress, or to the Secretary of Agriculture, Washington, D. C. Numbers omitted have been discontinued, being superseded by later bulletins.

22. The Feeding of Farm Animals. Pp. 40.
24. Hog Cholera and Swine Plague. Pp. 16.
25. Peanuts: Culture and Uses. Pp. 24.
27. Flax for Seed and Fiber. Pp. 16.
28. Weeds and How to Kill Them. Pp. 30.
29. Souring and Other Changes in Milk. Pp. 22.
30. Grape Diseases on the Pacific Coast. Pp. 15.
32. Silos and Silage. Pp. 30.
33. Peach Growing for Market. Pp. 24.
34. Meats: Composition and Cooking. Pp. 31.
35. Potato Culture. Pp. 24.
36. Cotton Seed and Its Products. Pp. 16.
39. Onion Culture. Pp. 30.
41. Fowls: Care and Feeding. Pp. 24.
42. Facts about Milk. Pp. 32.
44. Commercial Fertilizers. Pp. 38.
46. Irrigation in Humid Climates. Pp. 27.
47. Insects Affecting the Cotton Plant. Pp. 32.
48. The Manuring of Cotton. Pp. 16.
49. Sheep Feeding. Pp. 24.
51. Standard Varieties of Chickens. Pp. 48.
52. The Sugar Beet. Pp. 48.
54. Some Common Birds. Pp. 48.
55. The Dairy Herd. Pp. 30.
56. Experiment Station Work--I. Pp. 30.
58. The Soy Bean as a Forage Crop. Pp. 24.
59. Bee Keeping. Pp. 48.
60. Methods of Curing Tobacco. Pp. 24.
61. Asparagus Culture. Pp. 40.
62. Marketing Farm Produce. Pp. 31.
63. Care of Milk on the Farm. Pp. 40.
64. Ducks and Geese. Pp. 55.
65. Experiment Station Work II. Pp. 32.
66. Meadows and Pastures. Pp. 30.
68. The Black Rot of the Cabbage. Pp. 22.
69. Experiment Station Work-III. Pp. 32.
70. Insect Enemies of the Grape. Pp. 23.
71. Essentials in Beef Production. Pp. 24.
72. Cattle Ranges of the Southwest. Pp. 32.
73. Experiment Station Work--IV. Pp. 32.
74. Milk as Food. Pp. 39.
77. The Liming of Soils. Pp. 24.
78. Experiment Station Work--V. Pp. 32.
79. Experiment Station Work--VI. Pp. 27.
80. The Peach Twig-borer. Pp. 16.
81. Corn Culture in the South. Pp. 24.
82. The Culture of Tobacco. Pp. 22.
83. Tobacco Soils. Pp. 23.
84. Experiment Station Work--VII. Pp. 32.
85. Fish as Food. Pp. 32.
86. Thirty Poisonous Plants. Pp. 32.
87. Experiment Station Work—VIII. Pp. 32.
88. Alkali Lands. Pp. 23.
91. Potato Diseases and Treatment. Pp. 15.
92. Experiment Station Work—IX. Pp. 30.
93. Sugar as Food. Pp. 31.
95. Good Roads for Farmers. Pp. 46.
96. Raising Sheep for Mutton. Pp. 48.
97. Experiment Station Work—X. Pp. 32.
98. Suggestions to Southern Farmers. Pp. 48.
99. Insect Enemies of Shade Trees. Pp. 30.
100. Hog Raising in the South. Pp. 40.
101. Millets. Pp. 30.
102. Southern Forage Plants. Pp. 48.
103. Experiment Station Work—XI. Pp. 30.
104. Notes on Frost. Pp. 24.
105. Experiment Station Work—XII. Pp. 32.
106. Breeds of Dairy Cattle. Pp. 48.
107. Experiment Station Work—XIII. Pp. 32.
108. Saltbushes. Pp. 20.
109. Farmers' Reading Courses. Pp. 20.
110. Rice Culture in the United States. Pp. 28.
111. Farmers' Interest in Good Seed. Pp. 24.
112. Bread and Bread Making. Pp. 40.
113. The Apple and How to Grow It. Pp. 32.
114. Experiment Station Work—XV. Pp. 28.
115. Hop Culture in California. Pp. 28.
116. Irrigation in Fruit Growing. Pp. 48.
118. Grape Growing in the South. Pp. 32.
119. Experiment Station Work—XV. Pp. 30.
120. Insects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp 32.

ee Planting in Rural School Grounds. Pp. 32.
rghum Sirup Manufacture. Pp. 40.
rth Roads. Pp. 24.
e Angora Goat. Pp. 48.
rigation in Field and Garden. Pp. 40.
nmer: A Grain for the Semiarid Regions. Pp. 16.
neapple Growing. Pp. 48.
ultry Raising on the Farm. Pp. 16.
inciples of Nutrition and Nutritive Value of Food. Pp. 48.
nformation of Beef and Dairy Cattle. Pp. 44.
periment Station Work—XIX. Pp. 32.
rbon Bisulphid as an Insecticide. Pp. 28.
secticides and Fungicides. Pp. 16.
inter Forage Crops for the South. Pp. 40.
periment Station Work—XX. Pp. 32.
earing New Land. Pp. 24.
airying in the South. Pp. 48.
ables in Cattle. Pp. 32.
rchard Enemies in the Pacific Northwest. Pp. 39.
he Home Fruit Garden: Preparation and Care. Pp. 16.
ow Insects Affect Health in Rural Districts. Pp. 19.
e Home Vineyard. Pp. 22.
e Propogation of Plants. Pp. 24.
ow to Build Small Irrigation Ditches. Pp. 28.
ab in Sheep. Pp. 48.
ractical Suggestions for Fruit Growers. Pp. 30.
periment Station Work—XXI. Pp. 32.
ape as a Forage Crop. Pp. 16.
lkworm Culture. Pp. 32.
heese Making on the Farm. Pp. 16.
ssava. Pp. 32.
arl Millet. Pp. 16.
periment Station Work—XXII. Pp. 32.
rinciples of Horse Feeding. Pp. 44.
ale Insects and Mites on Citrus Trees. Pp. 43.
rimer of Forestry. Pp. 48.
room Corn. Pp. 30.
ome Manufacture and Use of Unfermented Grape Juice. Pp. 16.
ranberry Culture. Pp. 20.
uab Raising. Pp. 32.
sects Injurious in Cranberry Culture. Pp. 32.
orseshoeing. Pp. 30.
runing. Pp. 39.
oultry as Food. Pp. 40.
eat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
arketing Live Stock. Pp. 40.
eautifying the Home Grounds. Pp. 24.
xperiment Station Work—XXIII. Pp. 32.
rainage of Farm Lands. Pp. 38.
eeds used in Medicine. Pp. 45.
xperiment Station Work—XXIV. Pp. 32.
arnyard Manure. Pp. 32.
xperiment Station Work — XXV. Pp. 32.
lfalfa Seed. Pp. 14.
nnual Flowering Plants. Pp. 48.
sefulness of the American Toad. Pp. 16.
nportation of Game Birds and Eggs for Propagation. Pp. 30.
trawberries. Pp. 24.
orn Growing. Pp. 32.
urkeys. Pp. 40.
ream Separator on Western Farms. Pp. 23.

202. Experiment Station Work — XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
205. Pig Management. Pp. 40.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
216. The Control of the Boll Weevil. Pp. 32.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work—XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
240. Inoculation of Legumes. Pp. 8.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. 36.
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
251. Experiment Station Work—XXXIV. Pp. 32.
252. Maple Sugar and Sirup. Pp. 36.
253. The Germination of Seed Corn. Pp. 16.
254. Cucumbers. Pp. 30.
255. The Home Vegetable Garden. Pp. 47.
256. Preparation of Vegetables for the Table. Pp. 48.
257. Soil Fertility. Pp. 39.
258. Texas or Tick Fever and Its Prevention. Pp. 45.
259. Experiment Station Work — XXXV. Pp. 32.
260. Seed of Red Clover and Its Impurities. Pp. 24.

261. The Cattle Tick. Pp. 22.
262. Experiment Station Work—XXXVI. Pp. 32.
263 Practical Information for Beginners in Irrigation. Pp. 40.
264. The Brown-tail Moth and How to Control It. Pp. 22.
265. Game Laws for 1906. Pp. 54.
266. Management of Soils to Conserve Moisture. Pp. 30.
267. Experiment Station Work—XXXVII. Pp. 32.
268. Industrial Alcohol: Sources and Manufacture. Pp. 45.
269. Industrial Alcohol: Uses and Statistics. Pp. 29.
270. Modern Conveniences for the Farm Home. Pp. 48.
271. Forage Crop Practices in Western Oregon and Western Washington. Pp. 39.
272. A Successful Hog and Seed-Corn Farm. Pp. 16.
273. Experiment Station Work—XXXVIII. Pp. 32.
274. Flax Culture. Pp. 36.
275. The Gipsy Moth and How to Control It. Pp. 22.
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 40.
278. Leguminous Crops for Green Manuring. Pp. 27.
279. A Method of Eradicating Johnson Grass. Pp. 16.
280. A Profitable Tenant Dairy Farm. Pp. 16.
281 Experiment Station Work—XL. Pp. 32.
282. Celery. Pp. 36.
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. 42.
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. 48.
285. The Advantage of Planting Heavy Cotton Seed. Pp. 16.
286. Comparative Value of Whole Cotton Seed and Cotton-Seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. Pp. 48.
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. Pp. 30.
295. Potatoes and Other Root Crops as Food. Pp. 45.
296. Experiment Station Work—XLI. Pp. 32.
297. Methods of Destroying Rats. Pp. 8
298. Food Value of Corn and Corn Products. Pp. 40.
299. Diversified Farming Under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-grown Tea. Pp. 16.
302. Sea Island Cotton: Its Culture, Improvement, and Diseases. Pp. 48.
303. Corn Harvesting Machinery. Pp. 32.
304. Growing and Curing Hops. Pp. 39.
305. Experiment Station Work—XLII. Pp. 32.
306. Dodder in Relation to Farm Seeds. Pp. 27.
307. Roselle: Its Culture and Uses. Pp. 16.
308. Game Laws for 1907. Pp. 52.
309. Experiment Station Work—XLIII. Pp. 32.
310. A Successful Alabama Diversification Farm. Pp. 24.
311. Sand-clay and Burnt-clay Roads. Pp. 19.
312. A Successful Southern Hay Farm. Pp. 15.

Issued February 7, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 314.

A METHOD OF BREEDING EARLY COTTON TO ESCAPE BOLL-WEEVIL DAMAGE.

BY

R. L. BENNETT,

Special Agent of the Bureau of Plant Industry,
Collaborating with the Texas Agricultural
Experiment Station.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., October 14, 1907.

Sir: I have the honor to transmit herewith a manuscript entitled "A Method of Breeding Early Cotton to Escape Boll-Weevil Damage," by Mr. R. L. Bennett, a special agent of the Bureau of Plant Industry, collaborating with the Texas Agricultural Experiment Station, and recommend that it be published as a Farmers' Bulletin.

The governing board and officials of the Texas station have given every encouragement to this work, and it is due largely to their support and cooperation that valuable results have been so quickly secured.

The method of seed selection pursued in this collaborative work and described in this paper is especially valuable to the cotton growers in the region invaded by the weevil, as it will enable them to develop by their own efforts rapid-fruiting cotton, which is most important in producing a profitable crop.

The directions for seed selection are clearly presented by Mr. Bennett and will be readily understood by growers.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

ILLUSTRATIONS.

Page.

FIG. 1. An early, rapid-fruiting, productive type of cotton plant, with low fruit limbs, short joints, and continuous-growing, long fruit limbs ---------- 7

2. Another early, rapid-fruiting, productive type of cotton plant, having characters similar to those shown in figure 1 ---------- 8

3. A third early, rapid-fruiting, productive type of cotton plant, having characters similar to those shown in figures 1 and 2 ---------- 9

4. A late, slow-fruiting, unproductive type of cotton plant, with high fruit limbs and long joints ---------- 10

5. Another late, slow-fruiting, unproductive type of cotton plant, with characters similar to those shown in figure 4 ---------- 10

6. A third late, slow-fruiting, unproductive type of cotton plant, with characters similar to those shown in figures 4 and 5 ---------- 11

7. A fourth late, slow-fruiting, unproductive type of cotton plant, with characters similar to those shown in figures 4, 5, and 6 ---------- 11

8. Big-boll and small-boll continuous-growing fruit limbs and short determinate and cluster types of fruit limbs ---------- 13

9. A short, determinate fruit limb type of cotton plant ---------- 14

10. A small-leaf type of cotton plant ---------- 15

11. A very large leaf type of cotton plant ---------- 15

12. Progeny rows showing defoliate and foliate rows of early rapid-fruiting types of cotton ---------- 16

13. Cotton plant bred for unproductiveness and late fruiting ---------- 16

14. Small, non-stormproof, open cotton bolls ---------- 18

15. Large, thick, stormproof, open cotton bolls ---------- 18

16. Cotton bolls showing distinct differences in size. Large boll on right, 40 to the pound; medium boll in center; small boll on left, 90 to the pound ---------- 19

B. P. I.—320.

A METHOD OF BREEDING EARLY COTTON TO ESCAPE BOLL-WEEVIL DAMAGE.

INTRODUCTION.

The growing of early and rapid fruiting cotton is most important to escape damage from the boll weevil. This insect, which first appeared in south Texas and rapidly spread north and east, has certain habits in relation to the cotton plant which make the production of early cotton imperative. Weevils do practically no injury to the stem or leaf, only injuring and destroying the young squares or fruit, and in normal seasons most of the adults that survive the winter are out of hibernation at about the time the cotton begins to set squares. Then a race begins between the cotton in setting squares and the weevils in multiplying and destroying the squares. The cotton plant must, therefore, make fruit faster than the weevils can increase in number and destroy it.

The weevil feeds on squares and propagates in them, but does not injure bolls of any size until the squares are nearly all destroyed. The total destruction of squares occurs late in the season, when the weevils are greatly increased in numbers. When this happens the weevils begin feeding upon the youngest or latest bolls, but at this time the older bolls, whether open or not, are safe from injury. Danger to the late bolls increases with the increase in the number of weevils present. The hasty opening of bolls is not an important factor in the crop's escape from weevil damage.

Squares generally fall from the stalk shortly after being punctured, and this removal of the young fruit from slow-fruiting and late-maturing cotton induces under favorable moisture and plant food conditions a prolonging of the vegetative growth and the setting of squares that serve as food and propagating places for an increasing number of weevils to go into hibernation when frost occurs. These habits of the weevil compel cotton growers to plant a cotton that has early and rapid fruiting qualities and the additional quality of maturing the plant as nearly as may be possible under the prevailing soil-moisture and plant-food conditions.

Until the weevil appeared, Texas growers enjoyed a long growing season and generally grew the slow and late maturing cottons. When the rapid spread of the weevil created an urgent and immediate demand for early and rapid fruiting strains, growers were unable to obtain in Texas or from any other source such cottons with other desirable qualities as well, and, moreover, there was an absence of information concerning many features of the cotton plant that affect or were supposed to affect earliness. The growers therefore sought relief from these conditions by importing from the northern and the northeastern edge of the cotton belt thousands of carloads of seed of the small-boll early-opening cotton. This imported seed being non-stormproof and of inferior staple qualities was wholly unsuited to Texas conditions.

Before any cotton-breeding investigations were begun it was generally believed that a large-boll cotton, such as the native Texas cottons, could not be grown early enough to escape the weevil. Likewise it was believed that good staple cotton could not be early. It was a question, also, whether early qualities in cottons could be maintained in Texas with its long seasons, and whether new seed would have to be frequently imported; also, whether northern seed was earlier than southern seed. Such were the conditions and some of the questions before cotton growers in Texas four years ago.

In 1904 the writer began cotton-breeding investigations and cotton breeding in Texas under the first Congressional appropriation for boll-weevil work. At the end of the first season's work, in September, 1904, a statement of results of the investigations was published for the information of growers in selecting seed for the next crop. The results were to the effect that Texas cotton growers need not import early cotton to escape weevils. The investigations showed that early cottons of superior quality could be obtained from native big-boll, good staple Texas cottons on any grower's farm by selecting seed from plants of a type that could be recognized by certain distinguishing characters, which were described in the press reports. A report was also issued in a bulletin in October, 1904. At the close of the next or second season's investigation, 1905, press reports were made and a second brief bulletin issued on the results of the second season's work.

The results of four years' investigations are now completed, and early cottons have been bred and the method for seed selection developed. The results of this work show that growers may by seed selection develop or maintain early fruiting, rapid fruiting, and productiveness in their cotton to escape weevils, and that the method of seed selection for developing such qualities in the cotton plant is easy and inexpensive in practice. One selection rightly made from the proper type of plant increases earliness and productiveness to a surprising extent. The method may be employed to the greatest advantage by growers east of Texas before the weevil arrives in that section—and that it will go farther east there is no doubt since it is making advances annually. Growers immediately east of Texas are urged, therefore, to practice the method of seed selection herein described and save themselves losses such as the Texas growers sustained when the weevil was advancing through Texas. They may also save themselves the expense of importing seed when the weevil does arrive.

In reporting the results of the work the discussion of details that are familiar to cotton growers is omitted in order to restrict the bulletin to reasonable length.

THE DISTINGUISHING CHARACTERS OF PLANTS OF EARLY AND RAPID FRUITING COTTON.

"Early cottons" and "earliness" were the terms used almost exclusively to describe plants that opened their bolls early, or that opened before frost or before other cottons. The other cottons were called "late," since they opened so late that they were in danger of frost. But a different meaning must be given to "earliness" when the boll weevil is considered. The insect shortens the season for making or maturing fruit, but this fact does not require, as has been previously explained, that the bolls should open early to escape damage. Owing to the habits of the weevil the plant must begin to set fruit early and set it rapidly, and this is the meaning of the term "early cotton" as used in this bulletin.



FIG. 1.—An early, rapid-fruiting, productive type of cotton plant, with low fruit limbs, short joints, and continuous-growing, long fruit limbs. (Leaves removed.)

The cotton plant is made up of a main stem, wood or primary limbs, fruit limbs, leaves, and fruit. The main stem and the wood and fruit branches are divided into joints, or nodes. At each joint a leaf is formed, and at each joint on the fruit limbs fruit is set.

In studying the many plants of all standard varieties and of nameless cottons it was observed in these investigations that the plants that set fruit early had low fruit limbs—that is, sent out the first fruit limbs at the joint nearest the seed-leaf joint. Figures 1, 2, and 3 show plants with low fruit limbs, while late fruiting plants are shown in figures 4, 5, 6, and 7.

It was also observed that the plants that set fruit rapidly (that is, set much fruit in a short period of time) had short joints or internodes in the main stem and fruit limbs. Figures 1, 2, and 3 show short-jointed plants, while figures 4, 5, 6, and 7 show long-jointed plants.



Fig. 2.—Another [illegible] rapid fruiting [illegible]

The short-jointed plants with low fruit limbs grew as fast during the first part of the growing season as the long-jointed plants, and in the same period of time set many more squares. This equal growth continued until considerable seed began to form in the lower or oldest fruits. Then as the reproductive process increased in the short-jointed or more fruitful plants their rate of growth fell behind that of the long-jointed plants. The powers of short-jointed plants are at this stage devoted more largely to the growth of seed, while the long-jointed plants are making few seeds and hence continue a more rapid vegetative growth provided soil water is sufficient, which sometimes is not the case. [illegible] time the weevils [illegible] numerous as to de- [illegible] squares as fast as [illegible] plant matures its [illegible] the long-jointed [illegible] little fruit, although [illegible]

[illegible] fruiting season the [illegible] good yield, since they [illegible] the fruit by growing [illegible] plants fruit rapidly at [illegible] must begin at the first part of the growing season at the base of the plant and not at the latter part of the season at the top of the plant.

The rate of growth is very important for the rapid setting of fruit, and as some individual plants of either the long-jointed or short-jointed types grow faster than other plants of the respective types it is important to select seed from the largest plants of the character or type desired.

Another important character of early rapid-fruiting plants was found, namely, the continuous growing of the fruit limbs. This feature is of great importance for a maximum production in a short time. The terminal bud of the first fruit limb and of all subsequent fruit limbs should continue to grow and set squares, or fruit, until the entire plant ceases to grow. With fruit limbs of such a character the main stem may not grow so tall, but the continuous-growing fruit limbs make more fruit early in the lower part of the plant than either a determinate or cluster fruit-limb type. (Fig. 8.) Where there are weevils, continuous-growing fruit limbs are a great advantage in making a large quantity of early fruit. The quality has still another advantage as regards this insect, namely, the weevil seems instinctively to feed on the squares higher up the plant and thereby very often allows late-set squares to make bolls on the lowest continuous-growing fruit limbs. The continuous-growing fruit-limb type is shown in figures 1, 2, and 3. The short or determinate (or objectionable) fruit-limb type is shown in figure 9. The latter type may set and mature two or four bolls on the lowest or first fruit limbs, whereas the continuous fruit limbs may mature from six to eight or more.



FIG. 3.—A third early, rapid-fruiting, productive type of cotton plant, having characters similar to those shown in figures 1 and 2. (Leaves removed.)

The low first fruit limbs and short joints and the continuous fruit limbs which were first described by the writer in the press in September, 1904, and later, in October, 1904, in a bulletin, as a guide in seed selection, are distinguishing characters of early rapid-fruiting cotton plants. By these characters the grower can distinguish early and rapid-fruiting plants, and in selecting plants for seed he may select them at any time after fruiting has well begun or may delay selection until all bolls are open.



FIG. 4.—A late, slow-fruiting, unproductive type of cotton plant, with high fruit limbs and long joints. (Leaves removed.)

A medium-sized leaf, about 6 inches across at right angles to the midrib, is as large as a leaf should be for upland soil. Larger leaves mean too great vegetative vigor, and they prevent in large plants the sunlight from reaching the lowest bolls and opening them. A still smaller leaf, 4 to 5 inches across the midrib, is shown in figure 10. This is a desirable size for deep, fertile bottom soil, where still less vegetative growth and the admission of more sunlight at the base of the plant are desirable. An undesirable large leaf is shown in figure 11.

THE INDIVIDUAL COTTON PLANT AND ITS PROGENY.

The cotton plant in seed selection was studied with respect to its features as an individual and not considered as a variety. Its economic features are seed and lint, and the production of these in the greatest quantity is the desire of the grower. Other features that affect the economic characters are the size of the boll, the size of [illegible]

[illegible] slow-fruiting, unproductive [illegible] with characters similar to [illegible] (Leaves removed.)

[illegible] by insects. This

ormity is a most fortunate fact, since it enables growers to ob-
in a marked degree by
seed selection the quali-
of early and rapid fruit-
and maturity of plants
ssary for escaping boll
ils. Any crossing that
vary the progeny is per-
caused entirely by in-
and is of little or no
quence within the type
neral farm selection.

this work some hundreds
lants were selected and
eed of each mother plant
planted separately in a
e row of one-fiftieth of
cre, with equal spacing
similar treatment for all
The plants in each
were uniform in appear-
The variation in the
may be seen in figure 12, which shows rows differing distinctly in the time of maturing. In like manner the rows differed in the time of opening their ripened bolls and in the yield of seed cotton, as is shown by the one-half acre of rows reported upon in Table I, page 12. The planting was done between April 10 and 13, and the first picking took place on September 7, 1906.


FIG. 6.—A third late, slow-fruiting, unproductive type of cotton plant, with characters similar to those shown in figures 4 and 5.

When the seeds were planted from these first-year progeny rows they made plants of the second year like their parents, thus showing that the plants continue to breed true to their type.

The character of productiveness of fruit in the parent plant appeared uniformly in the second-year progeny. The seed of plants selected for short joints early maturity of the plants produced like characters in t

.—A fourth late, slow fruiting, unpro-
ive type of cotton plant, with char-
rs similar to those shown in figures
, and 6. (Leaves removed.)

second-year progeny. The progeny of plants of long-jointed, slow-fruiting, unproductive types was also uniform in likeness to the parents, as is shown in figure 13. The plant illustrated is two generations from an unproductive mother plant and grew in a row near and is of the same age as the plant shown in figure 2, which is a short-jointed productive type. The latter is the second generation from a short-jointed parent. Hitherto it has been generally believed that soil water controlled the length of joint, but these results show that heredity mainly controls, and that where water affects the length it affects similarly the long-jointed and the short-jointed types of plants. The first and second progeny resembled the seed parent, whether short jointed or long jointed. Low fruit limbs at joints nearest in number of joints to the seed-leaf joint, a very important quality, appear uniformly in the progeny.

TABLE I.—*Yield of progeny rows of cotton plants in selection tests covering one-fiftieth of an acre each.*

Number of row.	Average height.	Yield at first picking.	Yield at second picking.	Total yield.
	Feet.	*Pounds.*	*Pounds.*	*Pounds.*
39	2½	27⅜	6	33⅜
4	3	31	4	35
37	3	28	4½	32½
8	3¼	34	5	39
10	2¾	32	4	36
21	3½	33	6	39
32	3½	32	8	40
67	3¾	25	11	36
65	2½	30	3	33
100	3¾	26	10	36
124	3	31	8	39
131	3½	26	14	40
88	4½	24	14	38
98	4	26	15	41
129	2½	28	3½	31½
52	3	27	7	34
55	2½	24	¾	24¾
47	3½	33	12	45
24	3¼	31	5	36
118	4	29	12	41
135	3½	30	9	39
103	3¼	37	7	44
127	3¾	28	9	37
8 1	3½	22	15	37
17 1	3¼	27	13	40
Yield on the half acre				927
Yield to the acre				1,854

The continuous growth of the fruit limbs, also an important quality, is uniformly present in the product of such a mother or seed plant. This uniformity of transmission is likewise constant as regards such qualities as the length of staple, size of boll, number of locks, and percentage of lint. Each of these features costs nothing in itself, yet adds profit to the crop.

The number of locks in a boll, however, does not always appear to be the same as in the parent plants. The variation from five-lock bolls in the parents to four-lock bolls in some cases in the progeny plants may be due to seasonal influences, since the progeny seed y the following season produce almost exclusively five-lock bolls. e same seasonal variation occurs in the percentage of lint to seed. ese seasonal variations, however, do not affect the general increase seed selection of five-lock bolls, the percentage of lint, or the nsmission of such qualities to the progeny.

The uniformity of progeny in resemblance to the parent has been favoring factor in the introduction of the large number of va- ties of American Upland cotton, many of which have no merit or use for having been produced, the feature distinguishing them m other varieties being often some unimportant detail in appear- e of leaf or in a determinate or cluster character of fruit limb.



. 8.—Big-boll (1) and small-boll (2) continuous-growing fruit limbs and short determinate (3 and 4) and cluster (5) types of fruit limbs.

The uniform transmission of characters is of the greatest impor- ice to the general cotton grower, because it assures him that by seed selection he can largely increase the desirable qualities of cotton.

E TYPE RECOMMENDED FOR EARLY, RAPID FRUITING, AND FOR PRODUCTIVENESS TO ESCAPE WEEVILS.

The type wanted must be clear in the mind of the grower in order it he may recognize the most perfect plants of the desired type when searching for them in his field or seed patch. From the description previously given of the distinguishing characteristics of an early, rapid-fruiting, productive cotton, it is easy to state the type in specific terms.

(1) The first fruit limb must be low, not higher than the fifth or sixth joint above the seed-leaf joint.

(2) The wood or primary limbs must be low, and it is desirable that they should not exceed four in number. The first limb should not be higher than the fifth or sixth joint above the seed-leaf joint.

(3) The joints in the main stem, in the fruit limbs, and in the primary limbs must be short, not exceeding 1 to 3 inches in the lower part of the plant.

(4) Fruit-limbs should grow at the successive joints of both the main stem and the wood limbs.



(5) Fruit limbs should be continuous in growth for continuous fruiting until the plant is matured.

(6) The largest leaves should not be wider than 5 or 6 inches across at right angles to the midrib.

Other qualities which do not affect early and rapid fruiting, but which add greatly to the profits of the crop, are size of boll, percentage of lint, length of fiber, and storm resistance.

Picking can be done more rapidly and less trash will be gathered with the cotton [illegible] boll is large. Large [illegible] covering is thick and [illegible] locks unsupported [illegible]

[illegible] of lint as possible. [illegible] varieties that give [illegible] however, seems to [illegible] for lint, as much [illegible] on a seed of good [illegible]

fiber should not be less than an inch long, and this length is
nt for general
ses. For spe-
urposes of finer
facture longer
is required, but
quantity called
relatively small
npared with the
requirement for
staple. Fiber
shorter than 1
can be and is
but were there
of such short
its value rela-
o that of 1-inch
would be less
is ordinarily the



FIG. 10.—A small-leaf type of cotton plant.

leaf has no
t value, but if
ge—more than 6 inches across at right angles to the midrib in the largest leaves—it prevents the drying of the lower bolls and, where the plant is large, causes the loss of bolls by rotting.



IG. 11.—A very large leaf type of cotton plant.

The type of which the foregoing is a description is shown in figures 1, 2, and 3.

As before explained and as may be seen in Table I, the opening of the bolls of one plant earlier than those of another does not indicate superiority in escaping weevils. The weevil stops all the most is the one that best escapes the weevil, regardless of the date of opening. Large-boll cottons rarely begin to open as early as some



FIG. 12.—Progeny rows showing defoliate and foliate rows of early rapid-fruiting types of cotton.

small-boll cottons, though both begin setting fruit at the same time. But notwithstanding the few days' delay which may occur in the opening of the large bolls, some large-boll progeny rows in our experiments yielded more cotton than the small-boll early-opening progeny rows. (Compare rows 8 L and 17 L with rows numbered 129 and 55 in Table I.) This point as to the opening of bolls is specially emphasized and explained because a large boll is more desirable for many reasons than a small-boll cotton [illegible] preferred by growers [illegible] ers. The belief was general when this work [illegible] that the opening of bolls [illegible] days earlier than [illegible] other varieties was of [illegible] in escaping weevils, [illegible] earliest opening cotton had large bolls, [illegible] could not be grown

to yield successfully where there were weevils. Moreover, it was thought that the simultaneous setting of squares on different cottons should be followed by the simultaneous opening of their bolls. A similar belief equally erroneous would be that cottons setting squares at the same time should have bolls of the same size, shape, etc. The most successful escape from weevils is indicated by yield and not by the date of the first open boll or by greater yield at the first picking, and large-boll cottons have been bred in this work to fruit early and rapidly and to escape weevil damage as successfully as any small-boll cotton that opens all its bolls ten days or two weeks earlier.

SEED SELECTION FOR EARLY, RAPID FRUITING, AND FOR PRODUCTIVENESS TO ESCAPE WEEVILS.

Seed selection is generally believed to be a long process, one where a little progress toward improvement is made each year and in the course of several years the desired result may be obtained. This breeding work with cotton has shown that in the first selection from the right type of plants a marked increase can be secured in early fruiting, rapid fruiting, and productiveness, combined with good-sized bolls, a good average percentage of lint, and a good length of staple. If growers wish to develop such qualities or to maintain them in a cotton they can do so by pursuing the method of seed selection here recommended. They can by one year's selection largely increase the early, rapid-fruiting qualities in a cotton and obtain a crop that will successfully escape serious weevil damage.

For the best results a grower should make his selections from a cotton that conforms nearest to the type for boll-weevil conditions. There are many varieties that are far from this type, and to begin selection from them would be a decided disadvantage. Texas growers prefer a large-boll cotton, 50 to 60 bolls to a pound. The bolls of many varieties are so small that it takes 90 of them to yield a pound of cotton (fig. 16) and picking is necessarily slow.

There is a disposition on the part of many growers to judge the yielding quality by the eye when all the bolls are open. This practice is extremely deceptive with a small-boll small-leaf cotton as compared with a large-boll medium-leaf cotton. The latter shows less bolls than it really has because of its larger leaf, and it may have fewer bolls but exceed the yield of the smaller boll cotton. Only with scales can a considerable difference in yield be determined.

After all bolls are open, the stalks of the type are selected and all the largest bolls around the center of the stalk should be picked for seed. All bolls at the top and ends of the limb, whether open or not, may be rejected—perhaps about one-third of all the bolls—only about two-thirds being picked. Around the center of the plant the most perfectly matured and largest bolls are grown, and their seeds are heavy, well developed, and well matured. In rejecting the smaller and defective bolls all weak and light seeds are excluded. Where growers plant seed from the first picking of all bolls without any selection as to either plants or bolls, they get seed from all kinds of stalks and bolls, and get heavy and light seed, making an average grade of seed and an average yield.



FIG. 14.—Small non stormproof, open cotton bolls.

Growers generally consider seed selection a heavy task, and it would be so if enough seed were carefully selected to plant a grower's entire crop, but selection on a large scale is unnecessary. A grower cultivating 50 acres of cotton and planting 1 bushel of seed to the acre, which is the quantity generally used, would require 50 bushels of seed. This quantity of seed should be grown on a seed patch, which should be made to produce as much as three fourths of a bale to the acre, by using either good soil or fertilizer. Thus 1,200 pounds of seed cotton would yield 800 pounds of



FIG. 15.—Large, thick, stormproof, open cotton bolls.

seed, and by picking only two-thirds of the crop for seed the yield would be 533 pounds, or 18 bushels of planting seed to the acre.

A seed patch of only 3 acres would make 54 bushels, or 4 bushels more than enough to plant a grower's 50 acres of general crop. To search carefully for enough type plants to plant the 3-acre seed patch is a small task. One peck of seed to the acre is enough, and 24 pounds, or 3 pecks of seed, represent 36 pounds of seed cotton to be picked from type plants. Should the type plants yield one-fifth or one-fourth pound each, it would mean finding and picking 180 or 144 type plants. The first year's selection of the 200 type plants could be made from the general crop, and selections after the first year would be from the 3-acre seed patch. After selecting and picking enough type plants to plant the seed patch, two-thirds of the remainder is picked to plant the general crop. Should a grower cultivate 100 acres a 6-acre seed patch would be needed.



FIG. 16.—Cotton bolls showing distinct differences in size. Large boll on right, 40 to the pound; medium boll in center; small boll on left, 90 to the pound.

In general seed selection the plants may be selected and picked together and not kept and planted separately, but where the grower is disposed to give the necessary time and care to the matter the seed of each of the 200 or 300 type plants may be planted in separate rows to determine through the progeny the individual plant that has the greatest producing power. In this case the seed patch is not planted until the second year, and it is then planted with the seed of the row that produced the most cotton. The producing power of the mother plants varies, as shown in the yield of progeny rows in Table I, but growers will get increased earliness and productiveness by one selection of seed plants without growing them separately. Owing to the details and care involved in determining the producing power of individual plants and in breeding for longer staple, finer quality, and high percentage of lint, on the other hand, such work is specialized and is more within the province of the breeder than of the general grower.

The usual description of planting seed offered for sale is the seller's assertion that the cotton made three bales or more per acre and that it is the best cotton on earth. Usually the seller's qualifications for judging cotton and his financial standing are unknown to the buyer. Many cotton growers have become skeptical of so-called improved seed, doubtless because of purchases from such sources. Where the grower finds it convenient to buy seed to plant his seed patch he should require the seller to state the qualities of the cotton in the terms of the type.

The size or diameter of boll in type or parent plants is easily measured by a caliper rule. A very sharp pointed boll is objectionable in picking, and a very round boll contains less cotton than an elongated boll of the same diameter. The height of the first fruit limb above the seed leaf joint and the fact that the fruit limbs are continuous in growth should be determined; also the length of joints of the fruit limbs and main stem and all other features specified in the type for early, rapid fruiting and productiveness.

Most of the long-staple varieties of Upland cotton have been developed for length of staple, and little attention has been given to early and rapid fruiting or to increasing the percentage of lint, but each of these qualities may be increased in long-staple cottons by seed selection from individual plants that have these qualities most highly developed.

Deterioration of the qualities in cotton comes about through nonselection of seed. Where seed selection is not pursued, the planting seed comes from both good and poor stalks, from immature, diseased, and insect-injured bolls, and from plants resulting from the crossing of good and poor varieties by insects.

If seed selection is not persisted in, high-grade seed will quickly deteriorate in productiveness and in other qualities. Failure to select seed accounts for the common complaint among growers that even seed that is very productive for the first few seasons soon declines.

EARLY AND RAPID FRUITING MEASURED BY THE YIELD OF THE SELECTIONS IN THE BOLL-WEEVIL DISTRICT.

After the type for early and rapid fruiting was determined in 1904, many individual plants conforming to this type were selected from a common Texas cotton, the name and history of which could not be learned. Its earliness and productiveness were above the average. Dr. J. H. Wilson, of Quanah, Tex., secured the seed in compliance with the request of the writer for a supply of seed of common Texas cotton. The results with a half acre of progeny rows planted with seed of parent plants are reported in Table I. The average yield to the acre of the progeny rows was 1,854 pounds, while the yield of Quanah common seed was 1,630 pounds. The gain in yield per acre was therefore 224 pounds.

The seed of the best yielding progeny rows was planted in 1907, and the plants were true to the type and characters of the parent progeny rows and to the original parent plant of each. The selections included parent plants of small, medium, and large boll types. Early, rapid-fruiting defoliate strains with medium bolls and early, rapid-fruiting nondefoliate strains with large bolls have been developed in this breeding work. Cottons for best results on very different soils and climates must be bred and developed on soil typical of the region where they are to be grown.

EARLY-MATURING DEFOLIATE COTTON.

In this work of breeding early cottons some strains matured their plants extremely early and shed their foliage a considerable time before frost. Two strains of this character, defoliates, are exhibited in figure 12. See also Table I, Nos. 65, 129, 39, and 55. These cottons deprive weevils of food and places for propagation and under certain conditions reduce the number of weevils at the latter end of the growing season which will go into hibernation and appear the next season.

This character at first seemed to offer useful possibilities in this respect, but in order for it to be effective the time between the maturity of the plants and the first frost must be sufficient to decrease the number of weevils by starvation and to prevent their propagation. The length of the growing season is not the same throughout the cotton belt or in the same place in all seasons, and therefore the period of fruiting of this cotton would of necessity have to be shorter in some sections or seasons than in others. Furthermore, such cottons, to be effective as regards the weevil, must have a limited period for making fruit, and as the seasons are not of the same length in different parts of the cotton belt and as climatic conditions prevent the weevils from being as numerous in some years as in others it is the conclusion of the writer, after developing and growing cottons of short and of long fruiting periods, that a cotton with a short fruiting period will not yield any more when weevils are numerous and will yield less when weevils are not numerous than a cotton with a longer fruiting period. Were there no winter season in the American cotton district to reduce the weevils, these very early maturing defoliate cottons would perhaps be of essential importance in reducing them.

Variation in rainfall and the occurrence of drought, high heat, a late spring, and early frost, together with irregular and indifferent planting and cultivation, are conditions that largely affect the crop. A cotton plant to yield a maximum amount under such varying conditions must not have a short and fixed fruiting period, but must begin fruiting early in the season of growth and must fruit rapidly and continue to set fruit until its growth and fruiting are brought to a close, as they will be when the weather conditions and length of season are normal by its inherent tendency to mature under the influence of its strong reproductive process acting upon the vegetative process and also by the influence of high heat and decreasing moisture. This early, rapid-fruiting cotton when planted early comes to some degree of maturity every season, but the degree of maturity varies with the time of planting and the climatic conditions that prevail toward the close of the growing season. It deprives the weevil under normal conditions of both food and squares to some extent and yet makes a maximum yield under the varying conditions. The early, rapid-fruiting, defoliate cotton yielded as much in 1907 when weevils were very numerous as the early, rapid-fruiting, nondefoliate or persistent fruiting cotton, but the latter yielded more in 1906 when weevils were not so numerous. The early-maturing defoliates Nos. 39, 65, 129, and 55 grew smaller, as may be seen in Table I, and yielded well, but produced less in 1906 than those progeny rows that were a little later in maturing. The latter never completely defoliate, but they practically stop growing and making squares before frost when planted early on upland at the place where developed, College Station, Tex. The indifferent planting and cultivation practiced on many farms would be more harmful to short-fruiting cotton than to longer fruiting cotton. The long-fruiting period of the cotton plant is the factor that has for all time enabled every degree of poor farming to produce cotton.

RESTRAINING RANK VEGETATIVE GROWTH BY SEED SELECTION.

On rich bottom land, growers have trouble on account of their cottons growing too rank or large. The lower bolls rot more or less and the plants grow out of all proportion to their yield. Seed selection was made to determine what could be done to restrain the size of plants. The selections were made in the King and Jones varieties and in an unknown variety. These cottons were growing on very rich river bottom land and the stalks were 7 to 9 feet tall. By careful search small plants were found of the King and Jones varieties, from 2½ to 3 feet in height and very full of open bolls. In the unknown variety there was very little difference in the height of the plants and no very small plants could be found.

Seeds were taken from the very small and from the large plants and in the following spring they were planted on bottom land and on hill land. The stand on the bottom land was destroyed by unfavorable weather, but the planting on the hill land or upland grew and exhibited the characters of the parents. The progeny of the small King plants grew to be 2 feet tall. The progeny of the large King plants grew to 3¾ feet tall. The progeny of the Jones variety from small plants grew to 2¼ feet tall and from large plants to 3¼ feet. The progeny of the unknown variety, in which no small plants were found, exhibited little difference in height. This lack of difference in the height of the progeny was in conformity with the parents of the unknown variety. In the King and Jones varieties the small progeny plants were more fruitful than the large ones. The latter had very long joints.

These differences in the progenies would undoubtedly have been greater if the plants had grown on bottom land. The conditions there would have favored and continued the strong vegetative growth of the large plants.

Growers may by seed selection limit the size of their plants either on bottom land or upland, and in doing so make them more fruitful. The selection must be from very small and fruitful plants.

CROSSING OR HYBRIDIZING.

Crossing is not difficult, though it is sometimes so regarded. Some growers have thought crossing to be the first essential to the improvement of the economic qualities of a staple crop, such as cotton. Crossing one plant with another is accomplished by simply transferring pollen of the flower of one plant to the receptive stigma of the flower of another plant after having first removed the pollen of the latter, if a self-fertile flower, to prevent its fertilizing the stigma. The flower is then covered to prevent fertilization from other sources. Crossing is practiced when it is desirable to add one quality or character of the plant of one variety to another or to make a new type with new combinations of characters or to increase vigor and productiveness. In the Upland cotton plant, where early and rapid fruiting and productiveness are wanted to escape the weevil, the grower need not concern himself with crossing. These qualities can be had by pursuing the method of seed selection described in this bulletin. The desired qualities in marked degree can be secured in one selection. If all the cotton growers in the South would follow this method of seed selection the increased yield of American cotton would be 10, and more likely 20, per cent.

TREATMENT TO INSURE A STAND OF EARLY-PLANTED COTTON.

Next in importance to early and rapid fruiting seed to escape weevil damage are early planting and an early stand. Every day of delay in planting after the earliest possible time to plant lessens the yield, especially in years when weevils are present in great numbers. The reduced cotton crop in Texas in 1907 was mainly due to failure and repeated failure to get or to keep a stand of cotton. The final planting that made the crop in a large part of the State was so late that the plants had but little time in which to make fruit before the weevils, which were favored by a very mild winter, became too numerous for the plants to fruit longer. Had growers succeeded in getting and keeping an early stand, a normal yield would undoubtedly have been obtained. The growers sustained a loss in the yield and a loss in replanting, besides paying the increased cost of cleaning the soil, which became very foul from delay of cultivation while waiting for seed to germinate a second and, in some localities, even a third time.

An early stand is so essential to a full crop and low cost of production that growers need to begin preparing the seed bed as soon as [illegible] finished [illegible] autumn. As winter rain is not always cer- [illegible] able in order that if there be any [illegible] one essential in getting [illegible] early stand, however, is [illegible] it is only certain when [illegible] otherwise the conditions [illegible] when rain and cold [illegible] occur to some ex- [illegible] stand in planting [illegible] observations and ex- [illegible] years of this breed-ng work, and as a result it is confidently believed that there need be o uncertainty in any season in either getting or keeping a stand in arly planting. Growers are urged to follow the suggestions and ractice the method of planting shown to be the best by experiments. This course will assure a stand, which is essential to escape weevils nd bollworms and to make a full yield.

FAILURE OF EARLY-PLANTED SEED TO COME UP CAUSED BY DEEP COVERING.

In the investigations referred to it was found that when good seed planted early failed to come up the failure was due to the depth of planting or to covering the seed too deeply. When early-planted seeds were covered more than an inch and rain and cold—not frost—followed, they failed to come up, although in some instances they had germinated, but when good seeds were planted early and covered very shallow, less than an inch, the stand came and remained regardless of rain and cold weather after planting.

Shallow covering is absolutely essential when planting is done very early, and the depth of covering should be less than an inch. Seeds planted shallow and covered less than an inch are warmed by the sun, and the air takes away surplus soil water, whereas when covered deeply they are not warmed by the limited heat of the sun of the early season and a rainfall followed by cold destroys them. The seed must be scarcely covered.

COTTON DYING AFTER COMING UP.

The weather immediately following early planting may not be too cold and wet for the stand to come up when the seeds are planted the ordinary way and covered deeply, but cotton often dies after coming up, especially when the weather is wet and cold. This appears to be due chiefly to the fact that the young plants have largely exhausted themselves in coming through the deep covering.

When the soil is not warm, more time is required for the young plants to come through the covering of earth, and the delay and extra energy that they have to expend in coming through the heavy covering exhausts them, they are more subject to damping-off, and in cold weather they frequently die. When the seeds are lightly covered and planted in the right way little time or energy is consumed by the plants in coming up. They are virtually up all the time.

A stand of early-planted cotton may be lost by long-continued unfavorable weather conditions. In such a case the stand can be strengthened and maintained by shallow cultivation of the beds while the cotton is coming up and by frequent cultivation thereafter if the moisture or rainfall permits. This treatment when it can be given dries and opens the soil, admits air and warmth, and aids the cotton in its resisting power and in growth until the weather conditions become more favorable. A light wood-frame side harrow, weighing not over 35 pounds, with either "duck foot" or plain harrow steel teeth, is the best tool.

When the seeds are planted in a sweep furrow the stand of young cotton is often lost in a wet, cold spring on account of the lack of drainage. This is especially true in sandy soils.

SOME EXPERIMENTS AND OBSERVATIONS.

On March 20, 1906, 20 acres were planted with nearly a bushel of seed to the acre, the seed being covered with about 2 inches of soil. As the soil was warm germination began very promptly, but a moderately heavy rainfall, followed by a few days of cold weather, destroyed all the seed in the soil.

On April 10, 1906, these 20 acres were replanted at the rate of 1 peck to the acre, the seed being covered from one-half to three-fourths of an inch, and at the same time 6 acres were planted and the seed covered about 2 inches. A stand was obtained on the 20 acres where the seed was lightly covered, while not so good a stand came on the 6 acres, but no cold, wet weather followed these plantings to affect the seed which was covered 2 inches.

The month of April, 1907, was colder than March, and in the first week of April 20 acres were planted at the rate of 4 pounds of seed to the acre. A good planter was used, and the covering was not over three-fourths of an inch in depth. All the seed came up and lived. In 1906, some of this land was in sorghum, some in corn, and some in cotton. The roughest of the land was the corn land, and because of its open nature, due to stalks and grass and the absence of winter rains, some of the young cotton plants died, their roots not being able to come in contact with firm soil. Where the seed bed was firm none of the plants died. This experience shows the importance of a firm seed bed.

On 3 acres of land selected seeds were hand-dropped in 1907, one seed every 3 feet, and scarcely covered. All the seeds came up except where occasionally a seed was covered too deeply. This planting on April 12 was followed by two weeks of cold and rain that would have prevented deeper covered seed from coming up.

There is generally more moisture in the soil to germinate and bring up early-planted seed than there is later in the season, and there would always be sufficient moisture to bring up the earlylanted seed if the soil or beds were harrowed so as to hold moisture nd destroy weeds and grass till planting time.

Very little warmth is required to germinate early-planted seed that s lightly covered.

Where the seed bed is not firm it is practically impossible to cover arly-planted seed to the right depth. It is also practically impossible to cover early-planted seed to the right depth when the overing is done with small plows on the planter unless they are so onstructed as to prevent them from going too deep, an almost impossible thing to do, especially on a one-horse planter.

For growers to carry out successfully these suggestions as to shallow covering and keeping a stand in early planting, three things are necessary:

(1) The seed bed must be firm and clean.

(2) The soil of the beds must be harrowed before planting and cultivated shallow while the seeds are coming up, if necessary, and as often thereafter as moisture permits.

(3) The planter used must be of the right type.

It is necessary to have a gauge wheel in the rear of the planter to regulate the depth of planting and to press the seed into direct contact with the firm undersoil, so that the soil moisture can enter the seed.

All planting seeds should be as free from lint as it is possible to gin them. They can then come in contact with the soil and readily absorb moisture and will germinate more quickly.

These results are given for early planting only and in rainy districts. Late planting is not to be considered in weevil districts and is therefore not discussed.

Seed planted early escapes the heavy packing rains that come later in the season, and when the planting is rightly done a stand is more certain than from late-planted seed.

An early stand of cotton is so important where boll weevils and bollworms are present that a cotton grower can not afford to neglect anything that will aid him in securing and maintaining an early stand.

SUMMARY.

Productive cotton is important regardless of the weevil, but under weevil conditions the planting of early, rapid-fruiting, productive cotton is imperative for the making of a profitable crop. The method of seed selection recommended may be followed by growers outside of the weevil district as well as by those within the infested territory.

By applying this method in selection, slow-growing and unfruitful plants are eliminated and the selected seed will produce an increased yield of seed cotton, an increased proportion of lint to seed, and a better quality of lint or fiber.

The cost to the cotton grower to make a general seed selection and propagate enough seed in a patch to plant 100 acres of general crop will not exceed $5.

While growers are able to improve their own cotton by applying the method of seed selection described in these pages, yet the recommendation is made that they secure seed from breeders or from other sources whenever seed superior to their own can be obtained.

Early planting is essential to the making of a full crop under boll-weevil conditions, and the treatment recommended for insuring a stand does not require any extra expense. By planting the seed very shallow, less than an inch, on a firm seed bed, an early stand can be secured and maintained.

FARMERS' BULLETINS.

following is a list of the Farmers' Bulletins available for distribution, g the number, title, and size in pages of each. Copies will be sent free to dress in the United States on application to a Senator, Representative, or te in Congress, or to the Secretary of Agriculture, Washington, D. C. rs omitted have been discontinued, being superseded by later bulletins.

Feeding of Farm Animals. Pp. 40.
Cholera and Swine Plague. Pp. 16.
nuts: Culture and Uses. Pp. 24.
for Seed and Fiber. Pp. 16.
ds; and How to Kill Them. Pp. 30.
ring and Other Changes in Milk. Pp. 22.
pe Diseases on the Pacific Coast. Pp. 15.
s and Silage. Pp. 30.
ch Growing for Market. Pp. 24.
ts: Composition and Cooking. Pp. 31.
to Culture. Pp. 24.
on Seed and Its Products. Pp. 16.
on Culture. Pp. 30.
ls: Care and Feeding. Pp. 24.
ts about Milk. Pp. 32.
mercial Fertilizers. Pp. 38.
gation in Humid Climates. Pp. 27.
cts Affecting the Cotton Plant. Pp. 32.
Manuring of Cotton. Pp. 16.
ep Feeding. Pp. 24.
dard Varieties of Chickens. Pp. 48.
Sugar Beet. Pp. 48.
e Common Birds. Pp. 48.
Dairy Herd. Pp. 30.
eriment Station Work—I. Pp. 30.
Soy Bean as a Forage Crop. Pp. 24.
Keeping. Pp. 48.
hods of Curing Tobacco. Pp. 24.
aragus Culture. Pp. 40.
keting Farm Produce. Pp. 31.
e of Milk on the Farm. Pp. 40.
ks and Geese. Pp. 55.
eriment Station Work—II. Pp. 32.
dows and Pastures. Pp. 30.
Black Rot of the Cabbage. Pp. 22.
eriment Station Work—III. Pp. 32.
ct Enemies of the Grape. Pp. 23.
entials in Beef Production. Pp. 24.
le Ranges of the Southwest. Pp. 32.
eriment Station Work—IV. Pp. 32.
k as Food. Pp. 39.
Liming of Soils. Pp. 24.
eriment Station Work—V. Pp. 32.
eriment Station Work—VI. Pp. 27.
Peach Twig-Borer. Pp. 16.
n Culture in the South. Pp. 24.
Culture of Tobacco. Pp. 22.
acco Soils. Pp. 23.
eriment Station Work—VII. Pp. 32.
as Food. Pp. 32.
rty Poisonous Plants. Pp. 32.
eriment Station Work—VIII. Pp. 32.
ali Lands. Pp. 23.
ato Diseases and Treatment. Pp. 15.
eriment Station Work—IX. Pp. 30.
ar as Food. Pp. 31.
d Roads for Farmers. Pp. 46.
sing Sheep for Mutton. Pp. 48.
eriment Station Work—X. Pp. 32.
gestions to Southern Farmers. Pp. 48.
ct Enemies of Shade Trees. Pp. 30.
Raising in the South. Pp. 40.
lets. Pp. 30.
thern Forage Plants. Pp. 48.
eriment Station Work—XI. Pp. 30.
es on Frost. Pp. 24.
eriment Station Work—XII. Pp. 32.
eds of Dairy Cattle. Pp. 48.
eriment Station Work—XIII. Pp. 32.
bushes. Pp. 20.
mers' Reading Courses. Pp. 20.
e Culture in the United States. Pp. 28.
mers' Interest in Good Seed. Pp. 24.
ad and Bread Making. Pp. 40.
Apple and How to Grow It. Pp. 32.
eriment Station Work—XIV. Pp. 28.

115. Hop Culture in California. Pp. 28.
116. Irrigation in Fruit Growing. Pp. 48.
118. Grape Growing in the South. Pp. 32.
119. Experiment Station Work—XV. Pp. 30.
120. Insects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and Other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp. 32.
134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
136. Earth Roads. Pp. 24.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing. Pp. 48.
141. Poultry Raising on the Farm. Pp. 16.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
143. Conformation of Beef and Dairy Cattle. Pp. 44.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
146. Insecticides and Fungicides. Pp. 16.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propagation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.
179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.

183. Meat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
184. Marketing Live Stock. Pp. 40.
185. Beautifying the Home Grounds. Pp. 24.
186. Experiment Station Work—XXIII. Pp. 32.
187. Drainage of Farm Lands. Pp. 38.
188. Weeds Used in Medicine. Pp. 45.
190. Experiment Station Work—XXIV. Pp. 32.
192. Barnyard Manure. Pp. 32.
193. Experiment Station Work—XXV. Pp. 32.
194. Alfalfa Seed. Pp. 14.
195. Annual Flowering Plants. Pp. 48.
196. Usefulness of the American Toad. Pp. 16.
197. Importation of Game Birds and Eggs for Propagation. Pp. 30.
198. Strawberries. Pp. 24.
199. Corn Growing. Pp. 32.
200. Turkeys. Pp. 40.
201. Cream Separator on Western Farms. Pp. 23.
202. Experiment Station Work—XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
205. Pig Management. Pp. 40.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
216. The Control of the Boll Weevil. Pp. 32.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work—XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
240. Inoculation of Legumes. Pp. 8.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and Their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-Out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. 36.
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
251. Experiment Station Work—XXXIV. Pp. 32.
252. Maple Sugar and Sirup. Pp. 36.
253. The Germination of Seed Corn. Pp. 16.
254. Cucumbers. Pp. 30.
255. The Home Vegetable Garden. Pp. 47.
256. Preparation of Vegetables for the Table.
257. Soil Fertility. Pp. 39.

258. Texas or Tick Fever and Its Prevention. Pp. 45.
259. Experiment Station Work—XXXV. Pp. 32.
260. Seed of Red Clover and Its Impurities. Pp. 24.
261. The Cattle Tick. Pp. 22.
262. Experiment Station Work—XXXVI. Pp. 32.
263. Practical Information for Beginners in Irrigation. Pp. 40.
264. The Brown-Tail Moth and How to Control It. Pp. 22.
265. Game Laws for 1906. Pp. 54.
266. Management of Soils to Conserve Moisture. Pp. 30.
267. Experiment Station Work—XXXVII. Pp. 32.
268. Industrial Alcohol: Sources and Manufacture. Pp. 45.
269. Industrial Alcohol: Uses and Statistics. Pp. 29.
270. Modern Conveniences for the Farm Home. Pp. 48.
271. Forage Crop Practices in Western Oregon and Western Washington. Pp. 39.
272. A Successful Hog and Seed-Corn Farm. Pp. 16.
273. Experiment Station Work—XXXVIII. Pp. 32.
274. Flax Culture. Pp. 36.
275. The Gipsy Moth and How to Control It. Pp. 22.
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 40.
278. Leguminous Crops for Green Manuring. Pp. 27.
279. A Method of Eradicating Johnson Grass. Pp. 16.
280. A Profitable Tenant Dairy Farm. Pp. 16.
281. Experiment Station Work—XL. Pp. 32.
282. Celery. Pp. 36.
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. 42.
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. 48.
285. The Advantage of Planting Heavy Cotton Seed. Pp. 16.
286. Comparative Value of Whole Cotton Seed and Cotton-Seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. (In press.)
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. Pp. 30.
295. Potatoes and Other Root Crops as Food. Pp. 45.
296. Experiment Station Work—XLI. Pp. 32.
297. Method of Destroying Rats. Pp. 8.
298. Food Value of Corn and Corn Products. Pp. 40.
299. Diversified Farming Under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-Grown Tea. Pp. 16.
302. Sea Island Cotton: Its Culture, Improvement, and Diseases. Pp. 48.
303. Corn Harvesting Machinery. Pp. 32.
304. Growing and Curing Hops. Pp. 39.
305. Experiment Station Work—XLII. Pp. 32.
306. Dodder in Relation to Farm Seeds. Pp. 27.
307. Roselle: Its Culture and Uses. Pp. 16.
308. Game Laws for 1907. Pp. 52.
309. Experiment Station Work—XLIII. Pp. 32.
310. A Successful Alabama Diversification Farm. Pp. 24.
311. Sand-Clay and Burnt-Clay Roads. Pp. 19.
312. A Successful Southern Hay Farm. Pp. 15.
313. Harvesting and Storing Corn. Pp. 29.

Issued January 11, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 315.

PROGRESS IN LEGUME INOCULATION.

BY

KARL F. KELLERMAN,
Physiologist in Charge of Soil Bacteriology and Water Purification Investigations,
AND
T. R. ROBINSON,
Assistant Physiologist, Soil Bacteriology and Water Purification Investigations, Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

P. I.—328.

'ROGRESS IN LEGUME INOCULATION.

INTRODUCTION.

The peculiar value of legumes for maintaining and increasing the rtility of soils is due to certain bacteria which develop nodules upon e roots of leguminous plants and which have the unique power of ndering the free nitrogen of the atmosphere available for plant owth. Without these bacteria, legumes, like other crops, exhaust soil of its combined nitrogen. In many regions certain types of se important bacteria are abundant in the soil; in other localities y must be imported, either by distributing soil from a field where y are known to be present or by using pure cultures of the proper ganisms grown under artificial conditions. The old method of porting the bacteria by distributing soil from fields containing m is not only expensive but there is very great danger of spreading eds and destructive crop diseases as well as the desirable bacteria. der modern conditions, therefore, it is wisest to depend chiefly on the intelligent manipulation of pure cultures for inoculating uminous crops.

HE USE OF PURE CULTURES OF NITROGEN-GATHERING BACTERIA.

Recent improvements in the methods of preparing and distributing re cultures for inoculating leguminous crops have obviated many the difficulties previously experienced in their use. The directions handling by the planter have been simplified and adaptations ve been made to meet varying conditions of field and plat experi-nts. The directions accompanying the cultures distributed under e present plan may be summarized as follows:

For cultures that are to be increased by the planter, in one gallon of clean ter, boiled and cooled, is dissolved a small quantity of sugar and the tablet ich is supplied with the small bottle of culture. The liquid culture in this all bottle is poured into the gallon of solution and the mixture is allowed to develop for twenty-four hours at a temperature of about 70° F., and is then ready for use.[a] The seed should be thoroughly moistened with this culture without being soaked, and should then be spread out to dry in a clean, shady place. It is an advantage, though not an absolute necessity, to dry immediately by mixing with the moist seed a small quantity of dry, sifted earth. Planting should follow as soon as practicable, using the same methods as for untreated seed.

It is sometimes desirable to treat the soil direct instead of treating the seed. The solution is then mixed with enough dry soil (preferably from the field to be inoculated) so that it will just moisten the soil. This treated soil is again mixed thoroughly with a larger quantity of soil—say, half a wagonload for an acre. The inoculated soil is then distributed evenly over the prepared ground and should be harrowed in at once to avoid exposure to sunlight.

In special cases the amount of culture supplied is largely increased, and this is to be used immediately instead of waiting twenty-four hours for development. If the quantity of seed to be treated does not exceed 12 to 15 pounds the user has simply to open the bottle at once and pour the contents upon the seed. If more liquid is needed to moisten a larger quantity of seed, water up to 1 gallon may be added, reckoning 1 quart to a bushel of seed.

APPLICATIONS FOR CULTURES.

As cultivated soils in any one place are usually well supplied with the nodule-forming organisms adapted to inoculate the legumes that have been grown successfully for many years in that region, very little benefit will be obtained from further inoculation. To guard against useless experiments and to make those carried out of value for future guidance, the applicant for inoculating material is required to fill out a blank form which asks for information in regard to the legume to be treated, date of planting, soil conditions, etc.

On the reverse of the application form a circular letter gives briefly the plan of the distribution. Attention is called to the fact that the bacteria are beneficial only in connection with legumes, such as the various clovers (including alfalfa), vetches, peas, and beans, and are not applicable to other farm or garden crops.

REPORTS OF RESULTS.

It is expected that each one who secures a culture for inoculating legumes will follow the directions carefully and report the results, whether a success or a failure, to the Bureau of Plant Industry. Blanks for this purpose are furnished at the proper time. The main facts desired for this report are quantity of seed (or area) planted and date of planting; whether the culture was applied to the seed or soil; how the land was fertilized; whether it was new land, an old field, or garden soil; the kind of crop previously grown; and whether the culture when applied was clear, faintly clouded, milky, or frothy.

---

[a] One gallon will treat at least three or four bushels of seed.

As to results, the roots should be examined to determine whether the nodules are present or absent and should be compared, if possible, with plants grown on ground not inoculated. In making this examination care should be taken in *digging* the plants not to detach the small root hairs. Plants simply pulled from the ground will usually be stripped of nodules along with the broken-off rootlets. Even with careful digging in compact soil it is necessary to examine the clumps of soil about the roots as well as the roots themselves. Any unusual conditions which appear to have affected the results of the experiment should be mentioned especially, together with information as to the general appearance and yield of the inoculated crop compared with the uninoculated portion or with previous experience with the same legume.

THE EFFECT OF SOIL CONDITIONS UPON LEGUME BACTERIA.

In the investigation of the results of inoculation the wide range of soils for which cultures have been furnished has brought out the complexity of the subject and developed many special problems. The constitution or character of the soil itself has been found to have an effect upon the growth of nodule bacteria, as well as upon the formation of nodules.[a] Some soils have a chemical composition distinctly unfavorable to the development of the introduced bacteria; other soils are so compact or retentive of moisture as to exclude air and thus be unfavorable to the growth of the bacteria and to nodule formation.

A study was made of the reports received from experimenters who used cultures for inoculating legumes to correlate, if possible, type and condition of soil, treatment, legume species, etc., for those showing favorable results and those showing unfavorable results. Two representative and widely grown legume crops were studied in this way—alfalfa and red clover. The only selection made in the reports chosen for this study was in taking all those received during the two calendar months of November and December, 1906. These were classified (as illustrated in the reports quoted on pages 15 to 19) into "successes" and "failures." The third class, of "doubtful" character, is not included in this statistical study. Success, as here used, means an observed increase in nodule formation showing benefit to the crop, while a failure is scored when attempted inoculation failed to produce nodules or produced so few as to be of no advantage to the plant. When natural inoculation proved abundant the experiment was set aside as inconclusive, as were also crop failures reported as due to poor seed, decidedly adverse season, and other factors clearly apart from the influence of inoculation. The reports, about one thousand in all, have been carefully studied, and the influence of the various factors upon nodule formation is expressed in terms of percentage in the following table:

---

[a] For a discussion of this, see Bulletin 100, Part VIII, of the Bureau of Plant Industry, U. S. Department of Agriculture.

TABLE I.—*Percentages of successful and unsuccessful inoculations under different soil conditions during November and December, 1906.*

Conditions of experiment.	Alfalfa.		Red clover.	
	Successes.	Failures.	Successes.	Failures.
	Per cent.	*Per cent.*	*Per cent.*	*Per cent.*
On new ground	81	19	95	5
On sand or sandy loam	75	25	87	13
On loam	70	30	88	12
On clay or clayey loam	65	35	92	8
On fallow or sod turned under	69	31	91	9
On old cultivated field soil	64	36	90	10
Crop new to the region	61	39	92	8

An examination of the data here shown does not warrant general conclusions of a positive character. Apparently none of the physical conditions reviewed are of great importance in determining the success or failure of inoculation. For the present, therefore, we must assume that such differences as exist in these particular cases, making one soil more favorable for inoculation than another, are, in part at least, biological, requiring more detailed investigation and experiment.

It is doubtless true that the cultures themselves have not always been in the most effective state at the time of use. With the safeguards observed at each point in their preparation and distribution, however, the cultures as they go from the laboratory are in a high state of efficiency. To secure the desired results they must of course be handled according to directions.

THE EFFECT OF INOCULATION UPON THE COMPOSITION OF THE CROP.

In some cases where there has been apparent failure to improve the legume crop, further examination may show a decided gain from inoculation. Even where the lack of nodule formation does not seem to hinder a healthy development of the plants careful comparisons from analyses have shown the greater protein content of those well supplied with nodules. The amount of nitrogen contained in a soy bean crop[a] was found in one case to be 113.55 pounds to the acre for the inoculated plants and 75.98 pounds to the acre for those not inoculated, yet the appearance in the fields was the same. With cowpeas, inoculated and uninoculated, the nitrogen was found to be 139.21 pounds to the acre for the former and 118.45 pounds for the latter. In each case, therefore, the inoculated crop, although apparently not improved, was in reality much more valuable for feeding or for green manure than the uninoculated crop.

In addition, it should be noted that with the inoculated plants the gain of nitrogen came largely from the air, while the plants lacking nodules drew upon the combined nitrogen of the soil. When the gain in nitrogen from inoculation is accompanied by largely increased plant growth the beneficial effect of nodule formation is, of course, most pronounced. Some chemical analyses[b] of Canadian field peas, inoculated and uninoculated, serve to show in a striking manner the comparatively rich growth of the inoculated peas. The plants bearing nodules had a nitrogen content of 2.29 grams per 100 of dry substance; the plants without nodules grown in the same soil had 1.60 grams per 100 of dry substance. The average dry weight of inoculated and uninoculated plants was 11.2 and 2.3 grams, respectively. It is evident, therefore, that the inoculated plants supplied more than seven times the amount of nitrogen furnished by those not inoculated, viz, 0.255 gram to the plant, as compared with 0.035 gram to the plant.

Similar results were obtained with wild hemp plants (*Sesbania macrocarpa*), inoculated and uninoculated.[c] Analyses[d] of the nodules themselves and of the roots from which the nodules were removed show that, though the noduled plants made a decided gain in nitrogen in both roots and tops, by far the highest percentage of nitrogen was found in the nodules themselves. The following table shows these figures in detail:

TABLE II.—*Occurrence of nitrogen in inoculated and uninoculated plants of the wild hemp.*

[Grams of nitrogen per 100 grams of dry substance.]

1. Roots, stripped of nodules	1.50
2. Nodules (from No. 1)	6.40
3. Tops (from No. 1)	2.09
4. Whole plants (inoculated, having numerous nodules)	3.01
5. Whole plants (not inoculated, no nodules)	1.71

---

[a] Grown at Agricultural College, Mich. For description, see Bulletin 224 of the Michigan Station.

[b] Analyses made by the Bureau of Chemistry, U. S. Department of Agriculture.

[c] Experiment carried on by Mr. David Fairchild, in charge of Seed and Plant Introduction for the Bureau of Plant Industry.

[d] Analyses made by the Bureau of Chemistry.

In view of the generally recognized importance of nitrogen to the growth of plants[a] the significance of the foregoing facts needs little emphasis. A difference between abundant nodule formation and the absence of nodules, which may affect the value of a legume crop in the ratio shown, can not fail to command attention when its bearing on successful farming is once realized. It is not enough merely to count yields in pounds or tons. The composition of crops for feed or green manure becomes in the light of these investigations a factor of importance.

GREEN MANURING AND INOCULATION.

Generally speaking, the experience of scientific farmers and the tests of agricultural experiment stations agree in ascribing an unusual benefit to succeeding crops from green manuring with leguminous crops, and this is clearly due in considerable degree to the nitrogen fixed by the root nodules and not to the length of the root system or other peculiarities of leguminous plants. Unfortunately, investigators have not given sufficient attention to the relative abundance or scarcity of nodules when experimenting with different leguminous crops for green manures. From the preceding data it is evident that legumes reach their maximum value as green manures only when abundantly supplied with nodules.

CONFUSION OF NEMATODE GALLS WITH NODULES.

Nematode galls, or root knots, are often mistaken for nodules, which they resemble in appearance. The nematode gall is extremely injurious, and in regions where it has been known to exist it is unwise to plant crops favorable to the development of the pest. Nearly all of the legumes should be avoided in such cases. This is important not only because the legumes susceptible to nematode attack are themselves injured, but chiefly because they furnish conditions favor- [illegible] multiplication of the nematode [illegible] ious menace to succeeding crops or [illegible] conditions they would scarcely [illegible] resistant varieties[b] upon which the [illegible] infested regions these re- [illegible] If a leguminous crop [illegible] apparently nodules makes a

---

[illegible] Agricultural Experiment Sta-

[illegible] resistant variety is the Iron [illegible] States the velvet bean (*Mucuna* [illegible] *mollis*) are valuable.

ickly growth, or if there is doubt as to whether a legume is inoculated or infested with nematodes, samples for examination should be orwarded to the Bureau of Plant Industry of the Department of Agriculture.

WHEN INOCULATION IS DESIRABLE.

Inoculation is desirable—

(1) If the soil has not previously borne leguminous crops.

(2) If legumes previously grown on the same land were devoid of nodules.

(3) If the legume to be sown belongs to a species not closely related to one previously grown on the same soil.

(4) If the soil produces a weak growth of legumes, even though their roots show some nodules.

It is significant of the relative value of pure culture inoculation that a high percentage of beneficial results is being obtained, not only where legumes new to the region are being tried, but where the ordinary legumes used in rotation have been inoculated, a phenomenon which is undoubtedly due to the increased virility of the nodule-forming bacteria resulting from the proper development of the pure cultures in the laboratory. It is also true that the crops following the inoculated legumes have in many cases shown gains not evident in the legume crop. The practice of inoculating is therefore justified where legumes are naturally inoculated but do not seem to reach their full vigor nor to give the best results as green manures.

WHEN INOCULATION IS USELESS.

Inoculation is of no value—

(1) If the legumes usually grown are producing average yields and the roots show nodules in abundance.

(2) If the soil is in such condition as to prevent the normal growth of the bacteria or of the leguminous plants.

(3) If the directions for handling the cultures are not studied carefully and followed intelligently.

(4) If the soil is acid and in need of lime. Liming to correct acidity is as important for the proper activity of the bacteria as for the growth of the plants.

(5) If the soil needs fertilizers, such as potash, phosphoric acid, or lime. The activity of the nodule bacteria in securing nitrogen from the air and rendering it available to the legumes will not take the place of such fertilizing elements as potash and phosphorus.

It must be remembered that inoculation will not overcome results due to bad seed, improper preparation and cultivation of the ground, and decidedly adverse conditions of weather or climate. Befo attempting to inoculate a new crop the farmer should first inform himself thoroughly concerning the proper handling of the crop itself; otherwise failure is almost certain. As an illustration, sowing alfalfa on hastily prepared land, on land foul with weeds, and on acid soils or soils underlaid with hardpan, is contrary to accepted practice.

Free publications covering the essential points in growing all common legumes may be obtained from the State experiment stations and from the United States Department of Agriculture.

DANGER IN INOCULATION BY SOIL TRANSFER.

Very satisfactory inoculations have been obtained by transferring soil from old fields where legumes have been grown, but there are dangers incident to such soil transfer which should be noted.

The source of supply should be very definitely known, and in no case should soil be used from fields which have previously borne any crops affected with a fungous disease, a bacterial disease, or with nematodes. Numerous animal and plant parasites live in the soil for years and are established in so many localities that it is manifestly unwise to ship soil indiscriminately from one portion of the country to another.

Of scarcely less importance is the danger of disseminating noxious weeds and insect pests through this plan of inoculating by means of natural soils. Even though weeds may not have been serious in the first field, the great number of dormant seeds requiring but a slight change in surroundings to produce germination is always a menace.

If soil[a] is to be used, however, whether obtained from near-by fields or shipped long distances, the evidence should be clear that the soil is free from the objections mentioned above.

RESULTS OF COOPERATIVE FIELD TESTS.

The results of cooperative experiments with planters throughout the United States, begun in the spring of 1906 and reported upon during the autumn of that year, are presented here in tabular form. These reports are divided into three natural classes: Successes, doubtful results, and failures. To explain further the plan followed in this tabulation, quotations from representative reports under each class are given.

An examination of these sample reports will show that the successes credited to the culture have been so recorded only when a clear gain was shown to be due to inoculation. A less strict interpretation of the doubtful reports would place many of them in the column of successes, and undoubtedly many classed as failures to secure inoculation would prove upon adequate investigation to have been failures from causes other than deficient nodule formation.

---

[a] The quantity of soil from a thoroughly inoculated field regarded as sufficient for inoculating an acre of land for alfalfa, for instance, is variously placed at 200 to 500 pounds.

TABLE III.—*Results of experiments with crops sown in connection with cultures of nitrogen-gathering bacteria in the spring of 1906.*[a]

Crop.	Successes.	Doubtful results.	Failures.	Total.
Alfalfa	403	657	182	1,242
Red clover	498	544	66	1,108
Garden pea	236	209	54	499
Garden bean	217	224	74	515
Cowpea	247	203	53	503
Canadian field pea	44	27	10	81
Vetch	16	19	4	39
Soy bean	23	40	23	86
Crimson clover	8	18	2	28
Sweet pea	22	29	8	59
Velvet bean	10	14	2	26
Alsike	33	24	3	60
White clover	2	2	0	4
Peanut	10	19	1	30
Bur clover	0	1	0	1
Beggar weed	0	1	3	4
Japan clover	1	0	0	1
Mung bean	0	1	0	1
Sainfoin	0	2	4	6
Sweet clover	0	3	0	3
Total	1,770	2,037	489	4,296

[a] Approximately 8,000 cultures were sent out. A little more than half of the recipients had reported results at the time this table was prepared. The general relation remains about the same, as additional reports have been tabulated since this table was prepared.

REPORTS OF INOCULATION EXPERIMENTS CLASSED AS SUCCESSES.

The following are examples of the experiments with nitrogen-gathering bacteria which have been classed as successes:

Alfalfa.—" Nodules are numerous on inoculated ground, while I fail to find any on uninoculated. The inoculated crop did fine, while the uninoculated was a failure, and always has been so far." (Ballagh, Nebr.)

Alfalfa.—" I find roots well filled with nodules. Alfalfa has a good dark-green color and grows thriftily, whereas in previous experiments it has kept small and yellow for the first three years. I cut three fair crops this year, although the rainfall was somewhat deficient." (Waupaca, Wis.)

Alfalfa.—" Quite a lot of nodules on inoculated plants and a very good stand; looks fine. Strip 30 feet wide and 400 feet long not inoculated has very poor stand and very few nodules." (Cleveland, Ohio.)

Red clover.—" The inoculated crop is of a strong and thrifty growth. All the seed that I sowed that was not inoculated died in forty to sixty days after planting, as did every clover field in this vicinity. There was a marked difference in the inoculated and uninoculated from the start; the inoculated seemed a better color and did not die out from the dry weather as the other did." (Paris, Mo.)

Red clover.—" By count I find from two to four times the number of nodules on inoculated area. I inoculated 20 acres; used commercial fertilizer on an adjoining 20 acres, and on a third 20 acres nothing was used. One week ago on the inoculated area was to be seen clover of a much darker color and of twice the growth found on fertilized area. The results were highly satisfactory in every respect." (Lima, Ohio.)

Red clover.—"Roots covered with nodules. Clover on adjoining land, but better land, very poor. Inoculation certainly did increase the nodules and, of course, improved the crop. Clover sown last spring in this vicinity is poor, but mine sown upon high sand hills is all that I can ask; it exceeds my expectations. I am convinced that it is useless to sow clover on this ground without inoculation." (New London, Wis.)

Cowpea.—"The growth of nodules was fully 200 per cent better on the inoculated than on a small portion that was not inoculated. The increase of peas over the uninoculated was fully three to one. The increase of hay I did not take into close consideration, but on a fair estimate, I think, about 2½ tons an acre in favor of inoculated." (Buttonwood, Pa.)

Cowpea.—"There was a good supply of nodules on the inoculated plot, one plant having a good handful of large size at harvesting time. There were no nodules on three plots of the same size that were not inoculated. The uninoculated plot (Whippoorwill) yielded 6½ pounds grain; the inoculated plot (Whippoorwill) 9 pounds grain." (Pataskala, Ohio.)

Cowpea.—"Planted one-half acre in same field, using no culture; both had 500 pounds of same fertilizer per acre. Compared with roots where culture was used, found less nodules and turned down scant growth of pea vines to sow scarlet clover and rye. Where culture was used, found large number of nodules and rank growth of vines which remained green until peas matured and yielded 20 bushels per acre. Land now seeded to rye and scarlet clover, which is looking fine." (Withams, Va.)

Cowpea followed by oats.—"On a part of the ground on which the treated cowpeas had been grown I planted oats. They turned out 50 bushels to the acre, and on ground where the untreated cowpeas had grown they turned out only 25 to 30 bushels to the acre, no other fertilizer being applied to either piece of ground. Fields just adjoining mine have yielded only 25 bushels an acre." (Hammond, La.)

Cowpea followed by oats.—"I made up with supplies sent me from the Department 100 gallons of liquid culture, which was distributed among 20 farmers in this vicinity. Those who planted peas for forage have gathered twice the quantity of pea-vine hay from the ground in which the inoculated seed were sown. I repeated last year's experiment in following the peas, after the hay had been cut off, with oats in drills. So far as the eye can judge, the improvement in the oat crop is proportionally as great as that in the crop of pea vines." Others in this same group of cooperators reported as follows: "Cowpeas are practically unknown here (a large body of land in a bend of the Coosa River) and when sown last season without inoculation no nodules were formed. The bacteria secured largely increased the yield; 3 tons of hay from an acre of inoculated seed, one-half ton from uninoculated seed; made twice as many peas on land inoculated as on land not inoculated. Season too wet to gather peas." (Rome, Ga.)

Cowpea followed by corn.—"Where cowpeas were grown last year we have corn this year. The field is a 4-acre lot and includes sandy gravel as well as good rich loam. Over the entire portion where the cowpeas were grown with the culture the corn has a rich black color; on the area where no culture was used there is a distinct difference, the corn being smaller and not of such dark lor. This is very distinct, even on the heavy loam. The growth of cowpeas as estimated at twice as much last year where the culture was used as where ere was none. The cowpea crop was cut last year, but on account of continual ins was left on the ground and plowed under." [a] (Vineland, N. J.)

Bean.—" Nonculture beans grew slowly, were light green (though not unealthy), and had slender stem and sharper pointed, more delicate-looking leaf. ulture beans grew rapidly, were stout and deep green, and the leaves were icker and blunter pointed. Nonculture beans bore ordinarily well, and after e bearing rusted and dried up. Culture beans were loaded, kept putting rth blossoms, and bore until frost killed them in October. On the roots of e nonculture beans there were a few minute and hard-looking nodules, and e roots were small and weak. On the roots of the culture beans the nodules ere plentiful and juicy; the roots were long and vigorous. On reading your ccount of seed raised in pure sand from inoculated seed, I thought I would y coal ashes, and planted three hills of two varieties in our last winter's ash eap, scooping out a hole, laying in the beans, and covering with mixed earth nd ashes. They grew wonderfully and bore until frost, and at that time had fourth crop of blossoms." (Woodfords, Me.)

Vetch.—"A strip 25 or 30 feet wide was sown without inoculation. That art inoculated showed roots full of fine nodules, while the plants uninoculated howed none at all. The growth in the part of the field that had received the noculation was three or four times as great as in that part not so treated." Irving, Mich.)

Vetch for citrus orchard.—" Vetch was tried three years ago and gives good esults. Eighty per cent of our orchardists now plant legumes to plow under, nd find it profitable. Inoculated vines about 20 per cent heavier than uninculated on soil never having had a crop of legumes. Our soil is a heavy ed clay adobe, formerly a desert, and devoid of humus." (Redlands, Cal.)

Garden pea.—" Planted inoculated and uninoculated side by side. Inoculated ad many nodules and large ones; uninoculated few and small, and some lants none at all. Inoculated foliage dark green; uninoculated yellowish reen. Stems longer and growth more vigorous on inoculated, yield about double hat of the uninoculated." (Parkersburg, W. Va.)

Canadian field pea for citrus orchard.—"The pea vines plowed under furnished range and lemon trees with plentiful nitrogen. Fruit trees were never so igorous as now. Where we did not inoculate we got less vine and nodules, and ruit trees are not so fine." (Glendora, Cal.)

Canadian field pea.—" Nodules well developed. No nodules on an adjacent ninoculated crop which, excepting inoculation, received the same treatment. Peas and hay much increased (nearly doubled) over adjacent uninoculated rop." (Mount Pleasant, N. J.)

Canadian field pea.—" The cultures were applied to one ton of peas; the ther half ton was planted without inoculation. The nodules on plants from the inoculated seed were larger and twice as numerous as from the uninoculated. The inoculated crop was much more robust and thrifty. The planting was done in a foothill orange orchard with steep gradients. The purpose of the planting was to prevent washing, as well as for fertilization. I planted the inoculated seed in one direction and the uninoculated crossing it in open spaces at right angles. The result was a decided checkerboard, with inoculated seed producing a crop twice as vigorous and high as the other." (Glendora, Cal.)

---

[a] The yields from these two portions were reported later as follows: Corn following uninoculated cowpeas averaged 75 bushels an acre; corn following inoculated cowpeas averaged 105 bushels an acre. These figures are for corn n the ear.

Soy bean.—"Inoculation increased nodules. On part of ground I spread soil from a soy-bean field; on part I planted seed with inoculating cultures; part of the field had no soil or inoculated seed. Both inoculated seed and soil from a soy-bean field caused vigorous growth of nodules; no nodules on ground not treated. Inoculated crop was dark green in color; uninoculated light green. Where soil was fertile the growth was about equal, but where soil was poor the growth of the inoculated bean was more than double that of the uninoculated." (Cazenovia, N. Y.)

Peanut.—"I planted one gallon of seed not treated through the center of the lot, making 14 rows. They were very inferior, with nodules about 50 per cent in number and about one-half the size of those treated. I consider the gain for the inoculated crop at least 100 per cent." (Winterpock, Va.)

Sweet pea.—"About one-third of plot I did not inoculate. In this area I could not find a single nodule, though the roots of the inoculated portion were literally loaded with them. The whole plot was manured the same and had the same treatment all the season. The vines on the inoculated portion were more rank and would weigh three or four times as much apiece as those on the uninoculated portion. There were noticeably more and better blossoms from the inoculated plot." (Townsend Harbor, Mass.)

Crimson clover.—"Inoculated clover had five times the number of nodules as that not treated; in fact, they were perfect. Two acres uninoculated did not have as much clover as 10 square feet where treated. The appearance of inoculated field is fine—stalks large and healthy; stalks on uninoculated portion small and few." (Manheim, Pa.)

REPORTS OF INOCULATION EXPERIMENTS CLASSED AS "DOUBTFUL."

The following are examples of reports which have been placed in the doubtful class:

Alfalfa.—"There is a good amount of nodules on roots. No other field of uninoculated alfalfa here; so I can not compare. General appearance good." (Jefferson, Oreg.)

Alfalfa.—"Could see no difference between the inoculated and uninoculated; first cutting, considerable weeds; second cutting averaged 1 ton per acre good alfalfa." (Floyd, Tex.)

Alfalfa.—"I failed to secure a stand; the wind blew the ground so that the young plants were destroyed." (Hansford, Tex.)

Alfalfa.—"I am sorry to report alfalfa was an entire failure, I think on account of ground being too wet." (Canisteo, N. Y.)

Red clover.—"This field has never had a very good stand of clover and it does not seem much better this year. Examined plants from both parts of field and both seemed to have plenty of nodules; possibly more plants and more nodules on inoculated portion." (West Chester, Pa.)

Red clover.—"Can not tell as to results. We had six weeks of dry weather, and my seed did not come up." (Mohemenco, Va.)

Garden pea.—"A very wet season made the crop a failure. No conclusions could be drawn." (Hanover, N. H.)

Garden pea.—"Very few nodules noticeable. No increase in crop; perhaps the culture had been mixed too long before being applied to seed—had stood about ten days." (Hanover, N. H.)

Cowpea.—"Roots full of nodules; peas grew rank whether inoculated or not. The cowpea seems to grow here so well that I do not think artificial inoculation any benefit when the season is wet and warm, as it was this year." (Millersville, Md.)

Cowpea.—"I could not tell much difference between inoculated and uninoculated. Owing to excessive rain, the peas were almost drowned out, and it was not a fair test." (Greensboro, N. C.)

Cowpea.—"I can not tell very much difference in quantity of nodules on inoculated and uninoculated seed; if there was any difference, it was in favor of the treated seed. The appearance of the treated seed is darker than untreated." (Valle Cruces, N. C.)

REPORTS OF INOCULATION EXPERIMENTS CLASSED AS FAILURES.

Examples of results classified as failures follow:

Alfalfa.—"The nodules were not present at any time. The plants grew nicely for a time, then died, as they did formerly on an adjoining plot of land. No crop of alfalfa ever matured on this or any adjoining lands." (Rome, Tenn.)

Red clover.—"Could not find any nodules on either inoculated or uninoculated crop. It is the first clover ever sown on that field; it has been in wheat and corn for thirty years. Got a good stand, but it is mostly small, except where stable manure was spread." (McMinnville, Tenn.)

Cowpea.—"I examined peas on all parts of my place and found but few nodules. I could find no difference in the treated and untreated seed. I am inclined to think my inoculation was not right when I used it. My land appears to be without the proper bacteria; nodules are almost entirely lacking, and of course I can get but little results from my pea crop." (Moro, Ala.)

Soy bean.—"Plants were carefully dug, but had no sign of nodules, either treated or untreated. Culture may have been beyond the milky state but did not appear frothy. Good rank root system but no nodules." (Higganum, Conn.)

Garden bean.—"I examined the roots at different times and found only two nodules on the roots, and they were imperfect in appearance. There was no perceptible difference between inoculated and uninoculated." (Reedsville, W. Va.)

Garden pea.—"No nodules on either inoculated or uninoculated; no difference in growth. Extremely dry weather seemed to be the only cause for this being the poorest crop I have ever grown." (Ashland, Va.)

Vetch.—"Inoculation had no effect; total failure; no difference; soil, sandy loam, very poor and hungry." (Anamosa, Iowa.)

SUMMARY.

1. Abundant nodule formation improves the chemical composition as well as increases the quantity of a leguminous crop.

2. Leguminous crops with nodules are more valuable as green manure than leguminous crops lacking nodules.

3. Nematode galls or root-knots resemble nodules in appearance, but they are very injurious and care should be taken not to confuse the two growths.

4. It is wisest to depend upon pure cultures for inoculating purposes. If soil is to be used, however, great precautions should be taken in selecting and handling the soil to guard against the introduction of weeds or plant diseases.

O

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 316.

Experiment Station Wo

XLIV.

Compiled from the Publications of the Agricultural Experiment Stations.

- DISTRIBUTING MANURE AND FERTILIZERS.
- WINTERKILLING OF PEACH BUDS.
- COLOR OF APPLES.
- RINGING HERBACEOUS PLANTS.
- POTATO SCAB.
- GAS INJURY TO TREES.
- THE TUNA OR PRICKLY PEAR.
- COOKING CEREAL FOODS.
- SILAGE MAKING.
- HORSE-FEEDING TESTS.
- SUPPLEMENTS TO CORN FOR
- TANKAGE FOR HOGS FOLI
- CATTLE.
- HOPPERS FOR POULTRY FEEI

NOVEMBER, 1907.

PREPARED IN THE OFFICE OF EXPERIMENT STATIONS.
A. C. TRUE, Director.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

THE AGRICULTURAL EXPERIMENT STATIONS.

Alabama—
  College Station: *Auburn;* J. F. Duggar.[a]
  Canebrake Station: *Uniontown;* F. D. Stevens.[a]
  Tuskegee Station: *Tuskegee;* G. W. Carver.[a]
Alaska—*Sitka:* C. C. Georgeson.[b]
Arizona—*Tucson:* R. H. Forbes.[a]
Arkansas—*Fayetteville:* W. G. Vincenheller.[a]
California—*Berkeley:* E. J. Wickson.[a]
Colorado—*Fort Collins:* L. G. Carpenter.[a]
Connecticut—
  State Station: *New Haven;* E. H. Jenkins.[a]
  Storrs Station: *Storrs;* L. A. Clinton.[a]
Delaware—*Newark:* Harry Hayward.[a]
Florida—*Gainesville:* P. H. Rolfs.[a]
Georgia—*Experiment:* Martin V. Calvin.[a]
Hawaii—
  Federal Station: *Honolulu;* J. G. Smith.[b]
  Sugar Planters' Station: *Honolulu;* C. F. Eckart.[a]
Idaho—*Moscow:* H. T. French.[a]
Illinois—*Urbana:* E. Davenport.[a]
Indiana—*Lafayette:* A. Goss.[a]
Iowa—*Ames:* C. F. Curtiss.[a]
Kansas—*Manhattan:* C. W. Burkett.[a]
Kentucky—*Lexington:* M. A. Scovell.[a]
Louisiana—
  State Station: *Baton Rouge.*
  Sugar Station: *Audubon Park, New Orleans.*
  North Louisiana Station: *Calhoun;* W. R. Dodson (*Baton Rouge*).[a]
Maine—*Orono:* C. D. Woods.[a]
Maryland—*College Park:* H. J. Patterson.[a]
Massachusetts—*Amherst:* W. P. Brooks.[a]
Michigan—*East Lansing:* C. D. Smith.[a]
Minnesota—*St. Anthony Park, St. Paul:* E. W. Randall.[a]
Mississippi—*Agricultural College:* W. L. Hutchinson.[a]
Missouri—
  College Station: *Columbia;* H. J. Waters.[a]
  Fruit Station: *Mountain Grove;* P. Evans.[a]
Montana—*Bozeman:* F. B. Linfield.[a]
Nebraska—*Lincoln:* E. A. Burnett.[a]
Nevada—*Reno:* J. E. Stubbs.[a]
New Hampshire—*Durham:* E. D. Sanderson.[a]
New Jersey—*New Brunswick:* E. B. Voorhees.[a]
New Mexico—*Agricultural College:* L. Foster.[a]
New York—
  State Station: *Geneva;* W. H. Jordan.[a]
  Cornell Station: *Ithaca;* L. H. Bailey.[a]
North Carolina—
  College Station: *West Raleigh;* C. B. Williams.[a]
  State Station: *Raleigh;* B. W. Kilgore.[a]
North Dakota—*Agricultural College:* J. H. Worst.[a]
Ohio—*Wooster:* C. E. Thorne.[a]
Oklahoma—*Stillwater:* W. L. English.[a]
Oregon—*Corvallis:* J. Withycombe.[a]
Pennsylvania—*State College:* T. F. Hunt.[a]
Porto Rico—*Mayaguez:* D. W. May.[b]
Rhode Island—*Kingston:* H. J. Wheeler.[a]
South Carolina—*Clemson College:* J. N. Harper.[a]
South Dakota—*Brookings:* J. W. Wilson.[a]
Tennessee—*Knoxville:* H. A. Morgan.[a]
Texas—*College Station:* H. H. Harrington.[a]
Utah—*Logan:* E. D. Ball.[a]
Vermont—*Burlington:* J. L. Hills.[a]
Virginia—*Blacksburg:* S. W. Fletcher.[a]
Washington—*Pullman:* R. W. Thatcher.[a]
West Virginia—*Morgantown:* J. H. Stewart.[a]
Wisconsin—*Madison:* H. L. Russell.[a]
Wyoming—*Laramie:* J. D. Towar.[a]

---

[a] Director.

[b] Special agent in charge.

EXPERIMENT STATION WORK.

Edited by W. H. BEAL and the Staff of the Experiment Station Record.

Experiment Station Work is a subseries of brief popular bulletins compiled from the published reports of the agricultural experiment stations and kindred institutions in this and other countries. The chief object of these publications is to disseminate throughout the country information regarding experiments at the different experiment stations, and thus to acquaint farmers in a general way with the progress of agricultural investigation on its practical side. The results herein reported should for the most part be regarded as tentative and suggestive rather than conclusive. Further experiments may modify them, and experience alone can show how far they will be useful in actual practice. The work of the stations must not be depended upon to produce "rules for farming." How to apply the results of experiments to his own conditions will ever remain the problem of the individual farmer.—A. C. TRUE, Director, Office of Experiment Stations.

CONTENTS OF NO. XLIV.

Page.

Distributing manure and fertilizers ---- 5
  Use of the manure spreader ---- 5
  Parking ---- 5
  Use of the fertilizer distributer ---- 6
  Hand application ---- 6
Winterkilling of peach buds ---- 6
Effect of fertilizers on the color of apples ---- 8
Ringing herbaceous plants ---- 9
Potato scab ---- 11
Effects of escaping illuminating gas on trees ---- 12
The tuna or prickly pear as a food for man ---- 14
  Fresh tunas ---- 15
  Dried tunas and tuna products ---- 16
Cooking cereal foods ---- 17
Some experiments in silage making ---- 19
  Losses in the silo ---- 19
  Steamed silage ---- 19
  Silage from cured corn fodder ---- 21
Recent horse-feeding tests ---- 22
  Oats ---- 22
  Molasses ---- 22
  Succulent feeds ---- 24
  Alfalfa ---- 25
Supplements to corn in hog feeding ---- 25
Tankage for hogs following cattle ---- 28
Hoppers for poultry feeding ---- 30

ILLUSTRATIONS.

Page.
FIG. 1. Tuna cardona, the most highly prized of all the Mexican tunas. About one-fourth natural size 15
2. Method of piping for steaming silage 20
3. The New York feed hopper 30
4. The new force-feed grit hopper, with three compartments 32

316

EXPERIMENT STATION WORK.[a]

DISTRIBUTING MANURE AND FERTILIZERS.[b]

In a bulletin dealing with the use of fertilizers in Mississippi,
. B. Ferris, in charge of the substation at McNeill, makes, as a
sult of his experience, some practical suggestions of general
terest regarding different methods of distributing manure and
rtilizers. He states that " there are two general methods of ap-
ying fertilizers and manures—broadcast and in the drill. It is
ought best to make very large applications broadcast. * * *
oughly speaking, we would say that any application of commercial
rtilizers heavier than 1,000 pounds per acre would best be applied
oadcast and any smaller amount in the drill."

USE OF THE MANURE SPREADER.

"A manure spreader is the best and cheapest means of handling
arnyard manure, provided, of course, there is enough of this ma-
ure on the farm to justify one in investing about $100 in such a
achine. These manure spreaders can be regulated to distribute
niformly almost any quantity of manure per acre, and will apply it
ther broadcast or in the drill. They can also be used for making
eavy applications of commercial fertilizers."

PARKING.

The merits of parking as a means of distributing manure on light
ils were tested at the McNeill substation in the following way:

> In the fall and winter of 1902-3, 30 head of steers were penned on 5 acres
> land and fed for one hundred days on cotton-seed meal and hulls. The
> oughs were moved at intervals so as to cause the cattle to distribute the
> anure as evenly as possible over the land, and several times during the feed-
> g period the land was plowed to prevent the washing of the manure over the
> rface. The land being comparatively level, very little of this manure was
> st, and the soil, being of a sandy nature, was not injured by the tramping of
> e cattle even in the wettest weather. The effect of this manure on subsequent
> ops has been quite marked, being practically as great in 1906 as it was in

---

[a] A progress record of experimental inquiries, published without assumption
responsibility by the Department for the correctness of the facts and con-
usions reported by the stations.

[b] Compiled from Mississippi Sta. Bul. 99.

1903, the first year after the work was done. * * * The average yield of cotton on the unfertilized soil (at McNeill) has been 405 pounds per acre of seed cotton, while three years' results on this parked land show an average yield of 1,253 pounds per acre: the yield of cotton grown for four years continuously on the same land and fertilized with a mixture of two parts acid phosphate and one part cotton-seed meal at the rate of 300 pounds per acre has averaged 933.5 pounds of seed cotton per acre, while the average of three results with the same fertilizer on the parked land has been 1,840 pounds per acre; the yield of corn for three years has averaged 21.4 bushels more per acre on the parked land than on similar soils unmanured.

This shows that under favorable conditions of soil and climate parking may be a very cheap and efficient means of distributing manure.

USE OF THE FERTILIZER DISTRIBUTER.

"The best and most economical way of applying commercial fertilizers in the drill is by means of a fertilizer distributer." Mr. Ferris has tried and recommends a form of drill distributer looking very much like an ordinary cotton planter, which will apply practically any quantity of fertilizer per acre from 100 to 600 pounds, and costs between $4 and $5.

HAND APPLICATION.

Mr. Ferris states that while a good proportion of the fertilizers used is applied by hand, wind is likely to make this method unsatisfactory. "A cheap tin fertilizer horn about 4 feet long and costing 20 to 25 cents enables one to do this work much better and with a great deal less stooping."

WINTERKILLING OF PEACH BUDS.[a]

Winterkilling of buds is the cause of frequent and large losses in peach growing. The injury is sometimes due to the starting of the buds before danger of late spring frosts has passed or to their swelling during exceptionally warm winter periods. By inducing trees to mature buds late in the fall the buds will not finish their resting period, and so will not be likely to start in the spring until danger of frost and cold is past.

In a recent bulletin of the Missouri Station W. H. Chandler reports the results of investigations which were undertaken to ascertain the effects of severe pruning and methods of training, thinning, and cultivation on the hardiness of peach buds and to determine the relative hardiness of different varieties. The more important of these results obtained are summarized as follows:

It is well known that the vigor of growth of a peach tree can be increased by heading back, by cutting off a considerable portion of the ends of the branches in late winter or early spring when the fruit buds have all been killed.

---

[a] Compiled from Missouri Sta. Bul. 74.

This is an excellent treatment to enable trees to recover from injury to the wood by severe winters.

The fruit buds formed on this vigorous growth of new wood in sections north of Missouri are more liable to injury from the cold of the following winter.

The buds on this vigorous new wood, however, finish their resting period[a] later and are therefore not so readily started into growth by warm periods in winter to be killed by cold periods following.

In Missouri, especially the southern half, there is in nearly every winter warm weather to start the buds into growth to a small or large extent.

In most of Missouri, then, fruit buds on trees that have made rather a vigorous growth, caused by reasonably severe heading back or by cultivation, are the less liable to winter injury. This has been true in the Missouri Experiment Station orchard and in others during each of the last two years.

Heading back may be too severe, however, since in any year the fruit buds most likely to come through the winter safely are those at the base of the whips of new wood, and if the heading back has been too severe the growth will be so dense that no fruit buds will be formed at the base of those whips.

In the experiment station orchard the trees having the smallest percentage of buds killed were those trained to a spreading, open head, and forced by pruning and cultivation to make a vigorous growth.

The fruit on trees with spreading heads does not rot so badly as that on trees with dense heads.

The fruit on trees making rather a vigorous growth, unless the growth is too vigorous, is larger than that on trees making smaller growth. This is true except with early varieties, where a tree making a rather small wood growth bears the better fruit.

Thinning the fruit enables the tree to set more hardy fruit buds for the next crop.

In the station orchard where only one side of a tree was thinned the side not thinned had from 5 per cent to 40 per cent more of its fruit buds killed by a temperature of 6° F. below zero on February 5, 1907.

Many varieties, like the Elberta, Crawford, Golden Gate, Oldmixon, and others, the fruit buds of which are known to kill badly in Missouri, do so because they finish their resting periods early and are therefore easily pushed into slight growth on warm days in winter.

Varieties of Chinese Cling and green-twigged types (excepting the Elberta, which has more the character of the Persian race) are generally late in finishing their resting periods and are, therefore, better adapted to the Missouri climate.

The results of these experiments show that in general those treatments which induce vigorous growth of new wood, prolonging thereby the resting period of the buds, lessen the danger of winter killing. It is thus seen that good cultivation, pruning, thinning, and the like, which are commonly employed to improve the quantity and quality of fruit, also tend as a rule to lessen the danger of winter killing referred to. In pruning, however, it should be remembered that the young whips produced are more sensitive to prolonged cold in winter than harder wood, and the trees should be headed back only into 2-year-old wood. The Missouri experiments indicate that the purple-twigged varieties as a rule finish their resting period earlier than the green-twigged varieties, and hence are more likely to be winterkilled, and this offers a possible basis upon which to develop more resistant and safer varieties.

---

[a] Plants generally have resting periods, a period when without special treatment they can not be forced into growth.

EFFECT OF FERTILIZERS ON THE COLOR OF APPLES.[a]

The opinion is sometimes advanced in popular articles on the subject of apple culture that the use of such fertilizers as potash and phosphoric acid will improve the color of fruit. In cases where these particular elements are seriously lacking in the soil it seems reasonable to believe that their addition in some available form will promote a better all-around development of the fruit, color included, since both of these elements are known to be important constituents of the apple. On the other hand, scientific knowledge with regard to the real value of potash or phosphoric acid, or any other fertilizer, in improving the color of fruit appears to be too limited to warrant the apple grower in resorting to commercial fertilizer as a specific treatment for that purpose.

In this connection experiments conducted at the New York State Station by S. A. Beach, and recently reported by U. P. Hedrick, are of special interest. These experiments were begun in 1893 on an orchard of 43-year-old apples on sloping upland with a medium heavy clay soil. They were completed in 1904.

> Throughout the experiments the orchard was given clean cultivation until about August 1, and was then seeded to a cover crop of oats, barley, or clover. * * * There were 94 trees in the test, representing the following varieties: Baldwin, Fall Pippin, Rhode Island Greening, Roxbury, and Northern Spy. The orchard was divided into 8 plats, 4 treated and 4 untreated. Wood ashes were applied to the treated plats at the rate of 100 pounds per tree, or 4,800 pounds per acre. During the last seven years of the experiment acid phosphate was applied at the rate of 8½ pounds per tree, or 408 pounds per acre. Calculations made from analyses of the fertilizers show that, on the average, 169 pounds per acre of actual potash were applied each year; 72 pounds of phosphoric acid from the ashes and 57 pounds from the acid phosphate; and lime at the rate of 32 pounds per tree, 1,536 pounds per acre. The amounts are in excess of the usual recommendations of these fertilizers for apples.

Yield and color of fruit were the two standards used for measuring the effects of the fertilizer. As for the increase in yield, it is reported that the results were practically negative from a financial standpoint. With regard to color it is stated that—

> Taken as a whole, the results are disappointing. They lack uniformity and were not decided enough in a sufficient number of the twelve seasons to enable us to state that the addition of the substances applied heightened the color of

---

[a] Compiled from New York State Sta. Bul. 289. See also U. S. Dept. Agr., Office Expt. Stas. Rpt. 1903, p. 537.

apples under the conditions of this experiment. The effects varied not only from season to season, but varieties varied greatly in some seasons, and in others the same variety would color differently in plats receiving the same treatment. When we consider the number of factors which are known to influence color in fruit we can not assume with any degree of certainty that the results set forth above show that the addition of these fertilizers changed the color of the fruit in this experiment in any season. Thus, exposure to light; the intensity of the light; amount of foliage on the tree; the healthfulness of the foliage; the amount of stored food in the plant; soil heat; the texture of the soil—all of these, besides potash and phosphoric acid, have an influence. The relations of these factors are so intricate that it is almost impossible to separate them in an experiment like this, and especially as the differences were so slight.

A comparison of the color data with meteorological data for the twelve-year period shows that the treatment seemed to have an influence in coloring fruit only in those years when the apple did not develop well, as in 1893 and 1902; and that in other seasons, as in 1896, 1900, 1904, when climatic conditions were favorable to the development of fruit and foliage, the coloring was as nearly perfect on the untreated as on the treated plats.

It is not to be inferred from the results of this experiment that commercial fertilizers are never needed in the apple orchard, but they do appear to show that—

An orchard soil may not need potash, phosphoric acid, nor lime, even though the soil may have been cropped a half century; that in a soil which produces apples of poor color, potash and phosphoric acid may not improve the color; and that the apple does not seem to be as exhaustive of soil fertility as farm crops. The experiment suggests, as well, that to assume without definite knowledge that a tree needs this or that plant food, often leads to the waste of fertilizing material; and that in the matter of fertilizing an orchard a fruit grower should experiment for himself, since an orchard's need of fertilizer can be determined only by the behavior of the trees when supplied with the several plant foods.

RINGING HERBACEOUS PLANTS.[a]

U. P. Hedrick, O. M. Taylor, and R. Wellington recently reported from the New York State Station the results of an experiment in the ringing, or girdling, of tomatoes and chrysanthemums. This is practically a new field of investigation. The first work to be noted along this line was that of L. Daniel, a French investigator,[b] who conducted the experiment with different species of crucifers, eggplants, and tomatoes. With cabbage and Brussels sprouts the operation resulted in a more open head combined with a decrease in size. With these plants, as well as with kohl-rabi and ruta-bagas, ringing appeared not only to have no practical value, but was also detrimental to their best development. With eggplant, however, the size of the fruit was nearly doubled by ringing and was also considerably increased with tomatoes, although the flavor of the fruit was unfavorably influenced. In 1901, U. P. Hedrick, in writing of an experiment conducted by one of his students in the ringing of chrysanthemums, said " that all competent judges who looked over the experiment agreed that there was an increase in size, and that the blossoms were hastened in their development.

---

[a] Compiled from New York State Sta. Bul. 288.

[b] Compt. Rend. Acad. Sci. [Paris], 131 (1900), p. 1253. See also Amer. Gard., 22 (1901), No. 328, p. 245.

These results were not considered conclusive, however, and were offered principally with the view of creating a greater interest along this line.

Ringing has been employed to some extent with woody fruit-bearing plants, such as the apple, the grape, and the currant, as well as with other tree fruits to a lesser degree for some time past. The outcome has been by no means uniform, and growers are usually advised to submit the practice to experiment under conditions common to their own soil, climate, etc., before making free use of it.

On the other hand, under favorable conditions, ringing has appeared " to cause unproductive plants to set fruit, to increase the size of the fruits and thereby the productiveness of the plant, and to hasten the maturity of the fruit." Work with grapes and apples along this line, in which the results appeared to be favorable, was reported by the Massachusetts Hatch Station.[b] The New York State Station also reported favorable results in some instances with grapes.[c]

With regard to the recent New York State Station experiment with tomatoes and chrysanthemums, the authors state that " if ringing would bring herbaceous plants into fruiting, increase the productiveness, and hasten the maturity of the product, as with grapes and apples, the operation would be of especial value in growing some greenhouse plants, since the qualities mentioned are essential to success in growing commercial crops under glass. It would commend itself, too, because the devitalization which eventually follows the ringing of plants would be of little consequence with most of those grown in the greenhouse, since they are grown for but one or two seasons and then discarded." Both the tomatoes and chrysanthemums were grown in the greenhouse under normal successful conditions. Several plants of the Lorillard tomato were ringed in the winter of 1905–6. The plants were trained to a single stem. " The members of one group of plants were ringed as soon as the second cluster of fruits had set; those of the second group when the fourth cluster had set. Plants in a third group were unringed. Ringing consisted of removing a five-eighths inch strip of bark, cutting through the woody tissue."

---

[a] Amer. Florist, 17 (1901), p. 729.

[b] Massachusetts Sta. Bul. 1.

[c] New York State Sta. Bul. 151. See also U. S. Dept. Agr., Farmers' Bul. 105.

Several varieties of chrysanthemums were treated in practically the same manner in the autumn of 1906. The first group was ringed just as the buds appeared, the second about two weeks later, when the buds were one-third grown.

The results of the ringing as noted in various ways were disappointing. With the tomatoes the time of maturity was unaffected, the average number of fruits was reduced 18 per cent by the first ringing and 10 per cent by the second ringing, and the effect on the weight of the fruit was variable and inconsequent. Neither the color nor the flavor appeared to be altered by ringing. The foliage of the plant was somewhat more rank, although the root system apparently suffered from starvation. With the chrysanthemums the principal results noted were that "the first ringing hindered the opening of the buds in all of the varieties except one; the second ringing slightly hastened the maturity of all except one. The size of the blossoms of all the varieties was reduced and the earlier the ringing the greater the injury."

As a general result of this work the authors are of the opinion that it is very doubtful whether ringing can be made beneficial to herbaceous plants, in view of the fact that the loss to the plant is great and there seems to be little or no compensating gain.

"The deleterious effects of ringing on herbaceous plants are so marked that the query arises as to whether woody plants do not suffer in similar degree and the operation possibly cause a greater loss to the plant than is gained in the product."

POTATO SCAB.[a]

Potato scab is a well-known and widespread disease which does an immense amount of damage to the potato crop annually. Injury and consequent losses due to scab remain very large in spite of the fact that the cause and efficient methods of controlling the disease have been known for many years. The minute parasitic organism which causes the disease was discovered and described by Roland Thaxter of the Connecticut State Station in 1890, and several other stations have contributed to the working out of efficient methods of treatment of the disease. The roughened, scabby, pitted surface of potato tubers due to scab is well known practically everywhere that potatoes are grown, and the use of untreated seed and the too common practice of reserving unsalable, scabby tubers for planting has resulted in an increase rather than in a decrease of the disease in many localities.

---

[a] Compiled from Maine Sta. Bul. 141.

In a bulletin of the Maine Station, W. J. Morse summarizes the more important practical facts regarding the disease as follows:

> Crop infection on old land may come from the soil, from the seed, or from both. On new land the source is largely from undisinfected seed. Soil conditions, the application of lime, ashes, chip dirt, etc., may favor the development of scab, but are incapable of causing it.
>
> Alkaline soils, the use of stable manure, lime, ashes, and certain chemicals of alkaline nature favor the fungus. Acid soils and certain other chemicals are unfavorable to it.
>
> Beets and the roots of a few other vegetables are attacked by the disease, but the fungus may persist in infected soil for several years without the presence of known host plants.
>
> Badly infested soils should be devoted to such crops as grains, grasses, and clovers, for as long a time as possible. Fertilizers favorable to scab should be avoided and "souring" the soil by green manuring is recommended.
>
> On clean soils, only healthy, disinfected seed tubers should be used. Manure containing uncooked scabby potatoes or refuse should be avoided, but no other precautions as to fertilizers are necessary. Clean soil may be infected by means of tools, bags, baskets, etc., which have been in contact with infected land or tubers.
>
> Small amounts of seed are best disinfected by soaking: (*a*) Two hours in solution of one-half pint formalin to 15 gallons water, or (*b*) one and one-half hours in 2 ounces of corrosive sublimate dissolved in 15 gallons of water.
>
> For large quantities of seed, formaldehyde gas, generated by the use of potassium permanganate, is the most practical disinfecting agent. Place seed tubers in bushel crates or shallow, slat-work bins in a tight room. For each 1,000 cubic feet of space spread 23 ounces of potassium permanganate evenly over the bottom of a large pan or pail in center of room. Pour over this 3 pints of formalin, leave room at once and allow to remain tightly closed for twenty-four to forty-eight hours.

The corrosive sublimate (a deadly poison), formaldehyde (usually sold under the name of formalin, a 40-per cent solution of formaldehyde), and the potassium permanganate can be obtained of any druggist. Corrosive sublimate costs about 15 cents per ounce, formalin, which should contain not less than 35 per cent of formaldehyde, 40 to 50 cents per pint, potassium permanganate 30 cents per pound.

Treatment is therefore neither very expensive nor difficult to apply according to the above directions. It would seem good economy to incur the small expense involved in protecting the potato crop from possible serious injury by scab and clean soils from infection by diseased seed.

EFFECTS OF ESCAPING ILLUMINATING GAS ON TREES.[a]

In a report of the Massachusetts Station, G. E. Stone calls attention to the increasing damage to shade and ornamental trees due to escaping illuminating gas.

---

[a] Compiled from Massachusetts Sta. Rpt. 1906, p. 180.

The increased death rate from this cause may be accounted for by the fact that gas is now more extensively used than formerly, and the larger pipes now in use, together with modifications in the methods of laying these pipes and calking, may be in part responsible for the increased leakage. At any rate, it would seem that where small pipes have been in the ground for many years with thread-joint connections there is much less leakage than where larger pipes are used, and where the calking is done with Portland or Roman cement and oakum or lead.

Even small leaks of only 2 to 3 cubic feet per day are capable of injuring trees in course of time, since the soil eventually becomes charged with gas. " Should the roots of trees happen to be near these leaks, the trees will become unhealthy, but perhaps will not die. There are hundreds of city trees affected in this manner, and gas is seldom suspected of causing their sickly condition."

There are two classes of injury which may readily be distinguished as resulting from gas poisoning: First, incipient cases; and, second, pronounced cases. In the first series we have those already alluded to as resulting from small leaks, and the ground in such cases never becomes fully charged for any considerable distance. They may not result in killing the tree directly, but cause it to be unhealthy, and there is likely to be a large amount of dead wood found on such trees annually. Occasionally a large tree may be located near a small leakage, and in such a case only a single root will be affected. Those portions of the trunk of the tree in direct connection with the leak will, however, show the effects of gas poisoning. Small leaks of this description often produce only local injury. Trees affected in this manner may suffer what is termed " general debility." * * * In severe cases of gas poisoning, such as take place where there is a large leak, the effects on a tree are very pronounced, and there is absolutely no hope of recovery for a tree which has once been severely injured by gas; in short, where a tree has been defoliated, or even half defoliated, from the effects of gas, there is no hope for it, although it might be possible, if one could dig up all the soil around it and expose it to the air, to eliminate much of the gas in the soil, in which case the tree might make some attempt to recover.

The characteristic symptoms of gas poisoning are quite marked to one familiar with them, and can generally be distinguished from other kinds of injury which are likely to affect a tree. It requires, however, pretty close observation and thorough understanding of conditions in order to distinguish gas poisoning from some other types of injury which may occur. * * *

In general, however, the symptoms shown by trees affected with illuminating gas are quite different from those arising from other causes which are likely to be active. Trees affected with gas are very susceptible to rapid disintegration. One of the first effects of poisoning in summer would be a yellowing and drying up of the foliage, and a greater or less defoliation of the tree, according to the degree of poisoning. The trunk of the tree is generally dark colored, indicating an absence of life; but this feature is not always present.

The occurrence of various species of fungi on trees affected by gas is rather conspicuous, since these fungi are often very numerous, and make their appearance soon after a tree has been injured; whereas on trees dying from other causes it is sometimes many years before the bark becomes covered with fungi. The sap-wood is often found to be discolored, and it has peculiar, characteristic odors which assist in a diagnosis. Sometimes, however, especially when the tree is injured by gas in late summer, at which time the flow of sap is not so pronounced as in the spring, the odors of the wood are not so marked. * * * There is considerable difference in the resistance of soils to gas. In gravelly soils we have known gas to travel 2,000 feet without any difficulty when the ground is frozen, and escape into the cellar of a house; whereas in heavier soils gas is more likely to be restricted to smaller areas.

Digging up and thoroughly airing the soil will generally overcome poisonous properties resulting from escape of gas, but where the escape has been long continued and the soil has become thoroughly charged with the poisonous compounds in gas the sweetening process is slow, and it will be some time before trees can be replanted on the soil with good show of success.

THE TUNA OR PRICKLY PEAR AS A FOOD FOR MAN.[a]

The prickly pear, Indian fig, Barbary fig, or tuna, for these and other names are applied to the fruit of varieties of Opuntia, a family of cacti, is eaten in large quantities in the warm countries where it grows, and is of some commercial importance outside its native region. In many of the northern fruit markets in the United States these fruits are fairly common in the late fall, the present supply coming almost exclusively from southern Europe. Tunas are common in the southwestern United States and are used as food to a considerable extent, but they are much more abundant and used to a much greater degree in Mexico. (Fig. 1.)

Recently published bulletins of the New Mexico Station and the Bureau of Plant Industry of this Department, by R. F. Hare and D. Griffiths, report an extended experimental study of the tuna and its uses as food, and discuss also the cultivation, harvesting, marketing, and storing of these fruits and related questions.

There are many varieties of Opuntias, including both wild and cultivated sorts, which yield edible fruits to which the name tuna is applied. The fruits vary in shape and color according to the species and the conditions under which they are grown. They are commonly from 1 to 3 inches in diameter and are usually pear-shaped or fig-shaped, though in some species they are nearly spherical, and weigh from an ounce to a half pound or more, and when ripe vary from a yellowish green to a dark purple color. All varieties have minute spicules arranged in bunches over their surface, about one bunch to every square inch in the better varieties, though in most species the spicules are more numerous. The fruits of most species have large spines also which correspond to those on the cactus plant, but they are much more delicate and usually fall off before the fruits are thoroughly ripe. A cross section shows that the fruit is covered with a thin skin or epidermis, beneath which there is a rind varying in thickness from one-eighth to one-half inch. Inside this is pulp or edible portion, in which are found embedded from 100 to 200 or more seeds, for, with a few exceptions, these fruits are characterized by a very large seed content.

---

[a] Compiled from New Mexico Sta. Bul. 64; U. S. Dept. Agr., Bureau of Plant Industry Bul. 116.

The extended series of analyses of Mexican and New Mexican tunas reported by Hare and Griffiths show that they resemble other succulent fruits in composition, the solid material constituting some 6 to 13 per cent of the total edible portion. The principal nutritive materials are sugars, 7 or 8 per cent being perhaps a fair average value. Small amounts of nitrogenous material, fruit acids, and ash are also present.



FIG. 1.—Tuna cardona, the most highly prized of all the Mexican tunas.

FRESH TUNAS.

In Mexico, where many varieties are eaten, some are considered more wholesome as well as more palatable than others. The harvesting of wild and cultivated tunas is a matter of much importance, and the methods which are followed in Mexico are described at length by Hare and Griffiths:

> During the height of the season, when the fruit is cheapest, women appear on the markets each morning with huge baskets of them ready peeled. * * * Each purchaser is furnished with a tip of maguey leaf or a thorn of the mesquite with which to eat the pulps. * * * By far the greater amount of fruit is sold unpeeled. This is especially true during the season when fruits are not abundant, for less waste attends it. Sometimes the purchaser peels the fruit himself and at others he eats it as the vender or his attendant peels it for him. The process of peeling is simple, * * * the knife being run across the top and down one side to the base, when the pulp may be picked out easily. When fully ripe much of the rind of some species is consumed with the pulp. * * *
>
> On the whole it may be said that tunas are easily injured and consequently much care is necessary in handling them when they are intended for packing. They must also be well aerated in storage, which is true of all fruits. * * * Contrary to popular opinion, some tunas can be preserved in the fresh condition about as long as the common fruits of the temperate zone, if properly handled.

DRIED TUNAS AND TUNA PRODUCTS.

Tunas are dried in large quantities, the thin skin which covers the rind being first removed. White or yellow varieties are usually selected for drying, as they yield a more attractive product than the red. A number of other food products are also prepared from tunas, notably a thick sirup known as "Miel de Tuna," or tuna honey, a thick, paste-like mass known as "Melcocha," and a more solid paste known as "Queso de Tuna," or tuna cheese, which in appearance somewhat resembles old-fashioned apple marmalade. A fermented drink called "Colonche" is also made from these fruits.

In making the tuna honey "the peeled tunas are put in the kettles and boiled until the free seeds fall to the bottom. This occupies usually about two hours, fresh material being added from time to time as the water evaporates. The seeds are removed with a sieve and the sirup returned to the fire and boiled slowly for two or three hours more, or until it approaches the consistency of honey. It is then poured into wooden troughs, where it is thoroughly mixed with wooden paddles until completely cooled. After setting for twelve to twenty-four hours it is packed away in bottles or earthenware jugs. It may be kept about the same as molasses, and is said to remain in good condition indefinitely. After a time, however, it candies and becomes difficult to handle."

Melcocha and tuna cheese are made from peeled tunas from which the seeds have been removed, a seeder being used for the purpose.

The most palatable prickly pear growing in New Mexico, according to the authors quoted, is a variety with dark-purple fruit and a brilliant red juice, and while it is not eaten very extensively fresh it is used by the Mexican residents in considerable quantity in the manufacture of preserves. In studies which were made with a view to determine the best use of the brilliant-colored juice the pulp was evaporated to a thin paste constituting about one-eighth of its original volume without suffering any change in color.

This paste was used for coloring apple jelly and candy, and was found to serve admirably for the former purpose. Because of the danger or prejudice against the use of the coal-tar dyes, it may have some value commercially as a vegetable coloring matter. Candy colored by means of it lacked the brilliancy of that colored with coal-tar dyes, and it is doubtful if it could ever be very generally used for this purpose. The paste prepared in this manner had 51.6 per cent sugar, only 0.48 per cent being sucrose. By removing the sugar and insoluble solids from the material the coloring matter could probably have been concentrated to as rich a color as cochineal paste. * * * As to whether or not the fruits will ever prove of commercial value for the preparation of a coloring matter will, we believe, depend solely upon the yield per acre that can be obtained. This can only be determined by experiment.

As regards the value of tunas in general and the possibilities of their cultivation, Hare and Griffiths believe that conservative judgment based on observation and experiment " would pronounce many species of prickly pear to be decidedly susceptible to cultivation and highly productive of both fruit and forage under proper conditions of temperature and moisture."

It is also true that there are species which thrive under moderate extremes of heat; that, as a rule, they are adapted to conditions of periodical rainfall and thrive where the distribution of moisture is too irregular and uncertain for commonly cultivated crops; that the spines and spicules have been practically successfully eliminated from the plant body in valuable species but not from the fruit; that all of the so-called spineless forms concerning which we have definite knowledge are less hardy, especially toward drought conditions, than spiny natives; that it is quite probable that by persistent breeding and selection the spines and spicules may be more completely removed and the plant bred to withstand a greater degree of cold; that the plants can be fed together with more concentrated foods with profit; that the fruit is now, in its spiny condition, an important and highly prized ingredient in the diet of the poorer classes of Mexico and Sicily especially; and that highly prized products are prepared from the fruits; that the group is of sufficient economic promise to merit thorough investigation.

COOKING CEREAL FOODS.[a]

Cereal breakfast foods may be roughly divided into three groups: (1) Those like old-fashioned oatmeal which are not cooked at all in the process of manufacture, (2) those like flaked or rolled grains which are partially cooked at the factory, and (3) those which have been submitted to some special cooking processes, like browning or baking, and may be eaten without additional cooking. Sometimes the cooked or partially cooked foods are treated with malt, which, it is claimed, converts some of the carbohydrates into soluble forms.

---

[a] Compiled from Connecticut Storrs Sta. Rpt. 1904, p. 180; Maine Sta. Bul. 118; Ann. Rpt. Ontario Agr. Col. and Expt. Farm, 32 (1906), p. 63; Jour. Soc. Chem. Indus., 26 (1907), p. 240.

Extended series of digestion experiments with cereal breakfast foods have been reported from the Connecticut, Maine, and Minnesota experiment stations and the Ontario Agricultural College, which warrant the general conclusion that these foods closely resemble different types of bread in digestibility as they do in composition, the breakfast foods from which the coarser part of the grain has been removed approximating white bread in thoroughness of digestion, while those sorts which retain the branny portions more closely resemble graham bread and whole-wheat bread.

The subject of composition and digestibility of these foods and related questions has been discussed in earlier Farmers' Bulletins.[a] It is generally believed that long-continued cooking renders cereal breakfast foods more easily and thoroughly digested. In experiments carried on by R. Harcourt at the Ontario Agricultural College it was found that the farinas were broken down and rendered soluble to a greater extent by cooking than the oatmeals.

Young men in good health served as subjects of digestion experiments in which cereal foods cooked for a short period, twenty minutes, were compared with those cooked for a long period, eight hours. "In order that the results might be strictly comparable, the same subjects were used in determining the digestibility of the meal cooked for the short and long periods. Different subjects, however, were used with each sample of meal. This was done to bring in as many conditions as possible." The average results of the experiments follow.

Average digestibility of rolled oats and wheat farina cooked for long and short periods.

Kind of food.	Organic matter.	Protein.	Fat.	Carbohydrates.
	Per cent.	*Per cent.*	*Per cent.*	*Per cent.*
Rolled oats (cooked twenty minutes)	94.2	81.5	92.5	98.0
Rolled oats (cooked eight hours)	95.4	84.3	94.6	98.3
Wheat farina (cooked twenty minutes)	95.5	79.3	94.9	98.3
Wheat farina (cooked eight hours)	95.3	79.4	95.6	98.5

From the above results, it is evident that the length of time the meal was cooked did not very materially influence the percentage amount digested. It is, of course, possible that less energy may have been expended in digesting that which was cooked the longer time, but no figures could be procured on this point. It is, however, important that starchy foods be cooked sufficiently long to cause the rupture of the starch cells. Judging by results, this apparently was accomplished, at least, nearly as well in one case as in the other.

---

[a] U. S. Dept. Agr., Farmers' Buls. 237, p. 14; 249.

From all the data which are reported regarding composition, digestibility, and comparative cost of a number of kinds of cereal breakfast foods Professor Harcourt concludes that—

> It is evident that corn meal, rolled oats, and the farinas, especially if bought in bulk, are the most economical breakfast foods. It is, however, true that these foods do not agree with everyone and that the so-called predigested foods may be useful for those people who have difficulty in digesting starch. They may also have a place in a hurry-up breakfast, but it is evident that a curious name given to a much-advertised food does not indicate a high nutritive value, and the intelligent buyer who has to consider economy will hardly pass by the old forms of breakfast foods unless his own experience has actually demonstrated that these newer foods have a superior value.

SOME EXPERIMENTS IN SILAGE MAKING.[a]

The fermentation of silage entails more or less loss of material, but is commonly considered beneficial, as it develops flavors and softens plant tissue.

LOSSES IN THE SILO.[b]

The amount of material lost when green crops ferment in the silo has been frequently studied. In recent tests carried on at the Canada experimental farms with an experimental silo it was found that corn lost 15 per cent of its gross weight, a mixture of corn and rape 33 per cent, and rape alone 54 per cent. The material was placed in the silo in September and taken out in March.

STEAMED SILAGE.

Excessive fermentation produces silage with a high acid content, in addition to causing a large loss of nutritive material. The effect of checking extensive fermentation by treating silage with steam has been studied by A. L. Knisely at the Oregon Station for a number of years. The silos were filled in the usual way and steam generated in a boiler was passed through a pipe into the mass until it was thoroughly heated (twelve to fourteen hours at 20–40 pounds pressure) in case of silos 5 feet in diameter and 12 feet deep. Large as well as small silos were used. The method of piping to introduce the steam at the bottom and in the middle of the silos is shown in figure 2. The sugar, acidity, and moisture were determined in the fresh material and at frequent intervals when the silage was removed from the silo. In the case of cut vetch and whole and cut clover the acid in the fresh material before ensiling ranged from 0.18 to 0.27 per cent, calculated as acetic acid, and in the steamed silage when taken from the silo from 0.42 to 0.88 per cent. The sugar in the fresh material ranged from 1.36 per cent to 2.07 per cent and in the silage from 0.93 to 2.08 per cent. In a test in which the silage was not steamed the fresh clover contained 0.18 per cent acid and the ensiled material 1.01 per cent, the proportions of sugar in the fresh and ensiled material being 1.82 per cent and 0.75 per cent. Another sample of ensiled clover, which was not steamed, contained 1.16 per cent acid. In later experiments the acidity of unsteamed silage of all kinds (corn, vetch, and clover) varied from 1.01 to 1.94 per cent, averaging 1.58, of steamed silage from 0.3 to 0.88 per cent, averaging 0.53 per cent. Steaming seems to be more effective in checking the acid fermentation in corn than in other crops.

---

[a] Compiled from Delaware Sta. Rpt. 1903, p. 36; Oregon Sta. Bul. 72, Rpts. 1903, p. 34; 1905, p. 53; Canada Expt. Farms Rpts. 1904, p. 166.

[b] See also U. S. Dept. Agr., Farmers' Bul. 133, p. 31.



FIG. 2.—Method of piping for steaming silage.

In one of the tests of steamed silage immature corn fodder which had been touched by frost was used. Full analyses of the fresh and ensiled material are reported, the acid in the silage being determined at intervals of a week for about two months. The fresh material contained 0.18 per cent acid and 2.43 per cent sugar and the material when taken from the silo 0.48 per cent acid and 2.15 per cent sugar. For purposes of comparison a full analysis was made of ordinary corn silage. This contained 1.65 per cent acid and 0.49 per cent sugar. A comparison of the two materials led the author to conclude that the ordinary silage "underwent considerably more chemical or biological changes than did the steamed silage, these changes being indicated by the large increase in acidity and decrease in sugar." The steamed corn silage was fed to stock and was found to have suffered very little injury from the frost.

As regards steaming silage in general, the author considers that the " operation was quite beneficial and the steamed silage was much better than that which was not steamed. Stall-fed animals were able to eat without the least injury 50 to 75 pounds of this steamed silage per day."

SILAGE FROM CURED CORN FODDER.

At the Delaware Experiment Station A. T. Neale has studied the possibility of making silage from cured corn fodder, being led to undertake the work by the fact that formerly good results were obtained locally by feeding cut corn fodder which was packed into boxes, moistened with hot water, and allowed to stand for twenty-four hours. Concentrated feeds, such as cotton-seed meal, could be mixed with the mass and such a mixture used in the place of bran. The method is too inconvenient for general use, but it suggested the possibility of making silage from dried corn fodder by the addition of water and subsequent fermentation. When the experiment was tried, a rise of temperature was noted in the silo and the development of an aromatic odor, as in the case of green silage. It was found that young and old stock ate such silage practically without waste and that cows preferred it to dried shredded fodder.

> It is a better and a safer mass to use with cotton-seed meal than dried fodder or hay. The meal adheres to the damp fodder, can not be separated from it by the stock, mastication is insured, and impaction of cotton-seed meal prevented. * * *
>
> In this experiment the quality of the fermented product varied. Where the moisture content was normal, the aromatic odor above noted was present. No points of excessive moisture were found. Fodder in the bottom of the silo was not as moist as that nearer the top. In places channels had formed, through which the water, pumped upon the surface, had flowed, leaving masses of only partially moistened fodder, in which to a limited extent a musty smell and visible mold in extreme cases were noted. This was also the case in the product stored in immediate contact with the cemented lining of the silo, a condition also likely to exist in silage made from green cornstalks.
>
> The fact that the fire risks were noticeably decreased by moistening the fodder corn was patent to all observers.

In connection with the Delaware work the loss of material from fermentation was calculated in making silage from dried corn fodder moistened with water. According to the data reported, " 100 pounds of the fodder would lose 2.81 pounds of starch, or its equivalent, to produce through its complete fermentation the necessary heat to raise the temperature of the mass to 165° F., and this amount, 2.81 pounds, is just 6 per cent of the total dry matter of the fodder."

RECENT HORSE-FEEDING TESTS.[a]

Various problems concerned with horse feeding and management have been studied at the agricultural experiment stations, and such work has been summarized in earlier Farmers' Bulletins.[b]

OATS.

Of recent work, that reported by F. W. Taylor, of the New Hampshire Station, is of interest, as it has to do with the comparative value of light and heavy oats for draft animals. Three pairs of work horses of Percheron blood were used in the test, one in each lot being fed heavy oats for thirty days and the others light oats. During an additional period of thirty days the conditions were reversed. In every case 16 pounds of the oats—that is, 5 pounds in the morning, 5 pounds at noon, and 6 pounds at night—were fed with mixed hay of average quality ad libitum. All the horses were used for farm work, requiring average exertion and endurance. As shown by weighings taken twice a week, 1 horse lost on both light and heavy oats, 5 gained on heavy oats, and 4 gained on light oats.

> The total gain or loss in any case was not material and was not much greater than the variation in weight from one day to another. The practical results of this experiment seem to indicate that, pound for pound, the light oats have nearly the same feeding value as the heavy oats. Although the heavy oats contain a higher percentage of protein, fat, and nitrogen-free extract and a less percentage of fiber than the light oats, it seems probable that the relative proportions of these constituents in the two grades are such that they are more easily and thoroughly digested. * * * The percentage of kernel, as would be expected, bears a close relation to the weight per bushel. It should be remembered that although the two grades are practically equal pound for pound they are not equal quart for quart, and that in feeding by measure, as is usually done, due allowance should be made for the heavy oats and a less quantity given. Since oats are bought and sold by weight instead of measure, there seems to be no gain made in buying the heavy oats at a much advanced price over the light oats.

The French investigator, Grandeau, states, on the basis of experiment and observation, that crushing oats increases their digestibility, and that crushed oats have been fed with satisfactory results for some years by a cab company in Paris and have effected a decided saving.

MOLASSES.

The possibility of substituting for oats a mixed feed made up of 60 per cent molasses, 20 per cent corn feed, and 20 per cent linseed meal was studied by H. van de Venne with army horses at Brussels,

---

[a] Compiled from Louisiana Sta. Bul. 86; New Hampshire Sta. Bul. 129; Utah Sta. Bul. 101; Breeders' Gaz., 48 (1905), p. 697; Centbl. Agr. Chem., 34 (1905), No. 12, p. 825; 2 Cong. Internat. Aliment. Ration. Bétail, 1905, Raps., p. 1; Jour. Agr. Prat., n. ser., 10 (1905), p. 777; Natal. Agr. Jour. and Min. Rec., 9 (1906), p. 1123; Soc. Aliment. Ration. Bétail, Compt. Rend., 10. Cong., 1906, p. 87.

[b] U. S. Dept. Agr., Farmers' Buls. 103, 133, 170, 222.

Belgium. Judging by the weight of the animals, he concluded that he normal ration made up of 12.13 pounds oats, 1.32 pounds bran, .61 pounds hay, and 4.41 pounds chopped straw was sufficient for heir needs. When about half the oats was replaced with the moasses feed somewhat greater gains were made than on the normal ation. The molasses ration had no marked effect on the amount of water consumed.

Molasses was an important constituent of the above-mentioned ation, and this material is attracting considerable attention at the present time as a feeding stuff for horses and other farm animals.

According to W. H. Dalrymple, of the Louisiana Experiment Staion, who has studied the question in the Louisiana sugar plantations, the custom of feeding molasses to the work stock on our large sugar states has been adopted in anything like systematic manner only within the past few years. Previously, and when the price was exremely low, quantities of the material were run into large iron roughs, and the mules allowed free access to it; and, to some extent, his rather prodigal method still prevails. The true value of blackstrap as a food stuff has become more apparent of late years, however, and as the question of feeding economically has become one of considerable moment to our planters, it is being used more as an ingredient of the 'balanced ration,' and, as a rule, mixed with other concentrates."

The average consumption on 47 plantations in the sugar belt was found to be about 10 pounds per head per day, and the range, according to the statistics gathered, about 2 to 21 pounds. A gallon of blackstrap molasses weighs on an average 12 pounds. Chopped hay, pea vines, alfalfa, and occasionally green cane tops, and some concentrated feed are commonly mixed with the molasses and the whole fed in three portions. It is desirable to begin with small amounts of molasses when this material is introduced into a ration.

The data collected are in accord with the generally accepted view that molasses, where it is available at reasonable prices for feeding purposes, constitutes a wholesome and easily digested, as well as an economical, constituent of a ration for draft animals. "It would seem that the somewhat general impression that molasses, from any source, is unduly laxative, must have been based upon the effect produced by the by-product from the beet factory, and not sugar-cane molasses, as there is abundant evidence in our own State of the harmless effect of blackstrap, so far as a purgative action is concerned."

Molasses, as everyone knows, owes its nutritive value largely to the sugar which it contains. A French investigator, who studied the feeding value of beet molasses, states that experimental evidence shows that sugar did not appreciably diminish the digestibility of the nutrients of a ration when the amount fed to horses was equal to 5 or 6 pounds per 1,000 pounds live weight. Sirup and molasses, however, when fed in smaller quantities decreased the digestibility of the ration, a fact which is explained by the laxative properties of the alkaline salts in beet molasses. The general conclusion drawn from the experimental evidence summarized by this investigator, however, was that beet molasses is a wholesome and hygienic feed when the amount consumed per day does not exceed 6 or 8 pounds per horse.

SUCCULENT FEEDS.

A number of investigators have recently studied succulent feeds for horses. R. W. Clark, of the Utah Station, states that 16 to 20 pounds of well-fermented, solid sugar-beet pulp was fed to horses experimentally for six or eight weeks and no irregularity in the health of the animals was noted which could be attributed to the pulp.

In a test covering two periods of twenty-eight days each, made with 4 work horses, alfalfa, oats, and sugar-beet pulp were fed in comparison with a ration without pulp. Little difference was noted in the effect of the two rations, the horses on pulp losing on an average 6 pounds and those without pulp 2 pounds per head. "The above results indicate that beet pulp can be fed to horses without detriment to their health, though the amount consumed (9 pounds per head daily on an average) was small. The horses on pulp received 1.5 pounds less of grain per day than those that received no pulp, the amount of hay fed being the same in each case. The animals in each lot did equally well, and whether or not 9 pounds pulp is equal to 1.5 pounds oats when fed as in this experiment, awaits further demonstration."

It is stated that for several years colts have been allowed access to sugar-beet pulp at the factory where the test was made, and in no instance, so far as can be learned, has any trouble arisen from feeding it.

Jerusalem artichoke tubers have at various times attracted considerable attention in the United States as a feeding stuff for farm animals.[a] Having noted that the peasants in southern France are in the habit of feeding Jerusalem artichoke tubers to work horses, a French investigator recently studied the value of this material with draft animals and obtained satisfactory results. In his opinion, not over 13 quarts should be fed. The artichokes, it is stated, should be mixed with crushed grain and 11 to 16 quarts of chopped hay, which will absorb the moisture. When artichokes were thus substituted for barley or oats for one hundred days no unfavorable results were noted.

In Natal corn silage has been tested with satisfactory results for army horses. The daily ration of horses running in paddocks conisted of 4 pounds of chopped corn silage, 2 pounds of alfalfa or forige, a few pounds of crushed corn, and an ounce of salt. "From the first they liked the ensilage, and did remarkably well on it. Many horses not doing well before showed improvement. The droppings were of a particularly healthy nature. The stabled horses also had a few pounds mixed with other food—even those working—at their midday feed, and did well on it."

---

[a] U. S. Dept. Agr., Farmers' Bul. 73, p. 92.

ALFALFA.

A recent publication of the Bureau of Animal Industry, by I. D. Graham, on the uses of alfalfa for farm animals, summarizes data n the value of this feeding stuff for horses as follows:

> Horses and mules "thrive on alfalfa pasture. * * * While * * * lfalfa is too rich a food for mature horses unless used in combination with ome other roughness, it is an excellent feed for young horses, as it seems to ontain just the elements necessary to develop bone, muscle, and consequent ize. Caution should be used, however, in feeding alfalfa to horses, particuarly if they have not been accustomed to it. Like other concentrated feeds, it eems to stimulate all the physical processes to such an extent that various lisorders of the digestive system may appear. This is particularly noticeable in he urinary and perspiratory glands. * * *"
>
> When alfalfa is fed to horses in considerable quantity the grain ration must e proportionately reduced and an abundance of other roughness furnished. When horses have attained a mature age and it is desirable to change from ther hay to alfalfa, this change must be very gradual, and the alfalfa selected or this purpose should be more advanced in growth at the time of cutting than hat which is to be fed to cattle or sheep. As a general statement, very ripe lfalfa hay is the best to use for work horses and driving horses, while that prepared in the usual way—that is, cut when the field is about one-tenth in bloom—is better for the colts. In any event, horses that are fed alfalfa hay must be given abundant exercise.

SUPPLEMENTS TO CORN IN HOG FEEDING.[a]

Corn must necessarily be used more freely than any other concentrated feed for hogs in the corn belt, as is pointed out in a recent bulletin of the Iowa Station, because if properly used it is especially well adapted to hog feeding and can usually be marketed as pork to the very best advantage. It is, however, becoming generally recognized that so far as health, thrift and rapidity of gain are concerned, corn alone, at least in dry lot feeding, does not give as satisfactory results, particularly with growing hogs, as corn combined with some other feed richer in protein. Wheat shorts is commonly considered the best supplementary feed for young hogs, but a number of other common feeding stuffs which contain large quantities of protein are on the market, and the experiments carried on at the Iowa Station were undertaken with a view to studying the merits of some of them. It is evident that if a small reduction per hog in the cost of feeding can be effected by the use of such feeds the aggregate gain will be very large.

---

[a] Compiled from Iowa Sta. Bul. 91. See also Farmers' Buls. 169, p. 29; 276, p. 21.

Corn alone, and with varying proportions of ground barley, wheat shorts, meat meal, and tankage, was compared in the tests with hogs which are reported by W. J. Kennedy and E. T. Robbins. The relative merits of dry lot as compared with pasturage and timothy and clover pasturage were also studied, especially with reference to their importance in connection with the feeding of corn alone and with other feeds.

Four lots of 12 well-grown hogs each were used in the first test, comparing corn alone and supplementary feeds, and the gains made in 32 days on the several rations were as follows: Corn, 1.88 pounds; corn, barley, and shorts 2:1:1, 2.21 pounds; corn and meat meal 9:1, 2.68 pounds; and corn and tankage 9:1, 2.34 pounds.

When different amounts of meat meal supplementing corn meal were studied with 4 lots of 9 young pigs each, the average daily gain per head on the several rations was 1.16 pounds on corn meal alone, 1.75 pounds on corn meal and meat meal 7:1, 1.79 pounds on corn meal and meat meal 8:5:1, and 1.86 pounds on corn meal and meat meal 10:1.

The feed eaten per pound of gain in the above 2 tests ranged from 3.7 pounds with the mature hogs on corn and meat meal 9:1 to 5.57 pounds with pigs on corn meal alone. The gain was most expensive with the latter lot, costing 3.97 cents per pound, and was least expensive with the mature hogs fed corn meal, barley and shorts, costing 3.15 cents.

A comparison of dry lot feeding and pasturage and of the effects of supplementing corn by other concentrated feeds under these conditions was studied with 10 lots containing 10 hogs each at the beginning of the trial, the test as a whole covering 112 days. When corn and shorts 2:1 and 1:1, corn meal and meat meal 5:1, and corn meal and tankage 5:1 were fed with timothy pasturage, the average daily gain ranged from 1.12 pounds on corn and shorts 2:1 to 1.37 pounds on corn and tankage 5:1. In the case of the same rations fed without pasturage the gain ranged from 0.81 pound on corn and shorts 2:1 to 1.09 pounds on corn and meat meal. On corn and timothy pasturage alone the average daily gain was 0.92 pound per hog and on corn and clover pasturage 1.19 pounds. Considering all the lots the concentrated feed eaten per pound of gain ranged from 3.98 pounds with the lot fed corn and shorts 1:1 on timothy pasturage to 5.12 pounds with the lot fed corn and shorts 2:1 in a dry yard, and was on an average 4.29 pounds. The cost of a pound of gain ranged from 3.35 cents with the lot pastured on clover and fed corn to 4.46 cents with the lot on corn and shorts 2:1 fed in a dry yard, and was on an average 3.92 cents.

In reporting these tests data are given regarding the shrinkage when slaughtering, and the profits are discussed at length on the basis of corn meal, meat meal, and tankage at different prices.

From a consideration of their results, the authors conclude that meat meal and tankage of similar composition are about equal pound for pound as supplements to corn in a ration for growing and fattening hogs and that both of these animal by-products are profitable adjuncts to corn and are more valuable for dry lot feeding than when pigs or hogs are being developed and fattened on pasture, especially if the pasture be composed of leguminous crops.

> Growing pigs fed meat meal or tankage to the extent of one-sixth of their ration, and older hogs having these feeds to the extent of 10 per cent of their ration, with corn, ate more feed and made more rapid gains than those fed on any other combination, such as shorts, barley and corn, or shorts and corn, tested in these experiments. In dry lot feeding a ration composed of corn with either meat meal or tankage produced from 25 to 40 per cent faster gains on quite mature hogs, and from 50 to 60 per cent faster gains on younger hogs, than a ration of corn alone, and in every instance the number of pounds of feed required per 100 pounds gain was decidedly less with the mixed ration.
>
> There was not very much difference in the results obtained when pigs of 137 pounds weight at the beginning of the experiment were fed corn with meat meal in the proportions of 7 to 1, 8.5 to 1, or 10 to 1. The proportion of 10 to 1 produced the most rapid gains and the greatest total profit, while the proportion of 7 to 1 required the least total amount of feed, but the greatest amount of meat meal, per 100 pounds gain. * * * Hogs fed on rations composed of corn and meat meal and corn and tankage were fully as acceptable to the buyers, both from the standpoint of the quality and condition of the flesh, as those fed on any of the other rations tested.

As regards the value of shorts as a supplement to corn, a ration of these 2 feeds 1:1 produced larger gains with less feed per pound of gain when fed to pigs on pasturage or in dry lots than a ration of corn and shorts 2:1.

"The advantage of the larger proportion of shorts was much more in evidence in the dry lot feeding than in pasture feeding. For feeding pigs on pasture with feeds at the prevailing prices a ration of corn alone produced 100 pounds of gain at a smaller cost than a ration of corn and shorts. The corn and shorts ration, however, yielded somewhat the greater total profit, due to the more rapid gains produced from the use of the same."

With respect to barley, the authors note "that a ration composed of corn 2 parts, barley 1 part, and shorts 1 part produced 100 pounds of gain at fully as low a cost as the rations containing meat meal or tankage in conjunction with corn. At the prevailing market price, barley proved to be an economical feed when combined with corn and shorts for finishing hogs for market."

When average results for pasturage and dry lot feeding were compared "there was less variation in the amount of concentrates required to produce 100 pounds of gain on pasture than in the dry lot feeding. With the pigs on timothy pasture, the most evident effect of increasing the amount of protein of the concentrated feed up to a point where the balanced ration was fed was to increase the amount of feed consumed and produce correspondingly larger gains."

In general, in dry lot feeding the most rapid and economical gains were obtained from those rations which contained a much larger proportion of protein to carbohydrates and fats than is found in corn.

The price which feeders can afford to pay for supplementary feeds, rich in protein, to add to the corn ration for the purpose of balancing the same must be regulated by the percentage of digestible protein contained in them and the market price of corn. When corn is high in price, supplementary feeds, as a rule, can be had at prices which will not prohibit their use; but when corn is very low in price, the feeder will very likely lose a portion, if not all, of his profits in pig feeding through the purchase of supplementary feeds. * * * With feeds at the usual prices, it is an easy matter by their judicious selection to so supplement corn as to add 5 to 15 cents per bushel to the profit from feeding corn, thus effecting a reduction of 50 cents to $1 on each 100 pounds gain in weight by the pigs.

TANKAGE FOR HOGS FOLLOWING CATTLE.[a]

In regions of the West where cattle are fed in large numbers on corn, many hogs are fattened upon the undigested grain found in the droppings of the cattle. B. E. Carmichael, of the Ohio Station, found that of 45 feeders in that State, of whom he obtained definite information, 35 "either used no feed besides that which was not digested by the steers or else gave corn in addition. Since corn is the chief grain used for fattening cattle, it follows that the hogs which depend solely upon the undigested grain in the steers' droppings must be confined to a ration made up almost exclusively of corn. Even if, in addition to corn, other concentrates richer in protein and ash than is corn are fed to the steers, the corn in the droppings is much more readily found, and the benefit derived by the hog from the feeds other than corn is not very great, although it is believed that some benefit may be derived." The feed of the hogs is therefore deficient in protein and ash.

The Ohio Station undertook a series of experiments to determine whether or not the prevailing practice can be improved by supplying a feed comparatively rich in protein and ash to hogs that follow fattening cattle. In these experiments six lots of steers, seven head in ach lot, were fed upon two different rations—three lots upon each ation, lots 1, 3, and 5 receiving shelled corn, cotton-seed meal, corn tover, mixed hay, and corn silage; lots 2, 4, and 6 receiving shelled orn, cotton-seed meal, corn stover, and mixed hay.

---

[a] Compiled from Ohio Sta. Circ. 73.

The three lots last mentioned received more corn and more dry roughage than id the lots first mentioned, on account of not receiving silage, which, of course, ontained both grain and roughage. All lots of cattle received the same amount f cotton-seed meal daily per steer.

During the first part of the experiment three hogs were put with each lot f cattle; later these hogs were replaced by a thinner lot and four hogs were laced with each lot. The first set of hogs was under experiment for 63 days, he second set for 56 days.

Not a large enough number of hogs was used in any of the lots to eat all f the grain that passed through the steers, although the amount left was in o case great. No corn was fed to the hogs, and, as the cattle feed racks were o constructed as to prevent the grain being thrown out, the hogs secured no rain except that which appeared in the droppings from the steers. * * *

The supplementary feed used in this test was digester tankage, a packing ouse by-product, of which the hogs in lots 1 and 6 received one-third of a ound daily per head after they had become gradually accustomed to it. The ogs in lots 3 and 4 received no feed other than that obtained from the droppings from the cattle. All lots were kept supplied with a mixture of ashes and alt. It is of interest to note that the lots fed tankage cared less for the ashes nd salt than did the other lots.

The tankage was fed in the form of a thin slop, once daily. It may be very onveniently fed in this manner, and was greatly relished by the hogs; in fact, hey exhibited an almost ravenous appetite for it.

The gains made by the tankage-fed hogs were more than one-half (52 per cent) larger as well as cheaper than those receiving no ankage.

The results show that a decided advantage resulting from the feeding of the tankage is that fewer hogs are required to consume the droppings from a given number of cattle, and that less time is necessary to produce a given amount of gain, thus both reducing the mount of money tied up in hogs and permitting a more frequent urning of the money.

Aside from these considerations, feeders will readily appreciate the fact that fewer hogs and a shorter feeding period would greatly lessen the liability to loss from cholera. Any method of feeding or management of live stock which makes it possible to reduce the number of animals necessary to furnish a given amount of product, or to cheapen in any other way the cost of production, is worthy of consideration by stockmen. It seems certain that the use of such supplementary feeds as are suggested in this circular will greatly increase the profits from hogs that follow cattle.

While, on account of its cheapness as a carrier of protein and ash and convenience for feeding, digester tankage was used in the work reported herein, it is believed that other feeds, such as linseed oil meal, soy beans, skim milk, buttermilk, or middlings would greatly increase the efficiency of the "cattle hog" in making economical gains. Feeders need, however, to exercise keen discrimination in the purchase of feedstuffs, for there is a likelihood of a heavy demand for certain feeds, making it possible for the manufacturers to raise prices beyond the amount justified by the feeding value.

While further work is needed "to determine what feeds are best suited for this purpose, and in what amounts they should be fed," sufficient has been done "to show that hogs following cattle are often not supplied with the ration best suited for the production of the greatest gains."



FIG. 3.—The New York feed hopper.

HOPPERS FOR POULTRY FEEDING.[a]

In the dry feeding of poultry, which is attracting considerable attention at the present time,[b] a hopper or some similar device for supplying feed is essential. Hopper feeding, according to J. E. Rice and R. C. Lawry, of the New York Cornell Station, saves labor, guards against underfeeding, and makes the keeping of fowls in large flocks less objectionable because it avoids crowding, which is likely to occur when considerable numbers are fed a wet mash.

---

[a] Compiled from New York Cornell Sta. Bul. 248.

[b] See also U. S. Dept. Agr., Farmers' Bul. 244, p. 25.

Experiments which have been conducted at the New York Cornell Station indicate " that for young fowls of the laying varieties, kept for commercial egg production, the feeding of a dry mash in a feed hopper which is accessible at all times during the day is to be recommended."

Whether the same system of feeding will prove as satisfactory with old fowls of the laying varieties or with young fowls of the general-purpose or meat varieties, we have not yet determined by actual comparative test. Nor has it been proved that the system can be used with safety with breeding fowls. This is a vital consideration. The ultimate test which will decide whether or not the hopper feeding of dry mash will be of universal application to the feeding of fowls, will be the effect on the vigor of the offspring. It is too early yet to decide this point. Many practical feeders, however, conclude from an extended experience that the breeding fowls having constant access to dry mash will not suffer in health from overeating or lack of exercise. We feel certain at this time that hopper feeding when properly employed has genuine merit and will become an established practice. To be successful, however, it must be adapted to suit the various breeds and other conditions as to age, season, and environment.

The authors have devised a hopper for use in the dry feeding of poultry which has been tested at the New York Cornell Station. It consists of a galvanized-iron box, having several compartments, with hinged cover, and on the front openings through which the feed can be reached by the poultry. A curved false bottom separates the upper or storage chamber of the hopper from the trough in the lower part and is arranged so that feed falls in small quantities into the trough. Figure 3 and the following quotation from the bulletin referred to explain the construction of this hopper:

The feed hopper which is used for feeding dry meals, meat scraps, or grain " is made of No. 26 galvanized iron, is 36 inches long, 24 inches tall, and 8 inches wide, divided into three compartments 12 inches wide, and will hold about 60 pounds of meal or 100 pounds of grain. It is built with a slanting top and has a door on the front that hinges up from below to close the opening when it is desired that the fowls should not eat. It is the outcome of a long series of experiments and is the only hopper of a large number tried at the station plant that will not waste feed and yet does not clog. The fact that it has a door to close and that it is made of galvanized iron makes it entirely rat proof. It is placed on a platform 5 inches tall that projects outward 6 inches in front to prevent the litter from being scratched into it. It has been found that one catch in the center of the door is more satisfactory than the two catches." The cost is about $4.

Recent experiments at New York Cornell Station have shown that lime and grit are required at all times by fowls for the best results as regards health and production. It is essential, therefore, that fowls should have access to cracked oyster shells or equivalent material at all times, and it seems also desirable that some other grit and perhaps charcoal should be provided. For this purpose a grit hopper was devised by the authors, which is large enough to make frequent filling unnecessary and is so constructed that it will keep clean and will not clog or waste. It is very similar in construction to the feed hopper described above, except that it is open above the trough instead of closed in. According to the authors, the cost of the hopper, which is made of galvanized iron, should not exceed $1. Figure 4 shows the appearance of the hopper and its method of construction. The rounded back and the overhanging lip in front prevent waste. The slanting top is also noticeable, as well as the eyes at the back, by which the hopper may be attached to the wall. The hopper illustrated is made in three compartments.



FIG. 4.—The new force-feed grit hopper, with three compartments.

67 Issued February 29,

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 317.

---

xperiment Station Wor

XLV.

Compiled from the Publications of the Agricultural Experiment Stations.

FARM HOME.
ING OF DITCHES AND RESERVOIRS.
IENT PIPE FOR IRRIGATION AND
HER PURPOSES.
LINATION OF FORCED TOMATOES.
REASING THE PRODUCTIVENESS
CORN.
SHRINKAGE OF CORN IN CRIBS.
GRAIN FOR COWS AT PASTURE.
STARTERS FOR RIPENING CREAM
WATER PANS FOR POULTRY.
CATCHING HOOK FOR POULTRY.

JANUARY, 1908.

PREPARED IN THE OFFICE OF EXPERIMENT STATIONS.
A. C. TRUE, Director.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

THE AGRICULTURAL EXPERIMENT STATIONS.

Alabama—
  College Station: *Auburn;* J. F. Duggar.[a]
  Canebrake Station: *Uniontown;* F. D. Stevens.[a]
  Tuskegee Station: *Tuskegee Institute;* G. W. Carver.[a]
Alaska—*Sitka:* C. C. Georgeson.[b]
Arizona—*Tucson:* R. H. Forbes.[a]
Arkansas—*Fayetteville:* W. G. Vincenheller.[a]
California—*Berkeley:* E. J. Wickson.[a]
Colorado—*Fort Collins:* L. G. Carpenter.[a]
Connecticut—
  State Station: *New Haven;* E. H. Jenkins.[a]
  Storrs Station: *Storrs;* L. A. Clinton.[a]
Delaware—*Newark:* Harry Hayward.[a]
Florida—*Gainesville:* P. H. Rolfs.[a]
Georgia—*Experiment:* Martin V. Calvin.[a]
Hawaii—
  Federal Station: *Honolulu;* J. G. Smith.[b]
  Sugar Planters' Station: *Honolulu;* C. F. Eckart.[a]
Idaho—*Moscow:* H. T. French.[a]
Illinois—*Urbana:* E. Davenport.[a]
Indiana—*Lafayette:* A. Goss.[a]
Iowa—*Ames:* C. F. Curtiss.[a]
Kansas—*Manhattan:* C. W. Burkett.[a]
Kentucky—*Lexington:* M. A. Scovell.[a]
Louisiana—
  State Station: *Baton Rouge.*
  Sugar Station: *Audubon Park, New Orleans.*
  North Louisiana Station: *Calhoun;* W. R. Dodson (*Baton Rouge*).[a]
Maine—*Orono:* C. D. Woods.[a]
Maryland—*College Park:* H. J. Patterson.[a]
Massachusetts—*Amherst:* W. P. Brooks.[a]
Michigan—*East Lansing:* C. D. Smith.[a]
Minnesota—*St. Anthony Park, St. Paul:* E. W. Randall.[a]
Mississippi—*Agricultural College:* W. L. Hutchinson.[a]
Missouri—
  College Station: *Columbia;* H. J. Waters.[a]
  Fruit Station: *Mountain Grove;* P. Evans.[a]
Montana—*Bozeman:* F. B. Linfield.[a]
Nebraska—*Lincoln:* E. A. Burnett.[a]
Nevada—*Reno:* J. E. Stubbs.[a]
New Hampshire—*Durham:* E. D. Sanderson.[a]
New Jersey—*New Brunswick:* E. B. Voorhees.[a]
New Mexico—*Agricultural College:* L. Foster.[a]
New York—
  State Station: *Geneva;* W. H. Jordan.[a]
  Cornell Station: *Ithaca;* L. H. Bailey.[a]
North Carolina—
  College Station: *West Raleigh;* C. B. Williams.[a]
  State Station: *Raleigh;* B. W. Kilgore.[a]
North Dakota—*Agricultural College:* J. H. Worst.[a]
Ohio—*Wooster:* C. E. Thorne.[a]
Oklahoma—*Stillwater:* W. L. English.[a]
Oregon—*Corvallis:* J. Withycombe.[a]
Pennsylvania—*State College:* T. F. Hunt.[a]
Porto Rico—*Mayaguez:* D. W. May.[b]
Rhode Island—*Kingston:* H. J. Wheeler.[a]
South Carolina—*Clemson College:* J. N. Harper.[a]
South Dakota—*Brookings:* J. W. Wilson.[a]
Tennessee—*Knoxville:* H. A. Morgan.[a]
Texas—*College Station:* H. H. Harrington.[a]
Utah—*Logan:* E. D. Ball.[a]
Vermont—*Burlington:* J. L. Hills.[a]
Virginia—*Blacksburg:* S. W. Fletcher.[a]
Washington—*Pullman:* R. W. Thatcher.[a]
West Virginia—*Morgantown:* J. H. Stewart.[a]
Wisconsin—*Madison:* H. L. Russell.[a]
Wyoming—*Laramie:* J. D. Towar.[a]

---

[a] Director.

[b] Special agent in charge.

EXPERIMENT STATION WORK.

Edited by W. H. Beal and the Staff of the Experiment Station Record.

Experiment Station Work is a subseries of brief popular bulletins compiled from the published reports of the agricultural experiment stations and kindred institutions in this and other countries. The chief object of these publications is to disseminate throughout the country information regarding experiments at the different experiment stations, and thus to acquaint farmers in a general way with the progress of agricultural investigation on its practical side. The results herein reported should for the most part be regarded as tentative and suggestive rather than conclusive. Further experiments may modify them, and experience alone can show how far they will be useful in actual practice. The work of the stations must not be depended upon to produce "rules for farming." How to apply the results of experiments to his own conditions will ever remain the problem of the individual farmer.—A. C. True, Director, Office of Experiment Stations.

CONTENTS OF NO. XLV.

Page.
Improving the convenience and comfort of the farm home 5
  Planning the home 5
  Use of labor-saving appliances 7
  Food 8
  Hygienic conditions and comfort 9
Lining of ditches and reservoirs to prevent seepage losses 10
Cement pipe for small irrigating systems and other purposes 12
Pollination of forced tomatoes 15
Increasing the productiveness of corn 17
  Varieties 17
  Moisture content 18
  Methods of culture 18
  Fertilizers 20
  Rotations 20
  Breeding 21
Shrinkage of corn in cribs 22
Feeding grain to milch cows at pasture 26
Practical use of starters in ripening cream 27
Water pans for poultry 28
Catching hook for poultry 31

EXPERIMENT STATION WORK.[a]

IMPROVING THE CONVENIENCE AND COMFORT OF THE FARM HOME.[b]

The question of sanitary appliances and other conveniences for the farm home has been discussed in a Farmers' Bulletin recently published by this Department.[c] Preparation of vegetables for the table, making of jams and preserves, and various problems concerned with the nutritive value of food and its reference to dietetics have also been discussed in Farmers' Bulletins.[d]

A number of the agricultural colleges and experiment stations have studied questions which have a direct bearing on the convenience and comfort of the farm home, such work in the agricultural colleges usually being done in the home economics department. Dr. Edna D. Day, who has charge of such a department at the Missouri Agricultural College, has recently discussed the need for convenience in the construction of the farm home, the value of labor-saving devices, and related questions.

PLANNING THE HOME.

In this connection she notes that in planning a home it is essential that the rooms should be located with a view to convenience in carrying on household tasks. "Be very careful in making the plans that you put more money into convenience than you do into size. Many a prosperous farmer, on rebuilding his home, has felt rich enough to make a house so large that his wife has not yet found time enough for its proper care. Not only are there more square feet of floor to be swept, but the steps necessary to do the ordinary routine work of the house have been multiplied many times."

---

[a] A progress record of experimental inquiries, published without assumption of responsibility by the Department for the correctness of the facts and conclusions reported by the stations.

[b] Compiled from Ann. Rpt. Mo. Bd. Agr., 39 (1906), p. 101; Boston Cooking School Mag., 12 (1907), p. 240; Cornell Reading Course for Farmers' Wives, 3. ser., 1905, No. 14.

[c] U. S. Dept. Agr., Farmers' Bul. 270.

[d] U. S. Dept. Agr., Farmers' Buls. 34, 74, 85, 93, 112, 121, 128, 142, 182, 203, 234, 249, 256, 293, 295, and 298.

In earlier times the farmhouse kitchen, commonly the largest room in the house and usually a pleasant, homelike room, often served as a dining room and living room as well, and one or more of the bedrooms were on the same floor as the kitchen. This meant a saving of time, since the housewife had fewer rooms to care for and fewer steps to take than is the case in the more modern farmhouse with a separate dining room and living room and with sleeping rooms in the second story. The more modern house undoubtedly has its advantages and is in accord with present-day standards of living, but such an extension of space should be counterbalanced by convenience of arrangement, the use of labor-saving devices, and all possible household conveniences.

As Professor Day points out, the proper location of the kitchen and dining room, the china closet, the kitchen sink, stove, and work table means a saving of very many unnecessary steps and much useless labor. If food must be kept in the cellar in summer time a dumb waiter with two or three shelves running from the kitchen to the cellar is well worth its cost. Of course, an ice box on the ground floor would avoid the necessity for keeping food cool in the cellar. If an ice box is used it should be so located that it can be conveniently filled with ice and yet be near the kitchen. Convenient cellar stairs are much less common than they should be, and their location, lighting, etc., are questions which should always be taken into consideration in house construction.

For use in cold weather "there should be a pantry on the ground floor in which the food is kept, and this pantry should be within walking distance of the dining room and kitchen. If this is not possible, a box can be turned on its side and fastened just outside the kitchen window and the food kept in it."

> If your house has been built without care to step saving in the position of dining table, sinks, and cupboards, a small table on rollers, especially if its capacity is increased by a lower shelf, will be found a great convenience. It can be used to advantage in setting and clearing the table. It is also helpful to have near the sink when the dishes are washed. They can be put on it and the table then moved to the china closet and emptied. Many a woman who is now tired of an evening would be fresh if she used [a wheeled table like this and] a high stool at the sink and work table.

A recent writer who discusses the construction and arrangement of a house that may be conveniently cared for by the housewife herself insists that the rooms "in which daily work is done must be centrally located. Bring the living room near the kitchen and your own bedroom as close to both as possible." If a dining room is considered essential it must be conveniently located, but the use of the living room as a dining room in winter and a screened porch for this purpose in summer is spoken of as an alternative.

A cart with compartments and mounted on small wheels is mentioned as a labor saver in the preparation and serving of meals. As n essential, hot water for bath and kitchen use in summer an rinter is insisted upon as well as few rooms to take care of, all tl ooms being large except the kitchen, for within reasonable limits tl maller the kitchen the fewer the steps which will be taken in tl itchen work.

> The model kitchen has four windows. One whole side of the room is lined with cu oards, some with glass doors, others of solid wood; beneath are drawers and flour bin he * * * range stands conveniently near the work table, and there is also a lar nameled sink with draining board. Between the large screened-in porch and tl itchen is placed the refrigerator, being filled with ice from the outside. The refrige tor doors open into the kitchen. Many times a day the cold storage has to be gone t nd this is an important matter, to have it right at hand. You will find that there ot any more ice consumed in a summer than if the ice chest was in the cellar. Wl hould steps be multiplied in going to it? The kitchen in the labor-saving plann ouse is small. The more articles you can reach with fewest steps, the lighter yo vork will be. * * * A narrow kitchen is a great labor saver. One does not reali his until she prepares a meal in the large square old-fashioned kitchen; the extra ste ount as miles in a day.

USE OF LABOR-SAVING APPLIANCES.

The general use of the sewing machine has saved the farmer's wi nd other housekeepers unnumbered hours of labor, and in the sam ray the general use of the proper kitchen conveniences will prov qually advantageous. It is just as important to supply the farmer rife with carpet sweeper, washing machine, bread mixer, and oth bor-saving devices, and with sharp knives, egg beaters, measurin ups, and other kitchen conveniences as it is to use separators i he dairy or other modern appliances in general farm work.

In a summary of data prepared for farmers' wives in connectic rith the extension work of the New York Agricultural College an Experiment Station, the need for kitchen conveniences is insiste pon. "A clerk does not like a poor pen, a typewriter a poor m hine, nor a carpenter a poor saw. So the expeditious cook objec o poor cooking utensils. They are a bar to progress, a menace t he success of her enterprise, and a serious temptation to her serenit f temper. Stirring cake with a small, frail spoon, beating eggs wit loose-jointed egg beater, as well as many other crippling processe hould not be her lot to endure." As the writer quoted points ou he needed utensils cost money, but so do all labor-saving and usef levices, and it is fitting to ask whether the labor-saving devices i he house have kept pace with those purchased for use in the barn ields. If the farmer's wife and daughters can economize in time an nergy required for household tasks they will have leisure for oth luties and pleasures and for rest and recreation.

FOOD.

Rational living on the farm or in any other community presupposes a reasonable variety of well-cooked foods of good quality with the various sorts in suitable proportion. In many homes the housekeeping is needlessly complicated and the result obtained is out of proportion to the labor expended. In other homes, particularly where the variety of easily obtainable foods is limited and the proper preparation of foods is not given due attention, the diet is too monotonous to be satisfactory or is so prepared that it is not well suited to the family needs. The question of lessening household labor by avoiding unnecessarily elaborate dishes and meals is discussed in the Cornell Agricultural College and Experiment Station publication referred to.

> In our own country the difference between the present table and that of the pilgrim fathers is so great as to account to some extent for the present lack of leisure of the housewife. To fish, brown bread, pork and beans, vegetables, have been added the present salads, ices, elaborate puddings, cakes, and the many forms of dessert. [In the earlier times] * * * there was a regular baking day, when large quantities of baked beans, pies, and bread were prepared.

The baking day and the preparation of large amounts of food at one time, with the consequent economy of labor, are much less common than was once the case. Changes in customs and standards of living and a more varied food supply have led to the selection of many dishes which are best if freshly prepared and to menus which are very often needlessly elaborate. All this means added work for the housekeeper. The careful selection of food and the planning of meals [illegible] do much to lessen household labor, and if this is done with due [illegible] ence to nutritive value of foods and wholesome combinations results will oftentimes be more satisfactory than is at present the case.

> All are coming to know that simpler living is necessary, not only for the c[illegible] of the housekeeper but for those who sit at her table. Elaborate menus are entire[illegible] possible when one woman does all the work. * * * The elaborate meals and the unnecessary dishes are not for the good of anyone. They interfere with the beautiful grace of hospitality; they prevent the happiness of the cook and the preservation of her strength. Simple, wholesome meals, with intelligent cooking and serving, are a blessing to any household.

In homes where the diet is too monotonous and the preparation of food is not in accordance with right standards of living, the knowledge of proper methods and ways of utilizing available food supplies will result in a much more satisfactory diet with the same amount of labor, or indeed oftentimes with less expenditure of time and energy.

Commenting on the lack of variety in food noticeable on many busy farms and ways in which it may be obviated, Professor Day makes the following statement: "Most farmers have to depend on chickens for the greater part of their fresh meat, and unless one is in the poultry business the care of chickens is another burden added to the household." The increased time which labor-saving devices in the home and convenient construction of the farm house make possible would give the farmer's wife time for her poultry, and then poultry keeping need not be a burden. There should certainly be no lack of fresh vegetables on the farm, but frequently the farmer can not give the necessary time to the kitchen garden and the farmer's wife is unable to find time for gardening, though most women doubtless consider gardening a recreation rather than a task. "If only the men can do the first hard work in the garden and see that the indoor burdens are lightened, most women will welcome the opportunity for work out of doors among the green things, and will be the better for it physically."

The above statements make it plain that if the diet is out of harmony with rational standards, either because it is too elaborate or because it is too monotonous or unsatisfactory in other ways, it is possible by the application of knowledge now available to improve conditions and at the same time lessen the housewife's burdens.

> In few departments of home life has there been so much improvement in the last one hundred years in the economy of labor and fuel and in scientific methods as in cookery. It remains, therefore, for the housewife to take advantage of the gain in time and labor to study the kind and quantity really necessary, and the best and simplest way of preparing food, in order that she may have time at her disposal for the other duties in and out of the home and to add to her own leisure and means of self-improvement.

HYGIENIC CONDITIONS AND COMFORT.

Professor Day also calls attention to the need of home conveniences th reference to comfort and hygienic conditions. Flies and other ehold insects not only make work for the housekeeper, but are agencies in the spread of disease, and there is every reason why they should be kept out of the house by screens at windows and doors. Much may also be done to prevent the breeding of such insect pests. per drains and other sanitary conveniences not only lighten the housekeeper's duties, but are also of the utmost importance in the hygiene of the home.

> The isolated home needs not only to use special care to make its numerous duties easily done, and to be most careful of all health conditions. * * * but it has also special problems in educative recreation.
>
> "Home is peculiarly the place of rest, though the birth place of all industries." * * * The home has not kept pace with the industrial world in improving the methods of adjusting household affairs. Housework should be carried on with no more loss of time or energy than is involved in the conduct of any well-managed business. To be independent we must sacrifice many of the customs to which we cling. The old order is passing away and the sacredness of home will not suffer, but, instead, we will have a greater development and more opportunities for freedom and happiness.

Recreation and amusement are essential features of a normal life and are as much the right of the farmer's family as of those who live in larger communities, to whom music, art, and many other forms of recreation involving high ideals are more conveniently accessible. However, by means of books, farmers' institute work, lectures, traveling schools, clubs for home study, etc., much that is really best is within the reach of all. The lightening of home burdens by means of a well-equipped and hygienic house, by the use of household conveniences, and by the proper understanding and systematizing of home work, means that the home maker and her family may have opportunity for something beside the daily tasks which too often leave neither time nor inclination for recreation.

LINING OF DITCHES AND RESERVOIRS TO PREVENT SEEPAGE LOSSES.[a]

In a recent bulletin of the California Station E. Mead and B. A. Etcheverry call attention anew to the enormous waste of irrigation water due to seepage from ditches and reservoirs. They show from general observation and from a large number of careful measurements that "the water which sinks into the soil from ditches and reservoirs is one of the chief sources of waste in irrigation. In gravelly soils, or where ditches cross gypsum strata, the losses sometimes amount to more than half the total flow." Measurements made on a large number of ditches in the course of the cooperative irrigation investigations of the Office of Experiment Stations and the California Station "show an average loss on main canals of about 1 per cent for each mile that water is carried; on laterals the loss amounted to between 11 and 12 per cent per mile; while on some California canals the loss in a single mile was 64 per cent. * * * Measurements made in 1906 on a storage reservoir having a surface of 10,000 square feet showed a seepage loss of 1,000 cubic feet per day. The reservoir is filled by a windmill, and this loss was 10 per cent of the average quantity pumped each day—a loss too heavy to be borne. The problem of this reservoir owner is the problem of hundreds of irrigators. * * *

"The water which escapes is often worse than wasted. It collects in the lower lands, fills the soil, drowns the roots of trees and plants, brings alkali to the surface, and is a prolific breeding place for mosquitoes."

In the course of the same investigations attempts were made to find practical means of lining storage works and canals and ditches to prevent or at least to reduce this waste and consequent loss. "From the results obtained the conclusion was reached that on large and costly aqueducts or important storage works, linings of cement, concrete, or asphaltum may be employed without the expense being prohibitive." It is pointed out, however, that a very large proportion of the irrigation of the country is done by means smaller, cheaper reservoirs and other works, the owners of 'can not afford the expense needed to line the reservoir with e or asphalt because the value of the water stored will not this expense."

---

[a] Compiled from California Sta. Bul. 188.

ɘw of the fact that the greater proportion of the losses occur on ditches and small storage basins, it is necessary to find some and cheaper, but efficient, lining which can be applied by ı and unskilled laborers. It is clear that the general use of nethod would result in a great improvement of irrigation pracl a marked increase in the duty of water.

lling was tried, but as a rule there was not sufficient clay in the make this efficient. A natural silting up, with consequent ement of water-holding capacity, of reservoirs and ditches g muddy water frequently occurs, but a large proportion of ;ation water used, notably that obtained by pumping, is clear, refore no silting results.

ıe large number of available raw materials promising well as nd reservoir lining, cement, clay, and crude petroleum were ıs ditch linings in the California experiments. The principal ɔf the test are given in brief in the following table:

Results of tests of various ditch linings.

Description of lining.	Efficiency ratios.	Saving.	Experimental cost of lining per square foot.	Actual cost of lining per square foot.
		Per cent.	*Cents.*	*Cents.*
ıcrete, 3 inches thick	7.17	86.6	8.30	7.50
ıe concrete, 3 inches thick	2.90	65.5	8.30	7.50
rtar	2.73	63.3	3.88	3.25-3.50
3⅜ gallons per square yard	2.02	50.4	1.20	1.20
ɘ, 3½ inches thick	1.78	47.8	3.90	1.20
3 gallons per square yard	1.50	38.0	1.00	1.00
2½ gallons per square yard	1.37	27.3	.77	.77
gallons per square yard	1.08	7.3	1.00	.80
lining)	1.00	0.0		

;able shows wide variations in the efficiency and cost of the t lining materials.

there is no doubt that cement concrete is the most efficient as regards it is also the most expensive, being more than six times the cost of the heavy (3⅜ gallons per square yard), which saves 50.4 per cent of the water which ep were the ditch not lined. This saving with the concrete ditch is 86.6 or one and three-fourths times as large. Where water is very valuable there ıbt but that the concrete ditch is more permanent and economical. But e water is not so scarce and a little waste will do no damage, the expense the ditch with oil may be justified, while a more expensive lining would cticable. * * *

ıddle lining in the experiment showed a saving in seepage nearly equal to y oil lining when 3⅜ gallons of oil per square yard was used, and a greater an the other oil linings. This puddle lining, whose thickness was 3½ inches, would no doubt, if made thicker, be more efficient than any of the oil linings as regards seepage; but clay puddle when wet becomes very soft and will not resist the erosive force of the flowing water unless the velocity is very small. It will not prevent the growth of weeds. For these reasons it is probably not as efficient for canal linings as oil. But where clay is plentiful it would be preferable for reservoir lining. The slopes should, however, be protected against the erosive action of the waves by the use of cobblestones or other protection.

The use of oil in lighter quantities, while not very efficient in preventing seepage, will no doubt prevent the growth of vegetation. * * *

Cement-mortar plaster, so extensively used in southern California, showed a saving in seepage water of 63 per cent. Better results were expected, and it is probably safe to expect a greater saving where good work is done, especially where the work is constructed in cold weather. This lining had to be applied when the temperature in the field was probably 110° or over. The cement mortar was mixed in small quantity and quickly applied. As soon as the setting had started the lining was sprinkled and covered with wet canvas, but even with these precautions better work could be done in cooler weather.

This plaster, while very efficient and economical on small ditches, would not be of sufficient thickness and strength to be used on the larger canals and laterals of larger irrigation systems, where a thickness of from 2 to 4 inches would no doubt be successful.

CEMENT PIPE FOR SMALL IRRIGATING SYSTEMS AND OTHER PURPOSES.[a]

The need of better methods of using the limited water supplies available in many parts of the irrigated region, as illustrated by conditions in certain localities in Arizona, is thus presented by G. E. P. Smith in a bulletin of the Arizona Experiment Station:

Throughout southern Arizona there are scattered many sparsely settled valleys, traversed by the characteristic rivers of the arid region. These rivers are normally dry beds of sand, but at intervals they carry great floods of water. In most cases the soil, both of the bottom lands and the adjoining mesas, is fertile and easily cultivated, climatic and other conditions are good, and the markets are excellent. The water supply, however, is so slightly developed that agriculture is a very precarious business. Winter crops are sown with a large element of doubt as to whether harvests will be reaped, and through the summer much of the same land is not utilized at all, while adjacent areas of great productive capacity are still wastes of mesquite and catclaw. The water supply already developed in these valleys is largely derived from small ditches heading in the sandy river beds. A few pumping plants have been installed in favored localities.

While the area of irrigated land is being rapidly extended throughout the West, and many monumental enterprises are being developed, yet the smaller valleys above referred to seem to have been neglected and very little change has been wrought since their occupation began.

Without asserting that there are unlimited, or even abundant, water supplies for these valleys, yet it is demonstrably true that their cultivation can be very greatly extended, not only by largely increasing the water supply, but also by the adoption of modern methods in the development, distribution, and use of irrigating streams. At present the settlers are confronted with the many problems relating to such improved methods. The mountains must be surveyed for reservoir sites, the valley gravels must be explored and studied to locate and secure the water which they can yield, pumping plants must be more intelligently designed, for great economics are possible in their design and operation. the water must be saved from loss by seepage and evaporation in ditches, and the ground must be so mulched and cultivated as to conserve the water after it has been applied to the fields. It is no extravagance to say that by careful methods the present very low duty of water in these valleys can be more than doubled.

---

[a] Compiled from Arizona Sta. Bul. 55.

One of the most experienced irrigation engineers[a] in the West has recently stated that, of the millions of dollars spent annually by our irrigated districts for water and for applying it to cultivated crops, fully 70 per cent of the money is wasted. What an opportunity is thus offered for investigation. What an argument for the introduction of methods that may result in utilizing a part of that 70 per cent which at present is not put to any beneficial use. It seems imperative that agricultural interests should join in a campaign for a higher duty of water. The main purpose of this bulletin is to discuss one phase of this campaign, namely, greater efficiency in transmission and distributing systems.

The same authority quoted above states that as a rule cultivated fields do not receive more than 66 gallons out of every 100 gallons of water which pass through the upper headgates, the rest being lost by seepage and evaporation. In Arizona the river beds and banks are usually of very porous sand and the ditches leading through these deposits suffer great loss of water. Occasionally the extreme case occurs in which the entire flow is thus lost. * * *

In seeking a remedy it is to be observed that seepage losses can be stopped by proper lining for ditches, while both seepage and evaporation are prevented by closed conduits. The materials available for these purposes are wood, cement, and clay. All have been employed in various parts of the West. The only one tried so far in southern Arizona has been wood; but its short life and the warping and leaking which it undergoes, together with high cost, unfit it for use in ditches. Cement pipe for small ditches and cement lining for large ones are from every point of view to be recommended. Clay tile lacks strength, and since at present it is subject to long freight hauls, its cost is very much greater than that of cement pipe. The latter is composed largely of sand and gravel found in the vicinity of the ditches and only the cement ingredient is subject to a freight charge.

There are other advantages in piping ditch waters besides the prevention of seepage and evaporation. The maintenance of open ditches is very difficult. Under the subtropical skies of Arizona weeds and algæ grow rankly and unless removed at frequent intervals they soon obstruct and diminish the flow. The Flowing Wells ditch near Tucson costs $80 per mile per year for cleaning alone. Furthermore, gophers perforate the ditch banks and cause the waste of rivulets for days or even weeks before the holes are discovered. Sometimes the holes enlarge and the ditch bank breaks, with consequent loss of the entire stream. The maintenance of cement pipe lines should be very slight.

To determine the practicability of making cement pipes and the best mixtures and methods to be used, Professor Smith established a small plant and made six different lots of 15-inch pipe, "this size being of such capacity as to adapt it to many streams belonging to individuals or small companies of ranchers." Using a very lean mixture of cement, lime paste, and sand, the paste being thinned to a consistency that permitted it to mix thoroughly with the sand, for the body of the pipes, and a mixture of 1 part cement and 3 parts sand for the bell ends, very satisfactory results were obtained.

---

[a] Samuel Fortier, Irrig. Age, 21 (1906), p. 378.

The method of molding is described in detail. Several molding forms are on the market and can be rented by paying a small royalty. The molding outfit used in the experiments described contained molds for both bevel and tongue, and bell and spigot joints, and cost $60. "It could be made ample for continuous operation at 40 tile per day for $75 more."

The results of accurate observations on the cost of cement-sand and cement-lime-sand pipe are recorded in the following table:

Cost per 2-foot length of 15-inch pipe.

	Cement-sand.	Cement-lime-sand.
Cement at $4.50 per barrel	$0.563	$0.375
Cement, hauling 7 miles	.035	.023
Lime at $13 per ton, delivered		.058
Sand, no charge		
Water, no charge		
Labor: Foreman, $2 per day; 2 laborers at $1.25 per day	.112	.112
Wash of neat cement	.060	
Cost per 2-foot length	.770	.568
Cost per linear foot	.385	.284
Cost per mile	2,032.80	1,499.52

"Being made in close proximity to the river sand and within 20 feet of an irrigating ditch, no allowance is made for sand or water. [The] figures are based on Tucson prices during April, 1907, and must be modified to conform to the local prices at points where cement pipe lines are contemplated. * * * In some cases a considerable allowance should be made in the estimate for sand."

Observations on the construction of a redwood flume built in the same vicinity and at the same time as the cement pipe show that the cost of a flume of capacity (12 by 16 inches) equal to that of 15-inch pipe would be 25 per cent greater than the cement-sand pipe and 70 per cent greater than the cement-lime pipe, the differences amounting to $528 and $1,061 per mile, respectively. It must be borne in mind, too, that the chief advantages of the cement pipe are greater permanence and less loss of water by leakage.

The comparative merits of such pipe, clay tile, and concrete, crude oil, asphaltum, and puddled clay are discussed, the cement pipe being considered to possess decided superiority in many respects, particularly for the local conditions. The cement pipes are also shown to have a variety of other important uses.

The following example of the financial advantage of piping water in Arizona (and similar conditions are not uncommon elsewhere in the arid region) is cited:

In a certain ditch carrying about 100 miner's inches through sandy deposits, the loss of water per mile exceeds 10 per cent, say 10 miner's inches, capable of irrigating an additional 30 acres on the ranch, which would yield a net profit, estimated at $30 per acre in alfalfa, of $900 per year. This water could be carried in a 15-inch pipe line costing $2,500 laid, the interest on which at 8 per cent would be $200. The maintenance of the pipe should be very much less than that of the open ditch; the frequent cleaning of the weeds and algæ would be entirely eliminated. The net profit resulting from the pipe line would therefore be $700 per annum.

POLLINATION OF FORCED TOMATOES.[a]

It is well known that greenhouse tomatoes do not set fruit freely during the midwinter season. The only satisfactory method for correcting this trouble is to fertilize the blossoms by hand. A description of this method, together with a discussion of the conditions favorable for pollinating, is given in a Farmers' Bulletin on "Tomatoes" of this Department.[b] It is here desired to emphasize the importance of pollinating carefully and thoroughly. In house-grown tomatoes there is often a considerable percentage of one-sided fruit and of small fruit, which greatly detracts from the value of the crop. The general inferiority in size of winter-grown tomatoes can undoubtedly be attributed to the comparatively short periods of sunshine during that season of the year. On the other hand, the results of station investigations along this line show that imperfect pollination is an important cause of one-sided and small fruits. While working at the Cornell Station, W. M. Munson found that the amount of pollen used may have an important bearing in determining the form and size of the fruit.

> In the winter of 1890–91, while crossing tomatoes, two stigmas in the same cluster of flowers were given different amounts of pollen. The first was given a very small amount—10 to 20 grains—on one side of the stigma; the other was given an excess of pollen, the stigma being well smeared. The effect on the form and size of the fruit was very marked. The fruit receiving the large amount of pollen was of normal size and nearly symmetrical in form, while the other was small and deformed. The larger fruit produced an abundance of seeds and all of the cells were well developed; the smaller developed seeds on one side only, while the other side was nearly solid.

The experiments were repeated several times during the following winter, and similar results were obtained, both when "the flower nearest the base of the cluster received an excess of pollen, while the other received a very small quantity on one side of the stigma" and when "the flower at the base received the small amount of pollen, while the other was given an excess," thus indicating that the relative position of the flower had no influence in determining this point.

No conclusion was reached by Munson as to the exact number of pollen grains necessary to insure proper fertilization, but in no case was fruit secured "when all pollen was excluded, and in every case the size of the fruit was in direct proportion to the amount of the pollen used."

---

[a] Compiled from Maine Sta. Rpt. 1892, pp. 48–51; Indiana Sta. Rpt. 1904, p. 17; Michigan Sta. Spec. Bul. 39; New York Cornell Sta. Bul. 28.

[b] U. S. Dept. Agr., Farmers' Bul. 220.

Experiments with greenhouse tomatoes, recently reported from the Michigan Station by S. W. Fletcher and O. I. Gregg, not only confirm the results secured by Munson, but also appear to show, as indicated by earlier experiments by J. Troop of the Indiana Station, that there is no decided advantage to be gained by the cross pollination of varieties as compared with self-pollination. Six varieties of tomatoes were included in these experiments, viz: Ignotum, Stirling Castle, Earliana, Best-of-All, Lorillard, and Frogmore. "Four plants of each variety were used * * * to determine the effect of using varying amounts of pollen. All the flowers on one plant of each variety were emasculated and pollinated on one side of the stigma only. These invariably produced lop-sided and small fruits. All the flowers of one plant of each variety were pollinated with from one to five pollen grains. These produced very small, solid fruits, with an average weight of but 34 grams (about 1 ounce) and having no seeds, or but one or two. All of the flowers on one plant of each variety were pollinated with a large amount of pollen, spread all over the stigma. These produced fruits that were smoother and averaged 12 grams heavier than fruits produced from flowers that had but a small amount of pollen applied all over the stigma." The conclusions deduced from this work are that "when pollen falls upon one side of the stigma only, a one-sided tomato always results. The larger the stigma the greater the irregularity. The amount of pollen applied to the stigma determines to a great extent the size and smoothness of the tomato; but after applying a certain amount of pollen no further increase in size or weight results by applying more. The small, irregular tomatoes grown under glass are caused largely by insufficient pollination."

With the view of throwing some light on the relative value of cross and self pollination, "the blossoms on four plants of each variety were self-pollinated, and the blossoms of eight plants of each variety were cross pollinated with two other varieties. All set fruit equally well. The 265 fruits produced from self-pollination on all six varieties had an average weight of 77.3 grams. The 534 fruits produced from cross pollination on all six varieties had an average weight of 79.1 grams," from which it will be seen that there was practically no gain in the total number of cross pollinated fruits secured, and but a slight difference in the weight of the individual fruits in favor of cross pollination.

Although it does not appear necessary to raise several varieties for the purpose of cross pollination, there is no harm in alternating such varieties as are grown, and in some cases a possible benefit may be obtained, such as a slight increase in the average weight of the it.

All of the experiments, however, do show most conclusively that the setting of a good crop of smooth, heavy fruit depends very largely upon the care taken in distributing the pollen, especially during the cloudy weather which is likely to be of frequent occurrence in midwinter.

INCREASING THE PRODUCTIVENESS OF CORN.[a]

The production of every crop is influenced by many different factors, and in so far as these are under control the yield may be increased and the fertility of the land maintained or improved. It is necessary, therefore, to take all the different factors into consideration to reach the maximum production. In a recent bulletin of the Kansas Experiment Station, Professors Ten Eyck and Shoesmith describe the results of a series of expermients with corn carried on for four years, in which the more important factors entering into the production of larger and more profitable crops were taken into account.

VARIETIES.

During the period of the experiments 112 varieties of corn were planted for trial and comparison. The methods of cultivation for the last three years of the variety test are described. In 1904 the land was disked twice from March 10 to 15 for the purpose of conserving the soil moisture, and a second disking was given April 29 to May 2, just prior to listing the corn in furrows about 5 inches deep, with the rows 3½ feet apart and the kernels 16 inches apart in the row. For the test in 1905 the land was plowed November 24 to December 10, harrowed March 29 and again April 10, and the corn planted with a planter on April 28 and 29 at the same distances used in 1904. In 1906 the varieties were planted after winter wheat, followed by rape in the stubble after harvest, which was plowed under when about 16 inches high near the middle of October. The land was disked soon after plowing and was harrowed twice in the spring before planting. The corn was planted May 2 to 4 in the same manner as the year before.

Of all the varieties tested Hildreth, Kansas Sunflower, McAuley, Forsythe Favorite, Golden Row, Hammett, Leaming, U. S. P. B. Selection No. 77, Hogue Yellow Dent, Sander Improved, White Salamander, Red Cob White Dent, White Injun, Legal Tender, Warner, Mammoth Golden Yellow, Dyche, Meinhardt, and Hiawatha Yellow Dent were superior in productiveness. The ten most productive varieties in the three years, 1904–1906, ranged in average yield from 57.81 to 61.25 bushels, and the ten highest for the four years from 58.05 to 65.21 bushels per acre. In 1905 the 75 different varieties tested matured in 121 to 143 days, the average period being 129 days. Of 35 varieties grown for four years the 16 which required 126 days or less to mature gave an average yield of 61.45 bushels, while the rows requiring 127 or more days yielded on an average 64.94 bushels per acre.

---

[a] Compiled from Kansas Sta. Bul. 147.

White Injun, which held the highest 3-year record, is a red-cobbed white dent and a selection from Red Injun No. 81, originally selected by the station for breeding on account of its deep kernels and well-filled butts and tips. Red Cob White Dent, a hardy variety of medium growth and maturity and fairly uniform type, is considered valuable for general planting. McAuley, which also ranked high as a good yielder, is a white dent of fairly uniform type resembling Boone County White. It is described as medium late in maturing, of vigorous growth, hardy, and well suited to bottom land or fertile upland. Golden Row and Hogue Yellow Dent, received from the Nebraska Experiment Station, appeared to be well adapted to the northern part of the State.

The results of the variety tests also showed that Kansas-grown corn is better adapted to Kansas than seed corn from other States, although pure bred and highly productive. It is recommended that the varieties generally grown within the State be more extensively tested and improved and that some of the best varieties from other States be thoroughly adapted to the conditions prevailing in Kansas before their general dissemination.[a]

MOISTURE CONTENT.

After husking, the percentage of moisture in the different varieties of corn was determined by drying the kernels and cobs separately in an oven at 110° C. In 1904 the moisture content in the ear corn ranged from 11.90 to 29.02 per cent, in 1905 from 11.66 to 21.86 per cent, and in 1906 from 10.73 to 19.43 per cent. The data secured are taken as indicating that under Kansas conditions well-cured ear corn put into the crib in the fall contains on an average about 15 per cent of moisture.

METHODS OF CULTURE.

A comparison of different methods of preparing land for corn was begun in 1903. Early in April one plat of corn stubble land was double disked, another double disked and harrowed, a third listed in furrows 3½ feet apart, a fourth plowed and harrowed after plowing, and a fifth received no treatment. Early in May all plats were planted with a lister. On plat 3 the ridges were split at planting time, the corn being planted in the newly listed furrows. In 1904 and 1905 several additional treatments were introduced. One plat was plowed 6 to 8 inches deep, another 3 to 4 inches deep, and both were planted with the surface planter. In another set of plats the first was plowed and planted with a lister, the second was listed early and the corn planted in the same furrows, and the third was treated the same as plat 3, described above. These different treatments were always given as soon as the soil was in condition for cultivation. The results of these different methods of preparing the seed bed showed that listing early in the spring and splitting the ridges at planting time gave an increase in yield of 5.02 bushels per acre over land receiving no early treatment. No difference in the average yield apparently due to other early treatment was observed. During the four seasons surface planting yielded on an average 6.65 bushels more corn and 469 pounds more stover per acre than listing.

---

[a] See also U. S. Dept. Agr., Farmers' Bul. 244, p. 7.

In a single trial in 1905 surface planting with a disk furrow opener attachment yielded 53.24 bushels, ordinary surface planting 51.94, and listing 48.33 bushels per acre. The furrow opener is a device intended to secure the advantages of listing corn without all of its disadvantages. It was observed that the corn planted with the disk furrow openers sprouted quicker and made a more vigorous early growth than surface-planted corn, and that it retained this advantage throughout the season.

There is an advantage, also, in cultivating the disk-furrow planted corn similar to that secured by listing, in that the weeds in the row are more easily covered and destroyed by the early cultivation than is the case with surface-planted corn. Also, there may be a similar advantage, as obtained by listing, in that the corn roots lie relatively deeper in the soil and are covered with a greater depth of mellow soil at the last cultivation when the corn is laid by. It is well to remember, however, that when the furrow openers are used it is necessary to plow the land and prepare a good seed bed the same as for surface planting, and also that it requires four horses to operate the corn planter with the furrow-opener attachment.

The soil moisture determinations made show without exception that listing as compared with surface planting favored the conservation of soil moisture in the latter part of the season. This result is considered as possibly due to the larger growth of surface-planted corn, to the level culture given listed corn and the slight hilling of the surface-planted crop, and to the last cultivation of the listed corn being uniformly deeper than in the case of the surface-planted plats.

For two years tests were conducted with planting at different dates, and the average results show that planting May 26 gave the best yields, and that the May plantings gave better results than the April plantings.

Cultivation experiments were conducted only with surface-planted corn. Four cultivations were given each season. One plat was cultivated shallow and another deep throughout the season and on two plats the first two cultivations on the one were shallow and tl last two deep, while on the other this plan was reversed. Shallow cultivation was about 1½ inches and deep cultivation about 3½ to 4 inches deep. The disk cultivator and the weeder were also used to some extent in these tests. The average yields for the several seasons did not vary much and the results are taken as indicating that the exact method of cultivating is not so important as the conditions of soil and season. It was observed, however, that each season the shallow cultivated corn matured several days later than the deep cultivated corn, and further that in case of the shallow cultivation laying the corn by was a decided advantage, the average yields of stover being the greater on the plats receiving this treatment. The weeder proved effective on mellow soil when the weeds were small, but on hard ground with large weeds it did not take the place of a good cultivator.

FERTILIZERS.

In comparative fertilizer tests carried on in 1906 the largest yield, 56.63 bushels per acre, was secured on land treated with 13 tons of barnyard manure per acre. The next largest yield, 40 bushels per acre, was obtained on a plat treated with 50 pounds of nitrate of soda applied broadcast. The average production of the unfertilized land was 33.21 bushels per acre.

ROTATIONS.

The following crops were grown in rotation: Wheat, wheat followed by cowpeas as a catch crop, oats, barley, emmer, flax, millet, sorghum, Kafir corn, corn, corn followed by cowpeas as a catch crop, corn followed by rye as a catch crop, soy beans, and potatoes. The arrangement was such that each year corn was grown after the various crops and the various crops after corn, and the object of this rotation test was to study the effect of each of these crops upon the growing of corn. The data secured show that the largest average crop of corn, [illegible] bushels per acre, was grown after potatoes. The second largest yield of corn, [illegible] bushels per acre, was produced after soy beans, and the third largest, [illegible] bushels, after corn. After the other crops the yields were smaller than when corn was grown after corn, the lowest yields being produced after Kafir corn and sorghum. In average value of [illegible] the rotation of corn with potatoes ranked first with $[illegible].47 per acre, the corn being valued at $20.99 and the potatoes at $[illegible], corn after Kafir corn second, with $34.46 per acre, corn after sorghum third, with $[illegible].15, and corn continuously [illegible] with $[illegible]. While the lowest yields of corn were produced after Kafir corn and sorghum the large yields of these crops made the value of the total production from these rotations relatively high.

The plats growing corn continuously, in which rye was sown each fall ranked third in average yield and fourth in value of total production.

A catch crop of rye in corn helps to eradicate weeds, utilizes available plant food left in the soil in the fall which otherwise might be washed out or drained away, provides a protection to the soil through the fall and winter, thus preventing the soil from blowing, catching the rain, and stopping the drifting snow. When corn follows rye in this way it is necessary to plow or double list, and this should be done rather early in the spring, unless it is preferable to plow late in the fall. If rye is plowed under late in spring, the seed bed is apt to be left loose and dry, and if corn is listed in rye, the rye becomes a troublesome weed which is difficult to destroy and which may injure the growth of the corn.

The sowing of rye in the corn seemed to give better results than the catch crop of cowpeas, but a marked increase in yield of corn after wheat and cowpeas, amounting to 8.76 bushels per acre, showed the value of this crop as a fertilizer when grown between small grain and corn. The apparent advantage of rye over cowpeas in this test is considered due to the fact that the rye, having been sown late, did not compete with the corn for moisture and plant food to the same extent as the cowpeas, which had been sown earlier in the season. None of the rotation systems tried are regarded as ideal, as a practical and scientific rotation is intended not only to produce large yields, but also to maintain the fertility of the soil, and that such a rotation would include grasses and perennial leguminous crops, as well as the growth of annual leguminous plants and catch crops.

BREEDING.

In corn-breeding work the station found in some tests a difference of more than 400 per cent of the yields from different ear rows. In 1906, the Silvermine high-yielding-rows seed plat yielded 32 per cent more corn and 24.8 per cent more first-grade seed ears than the plat planted with first-grade seed. The Hildreth high-yielding-rows seed bed yielded 10.36 per cent more corn and 40 per cent more first-grade seed ears than the plat planted with first-grade seed of this variety. It is pointed out that the results of the breeding work show that the individuality of certain ears can be utilized in the improvement of a particular breed or variety. The breeding stock of Kansas Sunflower corn, after four years' breeding by the station, traces back to two original mother ears. Germination tests indicated that ears of corn may vary greatly in vitality regardless of selection and preservation, and that it is therefore very important that each ear of seed corn be subjected to germination tests in order to remove those of low vitality.

SHRINKAGE OF CORN IN CRIBS.[a]

In connection with the marketing of many farm products shrinkage is always an important consideration. Farm crops generally are subject to shrinkage when put in storage after harvest, but it often amounts to so little that it is entirely disregarded. In ear corn and hay, however, the loss of weight during storage may be quite large, and with these crops, therefore, shrinkage is as a rule taken into account. That ear corn generally sustains important losses in weight during storage is so commonly acknowledged that in many localities the custom prevails of taking 75 pounds of ear corn for a bushel in the fall and only 70 pounds in the spring. Observations on the shrinkage of stored crops have been made by several of the experiment stations, and the results have been noted in a previous bulletin of this series.[b]

In some of the more recent work along this line by the Illinois Station the purpose was to ascertain whether it would be more profitable to market corn as early as possible after husking or to hold it until winter or spring before selling it. Not only the losses in weight were determined, but the increases in price necessary to compensate for these losses were also calculated.

For the purpose of making these observations on the shrinkage of stored ear corn cribs were constructed at Urbana and Sibley in such a manner that they could be lowered to rest upon the platforms of large wagon scales and weighed. At Sibley a check experiment was made by weighing each wagonload of corn as it was put into a stationary crib constructed of ordinary fencing lumber on blocks and weighing out all the corn when the crib was emptied at the end of the trial. The first year the shrinkages of the two cribs at Urbana and Sibley varied between 12.3 and 19.8 per cent.

The data secured from other weighings and also the results from some preliminary trials are reported. On December 6, 1901, 20,545 pounds of corn were weighed into a crib at Sibley and weighed out again September 25, 1903, when the weight was found to be 18,690 pounds. The loss in weight amounted to 1,855 pounds, or 9 per cent for the entire period of over 22 months. Another crib close by, receiving the same amount and kind of corn and filled and emptied on the same dates as the other, showed a loss of 1,895 pounds, or 9.2 per cent. In still another test a stationary crib was filled during the week preceding November 11, 1905, with 19,850 pounds of ear corn. November 3, 1906, when the corn was taken out of the crib it weighed 17,280 pounds, showing a loss of 12.9 per cent for the year. Taking all the trials into consideration the loss in weight of the corn in the different cribs ranged between 9 and 20.7 per cent for nearly two years' storage.

---

[a] Compiled from Illinois Sta. Bul. 113; Kansas Sta. Bul. 147.

[b] U. S. Dept. Agr., Farmers' Bul. 149.

The data secured also indicate that the shrinkage for the second quarter of the year was not much in excess of that for the first, the difference being an average of only 2.10 per cent. The shrinkage for the third quarter, however, was noticeably greater than that of the second, the average difference being 8.70 per cent, while the shrinkage for the last quarter from June to September averaged only 2.10 per cent. It was found that by far the most noticeable shrinkage of ear corn in the cribs occurred during the months of April and May, after which period the corn sustained only a gradual loss.

The observations made on the loss in weight during the second year of storage point to the fact that practically all moisture comes out of ear corn during the first year of storage. In a trial at Sibley continued through the second year the shrinkage was 19.6 per cent at the beginning of the year and had only increased to 20.5 per cent by the following September. At Urbana the corn also lost 1 per cent in weight during the second year. From these results it is concluded that it seems safe to assume that old corn may be stored in cribs with very slight loss from shrinkage. The weekly weighings showed that the crib weights were influenced by the amount of moisture in the atmosphere.

In determining the increase in price that must take place between cribbing time and the following December, March, June, and September, it was assumed that the corn might have been marketed at cribbing time for 35 cents per bushel, and the average of the "high" and "low" Chicago cash prices for December and May as summarized from the Yearbook of this Department for 1905, which shows a difference of 3.8 cents per bushel in favor of May, was also taken as one of the factors in the calculation. Furthermore, it was pointed out that this average difference in price and the allowance of 5 pounds per bushel for shrinkage would make the actual average rise in price between May and December 6.3 cents per bushel. This computation shows that when the percentage of decrease in the weight of ear corn up to and including September of the first year runs from 12 per cent to nearly 20 per cent, as in the four different trials under consideration, an increase in price for September varying between 4.9 and 8.6 cents per bushel is necessary to cover the loss in weight and to insure the farmer against financial loss in holding his corn. In two of the trials the decrease in weight between December and June was greater than would be covered by the average increase in price of 6.3 cents between December and May, while in the other two trials it was smaller, so that the average increase in price, including the usual 5 pounds decrease in the number of pounds taken from 1 bushel, is considered as possibly covering the average shrinkage.

At the Kansas Station shrinkage experiments were conducted for three years in three small board cribs holding about 4,000 pounds of ear corn each. The cribs were lined with fine wire netting in order to confine the loss in weight as much as possible to the actual shrinkage of the stored corn. They were filled each fall when the crop was in good condition for storing with Forsythe Favorite and McAuley, white dent varieties, Reid Yellow Dent, Kansas Sunflower, and Hildreth, yellow dent varieties, and with mixed corn consisting of a few bushels each of many different varieties.

In 1903 the white corn at husking time contained 24.94 per cent of moisture and the yellow corn 19.73 per cent. The corn lost 2.33 per cent in weight on the average during the first month, with but little decrease in weight during the rest of the winter, but by May 6 the total average loss for all cribs had reached 6.14 per cent. The yellow corn showed a loss of 5.66 per cent in the last month of the trial, but in the other tests the weight of the corn remained about the same through the summer. The final weights showed a shrinkage of 7.92 per cent as an average for eight and one-half months for all cribs. The white and yellow dent corn lost on the average 3.79 per cent more in weight than the mixed corn.

In 1904 the corn ripened earlier than in 1903 and the first comparative weights were taken October 26, as compared with December 5 in the previous year. The white corn contained 18.95 per cent of moisture and the yellow corn 21.32 per cent when put into the crib. On January 31 the average loss in weight in all cribs was 5.17 per cent, the yellow corn showing the greatest decrease. Again, there was little loss in weight during the winter but a great shrinkage in weight during the spring and early summer months. The lowest weights for the year, with the exception of yellow corn, were recorded on June 20, the average shrinkage at that date being 11.32 per cent. The final weights taken October 7 showed an average shrinkage of 12.21 per cent. As in the year before the mixed corn again lost least in weight, the ratio of shrinkage being 6.72 to 14.88 per cent for the yellow and white corn. On July 20 and August 24 an actual gain in the average weight of the cribs was recorded and the mixed corn continued to gain from August 24 to the end of the test.

In 1905 the first comparative weights were taken November 16. By December 23 the cribs had lost only about one-half of 1 per cent of weight on the average and the crib of white corn had actually gained in weight. On February 6 the average shrinkage was 2.26 per cent and on April 19, 3.86 per cent. All cribs gained in weight during May, after which there was a gradual decrease in weight until October 16, when the final weights showed an average shrinkage for the entire test of 5.82 per cent in eleven months. The yellow corn showed a loss of 8.48 per cent in weight, the mixed corn of 6.42 per cent, and the white corn only 2.44 per cent during the whole period.

Five samples of white corn at husking time contained on the average 15.2 per cent of moisture and a single sample of Reid-Yellow Dent, husked a little earlier than the white, contained 18.9 per cent.

It is pointed out that the average results indicate that when corn is put into the crib fairly dry and in good condition the shrinkage during the winter months is not great, being a trifle over 5 per cent as an average for the first six months after the corn was cribbed, and that this loss would not be sufficient usually to equal the difference in weights which are required for a bushel of ear corn as sold in the fall and as it may be sold in the winter or early spring. It is believed that the loss on the original weight in the eight or ten months is not so great as the decrease in the actual value of the corn, when considering that at husking time the price is often more than 10 per cent less than in the spring or early summer. The total shrinkage of weight in a year of the nine cribs of corn was only 8.62 per cent. Attention is called to the fact, however, that precaution was taken to avoid loss in weight from other causes than shrinkage.

As to whether the farmer should hold his corn or sell it early in the winter may depend upon several factors, as the price of corn, size of the general crop, condition at husking time, and the accommodation which the farmer may have for saving his crop. If the crop is normal and the price of corn is unusually low at husking time, and the farmer has a good crop, the usual recommendation would be to hold the corn. Judging from these experiments corn may be kept safely without great loss in weight until March or April, and if there is a question as to the success of the new crop it may be advisable to hold old corn even later than the date named. However, in Kansas, and in States farther south, old corn is very apt to become infected with the grain weevil or grain moth and great loss occasioned in this way, provided the corn is held too late in the summer. In the northern States, where these pests do not prevail, corn may be safely held for late summer and early fall sale.

The results of the tests also indicate that the shrinkage in corn is not due entirely to the loss of moisture, but that there is an actual loss of dry matter. Samples of Forsythe Favorite cribbed in 1904 contained on October 25, 1905, 11.87 per cent of moisture in the grain, 12.85 per cent of moisture in the cobs, and 12.05 per cent in the ear corn, and a sample of ear corn taken from the seed-corn room on this date contained 11.42 per cent of moisture.

The shrinkage in the weight of the white corn in 1904–5, due to loss of moisture, could not have been more than 6.9 per cent, since the new corn contained only 18.95 per cent of moitsure when it was put into the crib. However, the white corn actually lost 14.48 per cent in weight in the trial referred to, and it will be observed that in almost every case the shrinkage in the weight of the corn was greater than may be accounted for by the loss of moisture.

Hildreth corn cribbed in the fall of 1906 contained 19.75 per cent of moisture in the ear corn and separate determinations showed that the grain contained 17.72 per cent of moisture, while the cobs contained 29.36 per cent. The sample contained 82.6 per cent of shelled corn and 17.4 per cent of cob. From these data it appears that t cobs and grain become about equally dry in old corn. "If the minimum moisture in the dry corn reaches 12 per cent this would give a shrinkage of 5.72 per cent in the grain and 17.36 per cent in the cobs, or an average shrinkage of 7.75 pounds for each hundred pounds of ears, and 3.02 pounds of this shrinkage, or 39 per cent of the total shrinkage, would actually occur from the drying out of the cobs."

FEEDING GRAIN TO MILCH COWS AT PASTURE.[a]

Under advanced methods of dairy farming it is recognized as essential to the greatest success to maintain the highest and most uniform flow of milk practicable throughout the year. Now, when good pasturage is available the change from barn feeding to pasture is as a rule highly beneficial, both as regards yield and quality of milk and health of the cows, but even in good grazing regions there are frequently parts of the season, usually late summer, when the pastures are apt to become dry and thus make it a matter of much practical importance to find some means of keeping up the milk flow. For this purpose the practice of feeding either grain or soiling crops to supplement the pasture has been suggested. The economy of feeding grain to cows at pasture has been a subject of investigation by several of the experiment stations.

In experiments at the Kansas Station a number of years ago "two lots of cows each were fed alternately on rations consisting of pasture alone, pasture and bran, pasture and corn meal, and pasture and ground oats, for periods of seven days each." The conclusion was that although the grain feed added materially to the milk yield, corn meal showing the greatest increase, the increased returns did not pay the cost of the grain. In fact there was a considerable loss.

In experiments at the New York Cornell Station one lot of cows was fed, from June 8 to September 21, a daily ration of 2 pounds of cotton-seed meal and 2 pounds of bran per cow, and another lot was fed, from May 25 to September 17, 6 to 9 pounds daily per cow of a mixture of wheat bran 100 pounds, cotton-seed meal 100 pounds, and malt sprouts 15 pounds, in addition to good blue-grass pasture. In neither case was there any profitable return in milk or butter for the additional grain fed.

In experiments with cows soiled in the barn on fresh grass there was an increase in the milk and butter production and a saving in grass barely sufficient to pay the cost of the added grain ration.

To determine whether the profit from grain feeding would be greater in case of poorer pasturage a herd of cows on light pasture was divided into two similar lots, one lot receiving only pasture and soiling, the other, beginning May 23, was fed 4 quarts per cow daily two feeds, night and morning), of a mixture of equal parts of corn neal, wheat bran, and cotton-seed meal. "On August 10, the pasures having become dry, both lots began to receive a ration of green corn fodder of about 16 pounds per cow per day. On September 9 the corn fodder ration was changed to millet, which continued until October 1, when second growth grass was used; this continued until October 13, when pumpkin began to be fed." The grain feeding in this case resulted in a profitable increase in milk production and also in a considerable gain in weight of the cows. The beneficial effect of the grain feeding was observable the following season, particularly in the development and performance of the younger animals (2-year and 3-year olds).

---

[a] Compiled from Mississippi Sta. Rpt. 1900, p. 31; New York Cornell Sta. Buls. 13, 22, 36, 97.

At the Mississippi Station no benefit was derived from feeding 3 to 4 pounds of cotton-seed meal and 4 to 6 pounds of wheat bran per cow daily to cows running on good pasture.

The question of grain feeding of cows at pasture has recently been investigated anew by J. H. Stewart and H. Atwood of the West Virginia Station. They found that there was no direct financial gain from feeding 6 pounds per cow daily of a rather rich grain feed containing 16.5 per cent protein and 3.5 per cent of fat to cows on pasture, notwithstanding the fact that in some cases the pasture became short from drought. "It is true that the cows which received grain were uniformly in somewhat better flesh than those that did not receive grain, but as far as the milk yield was concerned the increased flow was produced at an actual loss."

Summarizing the results of all the experiments which have been made on the subject, the conclusion seems justified "that unless dairy products are especially high in price it is not a profitable practice to feed grain to cows at pasture. It is true that more milk is obtained and the cows hold up their yield better and remain in better flesh when receiving the grain rations, but under ordinary circumstances there is no direct profit from the grain feeding, as the increased production usually costs more than it can be sold for."

PRACTICAL USE OF STARTERS IN RIPENING CREAM.[a]

In recent years butter and cheese makers have more generally adopted methods of manufacture that involved the use of cultures of bacteria, commonly known as starters, for the production of desired characteristics of flavor, aroma, etc. Under these conditions constancy in results depends largely upon uniformity in the quality of the starters employed. Considerable use is made of commercial starters, the quality of which is quite permanent, but the expense for starters is a considerable item. The desirable organisms having been obtained, they may be used according to a method recently described by L. D. Bushnell and W. R. Wright in a bulletin of the Michigan Station, which is designed to insure a permanent quality of starters and at the same time to lessen the actual expenditure for them. The method as described is applicable to butter making, but it could be easily adapted for use by the cheese maker also.

---

[a] Compiled from Michigan Sta. Bul. 246.

Some of the commercial starter usually employed is put into sterilized whole milk and allowed to develop there for twenty-four hours at a favorable temperature. For ease in manipulation the milk is sterilized in a quart bottle plugged with cotton. On the second day a portion of this milk is transferred to another bottle of sterile milk to continue the growth of the organisms, and the remainder is poured into a can of recently pasteurized skim milk. The latter is again kept for twenty-four hours at a temperature favorable to the growth of the organisms, and is then used as a starter for sweet cream. At the same time a portion of the second bottle of inoculated sterile milk, in which the organisms have been growing for twenty-four hours, is transferred to a third bottle of sterile milk, and the remainder of the second bottle used to inoculate another can of pasteurized skim milk for use as a starter on the following day. It is claimed that this method of growing the bacteria, if properly handled, will maintain a culture that will give uniform results for an indefinite period.

According to F. O. Foster, instructor in dairying at the Michigan Agricultural College, who has confirmed the application of the method to dairy practice, the advantages in it are as follows:

> The starter can be kept for a much longer period, thus saving one-half or more of the cost of pure cultures.
>
> The milk is always ready for inoculation and the mother starter can be transferred each day when in the best condition and kept vigorous.
>
> In case a starter is not needed every day, the mother starter can be carried along conveniently without the trouble of sterilizing milk.
>
> After a thorough trial we have adopted the method for our daily use. We find it no great task to sterilize the bottles of milk once or twice a month, and the little extra labor thus occasioned is more than offset by the convenience and sureness of the new method.

WATER PANS FOR POULTRY.[a]

Nothing is more important and few things are more difficult to insure than clean water for poultry. Ordinary receptacles and sources of water supply are as a rule quickly fouled and thus become breeders of disease. Poultry raisers generally recognize the importance of a watering device which will keep the water as free as possible from the dust and litter of the poultry house or yard and from the droppings of the fowls, and many forms of such devices have been devised. One that is simple in construction and has been found to be very satisfactory in use is described by J. E. Rice and R. C. Lawry in a bulletin of the New York Cornell Experiment Station. The construction of this watering pan is shown in figures 1, 2, and 3.

---

[a] Compiled from New York Cornell Sta. Bul. 248.



Fig. 1.—Sanitary water pan, showing the small space open for entrance of litter.



Fig. 2.—Sanitary water pan uncovered, showing flanged rim of cover.

The round, deep pan with flaring sides, is more easily emptied without injury to the pan in case of hard freezing. It presents a comparatively small surface to catch dust and dirt. The round, cone-shaped top prevents the fowls from roosting upon it. The openings in the side walls permit the fowls to drink from different sides at one time, and presents the smallest possible amount of opening for dust and litter to enter. The platform on which it stands, being 10 inches from the floor, is high enough to prevent the litter being scratched into it. It is found that where water pans are placed much higher than this, fowls do not drink as much water. The water pan and cover is made of No. 26 galvanized iron. It should not cost to exceed $1.40.



FIG. 3.- Sanitary water pan and cover in use on platform 10 inches above the floor.

Another form of water pan and "an inexpensive, handy, serviceable device" for keeping it clean is shown in figures 4 and 5. With this arrangement it is easy to empty or fill the pan, which should be placed on a slatted platform 10 inches above the floor and may be used to water either one or two pens.



FIG. 4. Water pan with cover lowered to prevent hens getting into the pan and the entrance of litter and dust.



FIG. 5.—Cover raised for emptying or filling the pan. The water pan is arranged to supply two pens.

CATCHING HOOK FOR POULTRY.[a]

In a recent bulletin of the New York Cornell Experiment Station R. C. Lawry says: "Every poultry farm should have several catching hooks. They save time in catching fowls and prevent much of the fright and injury which usually occurs on such occasions."



FIG. 6.—Catching hook, with wire turned back to avoid injury, wide open to catch quickly, and restricted clutch with enlarged hold.

He describes a catching hook which is an improvement of an old invention. The improvements described consist in so fortifying and bracing the wire portion of the device that it remains practically rigid, and in so shaping the hook end that the shank of the fowl may be easily caught and effectively held without injury. The only materials required for the construction of the hook are a broom handle and a 6-foot piece of No. 10 steel wire, which can easily be bent into the proper shape. As figure 6 shows, the hook end should have a restricted entrance which makes it difficult for the fowl to withdraw its shank, but it should also have a large aperture which gives freedom of action while the shank is held. Rigidity of the wire portion of the hook is obtained by reinforcing it for a considerable part of its length from the handle by a second piece of wire.

---

[a] Compiled from New York Cornell Sta. Bul. 248.

In using the hook it will be found that the wire portion is less conspicuous than the wooden handle and that the latter attracts the fowl's attention while the shank is caught by the hook. The fowl is then gently drawn from the flock, and the shape of the hook is such that the foot may easily be released.

O

Issued

U. S. DEPARTMENT OF AGRICULT

FARMERS' BULLETIN 318.

COWPEAS

BY

H. T. NIELSEN,
Scientific Assistant, Forage Crop Investigations,
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., January 30, 1908.

Sir: I have the honor to transmit and to recommend for publication as a Farmers' Bulletin the accompanying manuscript on "Cowpeas," prepared by Mr. H. T. Nielsen, Scientific Assistant in Agronomy in Forage Crop Investigations.

The cowpea is the most valuable legume for the Southern States and its use would be much more extensive were it not for the relatively high price of the seed, most of which is still picked by hand. Particular attention is therefore given to the matter of harvesting seed by machinery now in very successful use in several communities. These methods are so far perfected that the cowpea seed crop should receive much greater attention in favorable localities.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

CONTENTS.

Page.

Introduction 7

Cowpeas for hay 8

Cowpeas in mixtures 11

- Cowpeas and sorghum 11
- Cowpeas and corn 11
- Cowpeas and Johnson grass 12
- Cowpeas and millet 13
- Cowpeas and soy beans 13

Cowpeas for pasture 13

Feeding value of cowpeas 14

- Cowpea hay 14
- Cowpea seed 15
- Cowpea straw 15

Growing cowpeas for seed 15

- Hand picking 16
- Machine picking 17
- Mowing and thrashing 19

Cowpeas for soil improvement 22

Varieties of cowpeas 24

- Whippoorwill 25
- Unknown, or Wonderful 25
- New Era 25
- Groite 25
- Iron 26
- Clay 26
- Black 26
- Taylor 26
- Red Ripper 27

Summary 27

318

B. P. I.—343.

COWPEAS.

INTRODUCTION.

A system of agriculture without the use of a leguminous crop tends to lessen the productivity of the soil and makes necessary large outlays for nitrogenous fertilizers. With a leguminous crop grown at frequent intervals, the productivity may be maintained or even increased. The cowpea (fig. 1) is at the present time, and probably will continue to be, the most valuable legume for the entire cotton belt, and can be depended upon to succeed on practically all types of soils. It has been well said that the cowpea is to the South what red clover is to the North and alfalfa to the West.

It is safe to say that no one thing can add more to the agricultural wealth of the South than the more extensive growing of the cowpea. This will supply the southern markets with much of their hay, which is now shipped in from the North and West. It will tend to increase the production of live stock, which is very essential in securing the maximum returns in any system of agriculture; and it will go far toward keeping the soil in good tilth and maintaining its productiveness.

While cowpea culture has greatly increased in late years, this very fact has in part brought about a large increase in the price of seed. The more extensive use of the crop will be seriously retarded until seed becomes more plentiful than at present. Fortunately the development of improved machinery for handling cowpeas makes it certain that this will soon be the case and that the price of seed will be materially reduced without lessening the profit to the grower.

Cowpea seed for planting should be fresh and of good quality; or, if old, should be tested for germination, as seed more than one year old is likely to be very low in vitality. It is practically certain that seed which ripens and is harvested in dry weather is of superior quality. Varieties with hard seeds are injured to a less extent by wet weather at harvest time than those with soft seeds. They also retain their vitality for a longer time and are less subject to the ravages of weevils. The Iron cowpea is the only common variety which has any advantage over other sorts in this respect.

COWPEAS FOR HAY.

Good cowpea hay is fully as valuable a feed, pound for pound, as red clover hay, and very nearly equal in value to alfalfa or to wheat bran. The principal value of this hay lies in its high percentage of digestible protein, which is nearly four times that of timothy hay.



FIG. 1.—Cowpea plant (*Vigna unguiculata*), showing ripe pods.

One reason why cowpeas are not more extensively used as a hay crop is the difficulty often experienced in curing the large growth of succulent vines. Where proper care is taken in curing, especially where sorghum or a similar plant is grown with it in mixture, it is not a difficult matter to make good cowpea hay unless the weather is de-
dedly unfavorable.

When grown for hay production cowpeas are nearly always broadcasted or put in with a grain drill any time from May 15 to July 15. The quantity of seed used to the acre ranges from one to two bushels, broadcasting requiring from one-fourth to one-third more than is necessary when using a grain drill. The quantity most commonly used and which gives the most general satisfaction when the seed is put in with a grain drill is five pecks to the acre. The use of a grain drill is decidedly superior to broadcasting. Larger hay yields have frequently been secured by planting in rows 24 to 36 inches apart and giving two or three cultivations, the seed required in this way being from two to three pecks per acre. The increased yield of hay due to cultivation is not sufficient to cover the increased cost, especially as rather thick broadcast seeding is equally as effective in destroying weeds as cultivation in rows. The practice of broadcasting on small grain stubble and plowing under the seed is still common; also that of putting in the seed on grain stubble with a disk drill without plowing. Both of these practices are rapidly being replaced by good preparation of the soil before seeding.

As nearly as average conditions will permit, cowpeas for hay should be planted so that they will be at the proper stage for hay making in the latter part of August, in September, or early in October, as the rainfall is likely to be small during that time. With four to six days of dry sunny weather, cowpeas can be cured into hay of excellent quality if they are at the proper stage of maturity when cut.

The proper time to cut cowpeas for hay is when most of the pods are full grown and a considerable number of them are ripe. At this stage none of the best hay varieties have dropped their leaves. Of the large list of cowpea varieties, those with an upright habit of growth which seed fairly well and mature quite uniformly should be chosen for hay. The varieties more commonly used are Whippoorwill, Unknown, New Era, and Iron. These hold their leaves well and stand up much better than most of the other varieties. Such varieties as Black, Red Ripper, and Clay are not desirable for the production of hay, as they run to vine badly and are consequently very hard to cure and handle. The readiness with which the hay can be cured depends largely upon the maturity of the vine and the condition of the weather; hence the advisability of having the harvesting come when the season is most likely to be dry.

An ordinary mower is the most practical machine for cutting cowpeas for hay, and if an erect variety is grown the entire plant can readily be saved. The mowing should begin in the morning, as soon as the dew is off, and may be continued all day if desired, though some advocate cutting only till noon. The vines should be left in the swath until well wilted on top, but not till the leaves are dry and brittle. They should then be raked into windrows; this may be the same day or the day after mowing. They should be left in the windrows one or two days and then put into small cocks of one or two forkfuls. The cocks should be left till the vines are well cured, from two to five or six days, depending on the conditions which have prevailed during the curing period. A good rule to follow is that peas are ready for stacking or putting into the barn when it is not possible to wring moisture out of the stems by twisting a handful with considerable force.

The hay tedder can be used very advantageously in making cowpea hay. If the growth is very heavy the tedder should be used immediately after mowing, as it will open up the vines so the sun and air can get to them better. It can be used to good advantage on vines in the swath after the top part is wilted, as it opens them up so they will dry out more uniformly. It is also valuable for opening up the windrows a half day or a day before cocking. An ordinary rake can also be used for turning the windrows over. The tedder should never be used except when the vines are either green or damp, so as not to cause the loss of too many leaves.

In case of wet weather setting in shortly after mowing, the best practice is not to touch the vines at all until after the rain. It is a mistake to be in a hurry about handling after wet weather. If the vines are fairly mature before cutting, a wet spell during haymaking, unless prolonged, is not a very serious matter. If, however, the vines are immature when cut, great difficulty is always experienced in curing the hay in unfavorable weather.

Several special devices are more or less used in curing cowpea hay. The most common of these is a pole, usually with crosspieces nailed at right angles, around which the vines are cocked. Triangular pyramids from 2 to 3 feet high, built of poles with crosspieces nailed on to hold them together, are used to a small extent in the same way. The object of these devices is to get air into the vines by keeping them from becoming tightly packed together and to have an air space in the center of the cock. Canvas or other covers, or hay caps, to protect the cocks during rainy weather, also have a limited use. These devices give excellent results in curing cowpeas, but on account of the increased cost and labor they entail are not in general use. A good and comparatively cheap hay cap would find a ready market and could be sold in large numbers. It would be a great help in cowpea hay making.

COWPEAS IN MIXTURES.

While cowpeas can be satisfactorily grown alone for hay, it is a much better practice as a rule to grow them in mixtures. The most widely used crop for this purpose is sorghum. This includes both the sweet sorghums and the kafirs. The sorghum serves to support the cowpea vines, and its use usually results in increasing the yield of hay considerably. An additional important advantage is that the hay is more easily cured, as the sorghum prevents the matting together of the cowpea plants. Corn is also used very extensively in mixture with cowpeas, but only to a small extent for hay purposes. The two are grown together very satisfactorily in cultivated rows. Other crops that have been used to grow in mixture with cowpeas are millet, soy beans, and Johnson grass.

Cowpeas and sorghum.—In the Piedmont region of the South a large percentage of the cowpeas planted for hay is in mixture with sorghum, and the practice should spread rapidly, as this mixed hay is very nearly a complete ration and is relished by all farm stock. The mixture has given excellent satisfaction on the Arlington Experimental Farm, near Washington, D. C. The variety of sweet sorghum most used is the Amber, as it is not as coarse as the others and hence cures more rapidly. The seeding is best done with a grain drill on well-prepared land, the two kinds of seed being well mixed and sown at the same time. The best rate is one bushel of good seed of cowpeas to one-half bushel of sorghum to the acre. If a grain drill is not available for seeding, the cowpea seed should be disked or plowed in, and the sorghum seed should then be sown while the land is rough, and covered with a drag harrow. The Whippoorwill, Iron, Unknown, and Clay cowpeas require about the same time as sorghum to mature and therefore should be used instead of the early varieties. In general, the planting may be done from June 1 to July 15.

Growing cowpeas and sorghum together in cultivated rows gives excellent results. They should be planted together in rows 2½ to 3½ feet apart, three pecks of cowpea seed and about one-third of a bushel of sorghum seed being used to the acre. The Sumac and the Orange varieties are fully as good as the Amber sorghum for this use, as they grow larger and stronger plants. The harvesting is most satisfactorily done with a mower.

Cowpeas and corn.—Cowpeas are most widely used at present for growing with corn. When grown in this way a farmer secures a crop of corn, sufficient cowpea seed for use the next season, and either a hay crop or a certain amount of grazing for his stock. The cowpea is an excellent plant to grow with corn for ensilage, and is being used quite extensively for this purpose on many dairy farms, especially in the northern part of the cowpea region. When planted in the cornfield it is usually at the last cultivation of that crop. The quantity of seed used to the acre ranges from a half bushel or less to two bushels, depending largely on whether the planting is broadcast or in rows close to the corn. Generally the best results are obtained by the use of about three pecks of seed and planting near the rows of corn, preferably with a corn, cotton, or other planter, immediately after the last cultivation of the corn. Usually the peas are allowed to ripen a fair percentage of pods, which are gathered for next year's seed, and the vines are then pastured.

In the sugar-cane districts of Louisiana and in parts of Mississippi and Alabama the cowpeas are made into hay instead of being pastured after the corn has been gathered. This is a very good practice and is becoming general. The work is very satisfactorily done with a strong wooden-toothed rake, which pulls the vines and leaves them in small bunches for curing. The harvesting is also done with a mower to some extent.

In a few localities, especially in parts of Maryland, corn and cowpeas are sown thickly together for hay with excellent results. The seeding for this purpose is at the rate of one-half to one bushel of corn and one bushel of cowpeas to the acre. The two mature at practically the same time, the yield is large, and the curing is easily done.

Cowpeas and Johnson grass.—Where Johnson grass is not a pest or where it is well established on a field and there is no desire to clean it out, it can very satisfactorily form a part of a mixture with cowpeas. At the Arlington Experimental Farm in 1906 the mixtures of Johnson grass and cowpeas gave the best results both in yield and in the quality of the hay produced. There is no difficulty in killing out Johnson grass north of Tennessee and central Virginia, but south of these States the difficulty increases rapidly.

The mixture should be sown at the rate of one bushel of Johnson grass and one bushel of cowpeas to the acre; if the seeding is done with a grain drill, care must be exercised not to cover the Johnson grass seed too deeply. Where this grass is already established, the land may either be plowed or thoroughly disked in late spring, the treatment depending on the nature of the soil, and then the cowpeas alone should be sown in June. One and a half bushels of cowpea seed to the acre are frequently used, as the Johnson grass makes a more vigorous growth under such circumstances than when coming from seed. This latter practice is common at Augusta, Ga., and gives excellent results. The quality of hay obtained is very good and it is not as coarse as the mixture with sorghum. The fact that Johnson grass often becomes a troublesome weed is the only objection to it in mixture with cowpeas for hay production. In other respects it is the best plant for this purpose.

Cowpeas and millet.—German millet has often been grown in mixture with cowpeas. As it matures in a relatively short time it is adapted for growing only with the early varieties of cowpeas, such as the New Era, and even with these the yield is rarely increased. The millet aids materially in curing the hay, however, and possibly improves its quality by adding variety. Millet should never be used in mixture with the late and rank-growing cowpeas, as the results obtained are not satisfactory, since in addition to maturing too early the millet is not strong enough to hold up the cowpea vines.

Cowpeas and soy beans.—But little experimenting has been done in growing soy beans and cowpeas together, but the results obtained have been very promising. Only the larger-growing soy beans, such as the Mammoth variety, are suitable for this use. The soy beans are strong enough to assist very materially in holding up the cowpeas, and they also aid effectively in curing the hay. The combination is therefore worthy of much more extended use. The hay of this mixture is an exceedingly rich one, as the composition of both plants is high in protein. Seeding should be at the rate of a bushel of soy beans and a half bushel of cowpeas to the acre.

COWPEAS FOR PASTURE.

The use of cowpeas for pasture is not as a rule the best farm practice, but under certain circumstances it is advisable and fairly profitable. Grazing cultivated lands is likely to render succeeding tillage more difficult on account of the trampling by stock; and, unless care is exercised in pasturing cowpeas, loss of animals by bloating may result, especially in wet weather. However, the small amount of work and the insignificant cash outlay always associated with the grazing of stock commend the practice to the average farmer, and scarcity of labor often makes it necessary to pasture a crop whenever possible. Cowpeas when planted in corn are very commonly used for grazing, especially with hogs.

The best time to begin pasturing cowpeas is when the first pods are ripe. This practice is not generally followed, as at least a part of the seed is saved first. When the peas are grown in cornfields the grazing is deferred until the corn has been gathered.

In a feeding trial at the Alabama Agricultural Experiment Station it was found that pigs fed corn alone gained 0.36 pound daily, while pigs on cowpea pasture and corn gained 0.97 pound daily, consuming 36 per cent less corn for each pound of gain. The returns were $10.65 for an acre of cowpeas, with corn at 40 cents a bushel and hogs at 3 cents a pound.

The Oklahoma Agricultural Experiment Station reports that cowpeas planted early in July furnished two grazing periods for milk cows before frost in the fall and that the flow of milk was noticeably increased. At the Arkansas Station steers were fattened on cowpea pasture and cotton seed, making an average gain of 2 pounds a day for ninety days. So long as the pea vines were green and considerable seed was available, very little cotton seed was eaten. The cost of each pound of gain was only 2 cents for the cotton seed, thus showing the high value of the cowpea pasture.

FEEDING VALUE OF COWPEAS.

Cowpea hay.—The feeding value of cowpea hay has long been recognized, as it has been used extensively for all kinds of stock in the Southern States. With a fair number of ripe peas in the hay it has been found to be satisfactory when fed alone to stock at work, and can be used very successfully as a maintenance ration for horses, mules, cattle, sheep, and even hogs. The farmers in the sugar-cane districts of Louisiana make a very extensive use of cowpea hay for their work stock, it being practically the only roughage used. It is generally claimed that horses or mules at work stand hot weather better when fed cowpea hay than when fed a grass hay and corn. The difference in the appearance of the animals is also very much in favor of the cowpeas.

In a three months' test at the North Carolina Agricultural Experiment Station the rations fed two high-grade Percheron mares, used as a team and receiving the same care and shelter, differed only in the use of 10 pounds of cowpea hay in one and the same quantity of wheat bran in the other. The horse fed bran just held its own in weight while the one fed cowpea hay gained a little. The cowpea ration was 5 cents cheaper in daily cost.

At the Arkansas Agricultural Experiment Station two three-year-old steers were fattened on cowpea hay and cotton seed in a feeding trial lasting ninety days. The daily ration consisted of 13⅗ pounds of cotton seed and 20 pounds of pea hay. The average daily gain was 3 pounds for each steer, and the cattle were in excellent condition during the entire trial. The profit realized was $21.30. The Tennessee Agricultural Experiment Station found that 6 to 10 pounds of cowpea hay could be substituted for 3 to 5 pounds of cotton-seed meal in beef production. This indicates that this hay can be utilized to advantage in place of corn and cotton-seed meal when these feeds are high priced.

In the production of milk and butter, the Tennessee Agricultural Experiment Station reports that 1½ pounds of chopped pea hay is equivalent to a pound of wheat bran, and 3 pounds of chopped pea hay to a pound of cotton-seed meal. With bran valued at $20 a ton a yield of 2½ tons of cowpea hay would mean a return of $40 an acre for the crop, based on its feeding value. Cowpea hay is equally as good as bran for producing a flow of milk.

Cowpea seed.—The seed of cowpeas is rarely obtainable at a low enough price to be used as a feed. Its composition indicates that it is a richer feed than wheat bran. The Alabama Agricultural Experiment Station fed cowpeas to fattening pigs with excellent results. More lean meat was found in the bodies of the pigs fed cowpeas than in those fed corn meal only. A great many people have tried feeding the seed, either whole or in broken pieces, to poultry. Splendid results are obtained, the fowls being kept in good condition and producing a good supply of eggs, even in the winter months. Very good results are also obtained by feeding the hay, as the fowls eat all except the hard, coarse stems.

Cowpea straw.—Now that cowpea seed can be secured by running the vines through a thrashing machine the straw is coming to be quite an important feed. While no authentic data are at hand in regard to this straw, farmers and stable keepers who have used it claim that it is an excellent feed, some even preferring it to ordinary pea-vine hay. There have been no ill effects reported from its use. The straw sells for about the same price as the hay.

GROWING COWPEAS FOR SEED.

The greater agricultural use of cowpeas has been seriously handicapped in late years by the high price of seed. Until the last few years cowpea seed has been almost entirely gathered by hand, though that harvested by machinery makes up an increasing percentage of the commercial seed each year. Cheaper seed will undoubtedly bring about an enormous increase in the culture of the crop.

Cowpeas when grown for seed or for combined seed and hay production are nearly always sown broadcast or with a grain drill. Occasionally fields are planted in rows and cultivated. Experiments generally prove that the largest yields are secured by planting in rows and cultivating, but in many localities this increased yield is not sufficient to offset the additional cost of cultivation.

The planting of cowpeas for seed production should always be thinner than for forage purposes. Figure 2 shows a field of cowpeas of the Whippoorwill variety planted in rows one-fifth rod (about 3 feet 4 inches) apart and cultivated three times, while figure 3 shows a field of the same variety broadcasted thickly. Attention is called to the fair crop of pods and the larger size of the plants in the cultivated area. Figure 4 shows a field of Iron cowpeas planted in rows one-fifth rod apart and cultivated three times. The plants are much larger than those shown in figure 5, a field of the same variety broadcasted thinly; but the plants in both fields are well podded. When grown in rows 24 to 36 inches apart one peck to a half bushel of good seed per acre is required. When the seed is broadcasted the quantity ranges from 3 to 6 pecks to the acre, depending on the soil, the method of seeding, and the size of seed. Heavy clay or light sandy soils require more seed than loam soils. If sown with a grain drill only about two-thirds as much as for broadcasting is required. Of the smaller seeded varieties, such as the New Era and the Iron, 2 or 3 pecks will give the best results; while of the larger seeded varieties, such as the Black, the Unknown, and the Whippoorwill, the quantities range from 3 pecks to 5 pecks to the acre, a bushel generally being the best amount to use. In most of the cowpea region planting for

FIG. [illegible] Field of Whippoorwill cowpeas planted in one-fifth-rod rows and cultivated [illegible] times

[illegible] in the season, since late plant-
[illegible] yields than early plantings.
[illegible] northern Texas, where
[illegible] ly to the lighter rain-
[illegible] d crops in a season
[illegible] the first very early.

[illegible]

[illegible] only one practicable
[illegible] common practice
[illegible] d at the last cultiva-
[illegible] fore frost. The vines

climb the corn stalks, so most of the pods are well above ground, which greatly facilitates gathering them. They are picked by hand into bags, and later flailed or run through a pod huller. The cost of hand picking ranges from 40 to 75 cents a hundred pounds of pods, or the picker is given one-third to one-half of the total quantity gathered. This method of harvesting naturally makes the price of seed high. Fields grown to cowpeas alone for seed production are often hand picked. The yield of seed in such cases is as a rule much larger, and a larger number of pods can be picked in a day than when grown with corn. The Blackeye and similar varieties grown for table use are usually picked by hand.

FIG. 3.—Field of Whippoorwill cowpeas broadcasted thickly.

MACHINE PICKING.

The scarcity of seed and the difficulty of securing labor have resulted in the invention of several so-called pea pickers. These machines are intended to gather the pods from the vines in the field. The peas must be planted in rows for the most successful operation of a pea picker, and the entire plant must be ripe and dry before the machine will do satisfactory work. Two of these pickers are constructed on much the same principle, that of a winged drum revolving rapidly over a stationary moderately sharp edge. The pods are thus knocked back upon a platform and then elevated into a receiving box or bag. A third machine differs from the foregoing in that the picking apparatus is very much in the nature of a flailing operation, the cylinder consisting of four arms made up of pieces of gas pipe. This revolves rapidly and knocks the pods back into the gathering box. A fourth machine is a harvester and thrasher combined. In this, the vines are cut with an ordinary mowing arrangement and passed directly to the thrashing part of the machine, which is essentially the same as that of any thrasher. This last-mentioned



FIG. 4.—Field of Iron cowpeas planted in one-fifth-rod rows and cultivated three times.



FIG. 5. Field of Iron cowpeas broadcasted thinly.

machine is very satisfactory for harvesting perfectly ripe peas, since it very nearly completes the operation. For harvesting varieties grown for table use, such as the Blackeye, the Lady, and other white peas, it may find considerable demand.

MOWING AND THRASHING.

Cowpeas for seed production are quite satisfactorily harvested with a mower. A bunching attachment (fig. 6) has been used with excellent results. This gets the vines out of the way of the team, thus avoiding considerable loss of peas through trampling and crushing by the mower wheels. It also leaves the vines in a more desirable shape for curing, they being rolled into small windrows. The self-rake reaper (fig. 7) is a very satisfactory machine for mowing cowpeas for seed, accomplishing even better results than the buncher on a mower, as the vines are left in bunches of very convenient size for curing and handling.



FIG. 6.—A bunching attachment on an ordinary mower.

The bean harvester has been given careful trial in harvesting cowpeas for seed production, but it is not very satisfactory. Viny peas catch on parts of the machine and drag badly. There is also likely to be much soil worked into the vines, making the further handling difficult and disagreeable. The accompanying illustration (fig. 8) shows a bean harvester at work.

For seed production cowpeas should be allowed to mature a greater percentage of pods than when cut for hay. Half or more should be ripe before mowing, even at the expense of losing a part of the foliage. The vines should then be allowed to cure and become thoroughly dry, after which the thrashing may be done. The curing and drying may be done in the swath, cock, stack, or barn, as desired, weather conditions largely determining the method to be pursued. The hay or straw is of better quality if the curing and drying are done in the stack or barn, though, of course, the amount of work required is greater. It is a common belief that weevils do much less damage to seeds in the pods than to the thrashed seeds. On this account some growers store their crop and thrash it late in the winter or early in the spring. However, the unthrashed material requires much space for storage, and there is no effective way of combating the insects, while in clean stored seed all insect life is readily destroyed by treatment with carbon bisulphid.[a]

Cowpeas may be thrashed with an ordinary grain thrasher. In this case the riddles are adjusted for cowpeas and satisfactory screens are provided. The most essential point in thrashing cowpeas is to maintain a low and even speed of the cylinder, 300 to 400 revolutions per minute, while the rest of the machine should be adjusted to run at least as fast as for thrashing wheat or oats. Some operators prefer to have a greater clearance between the cylinder and concave spikes than for grain thrashing, while others do not think this an advantage. While expert operators sometimes do very satisfactory work with an ordinary grain separator, there are three important difficulties encountered: (1) Too many of the pods pass through with the straw unopened; (2) the machine is easily choked by the tangled vines wrapping around the cylinder; and (3) the percentage of cracked peas is usually large.



FIG. 7. Harvesting cowpeas for seed with a self-rake reaper.

To overcome these difficulties several modifications of thrashing machines have been devised so as to adapt them for handling cowpeas. One modification which has been adopted in several different machines is the use of two cylinders. These cylinders are adjusted to run at different speeds, the front one slowly, about 300 revolutions per minute, and the rear one more rapidly, about 450 revolutions per minute. Apparently the only advantage gained by two cylinders over one is that a smaller percentage of the unopened pods pass through with the straw. The use of two cylinders, however, results in a somewhat larger percentage of cracked peas.

---

[a] For destroying weevils or preventing damage by them, see article on "Insects Injurious to Beans and Peas," in the Yearbook of the Department of Agriculture for 1898.

A second modification which has been applied both to machines with one cylinder and those with two is to sharpen the spikes on the concaves or on both the concaves and cylinders. This sharpening means bringing the face of the spike to as nearly a sharp edge as can be done by ordinary blacksmithing. The beneficial effect of sharpening the spikes is very marked, as the vines pass through much more readily, there is little tendency to wrap around the cylinder, the amount of power required is very materially reduced, and the percentage of cracked peas is decidedly smaller. The straw is also chopped so it is in fine condition for feeding. A one-cylinder machine with the spikes sharpened does very satisfactory work except that a small percentage of the pods may pass through in the straw unopened, while by the use of a two-cylinder machine practically all the peas are secured.



FIG. 8.—Harvesting cowpeas for seed with a bean harvester.

In a third device all the spikes in both cylinder and concaves are sharpened, and there is a minimum of clearance. The concaves are arranged in two sets, one of two rows and the other of three. The two-row set is at the front of the cylinder on a plane with the shaft; the other is below the cylinder and at the back of it about 120° from the first. There is a perforated web under the cylinder which is hinged at the three-row set of concaves and has the front part attached to the shakers so that it is worked up and down by their backward and forward motion. When the vines come through the first concaves they drop on the web, rest momentarily, and are then picked up by the cylinder again and taken through the second concaves. This momentary rest results in the rearrangement of the straw, so that it virtually amounts to passing through a second cylinder, as in the two-cylinder machines. A perforated feeding table is used to get loose peas to the separating surface without passing through the cylinder. This machine is by far the most satisfactory pea thrasher yet devised. The number of cracked peas is very small; the vines are chopped as fine as if they had been through a cutting box, and all the peas are gotten out of the pods, while the material which can be run through in a given time is the maximum for present-day machines and the power required the minimum.

It is very essential in thrashing cowpeas that there be sufficient power to give a uniform speed to the separator. It is also highly desirable that the cylinder be kept uniformly full in order to get the best results, as running empty means an increase in the number of cracked peas.

The price of cowpea thrashers now on the market ranges from $300 to $600, exclusive of the engine. If the peas are stacked or put into a barn so they need not be thrashed immediately, one machine will be sufficient for 2,000 acres, as the crop from 20 acres can readily be handled in one day. As a rule only a moderate acreage of cowpeas for seed should be grown by any one farmer, as unfavorable weather may cause great difficulty at harvest time. It is very desirable to have enough cowpeas for seed grown in a community to justify the local ownership of a thrashing machine.

COWPEAS FOR SOIL IMPROVEMENT.

The beneficial results of growing cowpeas are due largely to the ability of the plants, like those of alfalfa and red clover, to take nitrogen from the air by means of the bacteria which live in the nodules on the roots. Cowpeas also improve markedly the physical condition of the soil. This, taken in connection with their ability to produce a crop quickly on even the poorer soils, makes the cowpea particularly valuable both as a catch crop and in regular rotations when utilized either for hay or seed production.

At the present time the most popular rotation for the entire South is one which allows the largest possible area to be planted in cotton each year. A system of cropping which is in general use is three years in cotton, the fourth year in corn and cowpeas, and then three years in cotton again. This system allows three-fourths of the farm to be in cotton each year, and is applicable to all of the better agricultural land. On the poorer soils of the cotton belt it is likely that better results would be secured by growing cotton only two years and corn and cowpeas the third year. This would leave two-thirds of the farm for cotton each year, and would undoubtedly be an excellent system of cropping. The Alabama Agricultural Experiment Station reports an increase in yield in one case of 696 pounds of seed cotton to the acre, or 83 per cent, due to plowing under a crop of cowpea vines on land which had been in cotton the previous season. The Arkansas Agricultural Experiment Station secured an increase in yield of 59 per cent where a crop of cowpeas had been grazed the preceding year.

Practically the same plan of rotation is followed in the sugar-cane districts of Louisiana. Three crops of cane are taken off the land, and the fourth year it is planted to cowpeas or to corn and cowpeas. The work stock are fed almost exclusively on pea-vine hay or are grazed on cowpeas in the cornfield after the corn has been gathered. This rotation gives excellent results in the succeeding crops of cane.

A rotation of wheat or oats and cowpeas is giving excellent results in parts of Missouri, Arkansas, and Tennessee. Cowpeas are sown on the land immediately after the removal of the grain crop and are utilized for hay or seed or for pasture. Grain is sown again in the fall, thus making two crops a year from the same land. In many instances landowners in Arkansas and Missouri have allowed tenants the use of land free of charge for producing a crop of cowpeas, stipulating, however, that the land must be well prepared. When the soil is given good preparation before sowing the cowpeas, it is not necessary to plow in the autumn for the grain. The fall preparation usually consists of disking the cowpea stubble and sowing the grain with a drill. Occasionally the seeding is done with a disk drill without any preliminary preparation. The increase in yield of wheat due to the cowpeas is generally given as from 3 to 5 bushels per acre. At the Missouri Agricultural Experiment Station, an increase in yield of 63 per cent with oats and 49 per cent with wheat following cowpeas as a catch crop was secured. The Arkansas Agricultural Experiment Station reports as the average of a four years' test on wheat an increase of 25 per cent from plowing under cowpea stubble the first fall, 39 per cent from plowing under cowpea vines, and 42 per cent where cowpeas were grown each year as a catch crop between the wheat crops, only the stubble of the peas being plowed under. The increased yield in the latter case amounted to 70 per cent in the fourth season, the yields having gradually increased from year to year, in addition to producing a fair quantity of very nutritious hay each season.

On farms where more or less live stock is produced the following three-year rotation is very popular and is a good one: First year, cotton; second year, corn with cowpeas at last cultivation; third year, winter oats or wheat, with a catch crop of cowpeas for hay or seed after the grain has been removed.

A few striking results due to the growing of cowpeas are here noted. The Alabama Agricultural Experiment Station reports a yield of oats following cowpea vines plowed under 247 per cent larger than where German millet was plowed under. The Arkansas station reports an increase in yield of 63 per cent on corn where cowpeas were grazed the season before. The Missouri station increased the yield of corn 79 per cent by growing cowpeas on the land for two years before planting the corn. In yield of hay the Arkansas station secured an increase of 116 per cent on oats following cowpeas grazed the year before. The Alabama station increased the yield of sorghum hay 2.01 tons, or 55 per cent, by plowing under cowpea stubble on land where sorghum was grown the previous year.

These and many similar experiments conclusively prove that it is much more economical to use cowpeas for hay or seed production in rotation with other farm crops than to use them for green manuring. It is only in special cases that it is advisable to utilize cowpeas as a green manure. On very poor sandy land or on stiff, heavy clay soils in bad mechanical condition a crop of cowpeas plowed under will give markedly beneficial results. Cowpeas give very good satisfaction as a cover crop in orchards, for which they find a limited use. In case of bad weather setting in at harvest time it may be desirable to utilize the crop for green manure, or to pasture it if the land is of such a nature as not to be seriously injured by the trampling of stock.

VARIETIES OF COWPEAS.

There are about 50 varieties of cowpeas known, but only a few of the best of these are extensively cultivated. The varieties differ in such characters as habit, size, earliness, prolificness, disease resistance, and especially in the color of the seeds, which are either entirely white, red, buff, black, or blue, or variously blotched or speckled. The varieties are all very constant in their seed characters. The variation in vines, however, is very marked, being influenced by the time of planting, the nature of the season, and the locality where grown. Early planting or a wet season usually results in a large growth of vines. Natural crosses between the varieties occur under favoring conditions, but they are far from common. The use to be made of the crop by the grower should determine largely which variety to select.

For table use the varieties with white or nearly white seeds are preferred, as they make a more attractive dish. The habit of growth of the table peas is of little direct concern, and, as a matter of fact, none of them is very satisfactory for forage purposes. The principal varieties are the Blackeye, of which there are several strains, the Browneye, the Lady, and the Cream. These are more properly considered vegetables. Several of the colored-seeded varieties are also used as table peas.

For forage purposes the most desirable varieties are those which have a fairly upright habit, grow to large size, hold their leaves well, and produce an abundance of pods. Descriptions of the most important varieties follow. Of the numerous remaining varieties none is grown to a very large extent, and most of them are distinctly inferior to those described here.

Whippoorwill.—The Whippoorwill variety is known under several other names, such as Running Speckled, Bunch Speckled, and Shinney. It may be considered the standard of all field cowpeas. It is suitable either for grain or hay production, or both. It makes a vigorous growth, is fairly erect, and still produces a large amount of vine. It can readily be handled by machinery, which is bringing it more and more into prominence. The seed is mottled chocolate on a buff or reddish ground color.

Unknown, or Wonderful.—The Unknown, or Wonderful, cowpea is another field variety which is grown to a large extent. It is the largest growing and most vigorous of the cowpeas, but is late in maturing, it being difficult sometimes to secure seed of it as far north as Washington, D. C. The principal objection to this pea is its light seeding. It is nearly as erect as the Whippoorwill variety; hence, it is quite readily handled by machinery either for grain or hay production. The seed is large in size and of a very light clay color.

New Era.—The New Era is the smallest seeded of the cowpeas that have found a wide use. The seed is bluish in color, owing to the innumerable minute blue specks on a gray ground. The New Era is the most nearly erect of any of the varieties, rarely having any prostrate branches. It usually produces a heavy crop of seed and matures in from seventy-five to ninety days. It is one of the earliest of the cowpeas and is the most easily handled by machinery. The small seed is not usually considered an undesirable character, as a smaller quantity is required for seeding than is the case with other varieties.

Groit.—The variety known as the Groit has been much confused with the New Era cowpea. In habit the two are much alike, but the Groit is a little superior, as it makes a larger growth and fruits more heavily. The seed is quite similar to that of the New Era, but has chocolate mottlings in addition to the blue specks. It is quite certainly a hybrid between the New Era and the Whippoorwill varieties.

Iron.—The Iron nence. In its habit it is only sl ly d though it is not quite as v or It he Unknown and the seed, th arly t c r, is much smaller, being but very little larger th that of E ra. The characteristic of the Iron cowpea which s been i l in bringing it into prominence is its resistance to wilt a to t-knot caused by eel worms. It is the only one of the c as been found to resist these diseases. Where they are preva in he soil, the Iron cowpea is the only variety which be succ ully grown, and since the diseases are spreading the ib n of the Iron cowpea is also increasing. Regardless of its to these diseases it is a valuable variety under nearly all co litions, b vigorous, prolific, and quite erect. The seed is hard and retains its vitality better than that of most varieties. It will lie in the ground through the winter and germinate the next spring. This variety and the Unknown hold their leaves better than any others.

Clay.—The Clay cowpea is more variable in its habit than any of the foregoing varieties. It is the most pronounced trailer of any of the peas grown quite largely, and is consequently in very slight favor where the pea crop is handled by machinery. The plants are very vigorous but low growing, and they usually seed sparingly. Since seed is such an important item at the present time, a variety which has but poor fruiting qualities is not apt to remain popular, even though it may be harvested readily by machinery. The seed is of the same color as that of the Unknown and the Iron, but is intermediate in size and flatter and longer.

Black.—The Black cowpea is used to a considerable extent in the sandy coastal plain soils of Virginia and North Carolina. On heavy clay land this variety makes a very heavy growth of vine, but produces very little seed, while on the sandy lands it grows more bushy and fruits quite heavily. It also finds some demand in the sugarcane section of Louisiana, where it is grown with corn in rotation with sugar cane. Where other varieties thrive the Black is not a favorite. The seeds are quite large and entirely black.

Taylor.—The variety called Taylor has larger seeds than any other cowpea. The seeds have nearly the same markings as those of the New Era, though the ground color is somewhat lighter. The Taylor cowpea has met with considerable favor in Maryland and Delaware, where it is erroneously called the Gray Crowder, but outside of this region does not seem to be a very val variety. In most cases it is too much of a trailer to be It also has a tendency to drop its leaves earlier than any of her varieties ept the Black.

Red Ripper.—The Red Ripper is a valuable pea, as it makes nearly as large a growth as the Unknown, or Wonderful, and is excellent for growing in corn. It is very late, usually maturing but a small number of peas at Washington, D. C. It is difficult to procure seed of it in quantity on account of its light yield. The seed is dark red and about the same size as that of the Whippoorwill variety.

SUMMARY.

(1) The cowpea is the best legume for the entire cotton belt, and can be profitably grown much farther north. It is especially suitable for combined hay and seed production or for hay alone.

(2) To make good cowpea hay requires careful handling of the crop. The plant should have made its growth and have at least the first pods ripe when the mowing is done. Uniformity in maturing is essential in getting the best results. The use of a tedder is very helpful. The serious loss of leaves can be avoided by not handling the hay when the leaves are dry and brittle. The curing is best done in small cocks, and the hay is ready for the stack or barn when no moisture can be wrung from the stem by twisting it with considerable force.

(3) Cowpeas for hay production are very advantageously grown in mixture with sorghum, Johnson grass, or soy beans. The yield is thus increased, the quality improved, and the curing more easily done. Cowpeas give very good results when grown with sorghum in cultivated rows and are very commonly planted in corn and used for grazing or ensilage.

(4) Pasturing cowpeas is not the most economical practice, but it is frequently resorted to because of the small expense it entails. Cowpeas are especially suitable for grazing hogs.

(5) Cowpea hay is very nutritious. It is nearly equal to wheat bran as part of a ration. It is satisfactory for work stock and for beef or milk production, and it gives good results when fed to poultry. The grain is a rich feed, excellent for poultry but little used for other feeding. Cowpea straw is an excellent roughage and nearly as valuable as the hay.

(6) Cheaper cowpea seed will result in the much more extensive growing of the crop. Harvesting for seed can be done most cheaply by the use of machinery. The crop should be cut with a mower or self-rake reaper when half or more of the pods are ripe. When thoroughly dry the thrashing may be done with an ordinary grain separator with some modifications, with a two-cylinder cowpea thrasher, or with a one-cylinder special machine which has all the thrashing spikes sharpened in addition to having ingenious devices which make it the most satisfactory thrasher for handling cowpeas.

(7) Cc s mechanical
T a with other
cro T r

(*a*) Cot thr c rpeas fourth year; and then
cotton again. T s all t etter soils of the South, but
the cotton an t years in succession on the
poor

(*b*) Wh or oats with cowpeas each season after the removal of
the grain cr the land being seeded to grain again in the fall, mak-
ing two cr a year from the same land.

(*c*) Cotton, first year; corn and cowpeas, second year; winter oats or wheat followed by cowpeas as a catch crop, third year; and then cotton again.

(8) The most valuable varieties are the Whippoorwill, the Unknown or Wonderful, the New Era, and the Iron for field purposes; and the Blackeye for table use.

(9) The Iron cowpea is practically immune to the two serious diseases, wilt and root-knot, which attack the other varieties more or less. It alone should therefore be grown wherever these diseases are prevalent.

FARMERS' BULLETINS.

The following is a list of the Farmers' Bulletins available for distribution, showing the number, title, and size in pages of each. Copies will be sent free to any address in the United States on application to a Senator, Representative, or Delegate in Congress, or to the Secretary of Agriculture, Washington, D. C. Numbers omitted have been discontinued, being superseded by later bulletins.

22. The Feeding of Farm Animals. Pp. 40.
24. Hog Cholera and Swine Plague. Pp. 16.
25. Peanuts: Culture and Uses. Pp. 24.
27. Flax for Seed and Fiber. Pp. 16.
28. Weeds and How to Kill Them. Pp. 30.
29. Souring and Other Changes in Milk. Pp. 22.
30. Grape Diseases on the Pacific Coast. Pp. 15.
32. Silos and Silage. Pp. 30.
33. Peach Growing for Market. Pp. 24.
34. Meats: Composition and Cooking. Pp. 31.
35. Potato Culture. Pp. 24.
36. Cotton Seed and Its Products. Pp. 16.
39. Onion Culture. Pp. 30.
41. Fowls: Care and Feeding. Pp. 24.
42. Facts about Milk. Pp. 32.
44. Commercial Fertilizers. Pp. 38.
46. Irrigation in Humid Climates. Pp. 27.
47. Insects Affecting the Cotton Plant. Pp. 32.
48. The Manuring of Cotton. Pp. 16.
49. Sheep Feeding. Pp. 24.
51. Standard Varieties of Chickens. Pp. 48.
52. The Sugar Beet. Pp. 48.
54. Some Common Birds. Pp. 48.
55. The Dairy Herd. Pp. 30.
56. Experiment Station Work—I. Pp. 30.
58. The Soy Bean as a Forage Crop. Pp. 24.
59. Bee Keeping. Pp. 48.
60. Methods of Curing Tobacco. Pp. 24.
61. Asparagus Culture. Pp. 40.
62. Marketing Farm Produce. Pp. 31.
63. Care of Milk on the Farm. Pp. 40.
64. Ducks and Geese. Pp. 55.
65. Experiment Station Work—II. Pp. 32.
66. Meadows and Pastures. Pp. 30.
68. The Black Rot of the Cabbage. Pp. 22.
69. Experiment Station Work—III. Pp. 32.
70. Insect Enemies of the Grape. Pp. 23.
71. Essentials in Beef Production. Pp. 24.
72. Cattle Ranges of the Southwest. Pp. 32.
73. Experiment Station Work—IV. Pp. 32.
74. Milk as Food. Pp. 39.
77. The Liming of Soils. Pp. 24.
78. Experiment Station Work—V. Pp. 32.
79. Experiment Station Work—VI. Pp. 27.
80. The Peach Twig-borer. Pp. 16.
81. Corn Culture in the South. Pp. 24.
82. The Culture of Tobacco. Pp. 22.
83. Tobacco Soils. Pp. 23.
84. Experiment Station Work—VII. Pp. 32.
85. Fish as Food. Pp. 32.
86. Thirty Poisonous Plants. Pp. 32.
87. Experiment Station Work—VIII. Pp. 32.
88. Alkali Lands. Pp. 23.
91. Potato Diseases and Treatment. Pp. 15.
92. Experiment Station Work—IX. Pp. 30.
93. Sugar as Food. Pp. 31.
95. Good Roads for Farmers. Pp. 46.
96. Raising Sheep for Mutton. Pp. 48.
97. Experiment Station Work—X. Pp. 32.
98. Suggestions to Southern Farmers. Pp. 48.
99. Insect Enemies of Shade Trees. Pp. 30.
100. Hog Raising in the South. Pp. 40.
101. Millets. Pp. 30.
102. Southern Forage Plants. Pp. 48.
103. Experiment Station Work—XI. Pp. 30.
104. Notes on Frost. Pp. 24.
105. Experiment Station Work—XII. Pp. 32.
106. Breeds of Dairy Cattle. Pp. 48.
107. Experiment Station Work—XIII. Pp. 32.
108. Saltbushes. Pp. 20.
109. Farmers' Reading Courses. Pp. 20.
110. Rice Culture in the United States. Pp. 28.
111. Farmers' Interest in Good Seed. Pp. 24.
112. Bread and Bread Making. Pp. 40.
113. The Apple and How to Grow It. Pp. 32.
114. Experiment Station Work—XV. Pp. 28.
115. Hop Culture in California. Pp. 28.
116. Irrigation in Fruit Growing. Pp. 48.
118. Grape Growing in the South. Pp. 32.
119. Experiment Station Work—XV. Pp. 30.
120. Insects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp 32.

134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
136. Earth Roads. Pp. 24.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing.. Pp. 48.
141. Poultry Raising on the Farm. Pp. 16.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
143. Conformation of Beef and Dairy Cattle. Pp. 44.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
146. Insecticides and Fungicides. Pp. 16.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propogation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.
179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.
18[illegible]. Meat on the Farm [illegible] Butchering, [illegible]ing, and K[illegible]ing. Pp. 37.
[illegible] Marketing [illegible] Pp. 4[illegible]
[illegible]
[illegible]
[illegible]
[illegible] Feeds [illegible]
[illegible] Experiment [illegible]
[illegible]
[illegible]
[illegible]alf[illegible]
[illegible]
[illegible]
[illegible] Pp. 1[illegible]
[illegible]
[illegible]ries. [illegible]
[illegible] Corn Growing. [illegible]
[illegible] Turkeys. Pp. 4[illegible]
[illegible]

202. Experiment Station Work—XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
205. Pig Management. Pp. 40.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
216. The Control of the Boll Weevil. Pp. 32.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work—XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
240. Inoculation of Legumes. Pp. 8.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
[illegible] The Lawn. Pp. 20.
[illegible] Cereal Breakfast Foods. Pp. 36.
[illegible] The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
[illegible] Experiment Station Work—XXXIV. Pp. 32.
[illegible] Maple Sugar and Sirup. Pp. 36.
[illegible] The Germination of Seed Corn. Pp. [illegible]6.
[illegible] Cucumbers. Pp. 30.
[illegible] The Home Vegetable Garden. Pp. 47.
[illegible] Preparation of Vegetables for the Table. Pp. 48.
[illegible] Soil Fertility. Pp. 39.
[illegible] Texas or Tick Fever and Its Prevention. Pp. 45.
[illegible] Experiment Station Work—XXXV. Pp. 32.
[illegible] Seed of Red Clover and Its Impurities. Pp. [illegible]

Issued Ap

U. S. DEPARTMENT OF AGRICULTURE

FARMERS' BULLETIN 319.

DEMONSTRATION WO
IN COOPERATION WIT
SOUTHERN FARMERS.

BY

S. A. KNAPP,

Special Agent in Charge of Farmers' Cooperative Demonstration Work, Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

B. P. I.—352.

DEMONSTRATION WORK IN COOPERATION WITH SOUTHERN FARMERS.

INTRODUCTION.

The Farmers' Cooperative Demonstration Work conducted by the United States Department of Agriculture through the Bureau of Plant Industry was inaugurated under authority of Congress in January, 1904, primarily because of the depredations of the Mexican cotton boll weevil in the State of Texas. By the rapid spread of this pest east and north it had then become evident that it would in time invade all of the cotton-producing States. This occasioned a general alarm among the cotton planters and in the industrial centers of the entire country. For a number of years prior to 1904 the Mexican boll weevil had been steadily encroaching upon the cotton-producing lands of Texas, until it had spread from the Rio Grande to a short distance beyond the eastern boundary of the State and threatened the entire cotton industry of the South. In sections where cotton was the sole cash crop the invasion of the weevil and the consequent loss of the cotton crop brought disaster to every interest and so completely demoralized financial conditions as to produce in some sections a panic.

The cotton crop had been generally produced upon a credit system by securing advances from merchants and bankers. Upon the advent of the boll weevil, confidence in securing a cotton crop was impaired and in some districts almost totally destroyed. The usual advances were either withheld or limited; labor became discontented and sought other sections or other States, and tenant farmers unable to obtain advances removed to noninfested districts, a marked decline in property values resulting.

These circumstances created a demand for immediate relief which appealed to the entire country, as the loss of the cotton crop would be a national calamity. In response to this appeal Congress made an emergency appropriation in January, 1904, which has been continued each year, thus affording opportunity for the growth and enlargement of the work.

THE TWO BRANCHES OF THE DEMONSTRATION WORK.

As at present organized and developed, the Farmers' Cooperative Demonstration Work may be said to consist of two divisions: (1) The demonstration of improved methods of agriculture in the weevil-infected districts, which is the natural outgrowth of the original plan, and (2) the extension of the same principles to other Southern States beyond the range of weevil infestation.

The territory covered by the first division of the work includes eastern and northern Texas, southern Arkansas, Oklahoma, Louisiana, and a portion of Mississippi. The total area thus covered is more than 300,000 square miles. The work in Arkansas, Oklahoma, and Mississippi has been broadly inaugurated only since October, 1907.

The second division of the work was commenced in Mississippi in March, 1906. In cooperation with the General Education Board of New York, this work in 1907 was conducted in a limited way in Alabama and Virginia, and has recently been extended into North Carolina, South Carolina, and Georgia. The expenses of this division of the work are defrayed by the General Education Board, which has appropriated the sum of $69,000 for demonstration work during the year commencing October 1, 1907. The board has shown deep interest, hearty cooperation, and a very broad philanthropy in this work of reaching the rural masses and bettering farm conditions.

PLAN OF ORGANIZATION.

The Farmers' Cooperative Demonstration Work is conducted by the writer as special agent in charge, who reports directly to the Chief of the Bureau of Plant Industry. A corps of field agents, classified according to territory in charge, as State, district, and county agents, is employed. The county agents are appointed mainly on the advice of local committees of prominent business men and farmers conversant with the territory to be worked. Each agent has in charge the practical work in one or more counties, strictly under such general directions as may be issued from the central office at Washington, D. C. The field agents have been selected with special reference to a thorough knowledge of improved agriculture and practical experience in farming in the sections to which appointed. District agents are expected to have not only a knowledge of scientific agriculture, but to be practical farmers and to have had considerable experience in the demonstration work. State agents are strong and capable men, who have shown their ability to successfully carry out the instructions of the central office over a large territory, and they are especially qualified for the work by the possession of the tact necessary to influence men.

The term " demonstration farm " is used to designate a portion of land on a farm that is worked strictly according to our instructions. This is visited by an agent as often as once a month, if possible, to see that these instructions are carried out and to give any further advice necessary.

A " cooperator " is a farmer who agrees to work a part or all of his crop according to our instructions, but a Department agent only visits him in exceptional cases.

During the ensuing year there will be employed in the cooperative demonstration work 59 agents paid from Government appropriations, and in the extension work 84 agents paid by the General Education Board. With this force about 12,000 demonstration farms had been established up to February 1, 1908, and 20,000 farmers had agreed to cooperate and make reports as to results.

SCOPE OF THE DEMONSTRATIONS.

The Farmers' Cooperative Demonstration Work is a system by which the simple and well-established principles of successful farming are directly taught to the men on the farms. The men who toil on the farms to produce the food that nourishes all the people, and who in a large measure provide the resources that support our civilization, are as justly entitled to a knowledge of the best that science and general experience have evolved for increase of production and for the betterment of agricultural conditions as the youth of our country are entitled to an education that will fit them for a broader citizenship.

One of the most serious problems in the reform of agricultural methods has been how to influence the farmer to adopt improved practices. It has been found that the mere dissemination of printed information sometimes does not accomplish this result, and therefore the method of neighborhood farm demonstrations in cooperation with progressive farmers has been evolved. The effect of a field demonstration is immediate and positive, and reaches all classes.

By actual count, it is determined that the number of farmers who annually visit each demonstration farm ranges from thirty to a hundred. If the average is placed as low as thirty the total number visiting 12,000 demonstration farms in one year would be 360,000. If we add the cooperating farmers, the aggregate is greatly increased.

The teaching by object lessons is more effective where it is simple, direct, and limited to a few common field crops, such as cotton, corn, cowpeas, and oats in the South, so that the comparisons may be evident and accepted at a glance. If general success can be secured with these standard crops, further diversification follows as a natural result.

Briefly stated, the salient features of the cooperative farm demonstrations are as follows:

(1) Better drainage of the soil.

(2) A deeper and more thoroughly pulverized seed bed; deep fall breaking (plowing) with implements that will not bring the subsoil to the surface.

(3) The use of seed of the best variety, intelligently selected and carefully stored.

(4) In cultivated crops, giving the rows and the plants in the rows a space suited to the plant, the soil, and the climate.

(5) Intensive tillage during the growing period of the crops.

(6) The importance of a high content of humus in the soil. The use of legumes, barnyard manure, farm refuse, and commercial fertilizers.

(7) The value of crop rotation and a winter cover crop on southern farms.

(8) The accomplishing of more work in a day on the farm by using more horse power and better implements.

(9) The importance of increasing the farm stock to the extent of utilizing all the waste products and idle lands of the farm.

(10) The production of all food required for the men and animals on the farm.

(11) The keeping of an account with each farm product, in order to know from which the gain or loss arises.

THE INSTRUCTIONS.

Our instructions have the following advantages: (1) What the Department of Agriculture at Washington knows from its vast stores of information about the special crop under consideration; (2) what the State agricultural experiment stations in the South have demonstrated to be the most advantageous methods; (3) what the best farmers in the South have tested and proved to be the most successful practices upon the farm, and (4) the knowledge obtained by the traveling agents of this demonstration work, who visit and have personal knowledge of the localities in the State in which they are stationed. Even then the instructions given are along the lines of correct principles, leaving many details to the good judgment of the farmer.

In this cooperative work great stress is laid upon a more thorough preparation of the soil in the autumn, because in our southern climate the frosts do not penetrate the soils sufficiently to open them and admit air; we must therefore do by plowing in the fall and by some winter cultivation what Nature does in the colder North.

In the richest soils there is but little food ready prepared for the plant, and Nature's plan is that this food shall be prepared more or less daily by the action of the air, the moisture in the soils, and the sun. These three agents make active the forces that prepare the food, so the plant can be properly nourished. This can not be done without plowing and cultivating to admit the air, and the earlier this work is commenced before the winter the greater the effect it will have upon the crop of the following season.

The effect of using good seed is not sufficiently appreciated, nor perhaps is it understood just what makes good seed. It must be the best variety for the purpose, carefully selected early in the fall and stored in a dry place. The reasons for very frequent cultivation are the admission of air, the conservation of moisture in the soil, and the prevention of a surface crust.

Young plants require excellent cultivation, just as young animals require the best food and care.

The judicious use of commercial fertilizers is one of the most important matters in modern agriculture, for this furnishes plant food directly and indirectly to the young plants. For soil improvement we must largely depend upon barnyard manure, the compost heap, and leguminous plants, such as cowpeas.

The importance of doing more as well as better work in a day has not been sufficiently impressed upon the southern farmer. This requires the use of stronger teams and better tools. Working 3 acres in a day where 1 is worked now and working each acre three times as well is a problem in profit easily understood after demonstration.

HOW FARMERS ARE INFLUENCED TO ADOPT BETTER METHODS.

In the South nearly all the merchants, bankers, and lawyers in the towns and smaller cities own farms and are intensely interested in agriculture. They form an effective center of influence, easily convinced of the value of the cooperative demonstration plan by reason of their high intelligence. Meetings are called and the work inaugurated. No further argument is necessary after the demonstrations have been made. Facts do the talking. The teachers in the public schools are generally alert and render most valuable assistance. The agricultural colleges and agricultural experiment stations give hearty cooperation. Thus, general interest is aroused in these demonstrations, which leads to careful observation and study on the part of the farmers and of the community. Public meetings are held for the discussion of these plans. In the cotton-producing States the first instructions include cotton as the main cash crop, corn as the standard food for work animals and the basis for more stock on the farm, cowpeas for food and for the renovation of the soil, oats or wheat as a winter cover crop, and the meadow and the pasture as the most economical source of food for farm stock. When the farmer has mastered these crops he is ready for diversification in any desired direction.

In districts where cotton is not the standard cash crop, instruction is given in whatever replaces cotton as a money-earning crop. These simple lessons at the start are gradually made progressive until they cover all information necessary to success in the agriculture of the district.

As a means of reaching thousands of farmers with whom our agents do not come in personal contact, systematic use is made of the newspapers. Every bulletin or letter of instruction sent to cooperators is also furnished to about 2,000 county newspapers, and by most of them published in full. The hearty cooperation of the press has been of great value to the demonstration work.

THE CULTURAL SYSTEM FOR PRODUCING COTTON UNDER BOLL-WEEVIL CONDITIONS.

As it is evident that the cotton boll weevil will soon spread over the entire cotton-producing territory of the United States, it is a matter of general interest to know how cotton is at present produced with the weevil present.

Success in making a cotton crop under boll-weevil conditions is based upon three principles. It was found (1) that the numbers of the weevils could be limited so that they would not become totally destructive to the crop until the first and middle crops are out of danger; (2) that the cotton plant can be so bred and selected as to throw nearly its whole life forces into the lower and middle crops, and (3) that the plant can be so hastened to maturity by the application of cultural methods that most of the bolls will be developed to the safety point before the weevils are too numerous.

Guided by the principles just mentioned, the Bureau of Plant Industry has worked out a cooperative plan of producing cotton under boll-weevil conditions, which is known through the South as the "cotton-cultural system." This plan is based upon our knowledge of the cotton plant and upon the life habits of the boll weevil as ascertained by the Bureau of Entomology.[a] Its chief features may be briefly mentioned, as follows:

(1) The destruction of the weevils in the fall (*a*) by burning the cotton stalks early in the fall while the weevils are still upon them and (*b*) by burning all rubbish in and about the field which might serve for hibernating quarters.

It is so difficult to secure a general adoption by the farmers of the plan of early burning of the cotton stalks that we have allowed the stalks to be turned under provided the immature bolls are destroyed.

---

[a] See Bulletin No. 51 of the Bureau of Entomology.

(2) Immediately after destroying the bolls breaking (plowing) the field as deep as conditions will allow.

(3) The shallow winter cultivation of the soil.

(4) As early planting as the season will allow with safety to the crop.

(5) The planting of early-maturing varieties of cotton.

(6) The use of fertilizers.

(7) Leaving more space between the rows, and on ordinary uplands having a greater distance between plants in the row than is usually allowed. On rich or highly fertilized lands it is better to crowd the plants slightly in the rows to avoid the excessive growth of the stalks.

(8) The use of the toothed harrow before and after planting and on the young cotton.

(9) Intensive shallow cultivation.

(10) Agitation of the stalks by means of brush attached to the cultivator.

(11) Picking up and burning the squares that fall, where practicable.

(12) Controlling the growth of the plant if excessive by barring off or topping.

(13) Selecting the seed.

(14) The rotation of crops and the use of legumes.

It will be noted that the system as outlined has a twofold object: (1) To reduce the number of weevils and (2) to aid early maturity in order to obtain a crop in advance of the weevil.

A few remarks concerning the main features of this plan may prove of value.

DESTRUCTION OF THE WEEVILS.

One of the greatest dangers to the cotton crop is the wintering of large numbers of weevils. By a failure to destroy early in the fall the immature cotton bolls and the rubbish in the fields, enough weevils may be wintered over to jeopardize the crops the ensuing year. If the immature bolls and the field rubbish are destroyed the stalks may be safely plowed under. The rubbish in the field which may serve for hibernating quarters includes the borders and fence corners.

Two methods of destroying the over-wintered weevils while they are feeding on the tender terminal buds are advocated: (1) They may be hand picked and burned or (2) some may be destroyed by the use of the harrow and brush.

FALL AND WINTER CULTIVATION OF THE SOIL.

After the destruction of the bolls in the fall, breaking (plowing) the field 1 or 2 inches deeper than usual assists in the destruction of the weevils and in the preparation of the field for successful cropping the following season. In order to air the soil and destroy grass, shallow winter cultivation of the soil should be practiced, i. e., working the land with a toothed harrow or a disk once every twenty or thirty days during the winter, as the weather may permit. The soil should be in excellent condition at the time of planting.

EARLY PLANTING AND THE USE OF EARLY-MATURING VARIETIES.

The object of early planting is to hasten the maturity of the crop. The Bureau of Entomology has shown that the weevils do not multiply until the squares begin to form and do not generally become numerous enough to destroy the entire crop before the last of July. In addition to this, early planting has been found generally helpful against cotton pests, such as the bollworm and the leafworm. Furthermore, the winter rains usually leave the soil with plenty of moisture, while in the spring there is liable to be a drought which may retard germination in late planting.

Varieties of cotton differ in time of maturity, and the same variety may differ owing to soil, moisture, fertilization, cultivation, etc. The planting of early-maturing varieties of cotton is not only important as an aid in securing a crop, but also as a means of destroying the weevil. The early-maturing cotton can be gathered and the immature bolls destroyed before it is time for the weevils to go into winter quarters. If all growers would plant early-maturing cotton and follow the plan here outlined it would result in greatly lessening the damage of the weevil.

In advising the planting of early-maturing cotton it is not the intention to advocate the exclusive use of small-boll cotton. These varieties may be better adapted to the northern limits of the cotton belt, but in nine-tenths of the cotton-producing territory there are large-boll varieties which can be just as successfully grown under boll-weevil conditions as the small-boll cottons. They must be varieties that are generally vigorous and that put out short-jointed fruit limbs close to the ground.

USE OF FERTILIZERS.

The use of fertilizers, especially acid phosphate and potash, to hasten maturity and increase fruitage, as well as the use of cottonseed meal when necessary to promote vigor and growth, is recommended. Soils and methods of application are fully explained, and it has been demonstrated that a small quantity of fertilizer properly applied accomplishes marvelous results.

SPACING BETWEEN PLANTS AND ROWS.

Planting in rows wider than usual and allowing more space in the row on light lands are advised under boll-weevil conditions. Special attention must be directed to have the rows the proper distance apart and to thin the plants in the rows. There must be width enough for the sun's rays to reach the earth between the rows and thus aid in destroying the larvæ of the weevil.

Generally speaking, more space to the plant makes a better stalk with more limbs, more bloom, and a higher grade of cotton. The spacing between the rows and in the rows must depend on the soil and the variety of cotton. More space should be given to fertilized than to unfertilized cotton. If, however, extreme space is allowed between plants in the rows and intensive cultivation is given there may be enough stimulus imparted to the growth of the plant to actually retard maturity unless the growth is controlled by barring off, as explained later; hence, on rich lands it is best to give plenty of space between the rows and to crowd the plants a little in the rows.

USE OF THE TOOTHED HARROW.

The use of the toothed harrow as soon as the crop comes up is of sufficient importance to warrant special mention. After early planting the germination is frequently slow and the earth may become crusted. The harrow may be used to break the crust before the plants are up and should be used soon afterwards to keep the soil loose so that the plants will take on rapid growth at once. The crop is surprisingly advanced by the judicious use of the harrow.

INTENSIVE CULTIVATION.

Plowing or cultivating deep the first time and shallow at all subsequent times is an important feature of good cotton production. It destroys weeds, increases the plant food, and conserves moisture, consequently hastening maturity. Under boll-weevil conditions the cotton crop should be cultivated every week. Some of our most successful cooperators have cultivated fifteen times and continued till picking commenced.

AGITATION OF STALKS.

Violent agitation of the cotton stalks when cultivating or plowing, by means of a brush attached to the cultivator or plow, is recommended. Some farmers attach a chain to the tongue and smooth poles to the whiffletrees, and also a pole to the handles, so as to brush the stalks more than once in passing. Bundles of soft, leafy twigs are better. This knocks off the infested squares. The great majority of squares fall off naturally in a very few days after they become infested. Abundant testimony has come from our cooperators to show that as long as weekly cultivation of the crop with violent agitation of the stalks is continued the damage done by the boll weevil is greatly reduced.

PICKING UP FALLEN SQUARES.

An important aid toward the destruction of the weevils is picking up the squares that fall. If two or three generations can thus be destroyed, it will result in retarding the increase of the weevil and in adding to the cotton crop. This reduces the rapidity with which the weevils multiply and is a great aid in saving the crop.

BARRING OFF OR TOPPING.

Under boll-weevil conditions the main cotton crop must be made upon the lower and middle limbs. There is no use of a tall plant. The growth of the plant should therefore be controlled by barring off or topping. As soon as the plant indicates too rapid growth, bar off on each side, thus slightly root pruning and retarding upward growth. The tendency will then be to throw more vigor into the lower limbs and to put on more fruit. This method is especially valuable on rich bottom lands where the stalks frequently grow 6 to 7 feet high. It should be noted that with the boll weevil no top crop is made; hence, more bottom crop must be secured, requiring a low, limby, vigorous plant.

SELECTING AND STORING SEED.

Scarcely any item in the cultural system is of more importance than the selection of the seed as an aid to early maturity in the following crop. The largest, best, and earliest bolls from the most vigorous short-jointed plants should be selected for seed in advance of the general picking and be stored in a dry place. The planting of early-maturing varieties and the selection of seed from the earliest and best bolls on the most vigorous and best developed stalks are fundamental principles in growing cotton irrespective of the boll weevil and can not be too closely followed.

ROTATION OF CROPS AND USE OF LEGUMES.

The Bureau of Plant Industry in all its instructions seeks to build up soil energy and to improve the mechanical condition of the soil as well. An important factor to this end is rotation of crops and the increase of humus by plowing under green plants, especially cowpeas. This builds up the soil and renders it more porous and responsive.

Some of the serious difficulties in cotton production arise from the growing of consecutive crops of cotton on the same land. This reduces fertility and hence operates against early maturity. With the best of efforts to clear fields of the weevil in the fall by burning the stalks and deep plowing, some weevils will survive, and a few soon infest a field. By planting one half of the land to corn and cowpeas and the other half to cotton, as much cotton can be produced as formerly and the land will be gradually restored to its original fertility. The corn and cowpeas will also add materially to the income of the farm, but the special reason urged for such rotation under boll-weevil infestation is that the crop of corn and peas leaves the field free from the weevil, as it feeds only upon cotton. It is evident that with the boll weevil it requires more labor to cultivate an acre of cotton; consequently, only as many acres should be planted as can be given the best attention, so as to produce a maximum crop, thus leaving more land for cereals and for meadows and pastures.

DEMONSTRATION WORK ON VARIOUS FARM CROPS.

The Farmers' Cooperative Demonstration Work, as before stated, aims to cover the entire scope of the management of the standard crops in the sections where the work is conducted. In addition to the cotton-culture system, which is the main feature of the work in many localities, it may be well to give brief mention of some of the cooperative work on other crops now under way, such as corn culture, the use of soil-renovating crops, and the production of good farm seeds.

CORN CULTURE.

Corn is the main grain dependence for farm stock and can be successfully raised in most portions of the South. Any considerable increase in its annual production would have a marked effect upon the value of the unused lands for grazing purposes and would perceptibly increase the income of the farms. The importance of corn for food and for rotation with other crops gives it a rank next to cotton as a standard farm crop. Notwithstanding this, its cultivation has been singularly neglected until the average yield per acre has fallen below the profit line in many States. Even at the high value per bushel allowed, the corn crop in many of the Southern States does not pay a living wage or a fair rent value for the land.

There is abundant proof that large and profitable crops of corn can be produced in the South by the use of the best seed and improved methods. The planting of low-grade seed in a shallow and impoverished seed bed is responsible in the main for deficient yields and quality. However, to secure the best results other reforms must be made, such as better drainage, an adjustment of distances between the rows and the stalks in the rows to meet the requirements of soil and climate, intensive cultivation of the crop, the use of cowpeas in the corn, and the following of the corn with a winter cover crop.

The Farmers' Cooperative Demonstration Work includes instruction along all of these lines, and the results have been most encouraging. Our investigations show that not even 1 per cent of the lands in the South planted to corn are plowed deeply enough at breaking, that they have not sufficient humus, and that they are not given the proper tillage to make the best crop. Seed is so generally defective that only about one-third of so-called good seed is suitable for planting if maximum yields are expected. Along these practical lines we are conducting cooperative demonstrations with the object of increasing the corn crop in the South Atlantic and Gulf States at least threefold per acre without additional cost. A system of seed selection for improving the quality and increasing the yield and methods of storage for the preservation of vitality are outlined, detailed instructions being given on application.

Selection of Seed Corn.

The object of the average farmer in planting corn is to secure the largest crop of good corn possible under the conditions. The selection of the seed is very important.

For the best results corn should be selected in the field. The Japanese select their rice seed before the harvest.

The model ear of corn is only a small part of the problem. The stalk, the leaf, the root habits, the husk, and the environment of the plant from which the ear is taken must be considered. Most of the Southern States are subject to a shorter or longer drought during the period of growth of the corn crop, and the crop will depend largely upon the drought-resisting habits of leaf and roots. Some varieties of corn which are model in ear have so open a husk that the weevils destroy much of it while in the field. Again the ear in the crib does not tell how many weak or bastard stalks grew in the vicinity.

COWPEAS AND OTHER SOIL-RENOVATING CROPS.

As just stated, corn requires a strong, well-tilled soil, and upon thin land, deteriorated by bad management, the yield soon drops below a remunerative average. Such lands will, however, profitably produce other crops of great value for the sustenance of farm stock, and, in addition, the growing of these crops will provide an excellent means of soil renovation. Lands that are now producing 10 bushels of corn per acre will with much less labor produce 1¼ tons of cowpea hay per acre, equal in nutritive value to 31 bushels of corn, or they will yield 1¼ tons of peanut hay per acre, equal in nutritive value to

23¾ bushels of corn, and in addition a peanut crop of 25 bushels per acre may be secured.

On rich lands that under good culture will produce 40 or more bushels of corn per acre satisfactory results can be secured by planting cowpeas between the rows of corn. Even rich bottom lands rated to yield 40 bushels of corn per acre if sown to alfalfa frequently produce 5 tons of hay per acre in a season, equal in feeding value to 105½ bushels of corn. In addition, such crops as cowpeas, peanuts, and alfalfa rapidly enrich the soil and leave it in excellent mechanical condition for the ensuing year.

Generally speaking, poor hill lands should not be used for corn culture unless they are placed under a thorough system of renovation, or unless fertilization with stable manure or compost is practiced to a high degree.

SEED FARMS.

The good-seed problem has been a most difficult one to solve in the South. Very few farmers have paid any attention to planting pure seed or keeping it pure when planted, and still fewer have tried to improve their seed by selection. Not one farm in one hundred in the South has proper storage for good seed. Through field agents prominent farmers in every county have been induced to establish seed farms, where the cultivation of the crop and the selection and storing of the seed are supervised by agents of this cooperative demonstration work under an agreement that the seed produced shall be distributed to the farmers at a moderate price. The best seeds for a given section are observed and a general interest is aroused among the farmers to plant a separate seed patch on every farm and carefully select for improvement.

PRACTICAL RESULTS ACCOMPLISHED.

The field operations in connection with the Farmers' Cooperative Demonstration Work extend over such a vast territory that it is difficult to state results in a concrete way. The following statements give the more important items in condensed form:

Amount available from Congressional appropriations for year 1907–8	$77,739.80
General Education Board, contribution[a]	69,000.00
Slater fund[a]	1,000.00
Voluntary local contributions (estimated)[b]	20,000.00
	167,739.80

---

[a] The responsibility for handling these funds remains in the hands of the contributors, acting under the advice of the agent in charge.

[b] Many counties ask for more demonstration farms and more improved seed than the Department of Agriculture can furnish on account of lack of funds. Some of these pledge the money necessary to thus supplement the work.

Agent in charge	1
General assistant agents	2
Field agents	143
States partially or wholly worked	10
Public meetings held annually	2,750
Circulars distributed annually	200,000
Number of demonstration farms, 1907–8, of which exact records are kept in central office	12,000
Number of cooperating farmers, 1907–8	20,000
Number of farmers visiting the demonstration farms annually (conservatively estimated)	360,000

Great interest is everywhere manifested in better preparation of the soil, in planting selected seed, and in general betterment.

Thousands of prize contests have been started in cotton and corn production among farmers and also among boys on the farm.

Thousands of letters bearing testimony to the value of the work have been received, but it is impossible to present any extended digest of these within the limits of a Farmers' Bulletin.

The following extracts from letters received show the people's estimate of the value of this demonstration work:

MARSHALL, TEX., *October 10, 1907.*

We, the undersigned committee for Harrison County, Tex., make the following preliminary report on the Farmers' Cooperative Demonstration Work done the past season in this county.

On account of the ravages of the boll weevil, Harrison County, Tex., was threatened with a disaster in the loss of the cotton crop that would affect every material interest in the county. The loss of money was not the sole consideration. Our tenants and farm laborers would to a large extent leave the county, and it would thus permanently injure our Commonwealth. In this emergency we appealed to the United States Department of Agriculture through you for advice and aid. You came to our county and organized the work in February, 1907, under an arrangement by which the Department of Agriculture would furnish superintendence and the people of this county would raise enough funds to buy improved seed for the demonstration farms. The citizens of the county promptly raised and deposited in bank $1,000 and later contributed $700 more, making a total of $1,700 invested in better seed. All agreements between the Department of Agriculture and the people were promptly and satisfactorily carried out. Almost without exception this was the worst season this section has ever known for producing cotton, but without reservation we wish to make the following statements:

(1) The results of the demonstration work have been in the highest degree satisfactory to our people, and they regard this movement as one of the greatest ever made for the upbuilding of our section.

(2) Our people are unanimous in asking for its continuance and would regard the discontinuance of the work as an untold disaster.

(3) Among the many good things accomplished we enumerate the following:

(*a*) It established over 300 demonstration farms, scattered over the entire county.

(*b*) It taught better culture and introduced better seed. These two items alone were worth more than $100,000 this year to our county in actual cash, to say nothing of future benefits. The improvement was so apparent that the observing traveler on the highways could pick out every demonstration field.

(*c*) This demonstration work saved a stampede of tenant farmers and laborers from the farms.

(*d*) It gave confidence to the merchants and bankers that a crop would be made, and thus promoted credit.

(*e*) It demonstrated to the farmers that a crop of cotton could be made under extremely adverse condition of weather and insect pests, and they enter upon another year with perfect confidence.

Great credit for the success of this year's work is due to the excellent supervision of W. F. Proctor, State agent for Texas, and to the untiring energy of T. O. Plunkett, local agent.

JNO. H. POPE. M. SCULLY.
W. T. TWYMON. H. B. MCWILLIAMS.
P. G. WHALEY. W. L. MARTIN.

The above committeemen are well known to me and are among the most substantial and reliable citizens of Harrison County, Tex., and I also personally indorse the statements made.

H. S. LYTTLETON,
County Judge, Harrison County, Tex.

PALESTINE, TEX., *January 1, 1908.*

DEAR SIR: We, the undersigned citizens of Anderson County, Tex., desire to acquaint you with the character of the work done in this county since last March through the department known as the Farmers' Cooperative Demonstration Work, and to call your attention to some of the beneficial results accomplished.

The work of the Department in this county was done on a comparatively small scale. The enterprising board of trade of the city of Palestine contributed $600 to this work, which constituted the sum of local support the work has had in the way of money contributed. But, notwithstanding this, the result of the work accomplished has been most gratifying in many ways.

Two hundred demonstration farms have been established; improved seed has been used; improved methods of cultivation have been employed, and a fine showing has been made. Outside of these demonstration farms a conservative estimate places the average yield of cotton per acre at about 300 pounds of seed cotton, or about 1 bale to 6 acres. The record made by the demonstration farms is 608 pounds of seed cotton per acre as an average. The yield of corn per acre outside of the demonstration farms is certainly not greater than 15 bushels per acre. The demonstration farms show an average yield of 28½ bushels per acre.[a]

This good showing on the cotton is still further augmented by the fact that while it formerly took about 1,700 pounds of seed cotton to make a bale, the improved seed used on the demonstration farms produces a bale with 1,400 pounds of seed cotton.

These manifest results of the work are proving very stimulating to the farming interests, and the advantages of the work of this first season are simply incalculable. We believe that one of the certain results is a general awakening of the farmers of this county to the need of better seeds and up-to-date methods of farming.

---

[a] The yields of cotton and corn given are unusually low because of the excessive rainfall.

It must be remembered that the showing that has been made this last year has been made under the most adverse circumstances imaginable. Adverse crop conditions have existed from the very beginning of the work.

We earnestly petition that the good work be continued in this county on just as large a scale as possible, and we pledge the same our hearty cooperation and encouragement. * * *

John R. Hearne,
President, Board of Trade, and
President, Royall National Bank.
R. R. Claridge,
President, Texas Div., Southern
Corn Association.
Y. L. Jones,
Merchant.
H. Horwitz,
Merchant.

H. W. Watts,
Ex-Sheriff, Anderson County.
Don M. Barrett,
Ex-Tax Collector, Anderson County.
S. M. Paul,
Farmer.
J. J. Strickland,
Representative,
Thirtieth Legislature.

Denison Board of Trade,
Denison, Tex., January 2, 1908.

Dear Sir: Referring to your esteemed favor of recent date, beg to say that we greatly appreciate your interest and cooperation in our efforts for agricultural advancement, and we expect great good to result from the work planned next year. The work of the past year has served to thoroughly arouse our people to an understanding of the great work that your Department is doing in the interest of agricultural advancement.

Your work in this community during the past year has been of inestimable value to our people. There has been a wonderful awakening of interest among our farmers, who are now on the alert for new ideas and progressive methods. There was a time, perhaps, when farmers regarded the work of the Department of Agriculture as empty theory and spurned the advice of what they pleased to term "book farmers," but they now realize the science of agriculture and the wonderful possibilities for improvement and for increasing their earning capacity. Such an awakening is manifest on every hand in the vicinity of Denison, where wonderful progress has been made during the past year. I feel safe in the assertion that there has been more scientific and methodical work on the farms about Denison during 1907 than ever before. * * * This is evidence of real prosperity—prosperity so firmly established that our little city and the surrounding country hardly realized the existence of the financial flurry which so upset conditions throughout the country.

We regard the work in the interest of agricultural advancement as being the most productive effort of this organization, and we feel deeply indebted to you for cooperation, which has made our work much more effective than it could have been otherwise. We feel that the object lessons provided by you last year were very effective, and the establishment of the 30 demonstration and cooperative farms planned for the next year insures even greater progress. Two of the farmers who operated demonstration plats the past year under the able direction of Mr. J. L. Quicksall have sold all their Triumph seed they had to spare at $1 per bushel.

We are especially anxious to encourage the corn growers whom we have succeeded in so thoroughly arousing during the past year. I have never known so much interest in the improvement of corn as is in evidence here at this time. * * * We are anxious to render any possible service that will facilitate your work in the vicinity of Denison, believing that your continued cooperation will assist us in making this the greatest agricultural section of the Southwest.

Very truly yours, T. W. Larkin,
Secretary.

Taylor, La., *January 5, 1908.*

Dear Sir: Some four years ago I worked a plat of land by your cultural method, which gave me much better results than the usual methods previously used. I have been following the same instructions in part for the last three seasons, and find this method gives better results, especially the thorough preparation of the seed bed and the distance between rows and plants. I find the crop much easier worked and the yield better in quality, as well as quantity. I also have tried to help a good thing along by showing your instructions and my crop to others and by having my tenants work by same. One of the parties to whom I read the instructions and showed the crop asked me to see his crop last summer, saying he had worked it my way and had the best crop he ever raised in his life. I think he had a fine crop for the season.

Respectfully, W. C. Wall.

Clarendon, Ark., *December 20, 1907.*

Dear Sir: I took up your plan of farming in 1906 in a small way with good results; in fact, was so well pleased with it that I planted and cultivated something like 400 acres this year. I followed your directions in preparation and cultivation, using 200 pounds of phosphate per acre. While we had the wettest and coldest and most backward spring I ever knew, causing me to plant the greater part of my crop over the fourth time and as late as June 9 to 12, then only getting about half a stand on most of it, and after that date only had rain enough to keep the plows out of the field a few hours until picking time, I am satisfied with the result, some of it paying me as high as $30 per acre net rent, the lowest $6 per acre, averaging about $13 per acre net. I more than doubled my yield of corn. I expect to go at it more extensively next year. I have had my plows going for two weeks, preparing cotton land for 1908.

Very respectfully,

W. S. Jeffries.

Stonewall, La., *December 13, 1907.*

Dear Sir: Having spent twenty-five years in paying for cotton lands and a cotton gin and otherwise getting in shape to grow and handle cotton to advantage, we have studied and watched with deep interest every movement which was calculated to relieve us from the ravages of the boll weevil, and now we write to thank you and Mr. Cowden (agent) for the work done in this community in the way of establishing demonstration farms this year. We feel sure this is the best manner to reach most of our people, who have grown skeptical of book farming, but are easily convinced by a practical application of your methods. We have tried your plans for two years and think it our only hope to outwit the boll weevil.

Trusting you may be able to continue your work in our parish next year,

We are, with regards, yours truly,

J. M. & M. G. Nels

THE BUSINESS MEN'S LEAGUE OF HELENA, ARK.,
Helena, Ark., January 11, 1908.

DEAR SIR: Our league has on foot a movement to increase the production per acre of cotton and corn in this section.

Two years ago an experiment was conducted under the immediate care of Messrs. E. D. Pillow and H. G. Stephens, one of your representatives having a general supervision of the experiment. No fertilizer was used, but the cultural methods adopted proved wonderfully beneficial and a large yield of cotton resulted. During the season just past, Mr. Stephens conducted an experiment upon his own behalf, using nitrate of soda as a fertilizer for cotton and cottonseed meal for corn. He has made us a report which we will publish, and that, together with a letter from Mr. E. D. Pillow, will be mailed by us to about 1,000 farmers in this section. * * * We would also ask your cooperation in this matter and would like to know if it would be possible to secure the services of a representative of the Agricultural Department to make a tour of inspection at short intervals for the purpose of aiding these farmers by way of instruction and general information. The experiment would be more apt to prove profitable if some one would make the rounds and let it be known in advance that an inspection would be made.

Kindly write us fully upon this subject and tell us to what extent and in what manner you can aid us in this movement.

Yours truly, E. C. HORNOR.

CONCLUSION.

It has been proved by our cooperative demonstration work that by following the instructions of the Bureau of Plant Industry a good crop of cotton can be raised in the worst-infested boll-weevil districts and despite the ravages of this pest. It is possible that the future may discover some better method of meeting the boll-weevil problems, but experience has shown that the method outlined is the only safe one at present. The boll weevil has now covered a large portion of Texas, Louisiana, Arkansas, Oklahoma, and several counties in Mississippi. It is annually invading new territory with a column 600 miles long and in numbers sufficient to cover every stalk of cotton to a width of 30 miles. A cotton crop can be produced despite the boll weevil, and the sooner American farmers face the situation the better it will be for all concerned. To demonstrate the truth of this theory is one object of the Farmers' Cooperative Demonstration Work.

In the foregoing pages have been mentioned only some of the lines of demonstration which have been undertaken for rural uplifting. The results have far exceeded our expectations, and the farmers have accepted the work gratefully and have cooperated to the best of their ability in every undertaking. It is along such lines as these that great economies can be practiced and valuable reforms wrought for the betterment of rural conditions and for solving the problems of the farm.

FARMERS' BULLETINS.

following is a list, by number, of the Farmers' Bulletins available for distri-
The bulletins entitled "Experiment Station Work" give in brief the results
riments performed by the State experiment stations. Titles of other bulletins
-explanatory. Bulletins in this list will be sent free to any address in the
States on application to a Senator, Representative, or Delegate in Congress,
ie Secretary of Agriculture, Washington, D. C. Numbers omitted have been
inued, being superseded by later bulletins.

Feeding of Farm Animals. Pp. 40.
Cholera and Swine Plague. Pp. 16.
nuts: Culture and Uses. Pp. 24.
x for Seed and Fiber. Pp. 16.
ds: And How to Kill Them. Pp. 30.
ring and Other Changes in Milk. Pp. 22.
pe Diseases on the Pacific Coast. Pp. 15.
s and Silage. Pp. 30.
ch Growing for Market. Pp. 24.
its: Composition and Cooking. Pp. 31.
ato Culture. Pp. 24.
ton Seed and Its Products. Pp. 16.
ts about Milk. Pp. 32.
mercial Fertilizers. Pp. 38.
cts Affecting the Cotton Plant. Pp. 32.
Manuring of Cotton. Pp. 16.
ndard Varieties of Chickens. Pp. 48.
Sugar Beet. Pp. 48.
ie Common Birds. Pp. 48.
Dairy Herd. Pp. 30.
eriment Station Work—I. Pp. 30.
Soy Bean as a Forage Crop. Pp. 24.
Keeping. Pp. 48.
hods of Curing Tobacco. Pp. 24.
aragus Culture. Pp. 40.
keting Farm Produce. Pp. 31.
e of Milk on the Farm. Pp. 40.
ks and Geese. Pp. 55.
eriment Station Work—II. Pp. 32.
dows and Pastures. Pp. 30.
eriment Station Work—III. Pp. 32.
entials in Beef Production. Pp. 24.
tle Ranges of the Southwest. Pp. 32.
eriment Station Work—IV. Pp. 32.
k as Food. Pp. 39.
Liming of Soils. Pp. 24.
eriment Station Work—V. Pp. 32.
eriment Station Work—VI. Pp. 27.
Peach Twig-Borer. Pp. 16.
n Culture in the South. Pp. 24.
Culture of Tobacco. Pp. 22.
acco Soils. Pp. 23.
eriment Station Work—VII. Pp. 32.
h as Food. Pp. 32.
rty Poisonous Plants. Pp. 32.
eriment Station Work—VIII. Pp. 32.
ali Lands. Pp. 23.
ato Diseases and Treatment. Pp. 15.
eriment Station Work—IX. Pp. 30.
ar as Food. Pp. 31.
d Roads for Farmers. Pp. 46.
eriment Station Work—X. Pp. 32.
gestions to Southern Farmers. Pp. 48.
ect Enemies of Shade Trees. Pp. 30.
Raising in the South. Pp. 40.
lets. Pp. 30.
thern Forage Plants. Pp. 48.
periment Station Work—XI. Pp. 30.
es on Frost. Pp. 24.
eriment Station Work—XII. Pp. 32.
eds of Dairy Cattle. Pp. 48.
eriment Station Work—XIII. Pp. 32.
tbushes. Pp. 20.
e Culture in the United States. Pp. 28.
mers' Interest in Good Seed. Pp. 24.
ad and Bread Making. Pp. 40.
Apple and How to Grow It. Pp. 32.
eriment Station Work—XIV. Pp. 28.
gation in Fruit Growing. Pp. 48.
pe Growing in the South. Pp. 32.
eriment Station Work—XV. Pp. 30.
ects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and Other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp. 32.
134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing. Pp. 48.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propagation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese-Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.
179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.
183. Meat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
185. Beautifying the Home Grounds. Pp. 24.
186. Experiment Station Work—XXIII. Pp. 32.
187. Drainage of Farm Lands. Pp. 38.
188. Weeds Used in Medicine. Pp. 45.

[illegible] Experiment Station Work—XX[illegible]
[illegible]
[illegible] Work—X[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible] Experiment Station Work—XXVI. [illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible] Experiment Station Work—XXVII. [illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible]
[illegible] Experiment Station Work—XXVIII. [illegible]
[illegible]
[illegible]
[illegible] Experiment Station Work—XXIX. [illegible]
[illegible] West. Pp. [illegible]
[illegible] Experiment Station Work—XXX. [illegible]
[illegible] Forest Planting and Farm Management. Pp. [illegible]
[illegible] Pp. 24.
[illegible] Diseases. Pp. [illegible]
[illegible] Uses. Pp. [illegible]
[illegible] Experiment Station Work—XXXI. Pp. 32.
[illegible] Pp. 24.
[illegible] Concrete. Pp. [illegible]
[illegible] Pp. 32.
[illegible] Experiment Station Work—XXXII. Pp. [illegible]
[illegible] States. Pp. 48.
[illegible] Fence Wire. Pp. [illegible]
[illegible] Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. [illegible]
243. Fungicides and Their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. [illegible]
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
251. Experiment Station Work—XXXIV. Pp. 32.
252. Maple Sugar and Sirup. Pp. 36.
253. The Germination of Seed Corn. Pp. 16.
254. Cucumbers. Pp. 30.
255. The Home Vegetable Garden. Pp. 47.
256. Preparation of Vegetables for the Table. Pp. [illegible]
257. Soil Fertility. Pp. [illegible]
258. Texas or Tick Fever and Its Prevention. Pp. [illegible]
259. Experiment Station Work—XXXV. Pp. 32.
260. Seed of Red Clover and Its Impurities. Pp. 21.
261. The Cattle Tick. Pp. 22.
262. Experiment Station Work—XXXVI. Pp. 32.
263. Practical Information for Beginners in Irrigation. Pp. 40.
264. The Brown-Tail Moth and How to Control It. Pp. [illegible]
266. Management of Soils to Conserve Moisture. Pp. [illegible]8
267. Experiment Station Work—XXXVII. Pp. [illegible]
268. Industrial Alcohol: Sources and Manufacture. Pp. [illegible]
269. Industrial Alcohol: Uses and Statistics. Pp. [illegible]
270. Modern Conveniences for the Farm Home. Pp. [illegible]
271. Forage-Crop Practices in Western Oregon and Western Washington. Pp. [illegible]
272. A Successful Hog and Seed-Corn Farm. Pp. [illegible]
273. Experiment Station Work—XXXVIII. Pp. [illegible]
274. Flax Culture. Pp. [illegible]
275. The Gipsy Moth and How to Control It. Pp. [illegible]
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 4[illegible]
278. Leguminous Crops for Green Manuring. Pp. [illegible]
279. A Method of Eradicating Johnson Grass. Pp. [illegible]
280. A Profitable Tenant Dairy Farm. Pp. [illegible]
281. Experiment Station Work—XL. Pp. [illegible]
282. Celery. Pp. [illegible]
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. [illegible]
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. [illegible]
285. The Advantage of Planting Heavy Cotton Seed. Pp. [illegible]
286. Comparative Value of Whole Cotton Seed and Cotton-seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. Pp. 48.
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. Pp. 30.
295. Potatoes and Other Root Crops as Food. Pp. 45.
296. Experiment Station Work—XLI. Pp. 32.
297. Methods of Destroying Rats. Pp. 8.
298. The Food Value of Corn and Corn Products. Pp. 40.
299. Diversified Farming Under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-Grown Tea. Pp. 16.
302. Sea Island Cotton: Its Culture, Improvement, and Diseases. Pp. 48.
303. Corn Harvesting Machinery. Pp. 32.
304. Growing and Curing Hops. Pp. 39.
305. Experiment Station Work—XLII. Pp. 32.
306. Dodder in Relation to Farm Seeds. Pp. 27.
307. Roselle: Its Culture and Uses. Pp. 16.
308. Game Laws for 1907. Pp. 52.
309. Experiment Station Work—XLIII. Pp. 32.
310. A Successful Alabama Diversification Farm. Pp. 24.
311. Sand-Clay and Burnt-Clay Roads. Pp. 20.
312. A Successful Southern Hay Farm. Pp. 15.
313. Harvesting and Storing Corn. Pp. 32.
314. A Method of Breeding Early Cotton to Escape Boll-Weevil Damage. Pp. 20.
315. Progress in Legume Inoculation. Pp. 20.
316. Experiment Station Work—XLIV. Pp. 32.
317. Experiment Station Work—XLV. Pp. 32.
318. Cowpeas. Pp. 26.

O

1081 Issued April 8, 1908.

U. S. DEPARTMENT OF AGRICULTURE.
7

FARMERS' BULLETIN 320.

Experiment Station Work,

XLVI.

Compiled from the Publications of the Agricultural Experiment Stations.

FISH FERTILIZER.
RECLAMATION OF SALT MARSHES.
BERMUDA HAY.
PROTEIN CONTENT OF FORAGE CROPS.
QUALITY IN WHEAT.
POTATO SPRAYING.
ANESTHETICS IN FORCING PLANTS.
FATTENING CATTLE FOR MARKET.
COTTON-SEED MEAL AND CORN SILAGE FOR COWS.
CARBONATED MILK.
PRESERVATION OF FENCE POSTS.

MARCH, 1908.

PREPARED IN THE OFFICE OF EXPERIMENT STATIONS.
A. C. TRUE, Director.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

THE AGRICULTURAL EXPERIMENT STATIONS.

- ALABAMA—
  - College Station: *Auburn;* J. F. Duggar.[a]
  - Canebrake Station: *Uniontown;* F. D. Stevens.[a]
  - Tuskegee Station: *Tuskegee Institute;* G. W. Carver.[a]
- ALASKA—*Sitka:* C. C. Georgeson.[b]
- ARIZONA—*Tucson:* R. H. Forbes.[a]
- ARKANSAS—*Fayetteville:* W. G. Vincenheller.[a]
- CALIFORNIA—*Berkeley:* E. J. Wickson.[a]
- COLORADO—*Fort Collins:* L. G. Carpenter.[a]
- CONNECTICUT—
  - State Station: *New Haven;* E. H. Jenkins.[a]
  - Storrs Station: *Storrs;* L. A. Clinton.[a]
- DELAWARE—*Newark:* Harry Hayward.[a]
- FLORIDA—*Gainesville:* P. H. Rolfs.[a]
- GEORGIA—*Experiment:* Martin V. Calvin.[a]
- HAWAII—
  - Federal Station: *Honolulu;* J. G. Smith.[b]
  - Sugar Planters' Station: *Honolulu;* C. F. Eckart.[a]
- IDAHO—*Moscow:* H. T. French.[a]
- ILLINOIS—*Urbana:* E. Davenport.[a]
- INDIANA—*Lafayette:* A. Goss.[a]
- IOWA—*Ames:* C. F. Curtiss.[a]
- KANSAS—*Manhattan:* C. W. Burkett.[a]
- KENTUCKY—*Lexington:* M. A. Scovell.[a]
- LOUISIANA—
  - State Station: *Baton Rouge.*
  - Sugar Station: *Audubon Park, New Orleans.*
  - North Louisiana Station: *Calhoun;* W. R. Dodson (*Baton Rouge*).[a]
- MAINE—*Orono:* C. D. Woods.[a]
- MARYLAND—*College Park:* H. J. Patterson.[a]
- MASSACHUSETTS—*Amherst:* W. P. Brooks.[a]
- MICHIGAN—*East Lansing:* C. D. Smith.[a]
- MINNESOTA—*St. Anthony Park, St. Paul:* E. W. Randall.[a]
- MISSISSIPPI—*Agricultural College:* W. L. Hutchinson.[a]
- MISSOURI—
  - College Station: *Columbia;* H. J. Waters.[a]
- MISSOURI—Continued.
  - Fruit Station: *Mountain Grove;* P. Evans.[a]
- MONTANA—*Bozeman:* F. B. Linfield.[a]
- NEBRASKA—*Lincoln:* E. A. Burnett.[a]
- NEVADA—*Reno:* J. E. Stubbs.[a]
- NEW HAMPSHIRE—*Durham:* E. D. Sanderson.[a]
- NEW JERSEY—*New Brunswick:* E. B. Voorhees.[a]
- NEW MEXICO—*Agricultural College:* L. Foster.[a]
- NEW YORK—
  - State Station: *Geneva;* W. H. Jordan.[a]
  - Cornell Station: *Ithaca;* L. H. Bailey.[a]
- NORTH CAROLINA—
  - College Station: *West Raleigh;* C. B. Williams.[a]
  - State Station: *Raleigh;* B. W. Kilgore.[a]
- NORTH DAKOTA—*Agricultural College:* J. H. Worst.[a]
- OHIO—*Wooster:* C. E. Thorne.[a]
- OKLAHOMA—*Stillwater:* W. L. English.[a]
- OREGON—*Corvallis:* J. Withycombe.[a]
- PENNSYLVANIA—
  - *State College:* T. F. Hunt.[a]
  - *State College:* Institute of Animal Nutrition, H. P. Armsby.[a]
- PORTO RICO—*Mayaguez:* D. W. May.[b]
- RHODE ISLAND—*Kingston:* H. J. Wheeler.[a]
- SOUTH CAROLINA—*Clemson College:* J. N. Harper.[a]
- SOUTH DAKOTA—*Brookings:* J. W. Wilson.[a]
- TENNESSEE—*Knoxville:* H. A. Morgan.[a]
- TEXAS—*College Station:* H. H. Harrington.[a]
- UTAH—*Logan:* E. D. Ball.[a]
- VERMONT—*Burlington:* J. L. Hills.[a]
- VIRGINIA—*Blacksburg:* S. W. Fletcher.[a]
- WASHINGTON—*Pullman:* R. W. Thatcher.[a]
- WEST VIRGINIA—*Morgantown:* J. H. Stewart.[a]
- WISCONSIN—*Madison:* H. L. Russell.[a]
- WYOMING—*Laramie:* J. D. Towar.[a]

---

[a] Director.

[b] Special agent in charge.

EXPERIMENT STATION WORK.

Edited by W. H. BEAL and the Staff of the Experiment Station Record.

Experiment Station Work is a subseries of brief popular bulletins compiled from the published reports of the agricultural experiment stations and kindred institutions in this and other countries. The chief object of these publications is to disseminate throughout the country information regarding experiments at the different experiment stations, and thus to acquaint farmers in a general way with the progress of agricultural investigation on its practical side. The results herein reported should for the most part be regarded as tentative and suggestive rather than conclusive. Further experiments may modify them, and experience alone can show how far they will be useful in actual practice. The work of the stations must not be depended upon to produce "rules for farming." How to apply the results of experiments to his own conditions will ever remain the problem of the individual farmer.—A. C. TRUE, Director, Office of Experiment Stations.

CONTENTS OF NO. XLVI.

Page.
Fish fertilizer 5
Reclamation of salt marshes 9
Bermuda hay 12
Protein content of forage crops 13
    Variation in protein content 13
    Alfalfa 14
    Clover 14
    Peas 15
    Soy beans 15
    Rape 15
    Corn fodder 16
    Brome grass 16
    Other forage plants 16
    Weeds 17
Quality in wheat 18
Does it pay to spray potatoes? 22
Use of anesthetics in forcing plants 23
Fattening cattle for market 25
Cotton-seed meal and corn silage for dairy cows 28
Carbonated milk 29
Preservation of fence posts 30

EXPERIMENT STATION WORK.[a]

FISH FERTILIZER.[b]

Dried and ground fish or fish guano is a valuable fertilizer furnishing nitrogen and phosphoric acid, which finds quite extensive use in this and other countries where the material is available. The use of fish as a fertilizer in this country dates from the time of the earliest settlement at Plymouth, for it is reported that Squanto, an Indian, taught the Plymouth colonists to put a menhaden under each hill of corn at the time of planting to increase the yield. Untreated fish and fish waste have been used to a considerable extent as a fertilizer either directly or in composts with other materials ever since that time in regions where such materials are abundant and easily obtained.

The fish fertilizer or fish guano now commonly in use, however, is a manufactured product derived from two main sources—(1) the refuse from fish packing and canning establishments, and (2) the pomace from the extraction of oil from inedible fish. By far the larger proportion of the fish fertilizer produced in the United States is prepared from the menhaden, which is taken in immense numbers, especially along the Atlantic coast. According to a report of the U. S. Bureau of Fisheries, over 85,000 tons of fish fertilizer, valued at more than $1,500,000, was made from menhaden in the United States in 1903, and about 20,000 tons, valued at $200,000, from miscellaneous fish products. Catches of from 800,000,000 to 1,000,000,000 menhaden, weighing in the aggregate from 250,000 to 400,000 tons, during a single season on the North Atlantic coast, have been reported.

---

[a] A progress record of experimental inquiries, published without assumption of responsibility by the Department for the correctness of the facts and conclusions reported by the stations.

[b] Compiled from Connecticut State Sta. Rpts. 1897, p. 257; 1900, p. 95; 1907–8, pt. 1, p. 44; Maine Sta. Bul. 88; New Jersey Stas. Rpt. 1901, p. 137; North Carolina Sta. Bul. 190; Washington Sta. Bul. 44; U. S. Fish Com. Rpt. 1902, p. 253; Report of the Commissioners on Fisheries and Game upon the Damage Caused to the Fisheries of Massachusetts by Dogfish during the Year 1905 (Boston, 1906, p. 61); Canada Expt. Farms Rpts. 1906, p. 158; Amer. Fert., 19 (1903), No. 6, p. 7; Ann. Sci. Agron., 3. ser., 1 (1906), I, No. 2, p. 166.

The product prepared from the menhaden is especially rich in fertilizing constituents, containing from 7 to 8 per cent of nitrogen and 6 to 8 per cent of phosphoric acid. The oil is removed from the menhaden and the material is prepared for use as a fertilizer by cooking in water in tanks heated with steam coils. This is the so-called process of tanking and is employed to remove the oil, which is a valuable commercial product, but interferes materially with the availability of the fertilizing constituents of the fish if not removed. The steaming also has a direct effect in increasing the availability of the phosphoric acid as well as the nitrogen of the fish. The boiling is continued until the oil rises to the surface and can be drawn off with the water, from which it is afterwards separated. The residue in the tanks is pressed in hydraulic presses, dried, and ground. In some cases the material is subjected after the first pressing to steam under pressure and to treatment with 5 per cent sulphuric acid to render the fertilizing constituents, particularly the phosphoric acid, more available.

The dry ground fish, or fish guano, obtained by this process is used to some extent directly as a fertilizer, but is usually mixed with other fertilizing materials (potash and phosphates) to make a better balanced complete fertilizer. The availability of the nitrogen in fish fertilizer prepared in this way is nearly as great as that of dried blood and tankage, which are considered among the best of the organic sources of nitrogen in fertilizers.[a] The phosphoric acid is also frequently more available than that in other organic matter.

Fertilizer prepared from fish waste from packing and canning establishments is more variable in its nitrogen content than that prepared from menhaden, owing to varying water content and proportion of bone, skin, and flesh in such waste. It is likely to be poorer in nitrogen and relatively richer in phosphoric acid than the menhaden product. According to Voorhees, the nitrogen in untreated fish scrap varies from 2.5 to 8 per cent and the phosphoric acid from 2 to 6 per cent, and these fertilizing constituents are much less available than in the tanked, dried, and finely ground material.

A large part of the fish offal accumulating at canneries and fish-packing establishments, particularly in the Columbia River region and in Alaska, which might be profitably used, is now wasted, but steps are being taken to establish fertilizer factories for the utilization of this material in these regions. In regions where it can be readily obtained from fishermen, fish scrap and waste are frequently used without preparation of any kind. Various methods of composting and other simple processes of treating fish for use as a fertilizer have been used with more or less success on a small scale.

---

[a] U. S. Dept. Agr., Farmers' Bul. 73, p. 7.

A report of the U. S. Bureau of Fisheries describes a method of composting as follows:

> A convenient process of converting a small quantity of refuse from dressing fish into fertilizer is to store it in a receptacle made in the ground. This should be about 5 or 6 feet deep, with the area depending on the amount of refuse, but usually about 6 feet square. It should be dry, and if the soil is sandy some clay should be spread at the bottom. First is placed a layer of wood ashes a few inches deep and then an equal layer of fish refuse covered by a sprinkling of lime. Then follow another layer of ashes, one of fish refuse sprinkled with lime, and so on until the hole is full. It should be covered with earth or sod and these covered with weighted boards and permitted to so remain for several months. The fish refuse quickly disintegrates and becomes mixed with the ashes, forming an excellent fertilizer.

It should be borne in mind in preparing such composts as this that the use of caustic alkaline substance such as wood ashes and lime in connection with easily decomposable organic matter, while admirably suited to the quick reduction of the material to a fine mechanical condition, is likely to result in the loss of a considerable amount of the nitrogen, which is the most valuable fertilizing constituent of the fish.

In the purchase of untreated fish and fish offal for direct use as a fertilizer farmers should be guided by the amount of water which it contains. Fresh fish and wet fish offal are very variable in water content, but probably contain on the average 50 to 60 per cent of water, with correspondingly lower percentages of nitrogen and phosphoric acid than the comparatively dry residue from oil extraction. It would hardly be profitable to transport such watery materials any considerable distance unless they could be obtained at a very low price. Voorhees states that if material of this kind containing 2.5 per cent of nitrogen can be obtained at $5 per ton it can be profitably used by farmers.

Fish and fish scrap have been successfully converted into fertilizer by simply drying and grinding. In this case it has been recommended to add a small amount of sulphuric acid (5 per cent) or muriate of potash to check offensive fermentation and to increase the fertilizing value of the resulting product. In Norway, which is one of the largest producers of fish fertilizer in the world, a common method is to spread the fish scrap on the rocks to dry, afterwards grinding it to the condition of a coarse meal. The Norwegian product is generally distinguished from the American fish fertilizer by its higher percentage of phosphoric acid and lower percentage of nitrogen.

Recently the possibility of utilizing the dogfish, which is proving so injurious to the fishery interests of the North Atlantic coast, for the manufacture of fertilizers, has been receiving considerable attention, especially by the Commissioners of Fisheries and Game of Massachusetts and the Department of Marine and Fisheries of Canada, and factories, notably one in Nova Scotia and two others in New Brunswick, have been established for this purpose under the auspices of the latter department. Analyses by F. T. Shutt, of the Canada Experimental Farms, of the products of these factories show a nitrogen content varying from 7.59 to 9.41 per cent and phosphoric acid from 2.94 to 6.49 per cent. The product is therefore of high value as regards nitrogen and phosphoric-acid contents. The samples examined, however, contained a very high percentage of oil (22.81 to 32.75 per cent), which seriously detracts from the fertilizing value of the product. There seems to be no insurmountable difficulty in the way of converting the dogfish into a high-grade fertilizer comparing favorably with the best forms of fish fertilizer, provided the dogfish can be supplied in sufficient amount to keep the factories running on an economical basis.

The foregoing statements, based upon a large amount of work by various experiment stations, make it plain that there is obtained from fish and fish waste a very valuable fertilizer, furnishing considerable percentages of both nitrogen and phosphoric acid, the former in readily available form. Fish fertilizer is especially valuable as a carrier of nitrogen either for direct use or in the preparation of mixed fertilizers. It should always be borne in mind that fish is deficient in potash and that in order to make a complete, well-balanced fertilizer it must be mixed with or used in combination with potash salts, and it is also improved by being reinforced with more soluble forms of phosphoric acid.

The following formulas are given by F. T. Shutt, of the Canada Experimental Farms, for combining fish with other fertilizing materials to make complete fertilizers for general use:

For cereals and grass:	Pounds.
Dry ground fish	300
Nitrate of soda	100
Superphosphate	300
Muriate of potash	50
Application—300 to 800 pounds per acre.	
For potatoes, roots generally, and clover:	
Dry ground fish	300
Nitrate of soda	50
Superphosphate	400
Muriate of potash	150
Application—300 to 800 pounds per acre.	

Dry sand or fine loam may be added to the mixed fertilizer to facilitate distribution. Probably the best plan of application is to broadcast the fertilizer on the thoroughly prepared land in the spring, previous to seeding, incorporating with the soil by one or more harrowings. It has been found that fish refuse gives the best returns on moderately light, warm, moist soils.

Like other organic manures, fish fertilizer is better suited to long-season crops than to short-season, early-maturing crops. Favorable conditions for nitrification, which renders the nitrogen available to crops, are necessary to the greatest efficiency of the fish fertilizers, as of other organic nitrogenous fertilizers.

In experiments at the North Carolina Experiment Station, W. A. Withers found that while the rate of nitrification varied widely with the character of the soil, fish fertilizer in certain cases nitrified more rapidly than sulphate of ammonia, dried blood, cotton-seed meal, and bone. A warm, porous soil well supplied with lime is especially suited to the rapid nitrification of such manures as fish.

RECLAMATION OF SALT MARSHES.[a]

The New Jersey legislature in 1902 passed a bill providing, in a comprehensive way, for the locating and abolishing of mosquito-breeding salt-marsh areas, placing the management of the work in the hands of the entomologist of the New Jersey experiment stations. It was urged in favor of this bill "that in addition to the direct advantage to the State of the eradication of the mosquitoes, the indirect returns that would be derived from the drainage necessary in abolishing the mosquito-breeding areas would in a few years exceed the total appropriations asked for. This argument was based on the assumption that the water-logged marsh areas, now largely waste lands, would then grow instead grasses of commercial value. No definite statement could be made as to the area likely to be improved, nor its possible increase in value."

In order to obtain more definite information as to the benefits resulting from the drainage incidental to the mosquito extermination, as well as the possible benefits which might be derived from more thorough drainage, the executive officer in charge of the mosquito work was authorized to make such observations and investigations on the areas already drained as would serve as a basis for estimating the possible value to the State of such drainage work. In a recent report Prof. John B. Smith, the officer in charge of the mosquito work, summarizes his observations on this subject.

Three types of marsh lands were taken account of in his estimates of the possible increase of land values as a result of partial or complete drainage.

---

[a] Compiled from New Jersey Stas. Bul. 207; U. S. Dept. Agr., Office of Expt. Stas. Rpt. 1906, p. 373; Circ. 76.

The first and smallest in area is that which is covered at every mean high tide and which may or may not be covered with sedge or joint grass. It is an area that has never been made useful for any purpose, is not dangerous as a mosquito-breeding territory, gradually rising or making up. It merges gradually into the second type.

The second type is in area rarely covered at ordinary tides, but so little above mean high water that even the slightest rise, due to wind, storm, or moon changes, results in a watery covering. Such areas may be covered by sedge, but more usually have a scanty growth of the joint grass and are inhabited by fiddler crabs. This area is also without present value and is not dangerous as a mosquito breeder, for the burrows of the "fiddlers" provide effective drainage. Such marsh is usually very flat and level, and if holes occur they are of considerable size and naturally and continually stocked with fish and other marine organisms. This type of marsh is also gradually rising. The surface is quite generally a slippy mud, and there is not even shelter to tempt adult mosquitoes to rest on it.

The third type of marsh is all that area above mean high tide and more or less completely covered with vegetation.

These marsh lands have very little present value, although "all salt marsh of the third type may be made to produce an income of from $10 to $40 per acre annually, and all salt marsh of that type can be made of actual value. As a matter of fact, there are many hundred acres that do produce such incomes as against many times more that produce nothing—but can be made to do as well." Some of the higher lands produce a coarse hay which has some value for feed, bedding, packing, etc. Even the partial drainage carried out in the course of mosquito extermination has, in many cases, greatly increased the yield and improved the quality of the natural growth of hay.

Diking and drainage are the two recognized methods of reclaiming such marshes.

As to the relative cost of draining and diking and the cost of maintenance, that is all in favor of the drainage. An average salt marsh can be drained for about $12 an acre, and on a large marsh area the average cost per acre of mosquito drainage is much less. The cost of maintaining the ditches need not exceed $1 per annum per acre and would probably be less. No effective diking could be done at any such rate, especially as, in any case, ditching would have to supplement it to get rid of the surface water. An area once diked and placed under cultivation can not be restored as a salt marsh for many years, if ever. A well-drained salt marsh may at its highest points be cultivated and used to produce such truck crops as will grow in salt land, and is not in any way unfitted for later reclamation by diking.

A salt marsh properly drained for the production of maximum grass crop will not breed mosquitoes, because there will be no stagnant water on it anywhere. On the other hand, a mosquito-drained marsh may not be sufficiently drained for the production of maximum crops. In the mosquito work we are looking only to removing the excess of water and not to supplying water where there is none. A perfectly dry, high marsh area is untouched in the mosquito work, though it may be altogether too dry to produce the best grass crop.

Therefore, while the effect of the work now in progress will be the material improvement of all the salt-marsh area treated, it will not result in the greatest possible improvement of all the marsh.

It seems evident from what has already been accomplished that a comprehensive plan of thorough drainage is not only feasible, but is economically advisable for a large proportion of these marsh lands which cover an area of over 296,000 acres in New Jersey. It is certain "that in the State of New Jersey there are at the present time thousands of acres of land capable of being put into shape to produce good, paying crops at a comparatively small outlay of money. The methods of doing this work are well known, have been sufficiently tried out, and are effective. The adoption of some scheme to secure this improvement will add at least $2,000,000 to taxable values within the State and should add at least $250,000 to the annual income of the owners of the lands."

In a publication of this Department[a] dealing with practical methods of reclaiming tide lands, Mr. J. O. Wright says of the importance and results of draining these lands:

> These waste places, rich in fertility and having an ample supply of moisture for plant growth, only need draining to enable heat and air to penetrate the ground to make them ideal locations for truck gardening on a large scale. Many of these are so situated as to offer economy in transportation which furnishes another important reason for their early reclamation. Either by rail or boat products can be landed cheaply and quickly in the market places of large cities or thriving towns at very little cost. This adds greatly to the commercial value of the land and allows for a much more liberal expenditure for its reclamation than could be borne if there had to be added to the cost of production the cost of a long-distance haul to market.
>
> About the only agricultural product grown on these lands in their native condition is marsh hay. This hay sells at present in the vicinity of Boston at $8 a ton. On areas which have been drained the hay sells for $25 a ton, and the yield per acre is larger than on the undrained tracts. The simplest form of improvement possible, therefore, increases the productive value of these lands threefold, but the greater part of the lands which have been reclaimed are too valuable for the growing of hay, and have been brought immediately into intensive cultivation. Cranberries are probably the most important crop at present grown on tide marshes. The area of cranberry bogs is being constantly extended and the trade in this fruit has assumed large proportions. Cranberry growing during the past two or three years has been quite profitable, and this has resulted in a marked activity in the extension of the area devoted to the crop and to the value of the lands reclaimed. Good bogs along the North Atlantic coast now sell for $1,000 an acre and pay a large return on this investment. The need of these marshes for truck farming is more apparent now than formerly because of the great increase in the number and population of some seaside resorts. Along Cape Cod and much of the Massachusetts coast the uplands have not the fertility needed for successful gardening. Much better results can be had from these marshes when drained than from the higher lands. In many places the

---

[a] U. S. Dept. Agr., Office of Expt. Stas. Rpt. 1906, pp. 373–379.

growing of fresh vegetables in the immediate vicinity of town, requires the reclamation of marshes, and they are proving well adapted to this use. Asparagus grows with unusual vigor in such soil, and in places near Boston excellent crops are being produced where the marshes are occasionally flooded with sea water. Celery does excellently in some localities, but has failed, for reasons not well understood, in others. Cauliflower, cabbage, onions, muskmelons and watermelons, cucumbers, lettuce, sweet corn, field corn, potatoes, oats, redtop, timothy, and alsike clover are all crops being successfully grown on reclaimed marsh lands along the North Atlantic coast; onions, celery, asparagus, cucumbers, and melons being the most profitable crops.

For many years the tide marshes of the South Atlantic coast were largely devoted to rice growing, and this is still the most important use of these areas, but changes in the flow of the rivers, which have taken place as the result of the removal of the forests and from other causes not so well understood, are bringing about a change in these lands, under which they are being more and more converted into truck farms. Asparagus, peas, potatoes, lettuce, beans, and cabbage are being raised in large quantities and shipped to the northern markets for sale early in the season. The products are of good quality, the business is proving profitable, and the area is being continually extended.

The drainage of swamp and marsh lands is a leading feature of the work of the drainage investigations of the Office of Experiment Stations of this Department, and the data already obtained in these investigations throw considerable light upon the cost of reclamation by drainage under various conditions, the causes of failures, and the best methods of procedure, and they have also attracted attention to the feasibility and advantages of such reclamation.

BERMUDA HAY.[a]

Some of the first experimental work begun by the Oklahoma Station was a series of grass-culture tests, which was subsequently extended into cooperative experiments with farmers throughout the State. The earlier results of this work[b] have shown that of the different grasses grown Bermuda grass alone possessed the requirements of a pasture grass for Oklahoma conditions, and more recent experience with this species also indicates its superior value for hay as compared with the wild grasses. The following brief report on the yield of Bermuda hay obtained at the station is of interest in this connection:

The 2½ acres of upland soil that was planted to hardy Bermuda grass on June 29 and 30, 1905, has been cut for the third time this season. The first cutting in the season of 1906 was made June 12. The total yield of cured hay from the field was 13,145 pounds, or at the rate of 5,658 pounds per acre. The second cutting for 1906 was made August 2. The rainfall from June 12 to the time of second cutting was 6.53 inches. Before the second crop was fully cured it began raining again and 5.36 inches of water fell on the hay before it was hauled in and weighed August 15. This thorough leaching reduced the weight materially, but the final weight of dry hay was 7,275 pounds from the 2½ acres, or 2,910 pounds to the acre. The third cutting was made September 18, and the hay cured without being rained upon. The total yield of cured hay for the field was 7,840 pounds, or at the rate of 3,136 pounds per acre.

---

[a] Compiled from Oklahoma Sta. Rpt. 1907, p. 21.

[b] For previous article on this subject see U. S. Dept. Agr., Farmers' Bul. 281, p. 10.

The total yield of hay per acre for the season was 11,704 pounas or 5.08 tons. Land of the very same nature adjoining this field does not produce over one-half ton of prairie hay of inferior quality. Bermuda hay contains twice as much digestible nutrients as the best of prairie hay, is much more palatable, free from stems and weeds, and in every way superior to hay made from wild grasses. It is time Oklahoma farmers were beginning to wake up to the possibilities of this remarkable grass, not only as a pasture grass but also as a hay crop.

PROTEIN CONTENT OF FORAGE CROPS.[a]

VARIATION IN PROTEIN CONTENT.

Forage crops differ not only in yield or the number of tons of fodder produced per acre, but also in feeding quality or the quantities of valuable nutrients they contain. A comparative study of a large number of our common forage crops from this view point is reported by Prof. H. Snyder of the Minnesota Experiment Station. This investigator calls attention to the fact that by the use of more concentrated nitrogenous forage the amounts of the higher-priced grains and mill products generally employed in feeding may be decreased and, in consequence, a material financial saving effected. One of the most important constituents of all feeding stuffs is protein, and the most indigestible, and therefore the least desirable, constituent is crude fiber. It follows, therefore, that an increase in the protein and a decrease in the crude fiber content of forage crops is of great importance and value.

The observation was made in these investigations that forage crops when grown on well cultivated, fertile lands often contained from 25 to 30 per cent more protein and a smaller amount of crude fiber than when grown on poor soils. It is pointed out that a ration is not necessarily valuable in proportion to the digestible protein it contains, but that the important problem is the determination of the right combination of protein and carbohydrates that is to be fed to stock. Ordinarily the protein of the ration is supplied largely by the grains and the carbohydrates by the coarse fodders. It is stated that average forage crops furnish less than half of the protein of a mixed ration, and it is believed that more attention should be given to the production of forage crops of maximum protein content in so far as this is under the control of the farmer mainly by means of the kind of crop grown, the fertility of the soil, and the composition and character of the seed.

---

[a] Compiled from Minnesota Sta. Bul. 101.

ALFALFA.

A comparison of analyses given shows the particularly high protein content of alfalfa, this being higher than that of clover and about twice as much as is found in timothy and prairie hay. Furthermore, alfalfa contains as much digestible protein as the average farm grains and mill products. Alfalfa also has the advantage of being cut at an earlier stage of growth than clover, which not only furnishes forage earlier in the season, but also tends to produce a fodder of a higher protein content.

CLOVER.

Clover is also one of the highest ranking protein producers among forage crops, and has the advantage that its culture is more familiar to farmers generally and that in many localities it is more easily grown than alfalfa. The number of cuttings, however, are in favor of the alfalfa crop when this is well established. Two crops of clover are usually produced each year, and the second is often considered the better for feeding purposes. Analyses given show that in the samples studied the second cutting contained a little more protein and less crude fiber than the first, and in samples from another crop the first cutting was found to contain 12.6 per cent, while those from the second contained 16.43 per cent of protein. It was observed that the maximum protein and usually the minimum fiber are produced on soils fairly well supplied with lime, available potash, and phosphoric acid, and that soils with the highest nitrogen content did not necessarily produce clover richest in protein. White clover is rich in protein and is in general a valuable plant, but when eaten in large amounts by horses it is said to often cause an abnormal flow of saliva, and is for this reason disliked by many horse owners.

An examination of many samples of alfalfa and clover seed of known purity and uniform ripeness showed that some seeds were dark brown in color and others lighter and of a yellowish tinge. Analyses of these dark brown and yellowish seeds showed in some instances a quite pronounced difference in protein content, amounting to more than 5 per cent in favor of the dark brown seeds, while in some samples the difference was less than 1 per cent. The dark brown seeds uniformly contained more protein than the light yellow seeds, and it is believed that as in wheat and corn glutenous and starchy kernels have a decided tendency to produce grains of the same type, so in the case of alfalfa and clover high protein seeds will produce crops of maximum protein content, and that therefore seed selection for the purpose of increasing the protein content may be practiced with these crops as well as with the cereals. The results obtained showed that the physical characteristics of the seed indicate in a measure their chemical composition and offer a means of selecting alfalfa and clover seeds of high or of low protein content. These investigations suggest that for seeding preference should be given to the darker colored seeds of high germinating power.

PEAS.

Pea hay constitutes a valuable forage rich in protein, but its comparatively difficult cutting and curing is probably the cause of its limited use. While peas show as much diversity in color, density, and general physical properties as any seeds, a close examination will show two general types—yellowish and green seeds. Both types consist of individual seeds either darker or lighter in color. In eight hand-picked samples, each representing a different variety selected on this color basis, the protein content was found to range from 19.15 to 31.74 per cent. The darker colored and harder seeds contained 3.74 per cent more protein than the light colored seeds, which were richer in starch. This difference in the type of seed, as in the case of alfalfa and clover, is considered a factor valuable in the production of more protein in the pea crop.

SOY BEANS.

Samples of soy beans selected in the same way as the samples of peas showed a difference in protein content of 6.27 per cent in favor of the high protein type. A mixture of corn fodder and soy beans containing a larger proportion of soy beans than of corn fodder showed a protein content of 14.87 per cent, or about as much as is found in clover hay. The soy beans alone contained 19.82 per cent and the corn alone 9.54 per cent of protein.

RAPE.

The rape plant was also studied in this connection, and it was found that plants grown on manured land contained 4.61 per cent more protein than those grown on unmanured land. The statement is made that under average conditions the dry matter of rape contains as much protein as clover. While the separation of rape seeds into high and low protein groups is difficult on account of the lighter colored immature seeds, it was found, however, that when special care was exercised in the removal of immature seeds it was possible to select glutenous and starchy ones with a difference of over 1 per cent of protein in favor of the glutenous type.

CORN FODDER.

No forage is more easily grown or affords a larger amount of nutrients per acre than corn fodder. In dry matter content it ranges between wide limits, containing sometimes as high as 90 per cent of water when very green and only 15 per cent when mature and field cured. The dry matter of corn fodder when produced under the most favorable conditions on well tilled and fertilized land contains from 8 to 9 per cent of crude protein. In the sample studied a difference of 3 to 4 per cent in protein content is found in favor of corn fodder grown on well tilled and manured land over that grown upon similar but unmanured land. Attention is called to the fact that corn silage is quite variable in composition, depending largely upon the character of the corn at the time it is put into the silo. The average silage contains about 75 per cent water and 25 per cent dry matter. The dry matter usually contains from 6 to 10 per cent of crude protein and about the same per cent of other nutrients as fresh corn fodder. A chemical analysis of a sample of corn smut showed that this substance is richer in proteid and nitrogenous matter than the corn itself. Corn stover or the stalks and leaves after the grain is removed contained 7.10 per cent of crude protein in samples of good quality and 5.02 per cent in samples of poor quality.

BROME GRASS.

Bromus inermis has about the same general composition in feeding value as timothy hay, but as the fiber and nonnitrogenous compounds increase rapidly in the later stages of growth it requires early cutting in order to secure the highest feeding value. The dry matter of fresh pasture grass is characterized by a high percentage of protein, but the amount of water in this grass is also very high, ranging from 85 to 90 per cent. In many localities the use of grass-seed mixtures consisting of clover, timothy, redtop, and other grasses has been found more satisfactory and profitable than seeding with just one grass alone. This mixed herbage has a high feeding value, particularly when 25 per cent of the grass-seed mixture is clover. A mixed hay crop containing clover and growing on a well-manured and well-tilled soil will contain from 10 to 12 per cent of crude protein, and this is forage of a high protein class. In addition to being of a high protein value, such a forage is a good mechanical mixture and affords a variety in the ration.

OTHER FORAGE PLANTS.

The forage crops of high protein content, as clover, alfalfa, peas, vetch, soy beans, and rape, in field-cured or air-dried condition usually contain from 12 to 20 per cent of crude protein; while those of medium protein content, as corn

fodder, timothy, millet, blue-grass hay, prairie hay, and *Bromus inermis*, contain from 5 to 11 per cent. Because of this wide range it is evident why so much stress is laid upon the importance of forage of high protein content and why there is a saving of grain and mill products when such forage is used in the feeding of live stock.

The forage obtained from millet, rye, timothy, prairie grasses, corn, *Bromus inermis*, and pasture and meadow mixtures are classified as forage of medium and low protein content. Analyses presented show that the dry matter of millet when the crop has been properly grown has as much protein as timothy hay or corn fodder, but that when produced under poor conditions its protein value is low. It is shown that rye fodder contains about the same amount of crude protein as the best grades of timothy at the same stage of growth. Analyses of samples of timothy hay presented show a range in protein from 5.11 to 9.10 per cent. It was further noted that in the use of timothy hay from soil highly fertilized with barnyard manure 25 per cent more protein and less fiber were obtained than from that grown upon poor soil. If grown under the best conditions, timothy hay may contain as high as 9 per cent of crude protein and then may be classed as forage of a medium high protein content, but if grown under poor conditions and on poor soil it may contain less than 5 per cent of crude protein or not more than is found in the best grades of straw. Bright, mediumly fine high-grade prairie hay is shown to contain nearly 9 per cent of protein and coarse low-grade, overripe and bleached samples less than 5 per cent.

WEEDS.

Analyses of 18 samples of the more common weeds showed that many of them withdraw large amounts of nitrogen from the soil. The large amount of protein in the dry matter was particularly noticeable in purslane, lamb's-quarters or pigweed, and cheese weed or mallow. It is stated that there is more protein in the dry matter of these weeds than in either alfalfa or clover, and it is suggested that it is advisable to keep a few sheep on every farm for utilizing and controlling the weed crop in order that under such a system the land may be reclaimed and the weeds utilized for both forage and green manure.

The foregoing facts suggest that by judicious selection and simple methods of improving forage crops with reference to protein content the feed bills now made up so largely of expenditures for costly concentrated feeds to supply the deficiencies of farm feeds in protein may be greatly reduced.

QUALITY IN WHEAT.[a]

Wheat growers are especially desirous of varieties which are resistant to disease and which give a large yield; millers are particularly interested in the yield and quality of flour, and bakers in the appearance and character of the goods which the flour produces.

In discussing the quality of wheat, one has to consider both the miller's and the baker's point of view. These two are often confused, and the term "milling quality" or "milling value" is sometimes employed in the same sense as "baking quality." The miller desires primarily a large yield of flour of good appearance, while the baker is not directly interested in the yield, but requires the flour to be of such appearance and strength as will suit his particular purposes. It might happen, therefore, that a sample of wheat of excellent milling quality might yield flour quite unsatisfactory to the consumer, and, on the other hand, a poor, somewhat shriveled sample of wheat might give a small yield of flour possessing admirable baking qualities.

In referring to flour, the terms "quality" and "strength" are often used as if they had the same significance, which is not strictly true. The term "strength" conveys a fairly definite idea, even though slightly different meanings may be attached to it at various times. "Quality," however, obviously signifies suitability for the purpose intended. A flour of high quality for pastry is a flour of low strength, whereas a flour of high quality for the production of very light bread or for mixing to improve the strength of weak flours must be of high strength.

Many tests designed to show quality have been devised, some of them simple and others very elaborate. In milling tests the weight of wheat per measured bushel and the percentage yield of flour of better grades are the important considerations. In baking tests the amount of water taken up by a given quantity of flour, the amount retained in the bread, the volume of the loaf, the form of crust, the texture and inside color of the loaf, the time of fermentation, and other similar factors are usually determined. With the data secured by such tests it is possible to so grade the flours that commercial requirements are met, for the majority of persons in purchasing bread disregard [illegible] nutritive value and digestibility and consider ap- [illegible]

[illegible] experiment stations in the United [illegible] composition, particularly protein content, as [illegible] milling quality of different varieties of wheat. [illegible] Virginia Experiment Station [illegible] which it was found that of a [illegible] the highest protein content, [illegible] 4.6 per cent, was found in [illegible] er, and Mediterranean also had high protein content, the values found being 16.80, 16.73, and 16.72 per cent, respectively. Turkey Red did not give good results at the Virginia Station.

---

[a] [illegible] 24; Minnesota Sta. Bul. 102; [illegible] p. 50; Canada Cent. Expt. Farm [illegible]

At the Colorado Station, W. H. Olin in reporting the results of a study of the comparative value of different varieties of wheat states that Defiance was found to be the best spring wheat and Turkey Red the best winter wheat for milling purposes. In this and many other reports of experiment station work the relative yield of different varieties and the weight per bushel are factors which are also taken into account.

C. E. Saunders, of the Central Experimental Farm, Ottawa, Canada, has reported an extended study of the baking quality of a large number of varieties of wheat, this work being of great importance in connection with the studies which are being carried on at the Dominion experimental farms with a view to breeding new varieties of high quality. The samples were ground in an experimental mill and classified according to their milling qualities. The flour was stored under uniform conditions and the baking tests were elaborate and carefully made.

Of the numerous varieties tested Red Fife stood first in the two years' work as regards baking strength, volume, and shape of loaf, Laurel ranking lowest the first year and Grant and Ebert the second year. The following varieties yielded flour of high strength in the second-year tests, which were more extended than those carried on the first year: Bobs, Chelsea, Marquis, Early Russian, Gatineau, Haynes Blue Stem, Outlook, Hungarian White, Red Fern, and White Fife C. Professor Saunders states that Colorado, Herisson Bearded, and White Russian were of rather low strength and therefore not suitable for the production of extremely light bread or for export to countries desiring strong flour.

Of the winter wheats, included in the second year's work, Dawson Golden Chaff was rather low in strength, but produced good bread of pale appearance and rather compact character. Padi wheat the author considers unworthy of general cultivation, particularly on account of the greenish-yellow color of the inside of the loaf. Reference is also made in the report to the characteristics of other varieties tested.

As regards the effect of storage on quality, it was found that flour stored a year improved in every respect, " taking up a large amount of water, retaining more, giving a loaf of larger volume and of better shape, crust, texture, and color. The behavior of the dough in the oven was most remarkable. While in the first tests, with a water absorption of 59 per cent, the dough had a tendency to fall after the twelve-months keeping, although the water was increased to 62 per cent. the dough had the ability to rise to a most remarkable degree when put into the oven. The sample of flour was kept for the twelve months under dry conditions in a glass-stoppered bottle. It would appear that this astonishing change in baking strength must have been due to an improvement in the quality of the gluten, as it could scarcely be explained on any other supposition."

The author does not consider appearance a trustworthy indication of quality. "There is no doubt some justification for the preference of bright samples of grain, that is, those which are free from blemishes, usually caused by frost or rain; but it is quite uncertain in many cases to what extent the actual quality of the interior of the kernal has been lowered when there is evidence of injury to the bran. It is often highly probable that the interior of the berry is in essentially perfect condition even though the bran may be dull and unattractive."

In this connection it is interesting to note that T. L. Lyons and A. Keyser report that "yellow berries," which are chiefly due to allowing wheat to become overripe and failure to stack the sheaves, had a lower gluten content, though lighter in weight, than the red normal kernels of the hard winter wheat studied at the Nebraska Station.

Contrary to the opinion of some other investigators, Professor Saunders found that two flours mixed in equal proportions gave results in baking tests which were a very close average for the varieties used.

In the principal tests which were carried on at the Central Experimental Farm the bread was uniformly made with a large proportion of yeast. To determine whether this factor influenced quality, additional tests were made under other conditions, but none of the variations introduced materially changed the rank of the different flours as already determined.

Professor Saunders also studied the quality of flour when baking powder was used instead of yeast.

> All the flours tested produced biscuits of about the same volume, and though they differed somewhat in character and considerably in color the differences were not so striking as those observed in bread. It appears that almost any flour will make tea biscuits of fair quality. The experiments show that the flours tested had sufficient strength of gluten to attain the necessary volume when the gluten had not been subjected to the prolonged influence of the yeast fermentation and when the quantity of gas evolved was not very large, for it must be borne in mind that even a well-made tea biscuit has a small volume compared with that of a very light loaf of bread produced from the same quantity of flour. In spite of the similarity in conduct of the various flours under the conditions just mentioned, it is clear that one is not justified in concluding either that the gluten of all flours is practically identical or that the volume of a light loaf of bread is determined primarily by the quantity

> of gas evolved. The making of ordinary tea biscuits can not be considered a test of the ability of gluten to withstand fermentation or of its power to retain a large quantity of gas produced inside the dough.

Two durum or, as they are often but less satisfactorily called, macaroni wheats were included among the varieties tested by Professor Saunders. The results which he obtained conclusively show, in his opinion, that the custom of regarding all such wheats as of one quality is absurd.

> While the ordinary Goose (or Wild Goose) can not be recommended for bread making, the Kubanka produced admirable bread, which, however, differs in some ways from that produced from most of the other wheats. The Kubanka dough must be made rather stiff in order that it may not be too sticky to handle conveniently. It rises very well, producing a large loaf of very fine texture and of good form. The crust is somewhat unusual, being of a rich brown color and having a tendency to be thin and tough. The inside color of the bread is quite yellow, but this gives an appearance of richness and can only be objected to on the grounds of prejudice. Taking all its characteristics into consideration, * * * the bread produced from this sample of wheat was of excellent quality.

These conclusions are in accord with similar work reported from a number of the experiment stations in the United States.[a]

In a recent bulletin of the Minnesota Station, Prof. H. Snyder reports experiments which show quite conclusively that not only the variety, but also the method of fertilizing, may be an important factor in determining the quality for bread-making purposes of the wheat produced. He made chemical analyses and milling and baking tests of 41 samples of flour milled from wheat grown upon fertilized and unfertilized plats at nine different places. In 30 of the 41 tests the fertilizer which gave the largest yields per acre produced wheats of the highest bread-making quality. It appears, however, that while both yield and bread-making quality are improved by the use of fertilizers they are not necessarily improved to the same extent by the same fertilizer.

> There appears to be no constant relationship between the percentage of protein in the grain and flour and the bread-making value, and while it is possible to increase the amount of proteids in flour by the use of nitrogenous fertilizers the bread-making value of the flour is not proportionately increased. In many istances the increase in nitrogen content imparts a negative value, as a part of the nitrogen is in nonproteid forms.
>
> The experiments taken as a whole show that not only the yield of wheat, but also the bread-making value, can be enhanced by increasing the fertility of the soil, and that there is a very close relationship between the amount of available plant food in the soil and the quality of the wheat produced upon the soil and its bread-making value.

---

[a] U. S. Dept. Agr., Farmers' Buls. 186, p. 6; 251, p. 14. See also U. S. Dept. Agr. Yearbook 1903, p. 329.

The importance of composition and digestibility of wheat flours and other cereal products, the value of such foods in the diet, and various questions concerned with bread and bread making have been considered in earlier Farmers' Bulletins of the Department.[a]

DOES IT PAY TO SPRAY POTATOES?[b]

As stated in a previous bulletin of this series[c] the New York State Experiment Station has in progress in cooperation with growers in different parts of the State a ten-year test of the profitableness of spraying potatoes as a protection against diseases and insect pests. During each of the five years that these tests have now been carried on, spraying with Bordeaux mixture and arsenicals has proved a useful and profitable practice. During the last of the five years reported upon to date, namely, 1906, the season "was in most parts of the State the least favorable of any of the five for the development of the principal potato disease, late blight and rot; yet in nearly all of the 80 tests reported spraying gave good returns for the money expended and labor applied."

The average net profit from spraying in 15 cooperative experiments carried out during the season of 1906 was $13.89 per acre, the net profit from similar experiments in 1905 being $20.04, in 1904 $24.86, and in 1903 $23.47.

"The highly favorable results obtained in the numerous experiments made by the station and by New York farmers during the past five years should stimulate potato growers to give spraying a trial. If it really is as profitable as these experiments indicate, they can not afford to neglect spraying."

The following recommendations regarding methods of spraying are made:

> In general, commence spraying when the plants are 6 to 8 inches high and repeat the treatment at intervals of ten to fourteen days in order to keep the plants well covered with Bordeaux throughout the season. During epidemics of blight it may be necessary to spray as often as once a week. Usually six applications will be required. The Bordeaux should contain 4 pounds of copper sulphate to each 50 gallons in the first two sprayings and 6 pounds to 50 gallons in subsequent sprayings. Whenever bugs or flea-beetles are plentiful add 1 to 2 pounds of Paris green or 2 quarts of arsenite of soda stock solution to the quantity of Bordeaux required to spray an acre.
>
> Thoroughness of application is to be desired at all times, but is especially important when flea-beetles are numerous or the weather favorable to blight. Using the same quantity of Bordeaux, frequent light applications are likely to be more effective than heavier applications made at long intervals; e. g., when

---

[a] U. S. Dept. Agr., Farmers' Buls. 112, 114, 192, 249. See also U. S. Dept. Agr. Yearbook 1903, p. 347.

[b] Compiled from New York State Sta. Bul. 290.

[c] U. S. Dept. Agr., Farmers' Bul. 251, p. 9.

> a horse sprayer carrying but one nozzle per row is used, it is better to go over the plants once a week than to make a double spraying once in two weeks. A good plan is to use one nozzle per row in the early sprayings and two nozzles per row in the later ones.
>
> Those who wish to get along with three sprayings should postpone the first one until there is danger of injury from bugs or flea-beetles and then spray thoroughly with Bordeaux and poison. The other two sprayings should likewise be thorough and applied at such times as to keep the foliage protected as much as possible during the remainder of the season. Very satisfactory results may be obtained from three thorough sprayings.
>
> A single spraying is better than none and will usually be profitable, but more are better. Spraying may prove highly profitable even though the blight is only partially prevented. It is unsafe to postpone spraying until blight appears. Except, perhaps, on small areas, it does not pay to apply poison alone for bugs. When it is necessary to fight insects use Bordeaux mixture and poison together.

The previous note on this subject referred to at the beginning of this article suggests that in order to secure economical and efficient spraying the growers might arrange for a "public sprayer," that is, some one man in a neighborhood who would make a business of spraying and would secure enough fields to keep him busy throughout the season.

USE OF ANESTHETICS IN FORCING PLANTS.[a]

Attention was called in a previous bulletin of this series[b] to the importance of controlling the dormant period of peaches, with special reference to preventing premature formation of buds and their subsequent destruction by frosts or freezing. Such control is now generally recognized as practicable with many plants and of value in their commercial production. Various means are employed to control the dormant period of plants, such as pruning, covering, attention to condition of growing wood in case of woody plants at the beginning of the period, and the like. In recent years attention has been turned to the use of anesthetics such as ether, chloroform, etc., for this purpose, especially with certain flowering and herbaceous plants. This method of treatment has been successfully practiced to some extent in Europe, but has not assumed commercial importance in this country.

Experiments by the Vermont Experiment Station with the use of ether in the forcing of rhubarb has been noted in a former bulletin of this series.[c] In a report of later experiments by this station along the same line, W. Stuart says:

> The use of anesthetics as an aid in the forcing of flowering shrubs, tuberous and bulbous plants, and herbaceous perennials, has not as yet assumed com-

---

[a] Compiled from Vermont Sta. Bul. 129; Rpt. 1906, p. 279.

[b] U. S. Dept. Agr., Farmers' Bul. 316, p. 6.

[c] U. S. Dept. Agr., Farmers' Bul. 233, p. 18.

mercial importance among growers in this country. In Germany and France, however, they are now used extensively in many of the large commercial establishments. Their use at the present time is almost wholly confined to flowering shrubs, such as lilacs, viburnums, deutzias, spireas, azaleas, etc., which lend themselves most readily to anesthetic influences. This class of plants come into bloom early in the spring, complete their growth at a comparatively early date, and then pass into a state of rest. Normally plants will not start into growth until they have entered into the latter part of the rest period. The largest measure of success, therefore, in the use of anesthetics must necessarily come from plants subjected to the influence of ether or chloroform during the earlier stages of rest.

The process of treatment is a comparatively simple one. Plants which are either dormant or are entering into the stage of dormancy are subjected to the vapor of ether or choloroform in an air-tight room or receptacle for from twenty-four to seventy-two hours, depending upon the earliness or lateness of the treatment and the temperature, the anesthetic being poured from above into an open vessel within the receptacle. The amount used per cubic foot of air space is largely governed by the temperature, moisture, season of year, and kind of plant to be treated. The higher the temperature and the later the season the more violent is the effect; hence the amount and time of exposure may be said to vary inversely with the temperature and the season when treatment is given. Apparently there is greater latitude in the amount that plants will stand than is currently believed. The action of chloroform is much more intense than that of ether, and only one-third to one-fourth the amount should be used.

The relative increase in earliness of blooming period of treated over untreated plants varies inversely to the earliness or lateness of the forcing period. It is claimed that growth is hastened about a month by treatment. The amount of bloom is considerably increased thereby, but on the average a gain of from ten to fifteen days is about all that may be expected.

As a result of his own experiments and of those of other investigators, Professor Stuart believes that "the anesthetization of flowering shrubs, such as lilacs, virburnums, azaleas, deutzias, spireas, etc., is a feasible and practical commercial enterprise for the florist." He found in his later experiments, as in the earlier, that etherization of rhubarb plants for winter forcing resulted in an increased yield, but that freezing of the rhubarb clumps at least early in the season, as is generally done in rhubarb forcing, is a necessary preliminary process, since etherization does not seem to perform the same function as freezing. He is of the opinion, however, that actual freezing may not be necessary for late forcing.

The action of ether on asparagus, potato tubers, apple, and palm seeds was also studied in the Vermont Station experiments.

There seems to be some evidence of a responsive action on the part of asparagus to ether, but the results secured thus far are so inconclusive as to preclude definite statement.

Dormant potato tubers were treated similarly as was the rhubarb, but in no case was there evidence of either beneficial or deleterious effect upon vegetation.

The etherization of apple seeds did not visibly accelerate germination; nor from the data now at hand is there likelihood that any beneficial results will accrue from the etherization of palm seeds.

The use of anesthetics would seem to have some promise of prac-cal value in the forcing of plants, especially as an aid in more com-etely controlling the period of maturing of the desired product, it undoubtedly many of the details of the practical applications of e method and the limits of its usefulness remain to be worked out.

FATTENING CATTLE FOR MARKET.[a]

In connection with extensive studies of problems concerned with ttening cattle for market, the Missouri Experiment Station has llected information from nearly 1,000 of the most successful cattle eders in Missouri, Iowa, and Illinois, which represents experiences tending over periods of nearly twenty years and with an aggregate approximately 2,000,000 cattle. The station has recently published digest of these data and the results of the numerous experiments a wide range of topics concerned with fattening cattle which have en carried on by the station.

In the opinion of Director H. J. Waters, who has compiled and ummarized this information, methods which are based on the expe-ence of successful men are in general satisfactory.

The practical man in the long run arrives at correct conclusions on the main ints involved in his practice. A theory that runs counter to the conclusions men of long experience or to the principles of a long established practice ould be well considered and should have the support of extensive and accu-te experimental data before being accepted.

The duration of the feeding period is a matter of great importance successful cattle feeding. As shown by the data collected from ractical feeders, the average length of the full feeding period was e hundred and seventy-seven days, or practically six months. ittle variation from this average was noted, and this factor seems be fairly well established.

In Missouri the weight of the steer returning the greatest profit as 1,345 pounds, in Iowa 1,358 pounds, in Illinois 1,390 pounds, and Nebraska 1,400 pounds, or on an average 1,367 pounds. In gen-al 1,500 to 1,600 pound steers have not been profitable.

Cattle were put on full feed at 2 years of age by 40 per cent of the eders and by 24 per cent at 2½ years of age.

Evidently the corn-belt cattle feeder is not yet making baby beef. This is e to the fact that older cattle feed more uniformly, finish in a shorter time, d with less attention to the details of feeding. Of even more importance rhaps is the fact that older cattle may be bought as feeders with enough ore margin than young cattle to make the feeding operation, on the whole, ore profitable. It is furthermore shown that aged cattle are in somewhat tter demand on the market, especially if somewhat underdone or of plain ality.

---

[a] Compiled from Missouri Sta. Bul. 76.

In the matter of the most favorable season for fattening cattle, the practical feeders consulted showed a decided preference for summer, or at least for some season other than winter. The experiments which Director Waters has summarized show that cattle gained much faster in summer than in winter and at about four-fifths the cost of winter feeding. It was also apparent that pigs following summer-fed cattle made better gains and that less labor is required for feeding, hauling manure, etc.

Gains are cheaply made on grass alone, but are low-priced, because the cattle are not in marketable condition and must be sold as feeders with sufficient margin to enable the buyer to fit them for market.

The season of the year affects the market demand of cattle. Certain weights and classes are required for certain seasons, while other weights and classes will meet the best demand at other seasons. The steer that is staple the year round is the thick-fleshed native, weighing from 1,200 to 1,400 pounds. This class answers the demand of the dressed beef, the live export, the dead export, and the eastern shipper trade. Or, all classes of buyers use a greater or less number of these cattle throughout the year, making them staple at steady prices.

Yearlings weighing 900 to 1,100 pounds when well finished and not offered in too large numbers find a steady market and a good demand throughout the year. When plain in quality, or somewhat underdone, or when a little oversupplied, the price declines sharply, because this class has a more limited use than the dressed beef steer just described.

Three-year-old cattle weighing 1,500 to 1,600 pounds find a good demand for hotel and resort trade the year round if not offered in too large numbers. The demand is better one year with another from the latter part of the summer to the 1st of December than at any other time for this class of cattle. They do not need to carry so much quality or finish as yearlings or even dressed beef steers to sell at the highest price for their class.

A great variety of opinions were expressed as to the value of roughage in full feeding, though in general the data collected show that feeders were indifferent as to the kind or quality of this part of the ration. Experiments conducted at the Missouri Station show that coarse fodder decidedly affects the rate and cost of gain and the finish of the cattle. It has been found that with cattle bringing 5 cents a pound corn combined with clover hay and cowpea hay was worth 8.25 cents more per pushel than when combined with timothy.

A large roughness consumption does not necessarily mean a diminished grain consumption. If the roughness be a legume hay, such as clover, or cowpeas, or alfalfa, the amount consumed will be materially larger than when it is timothy, or corn stover, or prairie hay, or millet, and at the same time the cattle will eat a larger amount of grain. The extra amount of protein in the legume hay has the effect of stimulating a larger total consumption of feed, a considerable portion of which is grain.

As regards the value of shelter in full feeding, it is shown, as a result of four years' experimental work, that steers on full feed gain more rapidly and somewhat more economically when having access to an open shed, or even when confined in an open lot, than when sheltered in a well ventilated barn.

There is a direct relation between the quality and condition of the feed and the ease and readiness with which cattle may be accustomed to it. Cattle may be gotten on full feed more quickly when coarse and relatively unpalatable material is used than when highly nutritious and well prepared feeds are used. * * *

The amount of margin required to cover the expense of fattening and pay a profit is governed by a variety of circumstances. Younger cattle require a smaller margin than older cattle, because they make cheaper gains. Short fed cattle a smaller margin than long fed cattle, because the costs of gains is higher the longer cattle are on feed. Cattle of high quality require a narrower margin than cattle of poor quality because of the higher price at which they sell when finished. A larger margin is required in winter than in summer, because, it requires more feed to make a pound of gain. The higher the price of feed, the larger the margin required, unless the price of finished cattle has correspondingly increased.

The farmers interviewed reported an average margin of $1.02 per hundred for a six months feed on 2-year-old cattle in the summer. It is estimated that for a similar feed in winter approximately $1.50 would be required.

It was apparent from the data collected that the average feeder gives comparatively little attention to the preparation of feed. About one-half of the feeders in Missouri, Illinois, and Iowa use ear corn exclusively, and if the feeders are included who use ear corn for part of the fattening period the proportion is much larger. Considering the data as a whole, shelled corn was fed dry either exclusively or at some season of the year by about 25 per cent of the feeders and corn-and-cob meal and ground shelled corn by less than 10 per cent on an average. A large number of the feeders made more effort to supply well prepared feed at the end of the fattening period than at the beginning or middle, with the object of maintaining satisfactory gains, as the feeding progressed, by catering to the appetite.

At this time the system is loaded with fat and the maintenance cost per steer is very high; at the same time the appetite is variable and is disposed to decline. Anything, therefore, that tends to increase the amount of food consumed will affect favorably the rate and cost of gain.

Better preparation is required in summer than in winter feeding, because the grass in summer is more palatable than the roughage used in winter, and for a large enough consumption of grain to produce a profitable gain it is required that the grain be palatable. Moreover, grain in summer is dry, hard, and more difficult to masticate, and is liable to have been somewhat fouled by mice and rats. These difficulties are in practice usually overcome by soaking the corn from twelve to eighteen hours.

Better preparation of grain is required for young cattle than for aged animals, in order to stimulate the most rapid possible gain. This is necessary to finish the younger animals within a reasonable time. They use so large a proportion of their food for growth that a high rate of gain is necessary to make them fat quickly.

The real reason for preparing grain for cattle is not to reduce the proportion of grain passing through the animal undigested, but rather to increase the rate of gain. This is so because whatever part of the grain the steer fails to utilize the hogs which follow the cattle will utilize to good advantage.

The feeder is interested primarily in the aggregate gain of steer and hog per unit of grain fed, and can not afford, under the ordinary farm conditions, to invest much labor and money in the preparation of feed which increases the steer gains wholly or mainly at the expense of the hog gains. So long as the food is offered in palatable enough form to make the steer gain at a rapid rate and make him fat in a reasonable time, the feeder is not interested in how much passes through the steer unmasticated or undigested, because the hog will make good use of it.

Taking the average price of all fat hogs and all the fat steers sold on the Chicago market for the past twenty-four years, it has been found that the hogs have brought a higher price per pound. It will be accepted without argument that less food is required to make a pound of gain on hogs than on cattle. As a rule, therefore, the hog end of the cattle feeding operation is more profitable than the cattle end.

The number of hogs required to utilize the waste per steer will vary greatly with the character of the feed, the way in which it is prepared, and with the size and age of the cattle. The range would be * * * at the rate of two to three hogs per steer on snapped ear corn, perhaps one and one-half on husked ear corn, about one on shelled corn, and from one-third to one-half a hog on crushed or ground corn.

Whatever factors favor rapid and profitable gains on cattle, excepting the better preparation of the feed, are liable to be favorable to the hog that follows. For example, hogs make better gains following cattle fed on clover or cowpea or alfalfa roughness with corn than they do when the roughness is timothy, millet, or sorghum. Likewise there is a material benefit to the hog by feeding the steer a limited amount of linseed meal. There is also a benefit to the hog from feeding cotton-seed meal to the steer, although it is less marked than when linseed meal is used.

It is almost as profitable to use a supplemental feed like tankage or linseed meal for hogs that are following cattle as for those that are being fed on fresh grain. Especially is this true of hogs following cattle fed on straight corn with timothy or stover for roughness in winter or blue grass or timothy pasture in summer. Likewise a clover, alfalfa, cowpea, or soja-bean pasture for hogs following cattle will affect just as favorably the profits as though the hogs were not following cattle. In view of the fact that a considerable part of the profit of steer feeding is in the hog gains, it is important that most careful attention be given to the hogs, in order that the maximum gain may be secured.

An abundant supply of pure water convenient to the feeding bunks and to the grazing grounds is absolutely imperative. It is fatal to good results to require the cattle to travel long distances to water or to drink from pools or troughs that are befouled by hogs or other stock. A steer on full feed and under the strain of rapid production requires a large quantity of water daily.

Cattle that are being fattened should be fed with the utmost regularity, should be kept as quiet as possible, and should be encouraged to lie down when not eating. They should never be frightened or disturbed in any way.

Changes in feed, location, or surroundings of cattle that are fat should never be made, except such as are decidedly for the better, and even then should be made only when most imperative.

COTTON-SEED MEAL AND CORN SILAGE FOR DAIRY COWS.[a]

John Michels and J. M. Burgess, of the South Carolina Station, state that " there is a prevailing belief that when cotton-seed meal is fed for long periods in quantities exceeding 4 pounds per cow daily the health of the animals will be more or less injuriously affected," but in a series of experiments which they report it was found that cotton-seed meal may be fed in conjunction with good corn silage to the extent of from 5 to 6 pounds per cow daily without affecting the health of the animals. Indeed such a ration appeared to keep the cows in an unusually good state of health. A ration consisting of cotton-seed meal and good corn silage was consumed by the cows with great relish, which was in no way lessened when the feeding of such a ration was continued for a period of five months.

---

[a] Compiled from South Carolina Sta. Bul. 131.

> No bad effects were noticeable from the practice of feeding cotton-seed meal and corn silage separately. On the contrary, such a practice appears to have distinct advantages over the common practice of mixing the meal with the roughage. Our results, therefore, tend to disprove the prevailing belief that heavy concentrates like cotton-seed meal will act detrimentally on the health of cows when fed unmixed with more bulky feeds.
>
> Cows fed exclusively on cotton-seed meal and corn silage for a period of five months exhibited no craving for dry roughage, but always preferred silage to good hay.
>
> According to the herd records, the cows yielded more milk and butter fat during this experiment than during any corresponding period in previous years. Cotton-seed meal and rich, well matured corn silage constitute an excellent ration for cows yielding from 20 to 30 pounds of milk daily.

These results are of special importance because cotton-seed meal and corn silage form by far the cheapest dairy feeds available to dairymen in South Carolina and elsewhere in the South. It is stated that the cost of such a ration is only slightly more than half that of the common dairy ration now fed in the State.

The good results obtained in these experiments in the exclusive feeding of cotton-seed meal and corn silage as a dairy ration was attributed largely to the fact that the corn silage was made from well matured corn rich in grain, making it especially rich in carbohydrates, for it is explained that unless silage is especially rich in grain a ration consisting entirely of corn silage and cotton-seed meal will be deficient in nonnitrogenous matter (carbohydrates).

It is believed that " with cotton-seed meal furnishing an unusually cheap protein supply, and with the great yields of corn possible in this State * * * milk can be produced as cheaply, if not more cheaply, in South Carolina than in any other portion of the world."

CARBONATED MILK.[a]

L. L. Van Slyke and A. W. Bosworth, of the New York State Station, report that in making a study of the chemical changes which occur in koumiss made from cows' milk it was noticed that lactic acid formed much more slowly in the koumiss than in ordinary milk. This was found to be due to the action of carbon-dioxid gas under pressure.

---

[a] Compiled from New York State Sta. Bul. 202.

A series of experiments was therefore undertaken to ascertain the effect of carbon dioxid under different pressures upon the development of lactic acid in milk. These experiments were made with (1) fresh separator skim milk, (2) fresh whole milk drawn and handled under good hygienic conditions, (3) fresh skim milk pasteurized at 185° F., and (4) fresh whole milk pasteurized at 185° F.

The best results were secured when newly pasteurized milk or cleanly drawn fresh milk was treated with carbon dioxid in a tank, such as is used in bottling establishments in preparing carbonated drinks, and then placed in siphon bottles. When charged under pressures of from 70 to 75 pounds and kept at temperatures ranging from 35° to 60°, bottles of clean fresh milk or pasteurized milk kept from four to five months without perceptible increase in acidity.

Milk carbonated under a pressure of 70 pounds comes from the bottle as a foamy mass, more or less like koumiss that is two or three days old. It has a slightly acid, pleasant flavor, due to the carbon dioxid, and has a somewhat more salty taste than ordinary milk. In the case of carbonated milk pasteurized at 185° F., there is, of course, something of a "cooked" taste. Though the cream separates in the bottle, it is thoroughly remixed by a little shaking as the milk comes from the bottle, and there is no appearance of separate particles of cream. All who have had occasion to test the quality of carbonated milk as a beverage agree in regarding it is a pleasant drink. In the case of milk bottled under a pressure of 150 pounds of carbon dioxid, the milk delivered from the siphon is about the consistency of whipped cream, but, on standing a short time it changes into a readily drinkable condition.

Carbonated milk furnishes a pleasant beverage, and it is suggested that it may find practical use as a healthful drink and as a valuable food for invalids and children in cases where ordinary milk does not digest well.

It is pointed out that in order to prepare carbonated milk successfully "the milk should be drawn so as to be as free as possible from dirt, and promptly cooled below 45° F. It should be carbonated within a few hours. All the vessels with which the milk comes in contact, from milking to bottling, should be carefully sterilized before use. In case milk can not be carbonated quite promptly after drawing, it should be thoroughly pasteurized before being charged and bottled."

PRESERVATION OF FENCE POSTS.[a]

As H. F. Weiss in a recent circular of the Forest Service of this Department points out, it is each year becoming more difficult to secure satisfactory fence posts, and since substitutes such as reen-forced concrete and iron are probably too costly to compete with wooden posts, the only solution of the difficulty lies in the use of cheaper woods and in preventing decay by preservative treatment.

---

[a] Compiled from Wyoming Sta. Bul. 75; Rpt. 1897, p. 29; U. S. Dept. Agr., Forest Service Circ. 117.

A great variety of preservative treatments have been tried with varying success. B. C. Buffum, of the Wyoming Experiment Station, reports that he has been able to preserve pitch-pine posts with but little injury for sixteen years by dipping the lower ends of the posts in crude petroleum to a sufficient distance to come above the ground line when the posts are set, and burning off the oil. He states that " this dipping can be done very cheaply and will undoubtedly pay. A second method is to simply dip 2½ feet of the bottom of the posts in crude petroleum or in tar; this did fairly well. The oil seemed a better protection to the posts than did the coal tar. Posts that were well charred by burning came in about third place. * * *

There is little advantage to be gained by simply oiling or tarring a band to protect the post from dry rot where it comes through the ground, and less from any treatment of only a portion below the ground. Such oil band helped preserve the post, but the time taken to apply the oil in this manner would make it more expensive than dipping the entire lower end of the post.

The Forest Service has made a very careful study of the subject of preservation of posts, and has obtained the most satisfactory results on the whole with the creosote treatment. The chief merit of this treatment is that it renders inferior woods as serviceable as those of better quality, thus saving the latter for other purposes and aiding in conserving the rapidly diminishing supply of the more valuable woods.

The process of treatment with creosote has been greatly cheapened by what is known as the "open-tank" method introduced by the Forest Service. It is stated that the necessary equipment for this treatment can be installed at a cost of from $30 to $45, or for much less if an old boiler is used. The essential requirements are that the creosote shall be heated to about 215° F. and that the butts of the posts shall be submerged up to about 6 inches above their ground line. A tank with a bottom 12 square feet in area has been found of sufficient size for treating forty to fifty 6-inch posts a day, or double that number when two runs per day can be made, as is possible with lodgepole pine posts. The amount of creosote absorbed was found in the Forest Service experiments to vary from one-tenth gallon with Eucalyptus posts to seven-tenths gallon with sycamore, cottonwood, and lodgepole pine. At the time these experiments were made the price of creosote varied from 10 cents per gallon in the East and Middle West to 27 cents per gallon in the Rocky Mountain States, and was about 16 cents per gallon on the Pacific coast. On the basis of these figures it is estimated that the cost of treating a post varied from 4 to 15 cents.

In experiments with the preservative treatment in Idaho it was found that the durability of lodgepole pine posts was increased sixteen years. On this basis, and notwithstanding the high price of creosote in Idaho, it is estimated that by treating the posts there was a saving with interest at 6 per cent of 2 cents per post yearly. It is pointed out that since the resistance of all treated posts to decay is alike regardless of the kind of wood only the cheaper kinds of woods should be used for posts, and, further, that as sapwood is more readily impregnated with creosote than heartwood, posts containing much sapwood are to be preferred to those which are largely of heartwood. It is quite important that the posts should be air dry before they are treated or set. "They should be cut at least a month before treatment. Wood dries fastest in spring or summer, but with those species which check badly, such as the oaks, cutting is best done in autumn or early winter."

Both the inner and outer bark should be completely removed before treatment. Round posts are, as a rule, preferable to split posts.

If butt treatments in the open tank can not be given, and yet some preservative method is desired, plunge the butts of the posts into a vessel of hot creosote or carbolineum or apply either liquid with a brush. A long bath in hot creosote, followed by a shorter one in cold creosote, will probably give best results. Usually woods with a porous structure, like the poplars, can be treated more easily than dense woods, like the oaks, and hence need not be left in the creosote for so long a time.

The tops of posts should be cut slanting, preferably with an axe, so that the rain will not remain on them. If cut with a saw the pitch should be greater.

Setting posts small end downward has no effect in checking decay.

There is some advantage from piling stones around the base of the posts or setting them in masonry or concrete, but not enough to justify the cost.

Charring the butt of the post, if properly done, gives good results. The posts in this case should be thoroughly dry and the charring should extend at least 6 inches above the ground line.

Soaking posts in solutions of copper sulphate or mercuric chlorid is not considered a practical method of treatment.

Good results, particularly with soft woods like sycamore and cottonwood, have sometimes been obtained by boring holes diagonally into the posts just above the ground line and filling them with some preservative solution, such as various forms of coal tar, but it should be borne in mind that the posts are weakened by the boring of such holes.

O

Issued April 18, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 321.

THE USE OF THE SPLIT-LOG DRAG ON EARTH ROADS.

BY

D. WARD KING.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL.

U. S. DEPARTMENT OF AGRICULTURE,
OFFICE OF PUBLIC ROADS.
Washington, D. C., March 17, 1908.

SIR: I have the honor to transmit herewith a manuscript by Mr. D. Ward King, an expert in this Office on the split-log drag, which gives directions for the construction of the split-log drag and its use on earth roads. It contains information which will be of practical value to a large number of readers, and I therefore respectfully recommend that it be published as a Farmers' Bulletin.

Respectfully,

LOGAN WALLER PAGE,
Director.

Hon. JAMES WILSON,
Secretary of Agriculture.

CONTENTS.

	Page.
Introduction	5
The construction of a split-log drag	5
How to use a drag	9
When to use a drag	10
Use of a drag on rocky or gravelly roads	11
Cost data	11
Construction and use of a ditch cleaner	13
Conclusion	14

ILLUSTRATIONS.

		Page
Fig. 1.	Plan and elevation of split-log drag	6
2.	Perspective view of split-log drag	7
3.	Plan, front and side views of plank drag	8
4.	Perspective view of plank drag	9
5.	Plan of plank ditch cleaner	13

THE USE OF THE SPLIT-LOG DRAG ON EARTH ROADS.

INTRODUCTION.

The earth road is by far the most common type of highway in this country. Its cheapness in comparison with other types of construction and the absence in many sections of the country of rock, gravel, or other hard natural materials for road building will render its use necessary for many years to come.

There are at present in this country about 2,000,000 miles of such roads, most of which must be maintained by some means more or less inexpensive. The split-log drag is of great service on roads of this class, and an increasing mileage of the rural highways of this country is being kept in repair economically and well by the use of this simple implement. It is now in use in many States of the Union and in foreign countries also, and its adoption in most localities where there are earth roads will doubtless increase.

The aim in writing this bulletin has been to give a concise description of the construction of the split-log drag and the method of using it which will give the best results. The ditch cleaner, another useful implement for use on earth roads, has also been briefly described.

THE CONSTRUCTION OF A SPLIT-LOG DRAG.

The author has experimented with a great variety of devices for road dragging, but has found the two-slab log or plank drag with liberal "set back" the most satisfactory. Double drags for working both sides of the roadway simultaneously have been tried with only limited success. The reason for this lies in the fact that both sides of an earth road are never exactly alike. This causes the two parts of the drag to work unevenly and to interfere with each other. It is also impossible for one man to operate both parts successfully, as will be shown later on.

Two mistakes are commonly made in constructing a drag. The first lies in making it too heavy. It should be so light that one man can easily lift it. Besides, a light drag responds more readily to various methods of hitching and to the shifting of the position and weight of the operator, both of which are essential considerations and are discussed more fully under the head "How to use a drag" (p. 9). A drag can be made heavier at any time by proper weighting.

The other mistake is in the use of squared timbers, instead of those with sharp edges, whereby the cutting effect of sharp edges is lost and the drag is permitted to glide over instead of to equalize the irregularities in the surface of the road. These mistakes are due partly to badly drawn illustrations and plans of drags which have occasionally appeared in newspapers and partly to the erroneous idea that it is necessary that a large amount of earth shall be moved at one time.

A dry red cedar log is the best material for a drag. Red elm and walnut when thoroughly dried are excellent, and box elder, soft maple, or even willow are preferable to oak, hickory, or ash.

The log should be 7 or 8 feet long and from 10 to 12 inches in diameter, and carefully split down the middle. The heaviest and best slab should be selected for the front. At a point on this front slab 4 inches from the end that is to be at the middle of the road locate the center of the hole to receive a cross stake and 22 inches from the other end of the front slab locate the center for another cross stake. The hole for the middle stake will lie on a line connecting and halfway between the other two. See figure 1. The back slab should now be placed in position behind the other. From the end which is to be at the middle of the road measure 20 inches for the center of the cross stake, and 6 inches from the other end locate the center of the outside stake. Find the center of the middle hole as before. When these holes are brought opposite each other, one end of the back slab will lie 16 inches nearer the center of the roadway than the front one, giving what is known as "set back." The holes should be 2 inches in neter. Care must be taken to hold the auger plumb in boring



FIG. 1.—Plan and elevation of split-log drag.

these holes in order that the stakes shall fit properly. The hole to receive the forward end of the chain should be bored at the same time.

The two slabs should be held 30 inches apart by the stakes. Straight-grained timber should be selected for the stakes, so that each stake shall fit snugly into the 2-inch hole when the two slabs are in the proper position. The stakes should taper gradually toward the ends. There should be no shoulder at the point where the stakes enter the slab. The stakes should be fastened in place by wedges only.

When the stakes have been placed in position and tightly wedged, a brace 2 inches thick and 4 inches wide should be placed diagonally to them at the ditch end, as shown in figure 1. The brace should be dropped on the front slab, so that its lower edge shall lie within an inch of the ground, while the other end should rest in the angle between the slab and the end stake.



FIG. 2.—Perspective view of split-log drag.

A strip of iron about 3½ feet long, 3 or 4 inches wide and ¼ of an inch thick may be used for the blade. This should be attached to the front slab, so that it will be one-half inch below the lower edge of the slab at the ditch end, while the end of the iron toward the middle of the road should be flush with the edge of the slab. The bolts holding the blade in place should have flat heads and the holes to receive them should be countersunk.

If the face of the log stands plumb it is well to wedge out the lower edge of the blade with a three-cornered strip of wood to give it a set like the bit of a plane.

A platform of inch boards held together by three cleats should be placed on the stakes between the slabs. These boards should be spaced at least an inch apart to allow any earth that may heap up and fall over the front slab to sift through upon the road again. The end cleats should be placed so that they will not rest upon tl cross stakes, but drop inside them, while the middle cleat can be shifted to either side of the middle stake. These cleats should extend about an inch beyond the finished width of the platform.

An ordinary trace chain is strong enough to draw the implement, provided the clevis is not fastened through a link. The chain should be wrapped around the rear stake, then passed over the front slab. Raising the chain at this end of the slab allows the earth to drift past the face of the drag. The other end of the chain should be passed through the hole in the end of the slab and is held by a pin passed through a link. One and one-half trace chains are sufficient.

In many logs the grain runs around the tree in such a way that when split the slabs will be in a "wind." If this wind is not more



FIG. 3.—Plan, front and side views of plank drag.

than 4 inches in 8 feet, the timber can be used to good advantage by setting it so that the blade end of the log shall slant forward when the other end [illegible] The construction of the drag in this case [illegible] must be taken that the holes [illegible] edging under the lower [illegible] og.

[illegible] stead of logs. There is [illegible] that calls for particular [illegible] anks along their middle [illegible] 3. A triangular strip [illegible] ade to give it the proper [illegible]

HOW TO USE A DRAG.

The successful operation of a drag involves two principles, which when thoroughly understood and intelligently applied, make road working with this implement very simple. The first concerns the length and position of the hitch, while the second deals with the position of the driver on the drag. Each influences the other to a large extent, and successful manipulation of the drag is dependent upon an understanding of both of them.

For ordinary purposes the snatch link or clevis should be fastened far enough toward the blade end of the chain to force the unloaded drag to follow the team at an angle of 45 degrees. This will cause the earth to move along the face of the drag smoothly and will give comparatively light draft to the team, provided the driver rides in the line of draft. Sometimes, however, conditions are met which require special treatment, and in a rolling country such conditions are not infrequent. Often a flat place several rods in length or a seepy spot needs special attention.



Fig. 4.—Perspective view of plank drag.

The distance from the drag at which the team is hitched affects the depth of the cutting. Shortening the chain tends to lift the front slab from the ground; a longer hitch causes the blade to cut more deeply. The length of hitch may be regulated by lengthening and shortening the chain at the end which runs through the hole in the blade end of the drag.

If small weeds are to be cut or a furrow of earth is to be moved, the doubletree should be attached rather close to the ditch end of the drag. The drag will now move nearly ditch end foremost, and the driver should stand with one foot on the extreme forward end of the front slab. This will swing the drag back to the proper angle and will cause the blade to plow. This hitch requires slow and careful driving in order to prevent the drag from tipping forward. If the blade should plow too deeply, as it may do in a wet spot, the driver should shift his weight toward the back slab.

If straw and weeds clog the blade, they can usually be removed if the driver shifts his weight to a point as far as possible from the ditch or blade end. Similarly, if he steps quickly away from the ditch end, the load of earth may be dropped into a low place or mudhole.

Some attention should be given to the edge of the blade. In the beginning, the average earth road requires no steel plate on the drag, though the drag will be better preserved if the steel is applied at first. At the end of a year's work, if the dragging has been faithfully done, a steel plate will be needed. If the twist of the log is properly used, or the three-cornered strip of wood is placed under the blade as described on page 7, a flat piece of steel will answer. In case the blade stands perpendicularly it should be slightly cupped when sharpened.

Usually two horses are enough to pull a drag over an ordinary earth road. When four horses are used, they should be hitched to the drag by means of a four-horse evener. The team should be driven with one horse on either side of the right-hand wheel track or rut the full length of the portion to be dragged, and the return made over the other half of the roadway.

The object of such treatment is to move earth toward the center of the roadway [illegible] gradually above the surrounding level. While this [illegible] accomplished, all mudholes and ruts will be filled, [illegible]

[illegible] DRAG.

[illegible] is moist, but not sticky. [illegible] faces of the slabs. If the [illegible] holes, it may be well to use [illegible]. This treatment is particu- [illegible] winter when it is possible to have [illegible]

A smooth road surface is secured by this method. Clay, when mixed with water and thoroughly worked, becomes remarkably tough and impervious to water. If compacted in this condition it becomes extremely hard.

Another valuable result of dragging is the reduction of dust, for the particles of clay cohere so tenaciously that there is but little wear when the surface is smooth. Dust on an earth road is due to the breaking up under traffic of the frayed and upturned edges of ruts and hoof prints. If the surface is smoothed after each rain and the road dries hard and even, no edges are exposed to crushing and the only dust which forms is that due to actual wear of the road surface.

There are so many influences at work and conditions are so varied in different localities that it is quite impossible to lay down a general rule for the number of treatments needed to keep a road in good condition. A tough clay or a stiff sandy clay will resist the action of wheels and hoofs for a longer period than a loam, other things being equal. Certain sections of a roadway will require more attention than others because of steep grades, seepage, exposure to hillside wash, etc. The best guide in meeting these conditions is the knowledge and experience gained while dragging the roadway.

There is one condition, however, in which special treatment should be given to a road. Clay hills under persistent dragging frequently become too high in the center. To correct this it is best to drag the earth toward the center of the road twice and away from it once.

USE OF A DRAG ON ROCKY OR GRAVELLY ROADS.

In soils full of loose stones or even small bowlders the drag has done good service. The loose stones are drawn into a windrow down the center of the road while the earth is deposited around the bowlders in such a way that the surface is leveled. The loose stones in the center of the road should of course be removed. Where there is a large proportion of small stones or gravel the drag will keep down the inequalities in the surface.

COST DATA.

There is little available data on the cost of maintenance of earth roads by dragging. However, there is no doubt as to the economy of the drag, either in first cost or in its operation. The most elaborate form will cost but a few dollars for material and labor, while one man and team can operate it successfully under all usual conditions. As a consequence, the statements given below are well within reason and indicate what may be accomplished with a very small outlay.

The following figures show the cost of maintaining ordinary country roads per mile per year without a drag, and may be taken as a of the cost of such maintenance. They were obtained in Kansas by Prof. W. C. Hoad, of the University of Kansas, in 1906, and were taken from the official records of the counties:

Crawford County	$52
Douglas County	38
Franklin County	34
Johnson County	48
Neosho County	40
Saline County	43

The average cost is $42.50 per mile per year, and it may safely be said that the cost of dragging would be trifling in comparison.

Mr. F. P. Sanborn[a] states: "The least expense per mile [for dragging] was about $1.50; the greatest a little over $6; the average expense per mile for 5½ miles a little less than $3." Commenting further, Mr. Sanborn declares: "The writer has lived by this piece of road all his life, and although we have had the extremes of weather this season, both wet and dry, not for forty years has the road in question been so free from mud and dust. Parties who have known the road all their lives are agreed that it never was in so good condition a season through."

When Mr. R. H. Aishton, general manager of the Chicago and Northwestern Railroad, investigated the work of the split-log drag at Sac City, Iowa, preliminary to the campaign inaugurated by that company in 1905, he learned that one township had experimented with the drag on 28 miles of highway, for a year. He found that the township paid for the making of the drags and hired men to use them, including the original cost of the drags when figuring the expense of the year's work. The total expense for the twelve months averaged $2.40 per mile, and the roads were reported to have been "like a race track" the larger portion of the year.

A neighborhood of farmers in Ray County, Mo., employed one of their number to drag a 5-mile stretch. He received compensation at the rate of $3 per day. When the end of the year came and a settlement was made, the cost for the year was found to be $1.66 per mile. The road is a tough clay and my informant declares it was always much better than the other roads in the neighborhood.

Prof. William Robertson, of the Minnesota Agricultural Station, after a year's experience in dragging a "main road made entirely of gumbo without any sand or gravel, and which during the past year has shown no defects either by rutting or development of soft places," fixes the cost of the work at not to exceed $5 per mile.

---

[a] Report of Highway Commissioner of Maine, 1906, p. 112.

CONSTRUCTION AND USE OF A DITCH CLEANER.

The ditcher or ditch cleaner is a convenient device for clearing ditches. It consists of a guide plank, 2 inches by 12 inches by 12 feet, and a mold board, 2 inches by 12 inches by 8 feet. These are braced with a crosspiece 3 feet long as shown in figure 5. The mold board should be shod with an iron plate ¼ inch by 4 inches by 3 feet, held in position with ⅜-inch bolts countersunk. The cross brace should be hollowed 3 inches on each side at the middle, the hollowing to begin not less than 4 inches from each end, in order that its bearing against the guide and mold board planks shall not be shortened, nor the nailing space decreased. This is done to prevent earth from heaping up in front of the brace. A light platform is needed to make the use of the ditcher safe.



FIG. 5.—Plan of plank ditch cleaner.

The hitch is made as shown in figure 5, the short side of the chain being about 2 feet 3 inches in length and the long side 8 feet 3 inches. The chain is made to pass over the mold board, so that it may clear itself more readily. Two or three horses, according to the difficulty of the particular condition, are necessary to clear a ditch.

To secure the best service from the ditcher, a weight of about 200 pounds should be placed over the front end. The essential thing to be gained is to have the ditcher maintain a smooth, even surface on the bottom of the ditch. There is then no obstruction to the flow of water. This requires that soft, muddy holes be passed over lightly and hard, high places be reduced. This result is obtained if the driver shifts his weight forward or backward as a high point or a mudhole is approached. If the driver shifts his weight forward, the point of the ditcher is driven into the ground. If he moves back, the p sure on the forward end is relieved and the pull on the chain tends to raise it.

Besides clearing the ditch, the ditcher assists in preserving the slope from the side of the road to the bottom of the ditch. This keeps the road safe from possible accident to traffic from ditches with too abrupt slopes.

CONCLUSION.

The advantages to be gained from the persistent use of a road drag may be summarized as follows:

1. The maintenance of a smooth, serviceable earth road free from ruts and mudholes.
2. Obtaining such a road surface with the expenditure of very little money and labor in comparison with the money and labor required for other methods.
3. The reduction of mud in wet weather, and of dust in dry weather.

There are also several minor benefits gained from the use of a road drag, besides the great advantages which always accrue from the formation of improved highways, of which may be mentioned the banishment of weeds and grass from the dragged portion of the road.

FARMERS' BULLETINS.

The following is a list, by number, of the Farmers' Bulletins available for distribution. The bulletins entitled "Experiment Station Work" give in brief the results of experiments performed by the State experiment stations. Titles of other bulletins are self-explanatory. Bulletins in this list will be sent free to any address in the United States on application to a Senator, Representative, or Delegate in Congress, or to the Secretary of Agriculture, Washington, D. C. Numbers omitted have been discontinued, being superseded by later bulletins.

22. The Feeding of Farm Animals. Pp. 40.
24. Hog Cholera and Swine Plague. Pp. 16.
27. Flax for Seed and Fiber. Pp. 16.
28. Weeds: And How to Kill Them. Pp. 30.
29. Souring and Other Changes in Milk. Pp. 22.
30. Grape Diseases on the Pacific Coast. Pp. 15.
32. Silos and Silage. Pp. 30.
33. Peach Growing for Market. Pp. 24.
34. Meats: Composition and Cooking. Pp. 31.
35. Potato Culture. Pp. 24.
36. Cotton Seed and Its Products. Pp. 16.
42. Facts about Milk. Pp. 32.
44. Commercial Fertilizers. Pp. 38.
47. Insects Affecting the Cotton Plant. Pp. 32.
48. The Manuring of Cotton. Pp. 16.
51. Standard Varieties of Chickens. Pp. 48.
52. The Sugar Beet. Pp. 48.
54. Some Common Birds. Pp. 48.
55. The Dairy Herd. Pp. 30.
56. Experiment Station Work—I. Pp. 30.
58. The Soy Bean as a Forage Crop. Pp. 24.
59. Bee Keeping. Pp. 48.
60. Methods of Curing Tobacco. Pp. 24.
61. Asparagus Culture. Pp. 40.
62. Marketing Farm Produce. Pp. 31.
63. Care of Milk on the Farm. Pp. 40.
64. Ducks and Geese. Pp. 55.
65. Experiment Station Work—II. Pp. 32.
66. Meadows and Pastures. Pp. 30.
69. Experiment Station Work—III. Pp. 32.
71. Essentials in Beef Production. Pp. 24.
72. Cattle Ranges of the Southwest. Pp. 32.
73. Experiment Station Work—IV. Pp. 32.
74. Milk as Food. Pp. 39.
77. The Liming of Soils. Pp. 24.
78. Experiment Station Work—V. Pp. 32.
79. Experiment Station Work—VI. Pp. 27.
80. The Peach Twig-Borer. Pp. 16.
81. Corn Culture in the South. Pp. 24.
82. The Culture of Tobacco. Pp. 22.
83. Tobacco Soils. Pp. 23.
84. Experiment Station Work—VII. Pp. 32.
85. Fish as Food. Pp. 32.
86. Thirty Poisonous Plants. Pp. 32.
87. Experiment Station Work—VIII. Pp. 32.
88. Alkali Lands. Pp. 23.
91. Potato Diseases and Treatment. Pp. 15.
92. Experiment Station Work—IX. Pp. 30.
93. Sugar as Food. Pp. 31.
95. Good Roads for Farmers. Pp. 46.
97. Experiment Station Work—X. Pp. 32.
98. Suggestions to Southern Farmers. Pp. 48.
99. Insect Enemies of Shade Trees. Pp. 30.
100. Hog Raising in the South. Pp. 40.
101. Millets. Pp. 30.
102. Southern Forage Plants. Pp. 48.
103. Experiment Station Work—XI. Pp. 30.
104. Notes on Frost. Pp. 24.
105. Experiment Station Work—XII. Pp. 32.
106. Breeds of Dairy Cattle. Pp. 48.
107. Experiment Station Work—XIII. Pp. 32.
108. Saltbushes. Pp. 20.
110. Rice Culture in the United States. Pp. 28.
111. Farmers' Interest in Good Seed. Pp. 24.
112. Bread and Bread Making. Pp. 40.
113. The Apple and How to Grow It. Pp. 32.
114. Experiment Station Work—XIV. Pp. 28.
116. Irrigation in Fruit Growing. Pp. 48.
118. Grape Growing in the South. Pp. 32.
119. Experiment Station Work—XV. Pp. 30.
120. Insects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and Other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp. 32.
134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing. Pp. 48.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propagation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.
179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.
183. Meat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
185. Beautifying the Home Grounds. Pp. 24.
186. Experiment Station Work—XXIII. Pp. 32.
187. Drainage of Farm Lands. Pp. 38.
188. Weeds Used in Medicine. Pp. 45.
190. Experiment Station Work—XXIV. Pp. 32.
192. Barnyard Manure. Pp. 32.
193. Experiment Station Work—XXV. Pp. 32.

194. Alfalfa Seed. Pp. 14.
195. Annual Flowering Plants. Pp. 48.
196. Usefulness of the American Toad. Pp. 16.
197. Importation of Game Birds and Eggs for Propagation. Pp. 30.
198. Strawberries. Pp. 24.
199. Corn Growing. Pp. 32.
200. Turkeys. Pp. 40.
201. Cream Separator on Western Farms. Pp. 23.
202. Experiment Station Work—XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work—XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and Their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-Out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. 36.
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
51. Experiment Station Work—XXXIV. Pp. 3[illegible]
52. Maple Sugar and Sirup. Pp. 36.
53. The Germination of Seed Corn. Pp. 1[illegible]
54 Cucumbers. Pp. 30.
5 [illegible]he Home Vegetable Garden. Pp. 4[illegible]
[illegible] [illegible]pare[illegible] [illegible]getables for [illegible] Pp. 4[illegible]
[illegible]l Fert[illegible]
[illegible]xas [illegible] Pp. 4[illegible]
[illegible] Experiment Station Work—XX[illegible]
6[illegible] Seed of Red Clover and Its Impur[illegible]
[illegible] The Cattle Tick. Pp. 2[illegible]
[illegible] Experiment Station Work—[illegible]
[illegible] [illegible] information [illegible]
[illegible]

266. Management of Soils to Conserve Moisture. Pp. 30.
267. Experiment Station Work—XXXVII. Pp. 32.
268. Industrial Alcohol: Sources and Manufacture. Pp. 45.
269. Industrial Alcohol: Uses and Statistics. Pp. 29.
270. Modern Conveniences for the Farm Home. Pp. 48.
271. Forage Crop Practices in Western Oregon and Western Washington. Pp. 39.
272. A Successful Hog and Seed-Corn Farm. Pp. 16.
273. Experiment Station Work—XXXVIII. Pp. 32.
274. Flax Culture. Pp. 36.
275. The Gipsy Moth and How to Control It. Pp. 22.
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 40.
278. Leguminous Crops for Green Manuring. Pp. 27.
279. A Method of Eradicating Johnson Grass. Pp. 16.
280. A Profitable Tenant Dairy Farm. Pp. 16.
281. Experiment Station Work—XL. Pp. 32.
282. Celery. Pp. 36.
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. 42.
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. 48.
285. The Advantage of Planting Heavy Cotton Seed. Pp. 16.
286. Comparative Value of Whole Cotton Seed and Cotton-Seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. Pp. 48.
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. Pp. 30.
295. Potatoes and Other Root Crops as Food. Pp. 45.
296. Experiment Station Work—XLI. Pp. 32.
297. Methods of Destroying Rats. Pp. 8.
298. The Food Value of Corn and Corn Products. Pp. 40.
299. Diversified Farming Under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-Grown Tea. Pp. 16.
302. Sea Island Cotton: Its Culture, Improvement, and Diseases. Pp. 48
303. Corn Harvesting Machinery. Pp. 32.
304. Growing and Curing Hops. Pp. 39.
305. Experiment Station Work—XLII. Pp. 32.
306. Dodder in Relation to Farm Seeds. Pp. 27.
307. Roselle: Its Culture and Uses. Pp. 16.
308. Game Laws for 1907. Pp. 52.
309. Experiment Station Work—XLIII. Pp. 32.
31[illegible] A Successful Alabama Diversification Farm. Pp. 24.
[illegible] Sand-Clay and Burnt-Clay Roads. Pp. 20.
31[illegible] A Successful Southern Hay Farm. Pp. 15.
[illegible] Harvesting and Storing Corn. Pp. 32.
[illegible] A Method of Breeding Early Cotton to Escape Boll-Weevil Damage. Pp. 20.
[illegible] Progress in Legume Inoculation. Pp. 20.
[illegible] Experiment Station Work—XLIV. Pp. 32.
[illegible] Experiment Station Work—XLV. Pp. 32.
[illegible] Cowpeas. Pp. 26.
[illegible] Demonstration Work in Cooperation with Southern Farmers. Pp. 23.
[illegible] Experiment Station Work—XLVI. Pp. 32.

Issued June 3, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 322.

ILO AS A DRY-LAND GRAIN CROP.

BY

CARLETON R. BALL,
Agronomist in Charge of Grain Sorghum Investigations,

AND

ARTHUR H. LEIDIGH,
Superintendent of the Amarillo Experimental Farm, Grain Investigations, Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., April 3, 1908.

Sir: In connection with the regular work of the Office of Grain Investigations conducted for the past five years on experimental farms and at other points in the Southwest, much success has been attained in the improvement of grain sorghums, particularly in the production of dwarf strains of milo characterized by good seed production and erect heads. It appears that much of this information is sufficiently definite and of such a practical nature as to make it of immediate benefit to the many farmers who are now settling in the semiarid plains, particularly as milo is one of the most satisfactory dry-land crops that can be employed. This matter has been brought together in the accompanying manuscript by Mr. Carleton R. Ball, Agronomist in Charge of Grain Sorghum Investigations, and Mr. Arthur H. Leidigh, Superintendent of the Amarillo Experimental Farm, Amarillo, Tex., and I would recommend its publication as a Farmers' Bulletin.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

CONTENTS.

Page.

Vhat milo is 5
  Relationships and classification 5
  Origin and introduction 6
  Common names 6
  Varieties 6
  Characters of ordinary milo 7
  Characters of improved milo 9
Vhere to grow milo 10
ow to grow milo 12
  Soils 12
  Preparing the seed bed 12
  Planting the seed 13
    Time of planting 13
    Methods of planting 13
    Rate of planting 14
  Cultivating the crop 15
  Selecting and saving seed 15
  Harvesting the crop 17
  Thrashing the seed 19
  Yields of grain 19
ow to use milo 20
  Feeding on the farm 20
  Selling the grain 20
russic acid poisoning 21
isect enemies and fungous diseases 21
  Insects 21
  Fungi 22
mmary 22

ILLUSTRATIONS.

Page.

IG. 1. Seeds of milo 5
2. Field of the ordinary unselected milo 8
3. Field of milo as improved by selection 9
4. Field of the true dwarf form of milo 10
5. Map of the United States, showing where milo is or may be grown 11
6. Milo heads; one pendent, one erect 16
7. Diagram showing named positions of heads of milo 17
8. Field of milo in shock, Channing, Tex 18
9. A form of row header used for kafir varieties 19

B. P. I.—367.

MILO AS A DRY-LAND GRAIN CROP.

WHAT MILO IS.

RELATIONSHIPS AND CLASSIFICATION.

The sorghums[a] grown in this country may be separated into four groups: (1) Broom corns; (2) sorgos, or sweet sorghums; (3) kafirs, and (4) durras. The broom corns are grown only for their brush, the sorgos for forage and sirup, the kafirs for grain and forage, and the durras almost exclusively for grain.

Milo (fig. 1) belongs to the durra group, which contains also white durra ("Jerusalem corn," "rice corn," "white Egyptian corn") and brown durra ("brown Egyptian corn"). The durras are characterized by dry and rather pithy stems and large, oval or egg-shaped, mostly pendent ("goose-necked") heads. The number of leaves on



FIG. 1.—Seeds of milo. *a*, cleaned seed; *b*, seed in hulls; *c*, small branch of head, showing awns on spikelets. (Natural size.)

---

[a] For further information as to the sorghums, the reader is referred to the following Farmers' Bulletins, which will be sent free upon receipt of a request addressed to the Secretary of Agriculture: No. 135, "Sorghum Sirup Manufacture"; No. 174, "Broom Corn"; No. 246, "Saccharine Sorghums for Forage"; No. 288, "The Nonsaccharine Sorghums."

each stalk is only 8 to 10 on the average. This scanty foliage and the pithy stems make them of little value for forage compared with kafirs and sorgos. The seeds of the durras are larger than those of the kafirs and sorgos, are nearly circular in outline, and are usually somewhat flattened.

The chief varieties of the durra group may be separated as follows:

Seeds white; hulls pale; flower awned	White durra.
Seeds reddish brown; hulls pale; flower not awned	Brown durra.
Seeds pale yellowish; hulls dark; flower awned (fig. 1)	Milo.

ORIGIN AND INTRODUCTION.

Milo was introduced into the United States between 1880 and 1885 and was first grown in South Carolina or Georgia. It came probably from Africa, but this is not certainly known. No sorghum brought since from Africa has been exactly like milo, though one found in Egypt and called there durra safra, or yellow durra, is quite similar to it.

Milo was first widely advertised and sold by the M. W. Johnson Seed Company, of Atlanta, Ga., in the spring of 1887. It soon became distributed over the South and as far west as Texas. In western Texas, and especially in the Panhandle region, it has become popular and widely grown because of its drought resistance and comparative earliness.

COMMON NAMES.

Milo was first known as "Yellow Millo Maize." The adjective "yellow" was applied because of the yellowish color of the seeds and because a white-seeded sorghum, related to the kafirs, was then being sold and grown as "White Millo Maize." Many other names have since been applied to milo. Among them are Branching doura, Dwarf milo, Dwarf milo maize, Dwarf yellow milo, Millo, Millo maize, Milo maize, Red Egyptian corn, Rural branching sorghum, Yellow branching dhoura, Yellow branching millo maize, Yellow branching sorghum, Yellow millo maize, Yellow milo, and Yellow milo maize. Several of these names are occasionally applied to brown durra also. Dwarf milo, Yellow milo, and Milo "maize" are the names most commonly used for milo.

The name "milo" is adopted and recommended because it is short, distinctive, and appropriate. The word "maize" should never be used for milo, as it confuses this crop with corn.

VARIETIES.

There is only one well-marked variety of milo yet offered for sale by seedsmen. It is usually sold as "yellow milo" or "yellow milo maize." What is commonly sold as "dwarf milo" is the ordinary milo grown on the dry and elevated plains of western Texas, Oklahoma, and Kansas, where it reaches a height of 4½ to 5½ feet. It is thus dwarfed because of the conditions under which it is grown. When its seed is carried to lower and more humid districts the crop grows to a height of from 7 to 10 feet, according to the conditions of soil and moisture. On the other hand, seed from this lowland crop if taken to the high plains will produce only the dwarfed crop 4½ to 6 feet tall. The ordinary "yellow" milo and the "dwarf" milo of commerce represent, therefore, one and the same thing, which is discussed in this bulletin simply as milo.

The only true "dwarf" milo known to the writers was secured a few years ago from Judge J. F. Bradley, of Memphis, Tex., who states that the original seed was brought from Oklahoma. So far as known, this dwarf strain (see fig. 4) is not yet handled by seedsmen. It is described later in the paragraph on the characters of improved milo. The so-called "giant milo" occasionally met with in the Plains region consists of hybrids of milo with other sorghum varieties, usually kafirs or sorgos.

CHARACTERS OF ORDINARY MILO.

When first introduced milo (fig. 2) was suitable for use only as a general forage crop. Owing to its small and scanty leaves and pithy stems it was inferior to kafirs and sorgos for forage purposes. On the western plains it began to be developed as a combined grain and forage crop. Like all sorghums it was strongly drought resistant. Compared with some other grain varieties of sorghum it was only fairly early and productive, but it possessed good seed-holding power, which white durra ("Jerusalem corn") and brown durra sadly lacked. From the standpoint of grain production it had, besides these desirable characters, several very objectionable habits. These were (1) the abundant stooling, (2) the free branching, (3) the size and height of the stem, and (4) the pendent, or "goosenecked," heads. (See fig. 6.)

Why are these four habits objectionable in a grain variety?

Stooling (1) and branching (2) prevent uniformity of height and of ripening. In sorghums the suckers comprising the stool from a single main stalk do not all develop at one time. In the same way the branches appear successively rather than all at once, beginning at the second node from the top and progressing downward. These suckers and branches produce heads which ripen at different dates, but none of them as early as the main heads. These branches and suckers are also of different heights, some higher and some lower than the main stalks. Uniform height and ripening are very necessary in a grain crop. The habit of suckering and branching must therefore be checked by selection.

The size and height of the stems (3) make hand cutting difficult and heading by machinery almost impossible.

The pendent heads (4), hanging downward (see fig. 2) from the apex of the recurved peduncle or stem, are an especial nuisance. Their position not only prevents the use of headers in harvesting the seed crop but makes it very difficult to handle the heads satisfactorily in any way. They are in an awkward and dangerous position to cut by hand. The curved stem is likewise objectionable. It prevents the stalks from lying parallel when cut. It makes the tops of bundles wider than the bottoms, thus forming shocks that can neither withstand winds nor turn water. The crook of the stem is always interlocking with adjacent stems, so that they can scarcely be separated in field or shock.



Fig. 2 Field of the ordinary unselected milo, from 6 to 7½ feet tall, with stout, branched stems and pendent heads.

Such were the characters of the original milo and such is in large measure the unimproved crop to-day.

CHARACTERS OF IMPROVED MILO.

In the past four or five years the development of milo as a grain crop has been progressing rapidly along the lines just shown to be desirable. The carefully selected milo (fig. 3) of to-day is a great improvement over the common, unselected crop. Ordinary milo has been reduced by selection to a uniform height of 4 to 4½ feet in the Plains regions lying at an elevation of 3,000 to 4,000 feet above sea level, or at an equivalent latitude. Through selection and thicker seeding the heads have been changed from mostly pendent to mostly erect. All heads not leaning over more than 30 degrees from the perpendicular (see fig. 7) are classed as erect, since for all practical purposes they are erect. From 75 to 90 per cent have been brought to this position in different strains. A large part of the remaining 10 to 25 per cent are merely inclined, i. e., bent over more than 30 degrees and less than 90 degrees, or the horizontal position. These inclined heads would be readily gathered by a header. Only a very small percentage of the heads are pendent, i. e., declined below the horizontal line.



FIG. 3.—Field of milo as improved by selection, from 4 to 4½ feet tall, slender, without branches, heads erect.

By the combined influences of selection and thicker seeding, branching has been almost entirely prevented, and stooling, or the production of suckers, has been greatly checked. About one-fourth to one-half the plants produce no suckers at all, and most of the remainder produce only one sucker on each plant. Earliness has been increased until these strains ripen in ninety to one hundred or one hundred and ten days under the conditions of altitude and climate found in western Texas and adjacent territory. The grain yields of the crop have been maintained and increased during all these changes in habit.

A true dwarf strain (fig. 4), growing only 3 to 3½ feet in height under the same conditions as the ordinary taller strain, has been improved in the same way as the ordinary milo, though the changes are not yet quite as firmly fixed.

All the work of selection and improvement here outlined has been done by the writers, under the direction of the Office of Grain Investigations. Most of it has been carried on at the experimental farms maintained by the office mentioned, formerly at Channing, Tex., and now at Amarillo, Tex. These improved strains are not yet generally on the market, but are gradually finding their way to the seedsmen and probably will soon be obtainable by everyone interested.



FIG. 4.—Field of the true dwarf form of milo, from 3 to 3½ feet high.

WHERE TO GROW MILO.

Milo is at present the most successful summer grain crop for the southern half of the Plains region. It is an earlier and more drought-resistant crop than corn and makes a satisfactory feeding substitute. The highest average yields of corn under the same conditions have been ten bushels to the acre less than those of milo. The yields of blackhull kafir have been five bushels less to the acre.

Milo is now a staple crop in a large part of western Texas and in the adjacent portions of New Mexico, Colorado, Kansas, and Oklahoma. This section lies at elevations of 1,500 to 4,000 feet above sea level and has a varying annual rainfall of 17 to 25 inches. Milo is well adapted to the whole southern half of the Plains region lying below an elevation of about 4,500 feet.

Milo can be grown successfully on the lower plains of eastern Oklahoma, eastern Kansas, and southern Nebraska, where kafir varieties are now the leading grain sorghums. In this eastern section of the plains corn is ordinarily a profitable crop, and the acreage of milo will depend on seasonable variations. In dry years milo should be largely grown there, but in wet years it will be replaced by corn to a considerable extent.



FIG. 5.—Map of the United States, showing where milo is or may be grown.

It seems very probable that the limits of successful production of milo can be rapidly extended northward and westward from the present area. The accompanying map (fig. 5) shows (1) the area where milo is now a staple crop, (2) the area to which milo is now well adapted, and (3) the area in which milo is being thoroughly tested and in much of which it will probably be grown successfully.

In 1907 milo was ripened at several points in eastern Colorado at elevations of 5,500 to 6,000 feet. It was fully matured at the agricultural experiment substation at North Platte, in western Nebra

At the experiment substation at Highmore, in central South Dakota. at an elevation of 2,000 feet, in latitude 44° north, the earliest milo was just ripe when frost occurred, on September 26, 1907.

Early strains of milo will be thoroughly tested in 1908 over all the northern Plains region and throughout the Great Basin or intermountain area as well. Farmers ripening milo outside the limits of present production should very carefully select their seed from hardy and early-maturing plants, thus founding a strain suited to their conditions.

Milo is not adapted to humid regions and should not be grown in them.

HOW TO GROW MILO.

SOILS.

The soil requirements for milo are about the same as those for corn. Well-worked sandy loams or clay loams are best. Light sands and heavy clays are much less desirable. The roots penetrate to depths of 3 to 4 feet in ordinary friable soils. Fair yields result on rather poor lands; better yields in good soils. In the semiarid country much depends, however, on the way the soil is handled to conserve moisture. Early and deep plowing to catch and hold the rainfall when it comes, with surface cultivation to keep down weeds and prevent evaporation, are the two principal lines of treatment possible.[a]

PREPARING THE SEED BED.

Fall plowing is preferable to spring plowing where it can be done, because it increases the water-absorbing power of the soil. Deep plowing is better than shallow plowing for the same reason and because it encourages deeper rooting. Harrowing should be thorough before sowing to mellow the soil for the seed bed and to destroy any weeds that may have started. Increased labor in preparing a field before sowing is almost always well repaid by an increased yield of the crop.

On sandy soils or other soils which blow about in windy weather, fall disking and medium-deep spring plowing may be required. When the lister is used, disking in the fall or early spring is advised or double listing may be practiced. Milo usually makes a fair crop on fresh sod and in the semiarid regions is thought to be the best crop for spring-broken sod land. The seed is dropped in every third or fourth furrow while breaking and covered by the next sod turned or is planted with a shoe drill. The crop thus sown can not usually be cultivated.

---

[a] For a full discussion of this subject the reader is referred to Farmers' Bulletin No. 266, by George H. Failyer, entitled "Management of Soils to Conserve Moisture, with Special Reference to Semiarid Conditions." This bulletin may be obtained by application to the Secretary of Agriculture, Washington, D. C., or to any Senator or Representative in Congress.

PLANTING THE SEED.

It should be remembered that the following directions for planting, especially those concerning the rate and the manner of sowing, are for growing milo as a grain crop. Those who are familiar with handling this and other sorghums as forage crops should note the difference required in the rate of seeding and in other practices.

Time of Planting.

The time to plant varies, of course, with the latitude and altitude. In general, milo should be sown about two to four weeks later than the average date for planting corn. The average date will therefore vary from about April 15 in southern Texas and the lower Southwest to about May 25 on the higher plains of northwest Texas, and to about June 1 to 15 in Nebraska and South Dakota. Because of its earlier maturity, milo can be planted later than the varieties of kafir wherever they are safe crops. Milo should not be sown until all danger of spring frost is past and the soil has become warm.

Methods of Planting.

Milo may be either listed or surface planted, as the experience in any particular locality has shown to be the best for crops of this class. Listing is a common practice in much of the Plains region where milo is now, or is likely to become, a staple crop. Certain advantages are secured from listing. The young plants are protected from the strong winds of spring and from the cutting action of sand carried by such winds, which sometimes cuts the stems of surface-grown crops entirely off. The root systems of listed crops are also said to lie deeper, because of the deeper sowing, but this fact is doubtful, owing to the later growth of surface roots. On the other hand, listing tends to make the crop ripen later because the young plants at the bottom of the furrow grow more slowly than those planted at the surface. In wet seasons the lister furrow fills with water and the young crop may be either washed out or covered up with sand or mud.

Surface sowing is the rule in a large part of the milo country and will probably increase in importance as a method of sowing even in sections where listing is now generally practiced, since better methods of conserving soil moisture are becoming understood.

Whether listed or surface sown the most common way of sowing milo is by means of special sorghum plates used in the corn planter or lister planter.

Rate of Planting.

For the highest yields of grain from 4 to 6 pounds of seed to the acre is sufficient if the seed is of good quality. Milo is usually sown in rows 3½ feet apart; sometimes only 3 feet apart. The quantity of seed used will vary somewhat with differences in soil and climate. Sections with rich soils and more abundant moisture can sow milo more thickly in the row than sections having thin sandy soils and lighter rainfall. Several years' tests on the experimental farm of the Office of Grain Investigations, at Amarillo, in the northern part of the Texas Panhandle, show that one plant to every six inches of row gives the highest grain yields under the average conditions obtaining there. The soil on this farm is a good clay loam, the elevation is 3,600 feet above sea level, and the average annual rainfall about 22 inches. Four pounds of seed to the acre produce under these field conditions plants averaging 6 to 8 inches apart—the desired stand. Thicker stands than this have generally been recommended for grain production but are not desirable under Panhandle conditions.

These figures are intended to be suggestive rather than final. A series of experiments covering three or four different rates of seeding must be carried on for several years at different points in the milo belt before the question of how much to sow to the acre can be fully settled. The best rate may prove to be different for each different set of conditions of soil, moisture, and length of growing season. It will also be dependent to a considerable extent on the cultivation given. Until these facts are more fully known, each farmer should test for himself two or three different rates of seeding. Four pounds, six pounds, and eight pounds of seed to the acre are suggested for such trials.

Where the plate on the planter can be set to run at different speeds only one plate will be required for planting seed at different rates to the acre. The proper speed to use for each desired rate can be ascertained by testing the planter on a floor or smooth, hard piece of ground. The distance at which the seeds are dropped can then be very readily observed and the proper distance secured. Where the speed of the plate can not be changed, several plates with different numbers of holes will be necessary to secure different rates of planting. Each hole should be large enough to drop two small seeds at once, but not two medium-sized or large ones. The holes should be countersunk well on the under side of the plate. The number of holes required in the plates in order to drop seeds 3, or 6, or 8 inches apart, respectively, can readily be figured out for each kind of planter, the holes then drilled by the farmer or a blacksmith, and the results tested as described above.

In general, thick sowing produces small stalks and small, erect heads, but many more heads on an acre. Thin seeding makes larger stalks and larger heads, but fewer of them. Thin sowing also produces a larger number of the objectionable pendent heads.

CULTIVATING THE CROP.

The cultivation of milo is much like that of corn. Milo, like all sorghums, grows slowly at first and may become choked by weeds on foul land unless care is taken. The harrow or the weeder should be freely used in such cases, running in the same direction as the rows. This applies both to listed and to surface-sown crops. When the plants are sufficiently large, any ordinary style of cultivator may be used. The various special tools for cultivating young listed crops are well adapted for use with milo. The earliest cultivation may be deep if desired, but after the root system has filled the space between the rows, cultivation should not be more than 2½ to 4 inches deep. Such shallow tillage does not injure the roots and keeps the surface in fine tilth, thus conserving moisture by preventing evaporation.

SELECTING AND SAVING SEED.

In the case of a new crop, like milo, it is very desirable that each farmer select carefully his own seed. This is especially true of the farmer who is outside the present milo region. If he is at a greater elevation, or at a more northern latitude, or in a more arid district than that of the principal milo belt, good home-grown seed will be best for his sowing. Selected seed will also be much better than ordinary bulk seed, even from his own fields.

As previously noted, the most important points for which milo is being selected are (1) earliness, (2) drought resistance, (3) productiveness, (4) uniform height and ripening, (5) freedom from branches and suckers, and (6) erect heads. (Figs. 6 and 7.)

Selections for any or all of these points must be made in the field instead of after the crop is harvested. Except for earliness and uniform ripening, the selecting may be done any time before harvest. Wherever earliness is an important point, the selecting must be done when the earliest heads are maturing, since later, when all have ripened, the early heads can no longer be distinguished from later ripening ones.

Selections should, if possible, be made in a part of the field where the stand is good and other conditions are the average. There is always a temptation to select where the stand is thin because of the fine large heads produced in such spots. In selecting for productiveness, or high yields, stalks should be chosen having the largest and heaviest heads where the stand is fairly thick. Erect, early-ripening heads on stalks of equal and average height, free from suckers and branches, should be selected and plainly marked in the field. Marking may be done by means of a pasteboard tag, a bit of white cloth, or a piece of white paper securely tied to the stalk just below the head. If tied so that it can flutter in the breeze, so much the better, as it will be easier to find the heads when they are to be gathered. The heads should be left on the stalks in the field until fully ripe, when they may be gathered by hand and hung up to a rafter or on the wall of the granary or toolhouse to dry. They may be laid on a shelf in a well-ventilated room if the layer of heads is not made too thick, but should not be hung in a stable, as the moisture is likely to injure the seed. They may be allowed to hang all winter and be thrashed out in early spring. Before planting time the seed should be tested for germination.[a]



FIG. 6.--Milo heads; one pendent, one erect.

---

[a] For a simple method of testing the germination of seeds the reader is referred to Farmers' Bulletin No. 111 (p. 21), which may be secured on application to any Member or Delegate in Congress or to the Secretary of Agriculture.

Any farmer who feels that he can not spare the time to select enough seed for sowing his entire field of milo for the succeeding season can at least select enough to sow an acre or more to be used as a seed plat. Forty or fifty heads will be quite sufficient for an acre. Good results may often be obtained by placing the work of selection in the charge of a bright boy. Help him to get in mind the desirable type of plant and interest him in improving the crop. Some premium might be given him if his selected seed plat outyields the unselected field.

HARVESTING THE CROP.



FIG. 7.—Diagram showing named positions of heads of milo.

Where sown as suggested milo is usually harvested with a corn binder and cured in the shock (fig. 8). In ordinary milo the recurved stems and pendent heads make the bundles so large at the top that shocks made from them are not firm, but are easily blown over by wind and wet by rain. Our improved strains, with heads mostly erect, are not open to these objections. When milo is bound with either the corn binder or grain binder, the heads may be cut from the bundles with a broadax or a heavy knife hung at the tip. The crop may also be thrashed without heading, or it may be fed in the bundle without thrashing.

Heading the crop in the field is naturally the most desirable method of harvesting, since it saves handling the stover and makes thrashing easier and more rapid. Ordinary milo, with pendent heads, can not be successfully harvested with any kind of header. The improved strains are adapted to harvesting with the row header, the grain header, or with either binder. A suitable type of row header is very much needed for harvesting all forms of grain sorghums.

Some machines of this kind are in use to a limited extent for heading kafir varieties. These machines (fig. 9) are built for attachment

[illegible]

[illegible] in the [illegible] are dried [illegible] hard [illegible] The stalks [illegible] nearly as early as [illegible] kafirs. [illegible] in the bundle it may [illegible]

THRASHING THE SEED

[illegible] grain separator. To [illegible] the seed, the concaves may be replaced with boards or part of the concave and cylinder teeth removed. The speed of the cylinder should also be reduced to about 600 revolutions a minute. Where the thrashed seed is intended for feeding to stock, there is no objection if much of it has been cracked in thrashing. In fact, milo is usually cracked or ground before being fed to stock, because otherwise much of it passes through the cattle without being digested. But where intended for use as seed grain it is, of course, worthless if cracked. Where it is desired to thrash shocked milo, the heads may be cut from the bundles as suggested or the bundle may be held in the cylinder until the grain is all removed from the heads and then thrown to one side. It is scarcely profitable to thrash the whole bundle, though this is commonly done.



FIG. 9.—A form of row header used for kafir varieties.

YIELDS OF GRAIN.

The yields obtained at the Amarillo and other experimental farms of the Office of Grain Investigations during the past five years have averaged almost exactly 40 bushels of milo to the acre. The highest has been 46 bushels. Yields of 30 to 55 bushels are reported by farmers. The seeds when of good quality weigh fully 60 pounds to the bushel. The limits of yield have probably not been reached and the average is likely to increase as the crop becomes more carefully selected and more intelligently handled.

HOW TO USE MILO.

FEEDING ON THE FARM.

The principal use of milo on the farm will be as a feeding grain,[a] similar to corn. Chemical analyses show that the seeds of corn and milo are nearly identical in composition. Whether their feeding values are as nearly equal is not certainly known. No accurate experiments have been made to determine this fact. Experiments made with the grain of kafir varieties prove them to be a little less valuable than corn for feeding purposes. Milo is equal to or somewhat better than the kafirs as a feeding grain. Unlike kafirs, milo has a beneficial laxative effect on the bowels.

More and more milo is being fed as a thrashed grain. To prevent waste by imperfect digestion, it is best to crack or grind the milo before feeding. Where hogs follow cattle, the waste in feeding whole grain is reduced, but the cattle will do better on the cracked than on the whole grain. The grain, like corn, gives the best results when fed with some other feed containing more protein, such as alfalfa, cotton seed, or cowpea hay.

Where milo is headed in the field or from the shock, the heads may be fed whole, or they may be ground and fed, or they may be thrashed and the grain fed. The whole heads are readily ground in any large feed mill, though thrashing first and then grinding the seed is said to require no more power.

A considerable amount of milo is fed in the bundle, especially in localities where little grain is grown and separators are not common. This is a fairly satisfactory way of handling the crop, provided the stand is fairly thick and it is cut as soon as ripe, before the stalks become bare and woody. When feeding milo in the bundle, care should be taken that no more is placed in the feed racks than is eaten each day. Stock will not thrive where their ration becomes moldy or much mussed over in the racks. Many cases of "blind staggers" and other sickness have been directly traced to feeding such moldy foodstuffs.

SELLING THE GRAIN.

There is now a growing market for milo grain. Apparently, increasing quantities are being used in poultry foods and in chops.

---

[a] The only feeding test with milo of which the writers have knowledge is reported in a circular issued by the Texas Agricultural Experiment Station, entitled "Panhandle Feeds for Beef Production." The experiment was carried out at the XIT Ranch, Channing, Tex., by J. J. Edgerton.

Some is sold on local markets for seed or for feeding purposes, but most of it is fed on the farms where grown.

PRUSSIC ACID POISONING.

All kinds of sorghums, including Johnson grass, sometimes become poisonous through the formation of deadly prussic acid in their leaves, especially when their growth is checked by any cause, such as drought or frost. They are dangerous only in the green state and are harmless when cut and fully cured. The grain is never poisonous. The writers have heard of no cases of such poisoning from green milo, but this may be because, unlike sorgos and kafirs, it is almost never pastured.

INSECT ENEMIES AND FUNGOUS DISEASES.

INSECTS.

Milo has few serious insect pests. Chinch bugs are occasionally troublesome to this as to all other sorghums. Aphides, or plant lice, sometimes occur in great abundance on the leaves of young milo and other sorghums. When very abundant they tend to stunt the plants by sucking the juices from the leaves. The fall army worm[a] (*Laphygma frugiperda* S. & A.) sometimes does considerable damage to milo and other sorghums. The larva, or worm, of this moth is large, somewhat resembling the corn or cotton boll worm in size and color. The adult deposits its eggs in the unfolding upper leaves before they unroll. The injury done by gnawing back and forth through the tightly coiled leaf appears as a series of parallel rows of round holes in the expanded leaf. Such leaves are frequently lost by breaking off on a line of these holes. The nearly full-grown worm, especially of the later broods, is particularly fond of tunneling in the stem, 3 to 6 inches below the head, being protected by the sheath of the upper leaf. Frequently the stem is so weakened that it breaks in the wind and the young head droops over and dies, turning conspicuously paler. The worms occasionally enter the head itself, where they do more damage by fouling it with their excrement than by the quantity of grain actually eaten.

In southern and eastern Texas the larva of the sorghum midge (*Diplosis sorghicola* Coq.) prevents seed production by absorbing the juices from the young ovary so that the grain never develops. This is the trouble often called " blast " by farmers.

---

[a] A detailed account of the fall army worm is given in Bulletin No. 29, new series, of the Bureau of Entomology.

FUNGI.

Milo is very free from fungi. It is especially noteworthy that it has never been known to be attacked by the kernel smut of sorghum, so destructive to most varieties. The head smut of sorghum also has never been found on milo.

SUMMARY.

Milo is one of the durra group of sorghums, closely related to white durra (" Jerusalem corn ") and to brown durra. It is probably of African, perhaps Egyptian, origin and was introduced into the United States between 1880 and 1886.

Milo is recommended as a short and suitable name for this crop. It is commonly known as dwarf milo, yellow milo, and milo " maize." The last name confuses it with corn.

There is only one variety handled by the seed trade. What is sold as " dwarf " milo is ordinary milo grown on the drier plains, where for lack of moisture it is low in stature. There is a true dwarf milo, but it is not yet generally sold on the market.

Ordinary milo stools freely at the base and branches freely above, is tall and rather stout, and is not uniform in height or in time or ripening. The heads are mostly pendent. As a crop it is difficult to handle rapidly and satisfactorily.

Improved or selected milo has to a large extent been prevented from suckering and branching, is low and rather slender, is uniform in height and ripening, and has its heads mostly erect. It may be handled easily by machinery and is fitted for harvesting with headers.

Milo is widely grown in western Texas and adjacent parts of New Mexico, Oklahoma, and Kansas. It is well suited to the entire southern half of the Plains region below 4,500 feet elevation. It can probably be profitably grown as far north as South Dakota and westward in Colorado and New Mexico to elevations of about 6,000 feet; likewise in the Great Basin region.

The soil requirements of milo are much the same as those of corn. The land should preferably be fall plowed and well prepared in spring to hold moisture and destroy weeds.

In general, milo should be sown about three weeks later than corn and after all danger from frost is past. Milo may be listed or sown at the surface as local conditions require. The seed is sown by means of special sorghum plates used in either the corn planter or the lister planter.

The best rate of planting for highest grain yields lies probably between 4 and 6 pounds to the acre, depending somewhat on the character of the soil, the average rainfall, the length of the season, and the cultivation given. Four pounds to the acre has given the best results in the Texas Panhandle. The rows should be about 3½ feet apart and the stalks 6 to 8 inches apart in the row.

The cultivation of milo is essentially the same as that for corn.

Farmers should carefully select their own seed of milo, especially where it is not yet a staple crop. Selection is usually made for (1) earliness, (2) drought resistance, (3) higher yields, (4) uniformity, (5) freedom from suckers and branches, and (6) erect heads. The yield and value of the crop can be greatly increased by such means. Select enough for a small seed plat if time lacks for more extensive work. Interest the farm boys in this work.

Harvesting is usually done with a corn binder or by cutting the heads by hand. Ordinary milo can not be headed by machinery because of the pendent heads. Our improved milo with erect heads may be cut with a grain header or with a row header. A good adjustable kind of row header is much needed.

Thrashing is done with a grain separator. Slowing the cylinder and removing the concaves or part of the concave and cylinder teeth will prevent cracking the seed.

Yields vary from 25 to 55 bushels of seed to the acre. The yields in the Panhandle of Texas average about 40 bushels to the acre. As tillage methods and the crop itself are improved the yields should be increased.

Milo is used mostly as a feeding grain on the farms. It may be fed as thrashed grain, in the head or in the bundle. The grain is preferably cracked or ground before feeding, except for poultry. The heads may also be ground. Milo is entering more and more into the production of chops and poultry foods.

Milo, like other sorghums, may become poisonous in the green state, especially when checked or stunted in growth.

The principal insect enemies are the chinch bug, aphides or plant lice, fall army worm, and sorghum midge. The last may totally prevent seed production in the Gulf region.

Milo is entirely free from the kernel smut and the head smut of sorghum.

O

Issued May 8, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 323.

LOVER FARMING ON THE SANDY JACK-PINE LANDS OF THE NORTH.

BY

C. BEAMAN SMITH,
*Assistant Agriculturist, Farm Management Investigations,
Bureau of Plant Industry.*

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., March 4, 1908.

Sir: I have the honor to transmit herewith a paper entitled "Clover Farming on the Sandy Jack-Pine Lands of the North," by Mr. C. Beaman Smith, Assistant Agriculturist, prepared under the direction of the Agriculturist in Charge of Farm Management Investigations of this Bureau.

Large tracts of sandy pine lands occur in several Northern States, particularly in Michigan, Wisconsin, and Minnesota, which by ordinary methods of farming do not give profitable returns. It has been proved that when special care is taken in handling these lands and special crops are grown a large part of the sandy pine lands can be built up into profitable farms. The growing of clover for seed is one of the special lines that have proved profitable. Exceptionally good yields of high-grade clover seed are now being grown on some of this land, and it is believed that the clover crop, whether for seed, for forage, or for green manuring, is the key to the situation for successful farming on this land.

The manuscript herewith gives a detailed account of the methods of handling the soil and growing clover followed by successful farmers on this land. The data presented apply to many million acres of land in the North now idle because people do not know how to handle them. I therefore recommend that the paper be published as a Farmers' Bulletin.

Respectfully,

B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

CONTENTS.

Page.
Introduction 5
Extent and character of the jack-pine lands 5
Attractions of the jack-pine lands 6
Reasons for failures on the jack-pine lands 7
Facts every settler should know 7
Clearing and breaking jack-pine lands 8
Depth to plow jack-pine lands 9
Preparation of the seed bed 10
Clover the key to successful farming on jack-pine lands 10
    Kind of clover to grow 11
How to secure a stand of clover 11
    Seeding clover without a nurse crop 11
    Seeding clover with a nurse crop 11
Clover inoculation 14
Effect of winds on the clover catch 15
Wind-breaks for sandy lands 16
Rough fields desirable on sandy lands 17
Handling clover for seed 18
    Reasons for pasturing clover or clipping it back 19
    The clover-flower midge 19
    Factors in successful clover-seed farming 20
    Harvesting and curing clover for seed 20
Clover straw 21
Clover following clover 21
Manures and fertilizers 22
    Manures 22
    Fertilizers 23
Summary and suggestions 23

ILLUSTRATION.

Page.
Fig. 1. Mower with attachment for bunching clover cut for seed 20

323

B. P. I.—361.

CLOVER FARMING ON THE SANDY JACK-PINE LANDS OF THE NORTH.

INTRODUCTION.

The sandy jack-pine plains of the States of Michigan, Wisconsin, and Minnesota have long been an agricultural problem. Farmers have generally failed to make a living on them. After building a house and barn, clearing up a patch of ground and cropping it for two or three years, the land has been abandoned. The crops raised were not sufficient to support the farmer or to encourage him to stay longer. More people have left these lands during the last thirty years than are now living on them.

The problem has been whether these lands could ever be farmed profitably or whether they had not best be used for forestry purposes. The recent successes of numerous farmers in growing clover and producing clover seed on these jack-pine lands indicate that a solution has at last been found for profitably farming at least a part of this hitherto rejected land.

This much has been demonstrated: These sandy jack-pine lands can not be farmed in the usual manner with profit. General farming fails. Success will come only from growing specific crops adapted to the soil and climate, and thus far the crop found most profitable is clover for seed. This is a most fortunate circumstance. With clover for a start, either for seed or forage, the land can soon be built up into almost any state of productiveness. It would seem that the key to the successful farming of these lands has been found.

EXTENT AND CHARACTER OF THE JACK-PINE LANDS.

There are perhaps 2,000,000 acres of jack-pine lands in Michigan alone, the bulk of it occurring in the northern central portion of the lower peninsula. In addition there are 8,000,000 or 9,000,000 acres of cut-over pine lands that are generally of a light sandy nature and require specially careful handling to make them productive of farm crops. In Wisconsin there are probably as many as 2,000,000 acres of jack-pine lands, and in Minnesota there are considerable areas of

323

jack-pine and light sandy pine lands. Small areas of land of very similar character are found as far east as Maine.

The typical jack-pine plains are generally rather openly wooded and often park-like in appearance. Jack pine (*Pinus banksiana*) is the common timber, and this is found in all stages of growth from seedlings to trees 35 to 50 feet high. Scattered with the jack pine are scrub oaks, poplars, willows, Juneberry, chokecherry, and other woods of shrubby growth. The small native vegetation consists for the most part of brakes, sweet ferns, huckleberries, wintergreens, and some rather coarse wild grasses. In the autumn golden-rod and wild asters are conspicuous.

The soil is usually a rather light yellow, brown, or gray sandy loam, often of a gravelly nature. Frequently red clay comes to the surface and is sometimes several acres in extent. Generally the subsoil is sandy, often to great depths. Analyses[a] show that the better grades of jack-pine soils are well supplied with the mineral elements necessary for plant growth, but are generally quite deficient in humus and nitrogen. This lack of humus and nitrogen is one of the fundamental reasons for the low productiveness of the jack-pine plains.

As with other lands, the jack-pine soils vary greatly in value for agricultural purposes. Generally that which is most open, sandiest, and most thinly covered with native grasses and other vegetation is the least productive. A thick mat of vegetation or dense underbrush containing many briers, willows, Juneberries, poplars, scarlet maples, etc., indicates a more productive quality of soil. The intending purchaser should carefully examine the land before he buys it.

ATTRACTIONS OF THE JACK-PINE LANDS.

The jack-pine land attracts farmers (1) because it is cheap, and (2) because it is easily cleared. It looks as though one could easily make a good farm out of it. Frequently a man can clear 2 or 3 acres a day and get it ready for the plow. The timber being small, most of the stumps can be plowed out the first year and by the second or third year the rest are rotted. This phase appeals to the man who has seen the labor and time taken to clear up a heavily timbered piece of land and get rid of the stumps.

The cheapness of the land, however, is undoubtedly the main reason for settlers occupying it. Much of it has been homesteaded. A good deal of it has had the scattering pine cut off by lumbermen and has reverted to the State or can be bought for back taxes. Thus secured the land costs 25 cents to $1.25 an acre. In other cases speculators have bought up the land and by advertisement and otherwise are inducing families to settle on it. Speculators are holding it for $5 to $15 an acre.

---

[a] Michigan Agricultural Experiment Station Bulletin No. 37.

The sandy pine stump lands present a different problem. The lumber on these lands was largely Norway and white pine. It takes a lifetime or more for the stumps of these trees to rot, while to pull or dynamite them out costs $15 to $25 an acre. The principles of farming are the same on the sandy Norway and white pine stump land, however, as on the jack-pine plains land.

REASONS FOR FAILURES ON THE JACK-PINE LANDS.

The principal reason why farmers have failed on the jack-pine lands is because they attempted to grow grains, roots, and grasses in the same way that they had been accustomed to on the heavier and more productive lands in other sections of the country. The methods of farming observed on heavier, more fertile lands fail here. The plains land is light. It is subject to drought. It is lacking in both humus and nitrogen. The yields by usual farming methods are increasingly disappointing from year to year. On average jack-pine lands handled in the usual manner potatoes will give as a first crop on spring breaking 35 to 60 bushels per acre, wheat 5 to 6 bushels, rye 5 to 8 bushels, oats 10 to 15 bushels and usually light in weight.

Other reasons for failure are deep plowing, burning off the humus, clearing the land at the wrong season of the year, and failure to recognize that the land is light, not adapted to general farming, and needs first of all to be built up with humus and nitrogen before either satisfactory crops of grain, roots, vegetables, or fruit can be grown. Success in farming this land will come from growing special crops like clover seed, potatoes, or truck, not from general farming.

FACTS EVERY SETTLER SHOULD KNOW.

The intending settler on the jack-pine lands needs to know at the outset that this sandy soil needs a little nursing and special care in handling. The land has been repeatedly burned over every few years for no one knows how many generations; hence, there is little humus or vegetable matter in it. It lacks nitrogen. It is likely to be a little leachy. It is likely to suffer severely in time of drought. It needs protection from the winds. In the beginning it should be plowed shallow. It usually needs rolling to make a firm seed bed, followed immediately by dragging to make a dust mulch for retaining the moisture in the soil and to reduce the velocity of the wind next to the soil surface.

On the other hand, when such sandy land is properly handled it responds with marvelous quickness to even small quantities of barnyard manure, green manure crops, or commercial fertilizers. It produces splendid crops with barnyard manure alone. The land can be handled whenever the sun shines. It produces a crop ten days to three weeks earlier than the heavy clays, and in the case of orchard fruits sometimes two to five years sooner. Besides, the quality of many crops grown on sandy land is superior.

CLEARING AND BREAKING JACK-PINE LANDS.

The successful handling of the jack-pine plains begins with the clearing of the land. The logs, brush, and stumps must be cleared away, but nothing should be burned off that can be plowed under for humus. The great need of the soil is for humus, or vegetable matter. Rotten logs should be picked to pieces and scattered thinly over the ground. All the sweet ferns, huckleberry bushes, brakes, and other small growths should be plowed and not burned off.

Burning over the soil not only depletes it of its humus content, but tends to make a sterile and dead soil of it, since the bacterial life which has so beneficial an action in the production of crops is for the most part active only near the surface of the soil. A fierce fire left to run over the land in clearing it will destroy most of these beneficial organisms, leaving the soil inert and unresponsive, like a freshly turned subsoil.

One of the most successful farmers found on the jack-pine plains clears his land and burns the log and brush heaps in the spring or fall, but makes it his general practice not to break the land until about the middle of July. By this time all the native vegetation, such as the ever-present brakes, sweet ferns, huckleberries, wintergreens, wild grasses, etc., has made its principal growth for the season. This mass of weeds, grasses, and shrubby growths is then plowed down by the aid of a chain attached to the end of the whiffletree and beam of the plow in the usual manner for plowing under green crops. When the land is broken up in the spring for crops, the roots and underground stems of the native vegetation, being full of stored food, start into a vigorous growth, producing stems, leaves, and new plants above ground, which seriously compete with the planted crops for moisture and a place to grow. These roots continue to send up stems all summer long, which necessitates continuous cultivation to subdue them.

On the other hand, when the land is not broken up until July and early August, the roots have become practically exhausted of their stored food supply in producing the growth of stems and leaves above ground. If at this time the ground is plowed and the exhausted roots turned up to the hot July sunshine, the plants are more easily and surely killed than at any other time of the year.

After plants have made their full growth above ground for the season they begin storing food in their roots and stems again for early spring growth the following season. For this reason fall breal likewise is less effective for subduing the native vegetation than s mer breaking, because the roots, being full of stored food at the t of the late plowing, start into growth promptly the following spr being but little injured in that northern climate, where the snow ı ally covers the ground all winter.

There is still another reason for waiting until midsummer be breaking the land. By that time there is a heavy growth of veg tion. This makes as good a green manure crop to turn under as or buckwheat would.

DEPTH TO PLOW JACK-PINE LANDS.

The jack-pine lands are light and thin. What humus they con is for the most part within 2 or 3 inches of the surface; below is subsoil. Now, in actual practice the men who are making the gr est success on these lands are plowing but 4 to 5 inches deep. Usu the nearer 4 inches deep the land can be broken up the better the ceeding crop will be. The depth of plowing is only gradually creased as humus and nitrogen are added to the soil. It will pr bly be found that about 6 inches is as deep as it will ever be fo necessary or desirable to plow the lighter lands of the jack-] plains.

On the more loamy or even clay lands sometimes found on jack-pine plains the plowing after the land has been enriched ⱽ humus can be gradually deepened to 7 or 8 inches; but at the breaking 4 inches has proved deep enough on any kind of jack-] land. This point is emphasized here because so many settlers in region make the serious mistake of burning the land over in spring to slick it off clean for the plow and then plow it 7 to 8 in deep. This is a mistake. It puts the thin streak of humus in surface soil down about 6 inches deep, leaving 3 inches at leas dead subsoil on top of the ground. Seeds started in such a to make a discouraging growth. Clover particularly makes a m better growth when the first breaking is less rather than more th inches deep; and this is the plant above all others that should be couraged, as it promises to convert these hitherto discouraging la into profitable farms.

Special attention is called to the desirability of breaking t lands shallow. Successful farming on these lands is absolutely pendent upon the observation of a few apparently insignificant pc which on better soils might be overlooked with impunity, but w on these naturally light soils must be observed if productive, p perous farms are to be built up.

PREPARATION OF THE SEED BED.

After the land has been broken up in July and the natural green manure crop of native vegetation plowed under about 4 inches deep, it should be gone over with a roller heavily weighted to pack the loosened soil down firmly. This hastens the rotting of the material turned under. The spring-tooth harrow is commonly employed on this land because with it many of the brakes and other roots which cause so much trouble by continuously springing into life when the land is spring or fall plowed are pulled out and can be gathered up and burned.

That is just what ought not to be done. Leave the trash and roots in the soil. Their decay there means the addition of just so much more humus to it, the thing above all others of which the soil stands most in need. The disk harrow, which cuts the roots up and leaves them in place, is a much more satisfactory implement to use in first working down new breakings. By the use of the disk harrow after the roller, any new growth that comes up between the time the land is broken in July and the time grain is sown in the fall can be easily kept in control. The disk should not run more than about 3 inches deep and should be set at only a slight angle. Where the disk is not available, a spike-tooth drag with the teeth slanting slightly backward is the next best implement to use.

If, however, the land is broken in early spring, when the roots and underground stems are filled with stored food, it will be advisable to drag out as many roots and stems as possible in order to reduce their numbers in the field during the growing season.

CLOVER THE KEY TO SUCCESSFUL FARMING ON JACK-PINE LANDS.

The vital fact in farming the sandy jack-pine lands is that clover will grow on it. A second fact is that clover builds up the land faster than any other crop commonly grown there. It supplies at the start both the nitrogen and humus that the soil so badly needs. A third fact is that by growing the crop for seed the enriching effects of the clover on the land can be secured and at the same time a cash crop of greater value than that from any other crop commonly grown on the jack-pine lands obtained. This is a point of paramount importance to the poor settler, who needs every cent he can get off the farm to meet his living expenses. Finally, as a green manure clover is the best crop yet found for the jack-pine plains.

In some sections, particularly in Michigan, very profitable returns have been secured from growing mammoth and common red clover for seed. These lands seem well adapted to clover-seed production. Yields of seed ranging from 2 to 6 bushels to the acre, having a gross cash value of $10 to $50 per acre, have been obtained. For the last few years the seed yield has averaged a little more than 3 bushels to the acre. As the price ranges between about $5 to $9 per bushel, this makes a very profitable crop. The income from clover-seed farming is thus seen to be as great as that from land yielding 20 bushels of wheat or 40 bushels of corn to the acre at average prices. But whether or not one grows clover for seed or goes into some other kind of farming, such as the dairy industry, sheep, potatoes, and the like, it is certain that clover lies at the base of every successful system of farming that has yet been devised for these lands and should be among the very first crops grown.

KIND OF CLOVER TO GROW.

Of the different kinds of clover the mammoth, bull, or sapling clover rather than the smaller common red clover or the alsike clover has been found most efficient on the jack-pine plains. It seems to grow better, gives more forage, and yields more seed to the acre than either of the other two varieties. The mammoth clover, of course, produces but one crop of hay a season, but most of the plains land is so far north that only one cutting can be safely taken from any kind of clover, while in that section cutting the first crop of common red clover for hay and the second for seed generally results in a very light and unprofitable crop of seed.

HOW TO SECURE A STAND OF CLOVER.

The first matter for the settler on the jack-pine plains to consider is how to secure a good stand of clover.

SEEDING CLOVER WITHOUT A NURSE CROP.

The surest way to get a stand of clover on jack-pine lands is to seed the crop alone without a nurse crop. Where the land has been broken up in July by plowing down the native vegetation 4 inches deep and rolling with a heavy roller, followed by an occasional cultivation until fall with a disk harrow or spike-tooth drag, the land will be in the best possible condition for seeding to clover about May 1 of the following spring.

Now, on that light sandy land it has been found best to drill or drag the clover seed in about 2 inches deep. Seeding the clover in spring on top of the land with fall-sown grain, as is the common practice on heavier lands, fails nearly every time it is tried on these light sandy lands. On the other hand, where the seed is put in about 2 inches deep it is able to withstand the usual drought which commonly occurs in those northern climates in May. Being rooted at least 2 inches deep, it is not so easily blown out or injured by the wind, which usually blows strongly from the west or southwest during the spring months. Many failures to secure a stand of clover on the jack-pine plains are due to shallow spring seeding and the drying up or blowing out of the plants by the persistent western winds common early in the year.

Another point in this connection is that by seeding 2 inches deep, the clover rootlets, after elongating an inch or so, come into immediate contact with the body of humus produced by turning under the mass of wild vegetation 4 inches deep at the time of breaking in July. Practically all of the available plant food of the soil is thus within easy reach of the clover rootlets just at a time when the plants are weakest and stand most in need of it. This decayed matter gives the clover plant a vigorous start until tubercles can be formed on the roots and the plants thus made able to secure their nitrogen from the air. The fact is now generally known to all farmers that the more tubercles or nodules found on the roots of the clover plant the greater the growth of the clover and the more valuable the crop for green manuring.

The seeding of the clover alone without any nurse crop whatever is especially advantageous on these light soils. It insures, in so far as it is possible by any method of farming to insure, a full stand of clover and after the land becomes fertile enough the production of a fair hay crop that same season. By this method of seeding, all the moisture of the soil and all the available plant food in the soil are put at the service of the clover plant.

When the clover is seeded with a grain crop it must compete with the grain crop for both moisture and food. The result is usually an inferior, unprofitable crop of grain and frequently only a half stand or an entire failure of the clover. Weeds which in other sections of the country may hinder the growth of clover seeded alone in spring do not make trouble on this new land when broken up in midsummer and occasionally cultivated.

SEEDING CLOVER WITH A NURSE CROP.

The financial conditions of many farmers who move on the jack-pine lands are such that they must grow their own forage and grain in sufficient quantities at least for their own stock. With most farmers on the jack-pine plains the need is immediate of growing some money crop as quickly as it can be secured. For these and other reasons it will be found necessary to grow a certain amount of grain, forage, and root crops from the start, drawing on the fertility already in the soil for their production. At the same time it is desirable that the ground be seeded with clover, so that the building up of the soil may be begun as quickly as possible.

With a favorable season, particularly one with plenty of rainfall, a good stand of clover may be secured by seeding with grain. In fact, it should be an invariable rule on the jack-pine lands always to seed clover with every grain crop put in. The clover may fail sometimes as a crop, but enough will usually catch to make it profitable to turn under for green manure and thus pay for the seed at least. Winter rye is a favorite crop to seed with, since it usually gives a larger yield on the light lands of this section than any other grain. If the land is broken up in July, as previously described, it will be in good condition for seeding to winter rye about August 25 to September 5 anywhere north of central Michigan and Wisconsin. This is a little too late to seed with clover, which should be put in as soon as the snow goes off the following spring. There are right and wrong methods of doing this.

As to the right method, as soon as the ground can be worked in spring run over the rye field with a spike-toothed harrow lengthwise of the rows. Sow on mammoth clover seed at the rate of 3 to 4 quarts, or 6 to 8 pounds, to the acre. Then run over the field again with the spike-toothed harrow with the teeth slanting back a little and follow with the roller. If the season is dry, cut the rye for hay and give the clover a chance.

This quantity of clover seed is entirely sufficient where it is intended to cut the clover for seed the following year. If the crop is intended for forage, then 6 to 8 pounds of orchard grass or timothy seed sown with the grain in the autumn will insure a larger hay crop the following year.

The harrowing will not injure the rye in the least, and it will cover the clover seed a little deeper than when sown on top of the ground and then dragged in. It is inviting failure to seed the clover on top of sandy soils and not harrow it in.

If wheat is sown in the fall instead of rye the wheat should be harrowed in the spring and the clover sown in exactly the same manner as noted for rye. Seeding clover with spring grains has been practiced by a large number of successful farmers on the jack-pine lands. This method has been quite successful during the past three or four wet years. But where the main purpose is to secure a crop of clover, this method is never so certain as seeding the clover without a nurse crop.

Perhaps three-fourths of the farmers visited on the jack-pine lands consider buckwheat one of the best grains to seed with; that is, they report the best catch of clover with this crop. Clover has also usually caught better in spring rye than in spelt or oats. In many instances also good catches have been secured with Canada field peas. Excellent catches have also been secured when clover was seeded in ruta-bagas in July. In fact this is one of the best crops of all to seed with when the ruta-bagas are sown in rows, the clover being planted between the rows at the last cultivation about the middle of July. For the region about Roscommon, Mich., Mr. F. L. De Lameter recommends the seeding of clover with oats or spelt up to May 15; with millet, buckwheat, or turnips up to June 20; and with rye or wheat up to August 15.

When clover is seeded with any of the spring grains it is safe and advisable to drill the clover in with the grain, letting the clover seed run down the grain tubes. This puts the clover seed down 2 to 3 inches deep, which is none too deep on light land. If the grain is broadcasted by hand, the clover seed, of course, is dragged in the same depth as the grain. In any case, whether the grain is drilled or harrowed in, it is advisable to follow the drill with a heavy roller to pack the soil down firmly around the seed, followed by a spike-tooth harrow to leave the topsoil rough and loose. A rough soil drifts much less than a smoothly packed soil, and moisture is retained to a greater extent when the topsoil is loose than when it is firmly packed down.

It should be a rule on the jack-pine lands to sow on clover seed at every opportunity, with every grain and grass crop, in the standing corn at the last cultivation, with ruta-bagas or turnips, and with every crop with which it will not interfere. As one farmer expressed it "Every time you scratch the ground, put in clover seed." But in dry or otherwise unfavorable seasons all the clover thus seeded may fail. In addition, then, to the clover thus seeded it is strongly urged that the main fields of clover, the ones in the regular rotation that are being depended upon for clover seed, be seeded alone. This method of clover farming insures a seed crop every year on a third to a fourth of the whole farm.

CLOVER INOCULATION.

When new land on the jack-pine plains is cleared and put into clover for the first time, it sometimes makes only a small growth. This is not necessarily because the land is poor, but is often because the soil is not well inoculated with clover bacteria.

In a thrifty clover field the roots are usually thickly studded with small tubercles. When clover is grown on virgin soil like the jack-pine plains, the organisms causing these tubercles are not plentiful or may be entirely wanting. In an examination of a number of fields of clover on the plains land many cases were found where there was only now and then a tubercle on the roots, or the tubercles might be entirely absent.

Now, the poorer the land the greater the need is of having the soil well inoculated with the bacteria causing these tubercles. It is by means of bacteria working within these tubercles, or nodules, that the clover plant is able to utilize the nitrogen of the air in its more rapid and vigorous growth.

There are three common ways of getting the soil inoculated with clover bacteria:

(1) When the seed is sown in the usual way nearly always some of the plants become inoculated. This is particularly true where old logging or other roads cross the fields. The field as a whole may be unsatisfactory. If this field is plowed and harrowed and clover immediately sown on again the chances are that the second crop will be much more vigorous than the first, because of the more abundant inoculation of the soil brought about by the greater distribution of the bacteria in the soil by plowing and harrowing, by the wind, etc. So if clover does not succeed the first year, it may be tried on the same land the second year. By the third year the field should be thoroughly inoculated and a good stand obtained. After that the field should remain inoculated for years.

(2) A second and very common way of inoculating new land with clover bacteria is to take moist topsoil from an old clover field and scatter it over the new field at the time the clover is seeded. About 200 to 250 pounds of this old clover soil should be scattered on each acre of new ground and immediately harrowed in. If the inoculated soil dries out, the vigor of the clover bacteria in it is greatly diminished. This is one of the reasons why it should be harrowed in and not simply scattered on top of the ground. Excellent results have been reported by this method of inoculating clover. The danger in this method lies in the possibility of introducing weed pests or plant diseases through the agency of the old soil.

(3) The most scientific method of inoculating the clover field is to obtain a pure culture of clover bacteria and moisten the clover seed with it just before sowing. These pure cultures have been put on the market commercially and can also be obtained in limited quantity from the United States Department of Agriculture.[a]

EFFECT OF WINDS ON THE CLOVER CATCH.

Throughout northern Michigan, Wisconsin, and Minnesota there is usually a persistent strong wind that blows steadily from the west and southwest nearly every day in spring and early summer. These winds are frequently very injurious to spring-planted grains on sandy lands and are especially severe on new clover seeding. Grain fields have been seen where practically all the seeding on the eastern side of the field had been destroyed by drifting sand and the drying effects of the wind. Frequently the clover in exposed fields is entirely killed out, except in sheltered spots like ravines and on hillsides or along fences which break the force of the wind. Time and time again the clover crop in the middle and east side of a field has been found a complete failure while an excellent stand was obtained on the western edge of the field where perhaps a board fence or a few scattering shrubs offered some light protection from the drying winds.

---

[a] Information as to methods of inoculating soils for various legumes and the benefits derived from inoculation is given in Farmers' Bulletin No. 314, which may be had free upon application to the Secretary of Agriculture.

In experimental work on sandy lands in Wisconsin, Professor King[a] found that, with a gentle breeze blowing, evaporation a foot above the ground was 25 per cent greater 20 rods out from the west edge of a field than it was 3 rods out. In this case there was a wind-break 12 to 15 feet high on the west side of the field. Even with only a hedge of scattering bur oaks 6 to 8 feet high, evaporation was 30 per cent greater 300 feet to leeward of the hedge than at 20 feet.

Not only does the land dry out much more rapidly with a strong wind blowing over it, but the finer portions of the soil itself may be blown away, greatly decreasing the soil fertility and lessening the power of the soil to hold moisture, for the finer the soil the greater its moisture-holding capacity. These various factors—the wind carrying sand particles which cut off the young plants or cover them over, the more rapid drying out of the soil exposed to the high winds of the spring, and the lessened fertility content of the soil caused by the finer particles being blown away—all tend to decrease the chances of success of the clover plant.

Another point in this connection is that under ordinary conditions of farming the finer particles of soil are brought to the surface every time the land is plowed or tilled. The wind carries many of these away, so that the natural tendency of these soils, if allowed to drift, is to become coarser, less able to retain moisture, and more subject to drought. Besides, in these coarser soils any vegetable matter that may be added in the form of green or stable manure is much more quickly burned out and the humus reduced to ashes than on the finer and more compact soil of the original field. This we do not want. A big yield on these lands depends upon there being a large quantity of humus in them.

WIND-BREAKS FOR SANDY LANDS.

The chances for securing a good catch of clover and a stand of grains are greatly increased by having a wind-break around each field. This can be easily provided by leaving an uncut strip one to two rods wide around each field at the time the land is cleared. Any blank spaces in this hedge can be filled in by transplanting to it some of the native trees and shrubs, such as jack pines, poplars, Juneberries, scrub oaks, willows, and the like. Spruce also does remarkably well on all jack-pine land and makes an excellent wind-break.

---

[a] Wisconsin Agricultural Experiment Station Bulletin No. 42.

Since also the prevailing winds come from the west and southwest, it is advisable to make the cleared fields comparatively long and narrow, the long way running north and south.

Many a farmer likes to see big fields. It is a pleasure to stand in the doorway and look over the whole farm, seeing nothing but cultivated fields. An overgrown fence row is an abomination that must be grubbed out. Nevertheless the farmer who fails to leave or provide a wind-break around his fields on the sandy lands of the jack-pine plains pays dearly for his negligence. It is one of the little things that make the difference between success and failure on these lands. A hedge row growing around a sandy field is a kind of insurance against failure, especially valuable where success is staked on the clover crop. What may seem like shiftlessness in overgrown fence rows on fertile clay loam farms has been found to be the wisest kind of farming on lighter sandier lands.

Long, narrow fields never more than 40 rods wide, with occasional wind-breaks, are recommended. In most cases the wind-breaks are already in place. They should not be cut down when clearing the fields. If they are not there they should be planted. This will pay a bigger interest on the investment than any other improvement that can be put on the place.

ROUGH FIELDS DESIRABLE ON SANDY LANDS.

Another point bearing on the relation of winds to the method of handling sandy lands may need explanation. After seeding any crop on sandy lands, the packing of the soil down firmly around the seeds by running over the field with a heavy roller is strongly recommended. Soil moisture from below rises more rapidly in firm than in loose soil, resulting in a better and quicker germination of the sown seed. If, however, the soil is left packed to the surface, evaporation from the soil is more rapid than where the topsoil is loose. Besides, where the soil is left smooth after the roller the winds blow over it much more rapidly than where it is left rough.

King[a] found that the force of the wind next to the soil surface was reduced about one-half on rolled land by running over it with a harrow. He cites a rolled field over which the wind was raising such a dust that it was almost impossible to see across it. A harrow was run over the field at right angles to the wind, when the cloud of dust practically subsided. Actual measurements showed that the velocity of the wind across the roughened field next the soil surface was much less—practically half less—than over the rolled smooth soil. Therefore, whenever the soil is packed down smooth with a roller—and this should be after every clover and grain crop is seeded—it should be followed immediately with a spike-tooth harrow to leave the top surface loose and rough.

---

[a] Wisconsin Agricultural Experiment Station Bulletin No. 42.

HANDLING CLOVER FOR SEED.

The usual custom in the north-central part of the southern peninsula of Michigan, where clover is being grown quite extensively for seed on pine and hardwood lands, is to cut the first crop of the season of either common red clover or the larger growing mammoth clover for seed. This is contrary to the general practice in the older clover seed sections farther south, where the usual procedure is to cut the first crop of common red clover for hay and the second for seed. Indeed, the belief is quite prevalent among farmers in the older clover sections that the first crop of June clover does not set seed. That the belief does not hold true in northern Michigan is shown by the fact that there are many authentic records of yields of 6, 8, 10, and, in one instance at least, even 12 bushels of clover seed per acre. These yields have been obtained from the first crop without either clipping or pasturing the clover back in spring. The average yield of clover seed in northern Michigan in fields with a uniform stand of clover is more than 2 and very close to 3 bushels of seed to the acre one year with another, while the better farmers will average 4 to 5 bushels. When, however, in that northern section, the first crop of common red clover is cut for hay and the second left for seed, the seed yield is nearly always disappointing, a yield of half a bushel to a bushel of low-grade seed containing a very large percentage of light and shriveled seed being the rule.

The farmers, however, who are uniformly getting the largest yields of seed in northern Michigan, Wisconsin, and Minnesota are the ones who first pasture back the clover, either common red or mammoth, with sheep or cattle until about June 15 to 20 in a normal season and then let the crop come on for seed. Some farmers who do not have sufficient stock clip the clover back with a mower about June 15 and get as good results as where the clover is pastured off. The mower is set high and the clippings left to fall back on the land. Even where the land is pastured off many farmers practice running over the field with a mower after the stock is removed to clip back any bunches that may be left, so that the crop may come on evenly over the entire field.

The past season, especially, it was a noticeable fact in northern Michigan that those farmers who pastured or clipped back their clover got larger yields of seed than those who did not. One instance from this year's observation may be cited in this connection. One farmer on the jack-pine plains in northern Michigan had a practically perfect stand of clover on about 50 acres of his farm. This clover was waist-high and full of blossoms in July, promising an extra heavy yield. It thrashed out a little more than 2 bushels of seed to the acre. A near-by farmer on similar sandy lands pastured back his rather poor stand of clover on a 40-acre field with cattle until June 20. This field averaged about 5 bushels of seed per acre.

REASONS FOR PASTURING CLOVER OR CLIPPING IT BACK.

Farmers have found from experience that by pasturing or clipping back clover and then letting the crop go to seed they get larger yields of seed generally than by any other method of handling the crop. The reasons generally given for such better yields are about as follows: By clipping or pasturing back, the clover is brought into bloom in a dry time. One farmer expressed it thus: "I don't care how much rain there is up to the time clover blooms, but after that a good seed crop depends upon dry weather." If rainy weather prevails during the blooming period the clover crop may as well be cut for hay.

Again, it is believed that by pasturing or clipping back, the plant does not grow so rank, is less likely to lodge and fall down, blooms more freely, and that a larger number of insects are present to cross-fertilize the crop than earlier in the season. Another advantage of pasturing back is that there is much less straw to handle at thrashing time. This is an item of special importance where the large mammoth clover is grown. A rank yield of plant and a large yield of seed do not appear to go together, but rather where the plant is rankest there the seed yield is least.

THE CLOVER-FLOWER MIDGE.

More pertinent, probably, than all the reasons previously given for pasturing or clipping back clover is the fact that by so doing the destructive action of the clover-flower midge is largely avoided. The clover-flower midge is usually noticed on the clover heads as a small orange-red insect about as large as a pin head, commonly present in all clover sections of the United States and observed by the writer the past season in northern Michigan, Wisconsin, and Minnesota. This insect feeds within the florets of the clover blooms at blossoming time and prevents the formation of seed. It probably does more to injure the seed crop than all other agencies combined except wet weather.

A detailed description and life-history account of the flower midge can not be given here, but the farmer who may be interested in clover-seed production is urged to write to the United States Department of

Agriculture for Bureau of Entomology Circular No. 69, entitled "Some Insects Affecting the Production of Red Clover Seed."

FACTORS IN SUCCESSFUL CLOVER-SEED FARMING.

Practice and science unite in showing that to secure the largest crop of clover seed the crop should bloom during dry weather. This necessitates keeping an account of the weather in each locality from year to year so as to know at about what period to expect dry weather. The plants should be comparatively thin on the ground and stocky for the largest yield. Closely crowded plants make weak stems which lodge and produce very little seed. Pasturing or clipping tends to make short straw and stocky plants, which are less likely to lodge and easier to handle at thrashing time. To avoid the greatest injury from the flower midge the crop should be brought into bloom a little later than the first crop of common red clover normally blooms and considerably earlier than the second crop of this clover usually blooms. This is brought about by pasturing the clover back until about June 15 to 20 in the northern part of Michigan, Wisconsin, and Minnesota, or clipping it back with the mower at about this time.

HARVESTING AND CURING CLOVER FOR SEED.

Practice varies as to the time for cutting common red and mammoth red clover for seed. The greatest quantity of seed is usually obtained by waiting until about 95 per cent of the heads are a dead, brown color, but before any of the heads begin to fall to pieces. A number of instances came under the writer's observation the past season where the crop was cut a little on the green side with the expectation that the seed would ripen up in curing. The results were quite uniformly unsatisfactory, much of the seed being shriveled and light. Where the crop is left until most of the heads are thoroughly ripe there is less loss of heads if the cutting is done in the early morning and late afternoon when the straw is a little tougher than at midday.



FIG. 1.—Mower with attachment for bunching clover cut for seed.

In cutting, farmers quite generally use a finger-like attachment to the mower with a trip worked by the foot. (See fig. 1.) This leaves the clover in bunches out of the way of the trampling of the horses.

After five or six days' curing in these bunches, if the weather conditions are favorable, the crop is thrashed direct from the field. One or two rains on the crop do not injure it, but with continued wet weather many seeds sprout and the quality of the crop is injured. If a clover huller is not available as soon as the crop is dry enough to hull, the clover should be stacked or put under cover in barns or sheds. When stacked or put into the mow the clover undergoes a sweating process. On this account hulling should be delayed at least three weeks after stacking.

Stacking is always a safe way of handling the clover-seed crop. Fall rains of a month to six weeks' duration are not infrequent in the Northern States, during which time if the clover is lying in the field the greater part of the seed is lost by the heads rotting off or disintegrating and by the seeds sprouting and becoming discolored. The stack must be covered with straw, marsh hay, or the like, to turn water. The crop is too valuable to take chances with, and the extra labor involved in stacking is not too much insurance to pay for the certainty of securing the crop in the best possible condition.

CLOVER STRAW.

When clover is cut for seed and cured quickly without rainfall the straw has some feeding value. Some farmers use it as a substitute for hay for sheep and cattle. If not required to eat it up too close, stock get along on such material about as well as they do on oat straw. But where the clover has lain in the field subject to dews and rains it gets more or less brittle and rotten and should be used only for bedding or manure.

Many farmers who thrash directly from the field spread the straw out thinly over the field as a manure. For this purpose it is worth about $8 a ton; that is, the amount of fertility in a ton of clover straw if bought in commercial form would cost $8. When this material is used as a light top-dressing on grain it aids in securing a stand of clover; in fact, the straw frequently contains considerable quantities of unthrashed seed which helps considerably in reseeding either old or new fields where it may be applied.

CLOVER FOLLOWING CLOVER.

Clover being the most paying crop yet found for the jack-pine lands, can it be grown year after year on the same land? Mr. Hubbard Head, of Roscommon County, Mich., has asked this question of the jack-pine lands and has been answered in the affirmative. For as many as fifteen years Mr. Head has grown clover continuously on the same fields, and the crop of 1907 was perhaps the best of all. Indeed, by the continuous culture of clover the naturally loose, sandy soil had become firm and compact, the color of the soil decidedly darker, and its fertility greatly increased.

On this farm the general plan is to cut clover for hay or seed until the clover in the field becomes thin; then to let the crop grow until about July, when the whole crop is turned under and the field rolled and reseeded to clover. The seed is sown at the rate of 3 quarts to the acre and harrowed in about 2 inches deep. Thus handled it has become possible, as the land has improved, to secure two, and sometimes three, clover crops in succession before it is found necessary to plow the field down again and reseed. Likewise it has become possible to seed such old clover land in early spring and get a crop of hay or even a small crop of seed the same season.

Frequently, however, bluegrass—or, as it is generally known in the Northern States, June-grass—gets into the clover field and becomes a pest, so that before the field is reseeded to clover it will be found best to put it into some cultivated crop, such as potatoes or corn, for a year or two. It is probable also that if the farm is near a railroad town more money can be made one year with another by alternating potatoes or other vegetable crops with clover than by growing clover continuously. Twelve to fifteen miles away from a railroad the growing of clover for seed alone may be the most profitable form of farming, in which case as much as possible of the farm should be continuously in clover.

MANURES AND FERTILIZERS.

MANURES.

The man who has even a small quantity of manure to apply on the jack-pine land will be astonished at the result. In this light, warm soil the full value of the manure seems to be effective on the crop at once. The crop comes up vigorous and strong, with a healthy color, and makes a rapid growth to maturity. When one is growing clover for seed the best method of applying the manure is as a comparatively light top-dressing on meadows in spring. When clover is seeded with grain in the spring the chances of success of the clover crop are greatly increased by a light top-dressing. An application of even 3 or 4 tons an acre has a marked beneficial effect and practically makes certain a full stand of clover where the manure is evenly spread over the surface.

When corn or potatoes are grown after clover sod, the sod should be plowed under in the fall and what manure is used should be applied as a top-dressing in the spring. In the case of either of these crops the manure can be lightly disked in. When clover is seeded in standing corn—a very desirable practice—the manure used as a top-dressing is of decided advantage in securing a good stand of clover.

Now, there is a difference in manures. The solid matter excreted contains barely half as much plant food in it as the solid and liquid manures combined. One of the first things the plains farmer needs to look after, then, is water-tight stalls and gutters and the use of enough bedding to absorb all the liquids. After the manure is made, the sooner it is applied on the land the more value the crops will get out of it. The best method of producing and caring for manure is told in another bulletin of this Department, which may be had for the asking.[a] Here we wish to emphasize only the desirability of saving the liquid as well as the solid manure by having water-tight floors and gutters, and using the manure in frequent light top-dressings rather than occasional heavy applications turned under.

FERTILIZERS.

Commercial fertilizers have scarcely been used as yet on the jack-pine plains. Superphosphates in a few instances have been found very beneficial to clover, more so than barnyard manure, but on grasses top-dressings of barnyard manure have given larger increases than when superphosphates were used.

Quite extensive experiments a few years since were made by Dr. R. C. Kedzie,[b] of the Michigan Agricultural Experiment Station, in using marl, plaster, and salt on jack-pine lands. Marl had an immediate and lasting beneficial effect on the plains and no injury resulted from its free application at any time. Marked benefit resulted from the use of land plaster up to 200 pounds an acre on nearly all crops, but no benefit was found with any crop from the use of salt as a manure. Splendid results are also being reported on the use of commercial fertilizers by the Wisconsin subexperiment station located in the northern part of that State, at Iron River, on a very good quality of sandy cut-over pine and jack-pine land.

SUMMARY AND SUGGESTIONS.

(1) There are millions of acres of jack-pine lands in Michigan, Wisconsin, and Minnesota that can be made into profitable farms if special care is taken to till the soil properly and follow a type of farming suited to the locality and soil.

(2) The successful farming of these lands is based on the fact that clover will grow on them.

(3) A type of farming which is proving profitable on these lands is the growing of clover for seed.

(4) The kind of clover that grows best and gives the largest yields of seed is the mammoth variety.

---

[a] Farmers' Bulletin No. 192, entitled "Barnyard Manure."

[b] Report of the Michigan State Board of Agriculture, 1889.

(5) The most certain way to succeed with the clover crop is to break new ground shallow in midsummer without burning over, cultivate with a disk harrow, sow the seed 2 inches deep the following spring without a nurse crop, cover with a heavy roller, and then run over with a light spike-tooth harrow to leave the topsoil loose and rough.

(6) The best time to break new ground on the jack-pine plains is during July, after the native vegetation has made its maximum growth for the season. Breaking should be done shallow—not more than about 4 inches deep.

(7) The chances for a successful clover catch are greatly increased by making the fields comparatively narrow east and west, and leaving a good hedge of native trees and shrubs along the west and north borders of every field for a wind-break.

(8) The clover crop is greatly benefited on the jack-pine soils by light top-dressings of barnyard manure or of superphosphates. Marl is also beneficial, and land plaster up to 200 pounds to the acre.

(9) Jack-pine lands are not uniform in character. Open plains and light vegetation generally indicate the poorest grade; mixed vegetation, luxuriant on the ground, and an abundance of willows, Juneberries, poplars, maples, briers, etc., indicate better grades. All the better grades of jack-pine lands can be made into profitable farms by growing clover.

(10) It requires an intelligent understanding of the principles of farming to obtain success on these naturally light lands. It takes about three years' time to get the farm on a paying basis. The first year, at least, the settler must have enough money on hand to carry him through, or he must be prepared to work out part of the time.

(11) If the settler will get his land into mammoth clover as soon as he can, keep it in clover as much of the time as possible, and make clover the main crop on his farm for five or six years, he will build up a fertile, profitable farm upon which he can carry out any type of farming suitable to the region.

323

O

Issued May 23, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 324.

SWEET POTATOES.

BY

W. R. BEATTIE,

Assistant Horticulturist, Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL.

U. S. DEPARTMENT OF AGRICULTURE,
BUREAU OF PLANT INDUSTRY, OFFICE OF THE CHIEF.
Washington, D. C., March 25, 1908.

SIR: I have the honor to transmit herewith a manuscript entitled "Sweet Potatoes," by Mr. W. R. Beattie, Assistant Horticulturist, and recommend that it be published as a Farmers' Bulletin to supersede the former publication of this title issued as Bulletin No. 129 of the same series.

The sweet potato is now one of the most important of our truck crops. It has a wide range of utility, both as a money crop and for home consumption, and it is especially adapted to growing on the "worn-out" cotton and tobacco lands of the Southern States.

Respectfully,

B. T. GALLOWAY,
Chief of Bureau.

Hon. JAMES WILSON, *Secretary of Agriculture.*

CONTENTS.

Page.
Introduction 3
Areas adapted to sweet potato culture 4
Climatic conditions required 4
Character of soil adapted to sweet potatoes 5
Fertilizers for sweet potatoes 6
Propagation of plants 9
Preparation of land for sweet potatoes 16
Setting the plants 18
Cultivation of sweet potatoes 22
Diseases 24
Insects 26
Harvesting sweet potatoes 26
Storage of sweet potatoes 29
Temperature and ventilation of storage houses 33
Loss from shrinkage while in storage 34
Marketing during winter months 34
Varieties of sweet potatoes 35
Cost of production and returns 38
Uses of sweet potatoes 38

ILLUSTRATIONS.

Page.
Fig. 1. Map showing range of production of sweet potatoes 4
2. A good hill of sweet potatoes 5
3. A one-horse fertilizer sower in operation 8
4. A manure-heated hotbed 11
5. A kiln or furnace heated bed 11
6. Cross section of pipe-heated plant bed 12
7. Sweet potato sets, or "drawings" 15
8. Roller for marking distances to plant 18
9. Drag or rake marker 19
10. A trowel and a dibble used in setting plants 19
11. Setting sweet potato plants by hand 20
12. Tongs, shovel, and forked dibble for setting plants 21
13. Transplanting machine in operation 22
14. A field of sweet potatoes after the vines have practically covered the ground 23
15. Device for hilling previous to "laying by" 24
16. Sweet potato affected with black-rot 25
17. Spading fork adapted for digging sweet potatoes 27
18. Special plows for digging sweet potatoes 27
19. Section of outdoor pit 29
20. Outside cellar 30
21. Cross section of large storage house 31
22. Wagon and baskets adapted for transporting sweet potatoes 32
23. Sweet potato barrels and device for pressing the heads into place 35
24. Some of the commercial types of sweet potatoes 36

. I.—359.

SWEET POTATOES.

INTRODUCTION.

Vith the passing of each year the sweet potato is becoming of ater importance as a commercial truck crop in the United States. ring a long period it has formed one of the principal sources of ⲕd for the people of the Southern States and of tropical America. a commercial truck crop the sweet potato would be included ong the five of greatest importance, ranking perhaps about rd in the list. As a food for the great mass of the people living the warmer portions of our country the use of this crop is ex- ded by hominy and rice only. In many of the islands of the cific, especially in the Philippines, the sweet potato is the principal getable food for large numbers of the lower classes, at certain sons being almost the only food available.

Γhe sweet potato industry in this country is readily divided into o classes of production: (1) For home use and (2) for market. quantity sufficient for home use can be grown under a wide range conditions, while production on a commercial scale is somewhat tricted by climate and soil and also by market and transportation ilities. The larger eastern markets are now well supplied, but re are sections where the people have not as yet become accus- ned to the use of sweet potatoes in large quantities. The field the production and use of sweet potatoes is very broad, and s crop promises to become of more general farm importance.

n view of the constantly increasing interest in sweet potatoes is the purpose of this bulletin to give simple cultural directions ering their production both for home use and for market, in- ding the soil and its preparation, the propagation of the plants, nting, harvesting, storing, and marketing, together with the s of sweet potatoes for stock feeding and for similar purposes.

Γhe sweet potato is of a tropical nature, its original home probably ng the West Indies and Central America. The true sweet potato, we have it growing in the United States, belongs to the morning- ry family, its botanical name being *Ipomoea batatas*. Through-

324

out the Southern States the s moist flesh are commonly known as "yams" a flesh as sweet potatoes. The name "yam" is m erly belongs to a distinct class of plants that are fined almost entirely to the Tropics.

AREAS ADAPTED TO SWEET POTATO CULTURE.

Owing to the tropical nature of e sweet potato it naturally thrives best in the South Atla d Gulf Coast States, but it may be grown for home use as far h outhern New York and westward along that latitude to the Ro Mountains. The areas suited to commercial production, as indic by the shaded portions of the map shown as figure 1, extend from New Jersey southward and westward to Texas, and are found again in the central valleys of California. In the Mississippi Valley the commercial area extends as far north as the southern part of Iowa, Illinois, and Indiana. The region around Louisville, Ky., is noted for excellent crops of sweet potatoes.



FIG. 1.—Map showing range of production of sweet potatoes. The shaded portion represents the area adapted to commercial growing. The dark line represents the northern limits of sweet potato culture for home use.

CLIMATIC CONDITIONS REQUIRED.

The climatic requirements for the production of sweet potatoes on a commercial scale are (1) a growing period of st four and a half months without frost, (2) warm nights dant sunshine during the day, and (3) a moderate rainfal the growing period.

here irrigation is depended upon for the supply of moisture, the test quantity of water should be applied between the time the ts are set in the field and the time when the vines practically r the ground. If too much water is applied during the latter of the season the result may be an abundant growth of vine and all yield of stringy potatoes. For some time before harvesting crop the water should be withheld altogether, in order that the s may ripen properly.

he climatic conditions prevailing throughout the shaded portion he map (fig. 1) are well suited to the requirements of the sweet to, except that irrigation is necessary in the western part, includ- a portion of Texas.

CHARACTER OF SOIL ADAPTED TO SWEET POTATOES.

weet potatoes thrive on a moderately fertile sandy loam which not contain an excess of organic matter. They are frequently n upon almost pure sand, especially where the subsoil is a yel- clay. Soils containing considerable calcium or underlain with stone are well ted to the ving of the . The sweet to is excep- al in that a y good crop be grown n soils that are poor for the luction of the ority of farm s. Sweet po- es yield a fair on the "worn-' tobacco and on lands of the th, especially n used in a tion including e leguminous for increasing humus in the soil. Like many other crops, the sweet potato ves on newly cleared land, but the crop should not be planted inuously in the same place. With the sweet potato, as with r crops, rotation is the keynote of success.



FIG. 2.—A good hill of sweet potatoes. To be perfect the lower ends of some of the larger potatoes should be more rounded.

Good drainage is essential, the ting upon high ridges being for the purpose of ura age. The surface soil should extend to a de o 8 and the subsoil should be of such a nature that it ll carry off excessive moisture without leaching away the fertil s a lied to the land. Too great a depth of loose surface soil or an luv l soil having no subsoil will produce long, irregular potatoes are undesirable for marketing. Planting upon land having a loo dy surface soil underlain by a well-drained clay subsoil will to produce the type of rather thick, spindle-formed potato that con nds the highest price. This type is illustrated in figure 2, which shows a hill containing five marketable potatoes. The depth of plowing is a prominent factor in the preparation of land for sweet potatoes, and on soils of too great depth before the subsoil is reached very shallow plowing should be practiced, leaving the soil firm beneath, against which the roots must force their way. If the surface soil is of insufficient depth, it should be gradually increased by plowing a little deeper each year or by subsoiling in the furrow behind the regular turning plow.

FERTILIZERS FOR SWEET POTATOES.

As already noted, the sweet potato will thrive on soils that are only moderately fertile. The root portion of the plant is the part having the greatest value, though the foliage and vines have some value as food for certain kinds of stock. It has been found that an excessive amount of organic matter in the soil will frequently produce an abundant growth of vines at the expense of the roots. It has also been noted that the potatoes will be small and the yield unsatisfactory on soils that do not contain sufficient organic matter to produce a fair growth of vine.

USE OF STABLE MANURE.

The use of stable manure as a fertilizer for sweet potatoes is recommended on lands that are deficient in organic matter. Heavy applications of fresh manure shortly before planting the land to sweet potatoes will stimulate not only the growth of weeds but also of the vines at the expense of the roots. Well-rotted stable manure may be used at the rate of 10 to 15 cartloads to the acre, spread broadcast or beneath the ridges and harrowed into the soil, but it is always well to apply the manure with the crop grown the previous season. By this method the manure will become thoroughly incorporated with the soil and become somewhat reduced before the sweet potatoes are planted upon the land.

Stable manure will be found most beneficial out soils, but on the more fertile soils its use should be l the method of application carefully studied. In some t e the organic matter in the soil is insufficient all kinds of vegetable matter, including manure, pine needles, corn fodder, straw, and stubble, are turned into the land to bring up the fertility. The sweet potato vines will go a little way toward keeping up the organic matter in the soil, but have a souring tendency and should be accompanied with a moderate application of lime or plaster.

Leguminous plants grown as cover crops or in the rotation will serve to keep up the organic matter in the soil the same as stable manure. Sweet potato growers are coming to realize the value of crimson clover for use in the rotation in which sweet potatoes are grown. If the land is planted to corn, crimson clover may be sown in the alleys at the time the corn receives its final cultivation. This will provide a covering for the land during the winter, and as the crimson clover starts into growth quite early in the spring a heavy crop is produced by the time it is necessary to plow the land for sweet potatoes. In order to secure the best results the crimson clover should be turned under not later than the appearance of the first blooms; if allowed to remain longer the stems become tough and do not decay quickly enough to be of benefit to the sweet potato crop which follows.

USE OF COMMERCIAL FERTILIZERS.

The sweet potato is one of the few of our crops that thrive equally as well (or better) upon commercial fertilizers as upon stable manure. A fertilizer for use on the majority of sweet potato lands should contain 3 to 6 per cent of nitrogen, 6 or 7 per cent of phosphoric acid, and 8 to 10 per cent of potash. Every grower should make a study of the requirements of his soil and apply the fertilizer that will give the best results. Many growers purchase the ingredients and mix their own special fertilizers, or use a standard fertilizer as a base and increase the percentage of certain elements by adding high-grade elementary ingredients. Some soils require that certain elements should be in a more available form than others; in the case of nitrogen it is often desirable to have a portion of that contained in the fertilizer quickly available and the remainder more slowly in order to feed the plants throughout the season.

A mixture adapted to the growing of sweet potatoes on most soils may be made by combining the following:

200 pounds of high-grade sulphate of ammonia, 25 per cent pure.
200 pounds of dried blood, or 300 pounds of fish scrap.
1,200 pounds of acid phosphate, 11 per cent pure.
400 pounds of high-grade muriate of potash, 50 per cent pure.

This mixture contains approximately 4.25 per cent of nitrogen, 6.6 per cent of phosphoric acid, and 10 per cent of potash. Nitrogen in two forms is present, the dried blood being quickly available and sulphate of ammonia more y, e later in the season when the potatoes are for n

Experience has demonstra l an abundance of potash in the fertilizers f potatoes. In experiments with fertilizers for this crop an in d yield of from 40 to 60 per cent has been noted on plots liberal application of potash had been made in comparison w p to which no fertilizer was applied. In most cases the hig y s secured where a complete, or balanced, fertilizer is .

QUANTITY AND TIME OF APPLYING COMMERCIAL FERTILIZERS.

The quantity of fertilizer that may be profitably applied will be governed entirely by local conditions. Many growers do not depend upon commercial fertilizers, but merely apply from 200 to 300 pounds to each acre as a supplement to the organic matter and natural fertility of the soil. Others apply from 300 to 1,000 pounds according to the condition of the soil, while a few growers use a ton to the acre. The general rule is to apply the fertilizer in the row where the crop is to be grown, but where large quantities are used it should be distributed at least ten days before planting and thoroughly incorporated with the soil. An application of 1,000 p f high-grade fertilizer placed in the row at planting time h wn to injure seriously or kill the plants. Hand and one-h buters, similar to that shown in figure 3, which merely ilizer in the



FIG. 3.—A one-horse fertilizer sower in operation.

row, are in use. Others are designed to scatter the fertilizer and work it into the soil, and tools that mark the land, sow the fertilizer, and throw up the ridges at one operation can be obtained. For the best results the fertilizer should be applied at least ten days before planting, or a portion of the fertilizer may be applied a month or more in advance and the remainder at the time of preparing the land for planting.

USE OF HARDWOOD ASHES AS A FERTILIZER.

Hardwood ashes are desirable for use on sweet potato land and may be applied at the rate of from 1,200 to 2,000 pounds to the acre. Th[illegible]alue of wood ashes depends upon how much they have become leached, but hardwood ashes should contain from 6 to 8 per cent of available potash. Wood ashes also contain considerable lime.

USE OF LIME ON SWEET POTATO LAND.

Where large quantities of any green crop are plowed into the soil there is a tendency to sourness, and occasional applications of from 1 to 2 tons of lime to the acre are beneficial. The presence of an abundance of lime in soils devoted to the growing of sweet potatoes hastens the maturity of the crop and increases the yield. On poor soils the lime and potash work together to produce potatoes of uniform size and shape, but on rich or alluvial soils the tendency is toward the production of over-large and irregular roots. The lime should be applied the previous season, or at least the autumn before planting the land to sweet potatoes.

PROPAGATION OF PLANTS.

The more common varieties of the sweet potato have for a great many years been propagated by cuttings, or sets, taken either from the potatoes themselves or from growing vines, and as a result the plants have ceased to flower and produce seed. The greater portion of the commercial crop is grown from sets, or "draws," produced by sprouting medium-sized potatoes in a warm bed of soil. In the Southern States the seed potatoes are frequently cut into pieces in the same manner as Irish potatoes and planted in the row where they are to mature. Where several plants appear in one hill they are thinned, and those removed are used for planting other land. In the South Atlantic and Gulf Coast States the sweet potato is frequently propagated by making vine cuttings. A comparatively small bed of seed potatoes is planted quite early and the sets so produced are used to plant a small patch from which vine cuttings are taken later by the cartload for planting large fields. In the southern parts of Florida and Texas and on the South Sea Islands the potatoes may remain in the soil from year to year, being dug only as required for use, those remaining over producing the sets for the following season's planting.

Where only a small area of sweet potatoes is to be grown for home use, the necessary plants can generally be secured from some one who makes a business of growing them. If an acre or more is to be planted it will in most cases be more economical to prepare a bed and grow the plants. The method of starting the plants will depend upon the locality and the acreage to be planted, the essentials being a bed of warm earth and a covering to protect the young plants during the early springtime.

SELECTION OF SEED.

The care of the seed potatoes during the winter is discussed later under the head of storage of sweet potatoes.

The potatoes that are to serve as seed from which to grow the plants for the next season's crop should always be selected at the time of digging and housing the crop. For seed purposes it is the custom to select the medium or under-sized potatoes, such as are too small for marketing. Those potatoes that will pass through a 2-inch ring or can be circled by the thumb and first finger of a man having a hand of average size are used for seed purposes.

The seed potatoes should be uniform in size and of the shape desired in the following year's crop. The seed should be free from cuts, bruises, decay, or disease of any kind. Throughout the handling of the seed potatoes they should not receive any treatment that would break eggs. The seed should always be handled and kept separate from the regular crop.

The oftener the seed is handled the greater the danger of decay, and it should not be sorted over until everything is ready for bedding.

The best seed is grown from cuttings taken from the regular plants after they have begun to form vines. These cuttings produce large numbers of medium or small-sized potatoes that are free from diseases and adapted for use as seed the following year.

MANURE-HEATED BEDS.

The ordinary hotbed is now in too common use to require a lengthy description and as constructed by many of the sweet potato growers of the eastern shore of Virginia it consists of one or more long, narrow beds similar to those shown in figure 1.

The hotbeds are generally located where they will have protection on the north by a piece of pine woods, a hill, or buildings, and where no natural protection is available a wind-break consisting of pine boughs or corn fodder is usually erected. In preparing the hotbed, 8 to 12 inches of fresh horse manure are first trampled into the bottom of the excavation, and as soon as this has begun to heat 3 or 4 inches of sandy loam are spread evenly over the manure. The sash or other covering is then put on and the bed allowed to stand until the temperature of the manure falls to about 80° or 85° F. before the seed potatoes are put in.



FIG. 4.—A manure-heated hotbed, showing the sash removed and piled where they can be easily placed upon the beds in case of danger from frost. Note the pine woods to the north and west of the plant beds.

KILN OR FIRE HEATED BEDS.

Where large numbers of plants are required and there is difficulty in procuring good manure for hotbed purposes, a large bed may be constructed with arrangements for supplying the heat by means of a brick furnace or a stove. An idea of the general plan of a bed of this kind can be most easily gained by reference to figure 5.

The side walls should be of stone, concrete, or brick, and a floor of boards upon timber supports is essential. From 4 to 6 inches of fine soil are placed upon the floor before bedding the potatoes, and a covering of about 3 inches of sifted soil or leaf mold is then added. The furnac



FIG. 5.—A kiln or furnace heated bed. (Redrawn from Bailey's Cyclopedia of Agriculture.)

should be so constructed that it may be fired from the outer end or just inside a door opening into the space beneath the bed. The brick furnace extends a few feet only and connects with one or more 6-inch chimney tiles which carry the smoke toward the rear for a distance of 25 or 30 feet and discharge it into the open space beneath the floor. At the opposite end from the furnace a wooden chimney collects the gases and carries them to the open air. Owing to the moisture absorbed from the soil by the flooring, there is very small danger from fire, but if wood is used for fuel it may be well to place a screen of wire over the openings of the tiles in order to prevent the passage of sparks.

In order to secure a uniform temperature under all parts of the bed, it may be desirable to cover the furnace and horizontal chimney tiles with earth and to so construct the bed that there will be a gradual rise of the floor toward the chimney end.

PIPE-HEATED BEDS.

Where a steam or hot water boiler is in use for greenhouse or residence heating, a very satisfactory plant bed can be constructed by burying four or five lines of pipes in the soil beneath the bed and supplying the heat from the boiler. This has been found to be an ideal method, as the lines of pipes can be controlled by valves and the temperature of the soil in the bed kept at the desired point. If hot water heat is used the pipes should be laid with the soil in direct contact with them, but for steam the pipes should be surrounded with 3-inch or 4-inch tiles to prevent too rapid passage of the heat and the consequent burning of the soil. The pipes should be placed 10 or 12 inches below the bottom of the special soil in the bed, and 14 to 16 inches below the line of the seed potatoes. If the pipes are laid 18 inches apart an even distribution of heat will be secured. For hot water heating, 2-inch pipes should be employed, but 1¼-inch pipes will be large enough for steam, provided the lines are not more than 60 feet in length. The lines of pipe should be carefully graded and have a uniform fall toward the return end; in fact, the rules governing greenhouse heating apply to the piping of beds of this kind. A general idea of the construction of a pipe-heated bed may be gained from the cross section shown as figure 6.



FIG. 6. Cross section of pipe-heated plant bed. A, natural soil; B, hot water or steam pipes; C, sifted sandy loam or leaf mold.

COVERINGS FOR PLANT BEDS.

Throughout the Gulf Coast and South Atlantic States it may not be necessary to provide a cover to retain heat or protect the plants from cold, but farther north some form of cover should be provided. In the northern part of the sweet potato district glazed hotbed sash, each about 3 by 6 feet in size, are most commonly used. In warmer sections a covering of light canvas or heavy muslin will be sufficient for the protection of the plant bed. Where sash are used they should always slope to the south, in order to admit the greatest amount of light. A canvas or muslin cover should be supported either upon laths or wires in such manner that water will drain off and not form puddles and drip upon the bed. Provision should also be made for rolling up the canvas on bright days to admit sunlight and secure ventilation.

Toward the end of the time that the plants are to remain in the plant bed the amount of ventilation should be increased by leaving the cover off a greater portion of the time, in order to harden the plants to outdoor conditions. After a time the covering may be left off all the time, but it should be kept where it can be put on quickly in case of a late spring frost. No matter how well the sweet potato plants are accustomed to open-air conditions they will be injured by the slightest frosting. The covering for the plant bed will last many years if stored in a dry place during the period that it is not in use. A roof of boards or paper will serve as a covering for the plant bed, but these materials are not so easily handled as are the sash or canvas. Where no regular covering material is available its place may be taken by a layer of fine straw or grass spread evenly over the surface of the bed.

Some growers follow the practice of spreading about 3 inches of fine, fresh horse manure over the bed as soon as the sweet potatoes are bedded; this serves both as a covering and to retain the moisture. When the sprouts begin to appear, a portion of the manure must be removed to prevent the plants from becoming too long and slender.

BEDDING THE SEED.

In the warmer portions of the sweet-potato-growing district the seed should be bedded when danger of frost has passed. In the northern portion of the area the seed should be placed in the hotbed from the 20th of March to the 10th of April, after the temperature of the bed has fallen to 80° or 85° F. and become regular.

If possible, select a warm, sunny day for this work, in order that the seed potatoes and the bed may not become chilled. The soil to be used for covering the potatoes should be sifted beforehand and placed in piles in the bed, where it will have become warm and in good condition for use. Leaf mold is perhaps the best material with to cover the potatoes, but where this can not be obtained a fine, rich, sandy loam is the best substitute.

Before placing the seed in the bed, an inch or more of the finely sifted covering material should be spread evenly over the surface of the regular soil in the bed. The potatoes are spread upon this bed, each one being placed by hand so that they will not touch, and about one-half of the bed surface is covered. If extra large potatoes are employed for seed they may be split lengthwise and placed with the cut side down in the bed. When the potatoes are in place, cover them to a depth of about 3 inches, water by using a sprinkling can, and then watch the temperature of the bed carefully until the potatoes have formed an abundance of sprouts.

TEMPERATURE OF THE PLANT BED.

As noted above, the temperature of the plant bed should be about 80° or 85° F. at the time the seed is bedded, and should gradually fall until it remains stationary at 58° or 60° F. at the end of six weeks, or before planting-out time. A thermometer should be kept plunged in the soil of the bed and the temperature noted every day for the first ten days or two weeks. If the manure hotbed is not located in a well-drained situation there is danger of soil water getting in with the manure and either destroying the heat altogether or starting a second fermentation which will cause the temperature to run too high and injure the potatoes. The air temperature beneath the sash or other covering should run between 60° and 80° F., and during bright days it must be controlled by ventilation. As the time for planting in the field or garden draws near, the plants should be given more exposure to harden them to outdoor conditions.

MOISTURE REQUIREMENTS OF THE PLANT BED.

The amount of water required by the plant bed will depend somewhat upon the method of heating employed. With a steam-heated or furnace-heated bed more watering will be necessary than if the ordinary manure hotbed is used. The watering given when the potatoes are bedded will generally be sufficient to last for several days, but after the plants begin to form leaves and the cover is left off during the greater part of the day, watering will be necessary every day. The water should never be poured on in a solid stream, but by means of a sprinkling can or a rose, or nozzle, on the end of a hose. Where very large plant beds are employed it will be necessary to keep some one in almost constant attendance to care for the watering, heating, and ventilation. The success of the crop depends largely upon the character of the plants, and proper management of the plant bed is essential to the production of the right kind of plants.

"DRAWING" THE SETS.

As a general rule sweet potato plants are set in the field shortly after a rain. In order to avoid delay in planting, the hands should begin to get out the sets as soon as the rain ceases falling and place them in crates or baskets ready for transportation to the field. The sets are not all produced at once, and only those that have formed good roots are "drawn," the others being left until later. In "drawing" the sets the seed potato is held down with one hand while the plants are removed with the thumb and finger of the other hand. It often happens that five or six plants will cling together at the base, and these should be separated in order to avoid loss of time in the field. Where plants are to be set with a transplanting machine it is essential that they should be in the best possible shape in order that they may be handled rapidly by the boys who feed the plants into the machine. The roots should all be kept in one direction, and if the tops are long or irregular they may be trimmed off even by means of a knife.



FIG. 7.—Sweet potato sets, or "drawings."

While "drawing" the sets it is a good plan to have at hand a large pail or a tub containing water to which there has been added a quantity of clay and cow manure which has been stirred until it forms a thin slime. As the plants are pulled from the bed they are taken in small bunches and their roots dipped into this mixture. This process, termed "puddling," covers the roots with a coating which not only prevents their becoming dry in handling but insures a direct contact with the soil when they are planted in the field or garden. Figure 7 shows four sets that are at slightly different stages of growth; those on the right are in prime condition for planting. After removing the sets that are ready, the bed should be watered to settle the soil where it has become disturbed and then left for the younger plants to develop.

PACKING PLANTS FOR SHIPMENT.

In preparing sweet potato plants for shipment or for sale, they are "drawn" from the bed and tied in bunches of 100 each with soft string. Sweet potato plants will not withstand excessive moisture and should always be packed while the tops are dry. A little damp moss or paper may be placed in the crate or basket and the roots bedded in it, but the tops should remain dry and have free ventilation. If the roots of sweet potato plants are carefully puddled without the mixture coming in contact with the tops, they will keep in good condition for a week or ten days.

PREPARATION OF LAND FOR SWEET POTATOES.

The character of soil devoted to sweet potato culture is generally quite easy to prepare. In preparing land for planting to sweet potatoes the plowing and fitting are practically the same as for corn. It should be borne in mind, however, that the work necessary for thorough preparation will be well repaid by the increased ease in handling the crop later. It is always desirable that a crop like sweet potatoes be grown as a part of the regular farm rotation. In the northern portion of the sweet-potato-growing area the crop will occupy the land the entire growing season, and a three or four year rotation should be practiced. Where the climate will permit, a crop of early snap beans, peas, or cabbage may precede the sweet potatoes, but in any case the land should not be planted to sweet potatoes oftener than once every three years. A good rotation is to devote the land to corn one year, sowing crimson clover in the alleys between the rows at the time the corn is given the last cultivation. During the following spring the crimson clover should be turned under and sweet potatoes planted; then in the autumn, after the potatoes are harvested, the land may be plowed, fitted, and sown to rye or winter oats with plenty of grass seed. In this way a crop of grain may be obtained during the time that the grass is becoming established. Allow the land to remain in grass one or two years and then repeat the rotation. Where corn is followed by sweet potatoes in the rotation, stable manure should be applied while fitting the land for the corn, and commercial fertilizers should be applied with the sweet potato crop.

As previously mentioned, the depth of plowing has considerable influence upon the character of the product. The usual depth of plowing in preparing land for corn will prove satisfactory for sweet potatoes. The fact that sweet potatoes are not planted in the field until quite late in the spring makes it possible for the grower to select a time when conditions are favorable for the preparation of the land. Plowing may be deferred until the soil has become sufficiently dry to break up fine and mellow. It is important that the land should be harrowed within a few hours after plowing; further fitting may be deferred until later, and if the soil is inclined to be lumpy the work of pulverizing may best be done shortly after a shower and while the lumps are mellow. When the primary work of preparation is finished, the soil should be mellow to a depth of 6 or 7 inches and the surface smooth and even. Subsequent handling of the soil preparatory to planting will depend upon whether ridge or level culture is to be followed.

APPLICATION OF FERTILIZERS.

For the general good of the land commercial fertilizers should be applied broadcast, but the majority of farmers feel that they can not afford to do this and that the quantity that they are able to apply will give greater returns when placed in the row. This is a matter for the decision of each grower and will depend greatly upon the capacity of the soil under consideration for retaining fertilizers from year to year.

PREPARATION FOR PLANTING.

After plowing and fitting the land it is generally allowed to lie several days before being put in shape for planting. If level culture is to be practiced, the only thing necessary will be to run the harrow over the soil once and then mark in both directions at the desired distances for planting. The marking is generally done with either a one-horse plow, a flat-soled marker, or a disk marker. The disk marker is well adapted to this work, as it throws up a slight ridge which furnishes fresh earth in which to plant. Some growers who practice level culture mark the ground with a small one-horse plow and throw up a slight ridge upon which to plant; behind the plow a roller is used to compress this ridge to a low, flat elevation.

Where the more universal ridge method of planting is employed the soil is thrown up by means of a turning plow.or a disk machine. The ridges should be made at least one week before planting, in order that the soil may become settled and compact. The majority of sweet-potato growers make the ridges whenever the land is in good condition to work and then either roll or drag the tops just ahead of the planters. By using a roller similar to that shown in figure 8 the ridges at one operation can be rolled and marked the proper distances for planting. A drag suitable for smoothing the tops of the ridges can be easily constructed by cleating together three pieces of 2 by 4 inch scantling.



FIG. 8.- Roller for marking distances to plant.

SETTING THE PLANTS.

The success of the crop depends largely upon the way in which the plants start after being removed from the bed and set in the field or garden. Practical growers always plan to set the plants during a "season" or period when the conditions are suitable to a quick start into growth, either just before a rain or as soon afterward as the soil can be worked. The method of setting will depend entirely upon local conditions and the acreage to be grown, the essential features, however, being to get the roots in contact with moist earth and the soil firmly pressed about the plants.

The use of water around the roots of the plants is desirable under most circumstances, as it not only moistens the soil but assists in settling it about the roots. A large quantity of water is not necessary, one-half pint to each plant being generally considered sufficient.

DISTANCES TO PLANT.

Where level culture is practiced, the plants are set from 24 to 30 inches apart in each direction. On the eastern shore of Virginia the greater portion of the crop is planted 24 inches apart each way, requiring about 11,000 plants to an acre. By planting 30 inches apart each way, only about 7,000 plants are required to set one acre. Where the crop is grown on ridges it is customary to have the ridges from 36 to 42 inches apart from center to center and to place the plants 14 to 18 inches apart in the row. By this method an acre will require from 8,000 to 12,500 plants. An acre of good sweet potato land will readily support 9,000 to 11,000 plants, and the number most commonly planted by the several methods will fall within these figures.

When planting for level culture the location of the plants will be indicated by cross marks, but for planting upon ridges it is necessary to provide some means of indicating the distances. This may complished in several ways, but a roller of the type shown in e 8 having cleats nailed at equal distances around its surface esirable and serves the purpose of both rolling and marking idges. Another device onstructed along lines lar to those of the ordi- wheelbarrow, pegs be- placed upon the rim of vheel to mark the plant- listances. In using the elbarrow marker it is ly pushed along the of the ridge. Another ce of this class is con- ted by placing three our wheels upon a long and drawing it with a e, the wheels being so nged that they can be t any point on the axle rovide for change in h of row.



FIG. 9.—Drag or rake marker.

very cheap and effi- ; marker can be constructed of 1 by 3 inch laths, as shown in e 9. This marker can be used to indicate planting distances g one row, or by draging it across the ridges the entire field can be marked before beginning to plant. The machine transplanters are provided with a spacing device which indicates the distance between plants; also with a row marker to show the location of the next row.



10.—A trowel and a dibble used in setting plants.

SETTING BY HAND.

Where a few hundred plants are to be grown for home use or if only an acre or two are to be planted, the hand method of planting will answer every requirement. A trowel or a dibble, as shown in figure 10, sed for opening the soil to receive the plant, and the earth is d about the roots by a second thrust with the implement, or eel of the shoe is used to press the earth about the plant. For l planting, the plants are dropped ahead of the "dibblers" by and girls. Seven thousand to ten thousand plants, or an is an excellent day's work for a planter when everything is in good condition. Where a few hundred plants are set in the garden it is always desirable to water them before closing the earth about the plant. Figure 11 shows the method of planting by hand.



FIG. 11.—Setting sweet potato plants by hand.

PLANTING WITH TONGS.

Setting by hand is at best a back-breaking process, and numerous devices have been invented to save the bending of the body in hand planting. One of the simplest of these is a pair of wooden tongs with which the plant can be caught by the root and thrust into the soil. The plants are either dropped ahead or carried in a small basket strapped to the waist of the operator. The tongs are provided with a spring to throw the jaws apart, and are held in one hand while the plants are inserted with the other hand. In case the plants are dropped ahead, the root portion is grasped between the points of the tongs without the use of the hand.

An implement, known as a shovel, which is sometimes used in conjunction with the tongs, consists of a piece of lath sharpened to a flat point. This is used to open a hole in the soil ready for the plant. In using the tongs and shovel, the plants are dropped as for hand planting. The person doing the setting carries the tongs in the left hand and the shovel in the right. The plants are picked up by means ıe tongs, while a hole is made by inserting the shovel in the soil ıe point where the plant is to be set. The plant is then inserted the earth closed about it either by a second thrust of the shovel y the foot of the operator. A man who is expert in the use of ; homemade tools can set plants quite rapidly without bending ›ody sufficiently for the work to become tiresome.

tool that is sometimes employed where vine cuttings are planted .ong dibble or a cane having a notch covered with cloth or leather ıe lower end. The droppers lay the cuttings across the row at ›roper distances and the planters place the notch over the middle ıe cutting and force it into the soil with both ends protruding. eneral idea of these devices may be ed from figure 12.



Fig. 12.—Tongs, shovel, and forked dibble for setting plants.

SETTING WITH MACHINES.

here a large acreage is grown, the work etting the plants in the field is greatly itated by the use of transplanting ma-es, of which there are several makes ı the market. The essential features hese machines are a device to open a l furrow, a tank for the supply of r, and disks or blades for closing the about the plants. With a transplant-machine it is not necessary to wait for season," as the machine automatically ws a small quantity of water around roots of each plant as it is being set. perating these machines it is necessary ave a steady team and two active boys are trained to drop the plants at er intervals, as indicated by a spacer he machine. Under reasonably favor-conditions, a machine will plant from 4 acres a day. In addition to being r savers, these machines do the work r and more uniformly than it is ordinarily done by hand. ıe plants can be set without the use of water, but the results are satisfactory where the water is used. A number of our most essful growers use water when setting after a rain, claiming that water has the effect of settling the soil firmly about the roots of plants and that they start into growth much more quickly. re the full amount of water is used it will be necessary to pro-a man and team to haul the water to the machine, but by this method plants may be set during dry weather without the loss of more than one plant out of every one hundred.

The majority of the transplanting machines are designed for planting either on the tops of ridges or on the level. The cost of setting an acre with one of these machines, using water, should be figured



FIG. 13.—Transplanting machine in operation.

on the basis of two teams with drivers and two boys for a period of three or three and one-half hours. If water is not used there will be a saving of at least one team and driver; also the time required for filling the tank on the machine. A transplanter in operation is shown in figure 13.

CULTIVATION OF SWEET POTATOES.

The methods of handling a crop of sweet potatoes do not differ materially from those employed with ordinary farm and garden crops. Within a few days after planting, a sweep or one-horse plow should be run in the alleys to break out the strip of earth left in ridging. The loose earth in the alleys should be worked toward the rows until a broad, flat ridge is formed upon which a small-tooth cultivator can be run quite close to the plants. After each rain or irrigation the soil should receive a shallow cultivation, and during dry weather frequent cultivations are necessary in order to retain moisture. About two hand hoeings are generally necessary in order to keep the rows free from weeds and the soil loose around the plants. As hand labor is expensive, it should be the aim to perform the greater part of the work by means of horse tools. Where sweet potatoes are planted in check rows and worked in both directions the hand work required will be reduced to a minimum, but a certain amount of hoeing is always necessary.



FIG. 14.—A field of sweet potatoes after the vines have practically covered the ground.

When the vines begin to interfere with further cultivation the crop may be "laid by," i. e., given a final working in which the soil is drawn well up over the ridges and the vines then allowed to take full possession of the land, as shown in figure 14. To do this it is often necessary to turn the vines first to one side of the row and then to the other by means of a stick or a wooden rake. After "laying by," very little attention is required until time for harvesting the crop.

TOOLS ADAPTED TO SWEET POTATO CULTIVATION.

Aside from planting and harvesting, the work of caring for a crop of sweet potatoes can be done almost entirely by the use of ordinary farm and garden tools. A two-horse riding cultivator is desirable for the general cultivation, and one having disks instead of hoes will serve for throwing the soil toward the rows. For the work of "laying by," a single-row celery hiller is suitable, or a one-horse sweep-stock can be fitted with sloping bo this purpose, as shown in figure 15. Many growers -horse turning



FIG. 15.—Device for hilling previous to "laying by."

plow for the final cultivation, going twice in each alley and working the soil toward the plants.

DISEASES.

The sweet potato is subject to injury from a number of diseases. Those diseases causing rot and decay are most prevalent and result in the greatest loss during the period that the crop is held in storage. Occasionally, however, the crop may be lost before harvesting, and one form of rot, known as black-rot, destroys the young plants, attacks the potatoes while they are in the ground, and causes them to decay while in storage. The spores that are responsible for the several forms of rot affecting sweet potatoes may remain in the soil from year to year, or they may be carried over winter upon the seed. Diseases are generally introduced with affected seed or plants, and when once established in the soil, the storehouse, or the propagating bed it is doubtful whether they can be eradicated except by the adoption of the most thorough methods.

BLACK-ROT OF THE SWEET POTATO.

As the black-rot (*Ceratocystis fimbriata*) y distributed and destructive, it is perhaps the only dise l cause great difficulty. The black-rot may be easily n the young plants either in the form of a blackened and shriveled condition of the terminal buds or as small black spots on the main portion of the root. On the potatoes this disease first appears as brown patches upon the surface. These patches are generally quite irregular in outline and spread rapidly until the entire surface is covered. As the patches enlarge, the central portion becomes darker, often almost black. The presence of black-rot upon the potatoes can usually be detected at digging time, or more certainly when selecting the seed for bedding in the spring. Some idea of the appearance of this disease can be gained from figure 16.



FIG. 16.—Sweet potato affected with black-rot: A, appearance of disease on potato; B, plant affected with black-rot. (Redrawn from Halstead, Bulletin 76, New Jersey Agricultural Experiment Station.)

OTHER DISEASES OF THE SWEET POTATO.

A disease known as stem-rot causes the stem of the plant to begin to die at the surface of the ground. This decay gradually extends downward to the potatoes and frequently kills the entire plant.

The diseases known as soft-rot, dry-rot, and white-rot are all similar in their method of attack to the black-rot. One form, known as soil-rot, causes the loss of the crop while it is in the field. Each of these diseases is caused by a particular fungus, but has received the common name suggested by its general appearance or some marked characteristic. Any one of the diseases of the sweet potato may be present without causing severe loss provided conditions are unfavorable to its development, and growers should be constantly on their guard to prevent the spread and development of diseases.

PREVENTION AND CONTROL OF SWEET POTATO DISEASES.

The diseases of the sweet potato have been under observation for many years, the New Jersey Agricultural Experiment Station having published a bulletin[a] upon the subject in 1890, and this work has been supplemented by the results gained by numerous observers. The diseases of the sweet potato are now widely disseminated, and one or more of them may at any time prove destructive.

A system of crop rotation by which the land will not be planted to sweet potatoes oftener than every four or five years is the first step toward disease control. Care in the selection and keeping of potatoes intended for propagation is of importance, while clean cultivation and proper handling at the time of harvesting are essential. Diseases will generally make their first appearance upon cut, broken, or bruised potatoes, and all that are in any respect injured should be stored separately from the seed and perfect stock. The storage house should be cleaned and fumigated with sulphur or formalin before storing begins, and all crates or baskets used for handling the crop should be in the house during the fumigation. Potatoes that show evidence of the presence of disease should not be used for propagation, and the hotbed should be cleaned and supplied with fresh soil each season.

---

[a] Bulletin 76, New Jersey Agricultural Experiment Station, by Halstead.

It is very apparent that some varieties are more subject to the attacks of diseases than others. The Big-Stem Jersey and the Jersey group generally are especially subject to disease, while varieties of the Hayman group, such as Southern Queen, are seldom affected.

INSECTS.

The sweet potato is reasonably free from the ravages of insects. Cutworms frequently destroy the young plants after they are set in the field, especially when the land has been in grass the previous season. The sweet-potato borer, which works in the roots, is widely distributed and causes considerable injury in the Gulf Coast States. A small insect known as thrips works on the under side of the leaves during the hot and dry weather of midsummer, but as a rule the real damage caused by this insect is slight.

HARVESTING SWEET POTATOES.

TIME FOR DIGGING SWEET POTATOES.

The harvesting and marketing of sweet potatoes direct from the field begins about the middle of August and continues until the crop is all disposed of or placed in storage for winter marketing. During the early part of the harvesting season the yield is light, but as a rule the prices paid are good. The supply for home use and those potatoes that are to be kept in storage should not be dug until just before frost. In the localities where frosts do not occur until quite late in the season the sweet potatoes ripen and the vines show a slight tinge of yellow when ready for handling.

EFFECT OF FROST ON SWEET POTATOES.

The foliage of the sweet potato is very tender and is easily injured by frost. A light frosting of the leaves will do no harm, but should the vines become frozen before digging they should be cut away to nt the frozen sap passing down to the roots and injuring them. e there is a heavy yield of potatoes the soil is frequently cracked ends of the potatoes protrude above ground and are liable to from severe frost.

n account or rainy weather or for any other the potatoes can not be dug before frost or diately afterwards, the vines should be cut and the potatoes removed at the first opnity. If cold weather continues it may be sary to draw a little extra soil over the hills tect the potatoes, or the vines may be piled idge over the row. A very slight frosting e potatoes will cause them to decay within rt time after being placed in storage.

IODS OF HARVESTING SWEET POTATOES.

digging a small area of sweet potatoes, the ng or potato fork illustrated in figure 17 is le. When digging by hand, the work will eatly facilitated by first throwing a small w from one side of the row by means of a one-horse turning



FIG. 17.—Spading fork adapted for digging sweet potatoes.

The removal of sweet potatoes from the soil in large quanis generally accomplished by the aid of sweet potato diggers or plows of the type shown in figure 18. These implements are provided with two sharp rolling coulters that cut the vines ahead of the plow, and differ from the ordinary plow in having a moldboard that does not turn a furrow and terminates in a number of rods or an extension of the moldboard for separating the potatoes from the soil.



. 18.—Special plows for digging sweet potatoes.

ere no special digging device is available, the ordinary twoturning plow is frequently used, a rolling coulter being beam to cut the vines. After plowing out the sweet p it will be necessary to stir the soil in order to find those that become covered. The machines employed for handling Irish potatoes may be used for digging sweet potatoes, but are not entirely satisfactory for this purpose, as they bruise and otherwise injure sweet potatoes.

It is desirable that the soil should be comparatively dry at the time of harvesting sweet potatoes, and bright, drying weather is essential to the proper handling of the crop. Sweet potatoes differ from Irish potatoes in that they are not so easily injured by sunlight. However, they should not be exposed for any length of time if the sunshine is very warm. During the handling in the field it should be the purpose to remove all soil and surface moisture from the potatoes. Sweet potatoes should not lie exposed upon the surface of the ground during the night.

MARKETING DIRECT FROM THE FIELD.

Where sweet potatoes are grown in large quantities for early marketing it is the practice to dig, pack, and load, all on the same day, direct from the field. As the potatoes are gathered up behind the diggers they are sorted into the various grades and packed into ventilated barrels ready for shipment. When the barrels are packed in the field they are as a rule covered with burlap or similar material. In parts of New Jersey the potatoes are sorted in the field and gathered into five-eighths-bushel baskets, in which they are hauled to the depot platform, where they are packed into barrels and headed. More than one-half of the commercial crop is marketed direct from the field without the use of packing sheds or storage of any kind other than that provided by the transportation companies.

GRADING AND PACKING.

In sorting sweet potatoes preparatory to packing, about four grades are recognized, as fancy, primes, seconds, and culls. Those packed as fancy include only the most select, both in size and shape. The primes include all those adapted to general first-class trade, while the seconds include the smaller and more irregular stock which goes to a lower priced trade. The culls are not marketed unless good stock is exceedingly scarce, and as a rule are used for feeding to hogs.

Sweet potatoes are usually shipped in barrels holding eleven pecks each. Some markets require that the barrels be faced and headed, while for others the tops are slightly rounded and covered with burlap. Small lots of extra-fancy sweet potatoes are sometimes shipped in one-bushel crates having raised tops; also in patent folding crates.

Throughout the process of handling care must be exercised to see that the sweet potatoes do not become bruised, for upon this their shipping and keeping qualities greatly depend.

STORAGE OF SWEET POTATOES.

METHODS OF STORING.

Unlike most perishable products, the sweet potato requires warmth and a dry atmosphere while in storage. The method of storing will depend both upon the locality and the quantity of potatoes to be cared for. The temperature and conditions of a rather cool living room are admirably adapted for keeping sweet potatoes intended for home use in the North, while in the South they may be placed in pits or stored in outdoor cellars. The home supply may be placed in crates and stored in a loft over the kitchen part of the dwelling. Sweet potatoes should not be stored in bags or in barrels without ventilation.

PITS AND CELLARS.

Where large quantities of sweet potatoes are stored for winter marketing, the method employed in the Southern States is to place them in outdoor pits and cellars, while at the North some form of heated storage house will be required. Whether the storage be in pit, cellar, or house, a dry, warm atmosphere with ventilation is essential to good keeping.

Storage pits should be located where the drainage is good. First, a little of the surface soil is thrown back to form a level bed 8 or 10 feet in diameter; then two small trenches crossing each other at right angles in the center of the bed are excavated and some boards laid over these. At the point where the trenches cross, a loosely nailed 4 by 4 inch box is set on end to form a flue up through the potatoes. The earth floor of the pit should be covered with 2 or 3 inches of hay, leaves, or pine straw, and the potatoes piled in a large, conical heap around the ventilator flue. When the heap is of the desired size, the potatoes are covered with hay or pine straw, and soil to the thickness of 5 or 6 inches is added, but the trenches and flue are kept open until it is necessary to close them to keep out the frost. In the South sweet potatoes are frequently kept throughout the winter by this method. A cross section of this type of pit is shown in figure 19.



FIG. 19.—Section of outdoor pit: A, wood box for air shaft; B, trenches for admission of air; C, board covering trench; D, straw or pine needles; E, soil.

OUTDOOR CELLARS.

The type of storage cellar illustrated in figure 20 is extensively used throughout the South. This form of cellar is built entirely above ground and consists of a line of posts through the center supporting a ridgepole upon which is placed one end of planks or puncheons with their opposite end resting on the ground on either side of the ridge. The ends of the inclosure are boarded up, a door being provided in one, and the structure covered with sod to a thickness of 5 or 6 inches. The sweet potatoes are stored upon the earth floor and the door is kept open for a time for ventilation. If the house exceeds a length of 12 or 14 feet, a top ventilator should be provided.



FIG. 20.—Outside cellar. Such cellars are extensively used throughout the Southern States for the storage of root crops.

STORAGE HOUSES.

In the North, where the winters are too severe for the use of the pit and the outdoor cellar, some form of regular storage house is employed. These houses are constructed with frost-proof air-space walls, and provision is made for heating during the curing period and severely cold weather.

The usual method of constructing storage houses is to first put down a concrete foundation, upon which a frame of 2 by 4 inch and 2 by 6 inch scantling is reared. On the outside a sheathing of 1-inch lumber is nailed, preferably diagonally, to add strength to the building. Over this sheathing heavy building paper is applied and a covering of "drop" or "lap" siding put on. The roof may be of tin or shingles, or one of the better grades of prepared paper roof-ing will answer. Inside the building, paper is first tacked to the studding, and then one thickness of ⅞-inch matched lumber is nailed on. The ceiling may be carried upon the rafters or squarely across, with several openings into the space above for ventilation. Where the ceiling is attached to the rafters, it is desirable to first nail 1-inch strips to the rafters and then run the matched ceiling up and down, in order that any condensed moisture will follow down the grooves to the sides of the house rather than drop upon the potatoes.

The floor may consist of boards, concrete, or hard clay. The bins for holding the potatoes may be constructed of 2 by 4 inch scantlings and 1 by 4 inch strips, a convenient size of bin being about 20 feet in length by 12 feet in width and 10 feet deep. The bins should be built 14 to 18 inches away from the outside walls and a 4-inch space should be allowed between the bins. A floor of narrow boards raised a few inches above the regular floor will provide for a free circulation of air through the potatoes. The size and number of bins will depend entirely upon the quantity of potatoes to be stored. For each 100 bushels of potatoes to be stored a space of 125 cubic feet will be required. A bin of the dimensions given above, if filled to a depth of 8 feet, will hold about 1,500 bushels of sweet potatoes.



FIG. 21.—Cross section of large storage house: A, driving shed; B, space between outer walls and potato bins; C, storage bins; D, ceiling ventilators; E, top ventilator; F, bottom ventilator; G, heater pipes.

Brick or concrete storage houses are desirable, but require to be lined with wood in order to be dry and warm. The greater number of storage houses in use are of frame construction, and any building which is dry, which can be properly ventilated, and in which the pr temperature can be maintained will be found suitable for storing sweet potatoes. If a house is built expressly for the purpose it is possible to provide many convenient features, including heating appliances and loading and unloading platforms, and a covered driveway along one side is desirable. Very few windows are required in the storage house, and these should be provided with tight shutters to keep out light and cold. A cross section of the type of storage house in general use is shown in figure 21.

STORING THE CROP.

In housing the crop the potatoes are hauled to the house in five-eighths-bushel baskets or in bushel crates and spread upon special tables for sorting.



FIG. 22.—Wagon and baskets adapted for transporting sweet potatoes from the field to storage house or shipping point.

Where large quantities of sweet potatoes are to be handled from the field to the storehouse or shipping point, it is desirable to employ wagons specially fitted for the purpose. If the road is at all rough, the wagons should be provided with bolster springs to lessen the jolting of the potatoes. A wagon for this purpose should have rather low broad-tire wheels and a shallow box or framework fitted for holding the baskets or crates. The wagon shown in figure 22 is the type used by the growers of New Jersey and is well adapted to the handling of a large number of baskets. For hauling barrels an ordinary hay rack is desirable. The ordinary wagon box, or bed, is not adapted to the handling of either baskets, crates, or barrels.

The seed stock for planting the following year should be selected and stored separately in a small bin. As the potatoes are separated into their respective grades they are put into baskets and carried to the bins.

Some growers prefer to do the grading in the field, but this necessitates the employment of a larger percentage of expert labor and delays the work of getting the potatoes hauled to the storehouse. Women and children can pick up the potatoes in the field, and two or three experienced men can do the sorting and grading at the house in a much shorter time and in a more satisfactory manner.

The most desirable form of table upon which to spread sweet potatoes for sorting consists of a wooden framework over which strong burlap or canvas is stretched. This forms a hollow surface from which the potatoes will not roll or become bruised in handling. The sorting tables should be placed alongside of the unloading platform and where the distance to the storage bins is short. If a shed is provided at the side of the storehouse, the sorting tables should be along the side nearest the bins, the wagons being driven on the outside and the baskets of potatoes to be sorted unloaded under the shed.

Before starting to fill a bin, 2 or 3 inches of dry pine needles, straw, or chaff should be placed upon the floor. Beginning at the back of the bin the potatoes are piled to a depth of 30 or 40 inches until the entire floor space is covered and a number of slats are required to be placed across the doorway opening. A few grain bags filled with straw should be placed upon the potatoes at intervals from front to back of the bin, and upon these planks on which the men may walk while carrying in the next layer of potatoes may be laid. In this way a bin may be filled to a depth of 8 or 9 feet by about three layers. By dumping them in layers the potatoes have an opportunity to become thoroughly dry before a new layer is placed over them.

TEMPERATURE AND VENTILATION OF STORAGE HOUSES.

Two or three days before beginning to bring in the potatoes, the storage house should be thoroughly cleaned and the heating appliance put in working order and started, in order to have the house both warm and dry when the crop comes in. Throughout the time of storing and for about ten days after the potatoes are all in the bins a temperature of 85° or 90° F. should be maintained in the house, with plenty of ventilation. This constitutes what is known as the sweating or curing process, and the keeping qualities of the potatoes depend upon the thoroughness with which this part of the work is done. Wood-burning stoves are frequently employed for heating sweet potato storage houses, but a hot-water boiler with coils of pipes along the walls of the building is very satisfactory.

After the crop is all in and thoroughly temperature of the storage house should be gradually y vary between 55° and 65° F., but considerable vent maintained.

Sweet potatoes should be handled very carefully and as few times as possible, the essentials to good l ıg being a reasonable degree of warmth, a dry atmosphere, and reful handling. Great care should be taken with the seed for the t year's planting to see that it is carefully handled and properly red.

While a temperature of 80° or 85° F. is required to properly start the seed into growth in the spring, a higher temperature during a long period of time in storage is liable to injure or even kill the buds. Potatoes intended for seed should not be stored in too great quantities, and where but a small supply is needed they can often be kept buried in dry sand after having first been thoroughly cured. The sand used for this purpose should be baked to insure the driving off of moisture, and may be placed around the potatoes while slightly warm.

In controlling the ventilation of the storage house during the winter months, outside air should be admitted only when quite dry and when its temperature is lower than that of the air in the storage house. If warm, moist air is admitted considerable moisture will be deposited upon the potatoes, thus injuring their keeping qualities.

LOSS FROM SHRINKAGE WHILE IN STORAGE.

Under proper storage conditions sweet potatoes will shrink from 6 to 10 per cent, but the loss in weight will be greater if the temperature of the house is carried too high. If the potatoes are not mature when dug from the field the loss from shrinkage may be as much as 15 per cent, and immature stock should be marketed early in the winter.

MARKETING DURING WINTER MONTHS.

For marketing from outside pits it is desirable to have the quantity stored in one pit small enough to permit of all being removed at one time. The potatoes may be removed from outdoor cellars as desired. In marketing from heated storage houses the potatoes should not be disturbed until they are barreled or crated, and then they should be placed directly upon the market and sold without delay.

When shipping during cold weather the barrels should at least be lined with paper, and a covering of heavy brown paper over the outside of the barrels will form a safeguard. If the p s are shipped in carload lots during the winter the cars should either of the regular refrigerator type or felt lined, and in cases a stove should be provided. When once placed upon the market the potatoes should reach the consumer within a comparatively short time.

Figure 23 shows the type of barrel employed; also the method of pressing the heads into place.



FIG. 23.—Sweet potato barrels and device for pressing the heads into place.

VARIETIES OF SWEET POTATOES.

Of the large number of varieties of the sweet potato there are not more than ten that are now of great commercial importance in the United States. For the markets that require a dry, mealy-fleshed potato those varieties belonging to the Jersey group are suitable. For the southern trade and where a moist-fleshed potato is desired those commonly designated as yams are in demand. Among the Jerseys that are extensively grown are the Big-Stem Jersey, the Yellow Jersey, and the Red Jersey. The principal varieties of the yam group are the Southern Queen, the Pumpkin Yam, the Georgia, the Florida, and the Red Bermuda. Of the varieties mentioned there are a large number of special strains, known under many local names.

In the selection of varieties for home use one must be governed largely by locality. As a rule those of the Jersey group will thrive farther north than those of the so-called yam types. For market purposes the particular variety or strain grown in the vicinity should first be selected, and afterward other varieties may be experimented with in a small way.

The following brief descriptions of a few of the leading varieties may be of assistance in selecting those best adapted to various conditions of soil and climate:

Big-Stem Jersey.—This variety (fig. 24, C) is the most popular among growers who are supplying the northern and eastern markets. It is a form of the Yellow Jersey, having been selected for its productiveness and dry, yellow flesh. The vines are slender and long; the potatoes are of spindle shape and inclined to grow rather large;

color of potatoes yellow; color of flesh light yellow or deep cream. While this variety yields heavily, it is unfortunately a rather poor keeper, and its flesh is inclined to become dry and "punky" toward spring. It will thrive well toward the north, but is better adapted for use as a commercial variety than for home consumption.

Yellow Jersey.—The vines of the Yellow Jersey variety are long and more slender than those of the Big-Stem Jersey, and the potatoes are of spindle shape, but much smaller; otherwise the two varieties are very similar in appearance. The flesh is dry and mealy. This variety is a fairly good keeper and retains its quality well. It is adapted for home use and thrives under a wide range of conditions, but does not yield heavily enough for commercial purposes.



FIG. 24 Some of the commercial types of sweet potatoes: A, Black Spanish, or "Nigger Choker"; B, Long, cylindrical type; C, Jersey group, spindle shape; D, Red Bermuda; E, Southern Queen.

Red Jersey.—This is similar to the Yellow Jersey variety, except that the roots are red and it is more productive under most conditions. It is suitable for home use.

Southern Queen, or Hayman.—The vines of this variety are strong and vigorous; the potatoes are large, thick, and blunt at ends or of short spindle shape; the color is white or light cream, while the flesh is of cream color, becoming darkened in cooking, moist, and very sweet. This variety is most extensively grown for market purposes where a sweet, moist-fleshed potato is demanded. The Southern Queen yields well, is an excellent keeper, and is adapted for both marketing and stock feeding and for home use in the South Atlantic and Gulf Coast States, but it does not mature when grown in the extreme North. (See fig. 24, E.)

Pumpkin Yam.—The vines are vigorous, short, sometimes of a bunch habit. The potatoes are of short spindle shape or quite round, with a dull yellow color on the outside. The flesh is orange or sometimes yellow and marbled with orange; it is moist and has a flavor very similar to that of good squash. This variety yields well and is adapted to home use and to stock feeding throughout the South.

Georgia, or Split-Leaf, Yam.—The vines of this variety are slender and long; the potatoes of medium size, spindle shape, yellow; the flesh a light yellow, marbled with salmon. The quality of this variety is excellent and very sweet, but it is a light yielder. It is a splendid sort for home use throughout the South Atlantic and Gulf Coast States.

Red Bermuda.—The Red Bermuda vines are large and vigorous. The potatoes are usually large and overgrown with heavy ridges and veins. The color of the potatoes is rose red; flesh, creamy; quality fair but not so sweet as Southern Queen. This variety is a heavy cropper and suitable for feeding to stock. It is one of the few so-called yams which thrive in the northern portion of the sweet potato area. (See fig. 24, D.)

Florida.—The vines of the Florida variety are large and vigorous. The potatoes are rather large, light salmon yellow, smooth and regular, of short spindle shape, with light yellow flesh. This variety is not so sweet as the Georgia and is inclined to be dry and mealy. It yields fairly well and is adapted for home use.

Pierson.—The vines of the Pierson are similar to those of the Red Bermuda variety. The potatoes are light yellow, of short spindle shape, very rough, with cream-colored flesh. This sort is extensively grown for the earliest market, but it is of only fair quality. It yields well if allowed to remain until late in the season.

Black Spanish, or " Nigger Choker."—The Black Spanish vines are very long, vigorous, and dark purple in color. The potatoes are long, cylindrical, crooked, or bent; dark purple in color, with snowy white flesh and poor quality. This variety is grown mostly for stock feeding. (See fig. 24, A.)

Shanghai.—The vines of the Shanghai variety are large and vigorous; the potatoes long, cylindrical; the outside color almost white. The flesh is creamy white, becoming darker in cooking. When baked the flesh is somewhat dry and mealy and the flavor rather poor. This variety yields fairly well and is adapted for use as stock food in the Gulf Coast States. (See fig. 24, B.)

COST OF PRODUCTION AND RETURNS.

The cost of growing an acre of sweet potatoes will vary with the cropping plan and the extent to which the crop is grown. On an average the cost of growing an acre of sweet potatoes in the regular commercial district is about as follows: Rental of land, $8; plowing and fitting, $5; fertilizers, $20; 10,000 plants, $10; planting, $5; cultivating, $5; digging and marketing, $25; total, $78. An average yield of sweet potatoes is at the rate of one barrel to 100 hills or 100 barrels to an acre. The price per barrel paid the grower is seldom less than $1.25, and $2.50 or $3 is not uncommon. During good seasons the net profit from one acre of sweet potatoes is about $75. While occasionally the net returns are from $100 to $150 an acre for a single season, there are seasons of crop failure or overproduction when very little, if any, profit is realized.

The sweet-potato growers on the eastern shore of Virginia as a rule plant about 10 acres in sweet potatoes, and this constitutes their money crop. The remainder of the cleared portion of their small farms is devoted to corn, pasture, and hay, all for home use. Here the sweet-potato crop is grown almost entirely without the aid of hired help, and the cost of production does not exceed $40 an acre. Where the crop is stored the gross returns are greater, but the cost of production is increased proportionately.

USES OF SWEET POTATOES.

The uses of the sweet potato as a table vegetable are too important and too well known to require more than brief mention in a publication of this character. In preparing them for the table they are baked, boiled, fried, or braised, while for pies they are used in the same manner as pumpkins.

A number of attempts have been made to build up an industry for the production and sale of desiccated sweet potatoes and sweet-potato flour. There is doubtless a great field for this class of goods, especially for export and for ship supplies.

USES FOR STOCK FOOD.

The vines of the sweet potato when properly cured make a medium grade of hay for feeding to cattle and sheep. In the green state the vines are eaten by sheep, cattle, and hogs, but their feeding value is comparatively small. The potatoes are fairly well adapted to feeding to range cattle, sheep, and hogs, although their nutritive value is quite low and they require the addition of cotton-seed meal or grain to make a balanced ration. On farms where sweet potatoes are grown extensively the culls are fed to hogs, together with a one-third or one-half ration of corn.

By employing one of the heavy-yielding varieties of sweet potatoes, such as the Southern Queen or the Bermuda Red, and drying and pulverizing them, a splendid stock food may be produced, especially when sufficient grain is added to form a balanced ration.

The principal uses of sweet potatoes are, however, for the table, and the demand for this purpose is rapidly increasing.

From the fact that by the aid of commercial fertilizer alone sweet potatoes can be grown on comparatively poor land and largely by the use of labor-saving machinery, this crop may in a great measure solve the problem of how to occupy the "worn-out" cotton and tobacco lands of the South, especially if employed in a rotation including corn, peanuts, and grass. By the perfection of some means by which sweet potatoes could be dried and converted into a condensed stock food on the farm, they in conjunction with corn, peanuts, and a little hay would serve to keep the stock on southern farms in good condition during the winter.

When removed from the ground the sweet potato contains about 71 per cent of water, 1.5 per cent of protein, 25 per cent of nitrogen-free extract, and 0.35 per cent of fat. It will be noted that both the protein and fat content of the sweet potato are comparatively low. The analysis of peanuts shows that the protein and fat are both quite high, and by combining them with sweet potatoes at the rate of one bushel of peanuts, ground in the shells, to three bushels of sweet potatoes a splendid stock food is produced. Three bushels of sweet potatoes are nearly equal to one bushel of corn in feeding value, but in order to make them satisfactory as a stock food it is necessary to add peanuts, cotton-seed meal, or grain.

USE FOR PRODUCTION OF ALCOHOL.

The starch and sugar content of sweet potatoes varies considerably in different varieties, but as a rule they contain about 16 per cent of starch and 4 per cent of sugar, making a total of 20 per cent of alcohol-producing material. It is possible that sweet potatoes will become one of the chief sources of denatured alcohol in the United States, but at present the methods of manufacture have not been sufficiently perfected to warrant their use for this purpose on a farm or community basis.

O

Issued May 9, 1908.

U. S. DEPARTMENT OF AGRICULTURE.

FARMERS' BULLETIN 325.

SMALL FARMS IN THE CORN BELT.

BY

J. A. WARREN,

Scientific Assistant, Farm Management Investigations,
Bureau of Plant Industry.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1908.

LETTER OF TRANSMITTAL.

U. S. Department of Agriculture,
Bureau of Plant Industry,
Office of the Chief,
Washington, D. C., March 4, 1908.

Sir: I have the honor to transmit herewith a paper entitled "Small Farms in the Corn Belt," by J. A. Warren, Scientific Assistant, prepared under the direction of the Agriculturist in Charge of Farm Management Investigations, and recommend that it be published as a Farmers' Bulletin.

In this bulletin an effort has been made to show some of the serious difficulties that confront a farmer of moderate means, to give some of the reasons for the alarming rapidity with which young men are flocking to the cities, and to show by actual records how some have solved the problems which all are facing.

Each of the farms here described has been visited in at least two different years and all the data have been obtained from the owners and are believed to be perfectly reliable. A number of such farms representing several other States which would have served as well for illustration have been studied, but the records were too meager to show what had been done.

The conditions here considered are much the same over most of the corn belt. The points brought out in the discussion are the results of several years of study along these lines and many years of experience in that region.

Respectfully,
B. T. Galloway,
Chief of Bureau.

Hon. James Wilson,
Secretary of Agriculture.

CONTENTS.

Page.

ntroduction ... 5

A forty-acre farm in Saunders County, Nebraska ... 7
  Description ... 7
  Cropping system ... 7
  Potatoes ... 8
    Seed tubers ... 8
    Cultivation of potatoes ... 9
    Potato beetles ... 9
    Digging potatoes ... 10
    Yield of potatoes ... 10
    Cost of producing potatoes ... 10
  Grass ... 10
  Pasture ... 11
  Fruit ... 11
  Manure ... 11
  Horses ... 12
  Cattle ... 12
  Poultry ... 12
  Equipment of farm in 1907 ... 12
  Sales, expenses, and net income of farm in 1906 ... 13
  Returns on investment ... 13
  Suggestions as to improved methods ... 14

A forty-acre farm in Adams County, Nebraska ... 17
  Introduction ... 17
  The land ... 17
  The owner and his prospects ... 17
  Management ... 18
  Potatoes ... 18
  Miscellaneous crops ... 18
  Orchards ... 18
  Timber ... 18
  Stock ... 19
  Labor ... 19
  Expenses ... 19
  Results accomplished ... 20

A twenty-acre farm in Pawnee County, Nebraska ... 21
  Introduction ... 21
  The soil and its use ... 21
  Methods and practices ... 22
  Manure ... 22
  Fruit ... 23
  Seed corn ... 23

A twenty-acre farm in Pawnee County, Nebraska—Continued. Page.
Exhibits of farm products 24
Sprays 24
Labor 24
Miscellaneous 24
Equipment 24
Income and expenses 25
Results accomplished 27
General conclusions 27

ILLUSTRATIONS.

Page.
FIG. 1. Diagram of the Beadle farm as it appeared in 1907 8
2. Diagram of the Beadle farm showing suggested improvements in arrangement 15
3. Rows of crops in the pear orchard on the Martin farm 23

B. P. I.—357.

SMALL FARMS IN THE CORN BELT.

INTRODUCTION.

In the great corn belt, or at least that portion of it comprised in Indiana, Illinois, Iowa, northern Missouri, eastern Kansas, eastern Nebraska, southeastern South Dakota, and southern Minnesota, the majority of the farms contain 160 to 320 acres. Farms of only 80 acres are comparatively scarce, and not many farmers consider less than 160 acres sufficient to furnish a respectable living. Yet no careful observer can travel this region without being convinced that many a man would have a larger net profit and an easier and happier life if he farmed less extensively and more intensively. Good farms in this section are worth $50 to $200 an acre, or $8,000 to $32,000 for 160 acres. To this must be added $2,000 to $3,000 for teams, stock, machinery, feed, and seed, making a total investment of $10,000 to $35,000. How can the young man who has nothing to start on secure such a place? This is the problem that now confronts the majority of young farmers.

Ten to fifteen years ago many men with little or nothing to pay down bought farms and have since paid for them, but they bought at a fraction of the present prices. Take the moderate price of $75 an acre, or $12,000 for 160 acres, and add $2,000 for equipment, making a total of $14,000. The interest on $14,000 at 5 per cent, which is the lowest rate obtainable, amounts to $700 per annum. To expect to clear this each year after paying running expenses and a living and have money left to pay on the principal requires more confidence than the average man possesses. Even if he takes the risk and wins, the chances are few that he will be able to pay his debts and have his home clear by the time he is old enough to need to be relieved from hard labor. If he is to remain on the farm, only two propositions remain open to him. He can rent, with small chance of ever owning, a farm or he can go elsewhere in search of cheaper land, neither of which courses is very inviting. The large amount of money necessary for the purchase of a farm and the dim prospect of ever obtaining it discourage the farm boy, and as a result he begins, although reluc-

325

tantly perhaps, to look for other employment, while the young men who are not farmers see no opportunities for them in rural life.

Farm wages seem small when compared with wages and salaries offered for other work, but as a matter of fact they compare very favorably when rightly considered. The farm boy, or even the farmer of mature years, has little conception of the cost of living in cities. In his experience most of the living has come from the farm and he has not realized that it cost anything. Thirty dollars a month with board and washing is common wages for any good hand in most of this region, and many can command more. A single man can save as much out of $30 on the farm as out of $55 or $60 in the city. A married man can usually secure $35 or $40 a month, a house, garden, milk, fuel, a chance to keep poultry, and often feed for a pig. This is much more to him than $60 a month or $2.50 a day in town.

The hours required on the farm are not very much longer than in other occupations. The farmer is inclined to say he works sixteen hours a day if he rises at 5 o'clock and retires at 9, but in most cases, after counting out meals and rest periods, it is found he has not actually been at work more than eleven or twelve hours. In winter the hours are nearly always much shorter, and at all times of the year there are stormy days when little work is done. In town a man working a team must work ten hours and take care of his team and go to and from work outside of that, so his ten hours is of about the same length on the average as the farmer's sixteen. For the man who works without a team the hours are not much shorter when the time required in getting ready and going to work and in getting home again are considered, and if he is in one of the larger cities 10 cents a day must be expended for street car fare.

These unconsidered points, it seems to the writer, constitute the main reasons for the increasing and deplorable migration of young men from the farms to the cities, about which so much is being said and written.

Can not the young man rent a farm or work for wages a few years until he gets several hundred dollars ahead and then buy a small tract—20 or 40 acres—upon which to make a comfortable home of his own and have it free from incumbrance while there are still many years of active life before him?

In this connection it may be interesting to see what is being done on a few small farms. It is not presumed or even hoped that anyone will copy exactly any of the farms here discussed, and it is highly probable that failure would result if he did. The personal factor is very important and no one should attempt to follow another's plans in every detail. Each man should follow the line in which he is most likely to succeed and use all his own originality as well as adopt the best practices of others. Then, again, varying conditions make one type of farm most profitable in one locality and another type in another locality, thus making a careful study of markets, soils, and climate indispensable. But there are hundreds of ways in which success may be attained on a small farm.

This bulletin aims to show how some practical men have solved the problem of securing homes on high-priced land, and if it suggests a way to others with limited means its purpose will be well served. It is true that two of the men whose farms are here described secured their land at a low figure, but their results show that they would have succeeded had they purchased high-priced land. No two of these farms are within 100 miles of each other—one is near a town of 2,500 inhabitants, one is 7 miles from such a town, and one is 10 miles from a town of 8,000 people.

The discussion of farms near the larger cities has purposely been avoided, as has that of dairy farms, because (1) cities as a rule are far apart and there is room for comparatively few farmers near them, (2) land is very high in the vicinity of cities, and (3) there is a mistaken idea that when located near a city the small farmer must be a market gardener or a dairyman, and there is a common prejudice against both of these types of farming.

All of the farms here described are found in a single State, but the conditions in all the States of the corn belt are so similar that if the localities were not mentioned no one could tell in which State they were to be found. Every statement applies with equal force to nearly all the region mentioned.

A FORTY-ACRE FARM IN SAUNDERS COUNTY, NEBRASKA.

DESCRIPTION.

Mr. C. E. Beadle owns and operates 40 acres of gently rolling upland prairie, much of it nearly level, in Saunders County, east-central Nebraska. The soil is a deep, dark silt loam characteristic of that region. The house, which is worth about $2,000, stands near the highway and is surrounded by a well-kept lawn bountifully supplied with trees and ornamental shrubbery. The farm buildings are not of special interest, because they were mostly on the farm when the present owner purchased it and are not such as he would have built.

In figure 1 is shown a diagram of this farm as it appeared in 1907.

CROPPING SYSTEM.

The cropping system followed is very simple, consisting of potatoes two or three years and mixed hay two or three years. In 1906 there were 14 acres in potatoes, 7 acres in hay, 11 acres in pasture, 1¼ acres in sweet corn to supplement the pasture (but this was not needed), 5½ acres in garden, orchard, and grounds, and 1 acre in a public road. In 1907 there were 7 acres of grass on the land that was in potatoes the previous year. Otherwise no changes were made. Hay enough for home use is produced, but all grain is purchased.



FIG. 1.—Diagram of the Beadle farm as it appeared in 1907.

POTATOES.

Seed Tubers.

Mr. Beadle plants nothing but northern seed potatoes and estimates that these yield 50 bushels to the acre more than if seed only one year removed from the North were used, while a better grade of potatoes is produced. Early Ohio and White Ohio are the varieties selected, the seed being grown at Fargo, N. Dak. The tubers are cut by hand to one or two eyes. Emphasis is placed upon the superior value of the first sprout from an eye, as this sprout comes from the main or central bud and is larger and stronger than the sprouts that come later. Then, too, in potatoes that have sprouted the plant food is unevenly distributed and many of the pieces from the stem end are worthless. For these reasons much care is taken to keep potatoes so they will not sprout till planting time.

Cultivation of Potatoes.

The clover and timothy meadow is plowed late in the fall and left till spring without harrowing. This late plowing exposes to the winter frosts many insects that might injure the potatoes. Leaving the ground unharrowed gives it a better chance to catch snow, and it also pulverizes better in the spring. The ground is disked before planting. The potatoes, after being cut to one or two eyes, are planted with a potato planter, 13 inches apart in the row and in rows 38 inches apart. This requires 10 to 12 bushels per acre.

Cultivation commences after the next rain. A four-shoveled cultivator is used, running very deep. Before the potatoes are up the ground is well harrowed, and as soon as they are up the cultivator is again used. The shovels are set to throw the dirt in and run deep, thus burying all the little plants. When the potatoes come through again the spring-toothed weeder is used both ways, leveling the ground nicely. The soil now has been stirred nearly as deep as plowed, is well pulverized, and is in excellent shape for root growth, to absorb water, and to withstand drought. It is perfectly free from weeds, for none can endure such treatment. From this time on the cultivator and the weeder are used alternately, the cultivator in these later cultivations having six 2½-inch shovels and running shallow so as not to disturb roots. The weeder is used until the plants are 10 or 12 inches high. The weeder is usually run crosswise and then lengthwise of the rows soon after each cultivation with the cultivator.

Potato Beetles.

As soon as any striped beetles, commonly called Colorado potato bugs, appear, boys are hired to gather them by the hundred. The price varies with the plentifulness of the insects, but is always high enough for the boys to make good wages, which are usually about 5 cents a hundred " bugs." The owner does not pretend to count the insects, but measures them in a can cover that holds 200. This is the cheapest and most effective way he has found for keeping the beetles in check. As this work is commenced early, very few young beetles are hatched. In 1905, 30,000 " bugs " were gathered from 14 acres at a cost of $15. In 1906, 35,000 were gathered from the same field. Sprays have never been used, but would doubtless prove profitable, as some damage is done by fungous diseases.

Digging Potatoes.

The digging gang consists of 1 man and 4 horses with the digger, 2 teams and wagons, 4 men to pick up, and 2 men to sort and store in the cave. This force puts in 600 bushels a day at a cost of 2½ cents a bushel, not counting the men and teams on the digger.

Yield of Potatoes.

Two hundred bushels of potatoes to the acre are considered a good crop, but 360 bushels have been produced. The yields are practically double the average of this part of the State. The increase is due to the high quality of seed, the thorough cultivation practiced, and the rotation and manure used.

Cost of Producing Potatoes.

The estimated cost of producing an acre of potatoes and putting them in the cave is—

Plowing and harrowing	$1.50
Disking	.40
Seed, 12 bushels at 55 cents	6.60
Cutting and planting	1.50
Cultivating	4.00
"Bugging"	1.25
Gathering 200 bushels	6.50
Total	21.75

At these figures 1 bushel when stored in the cave has cost 10.88 cents, without counting rent of land or use of machinery.

GRASS.

Nine pounds of timothy, 12 pounds of red clover, and 2 to 3 pounds of alsike clover are sown to the acre, without any other crop, on ground that has grown potatoes two or three years. This is very different from the common practice, which is to sow 8 to 10 pounds of timothy and 5 to 7 pounds of clover to the acre with a full crop of wheat or oats. It will be seen that Mr. Beadle sows the usual quantity of timothy and more than double that of clover. He considers heavy seeding and the full use of the land both essential to good grass crops. The weeds are clipped once or twice, if necessary, but a hay crop is secured in the fall.

A hay crop the first year is almost an unheard-of thing in this region. This man is able to produce it because of the good condition of his land and the fact that the grass has the full use of the soil. A large proportion of the grass sown with grain fails to make a stand, but a failure has never occurred on this farm. The second year two crops of hay are cut, and then there is usually a good aftermath to plow under or, if the grass is to stand another year, to leave for winter cover. No stock is ever allowed on the meadow. This is another important point. As a result of these practices the yields secured are more than twice those common in the neighborhood. In 1906, 52 loads, conservatively estimated at 1,500 pounds each, were produced on 7 acres, making a yield of over 5½ tons an acre for the season. The first crop in 1907 was 22 tons from the same field.

Hay is raked quite green and cured in the windrow and cock. As soon as sufficiently dry it is hauled to the barn. No salt or lime is ever used on the hay. A side-delivery rake has recently been purchased with the intention of using a loader on the windrows so as to save cocking and pitching.

PASTURE.

The pasture is permanent and consists of 11 acres of Kentucky bluegrass, timothy, and white clover. Throughout the season of 1906 it furnished plenty of feed for 5 cows and 5 calves, 3 yearling heifers, 1 horse, and the team when not in use. In July, 1907, there were 6 cows, 2 yearling heifers, 2 horses, 1 colt, and the team when not in use on this pasture, and still several tons of hay might well have been cut. In this locality tame pastures usually require 1½ to 2 acres for each head of stock, but it will be seen that this pasture is supporting about a head per acre besides the calves and colt, and there is feed to spare. The difference is due entirely to difference in care. Here manure is frequently applied, and weeds, such as thistles, dock, and ironweed, are either cut off or dug out. In this way a dense, luxuriant growth of grass is secured.

FRUIT.

While fruit growing is of minor interest on this farm, it adds considerably to the net income. Especially is this true of the half acre of strawberries, which returned $260 in 1907, and the quarter acre of blackberries, from which 375 quarts had been sold up to August 7, with one-third of the crop still on the bushes. Vegetables are rarely sold. These products are nearly all retailed at a good price, and special effort is made to deliver them in first-class condition.

MANURE.

Both meadow and pasture receive a heavy dressing of manure in the winter. No manure is used directly on the potatoes and no commercial fertilizer has ever been used. What is made in the summer is hauled directly to the pasture. During the winter the cattle yard, as well as the barn, is kept well bedded with wheat straw, so that as much manure as possible will be made. The straw is secured from the neighbors for almost nothing. What manure is needed is hauled from a near-by town, where it is to be had free of charge.

HORSES.

An old team and 1 young mare, 1 two-year-old colt, and 1 spring colt are now on the farm. The mare is a high-grade Percheron and the colts are always from the best available sire of that breed. They are fed but little grain during the winter and none in the summer. The work horses are never grained heavily and are pastured when not in use in the summer.

CATTLE.

All the cattle, except 1 milk cow which is kept for family use, are registered Shorthorns of good quality. The calves, of course, are allowed to run with the cows. A little corn is fed during the winter, but none in the summer. The cattle business is not yet well established, and unfortunately the young stock has not thus far sold at as good prices as the owner could justly expect. The herd now contains 6 cows, 2 yearling heifers, and 1 bull, and 6 calves are expected this season.

POULTRY.

About 50 Barred Plymouth Rock hens are kept primarily for family use, but most of the cockerels are easily sold at $1.50 each for breeding purposes; also a few eggs for setting. The flock is kept confined during the summer.

EQUIPMENT OF FARM IN 1907.

Stock.	Value.
2 horses	$200.00
1 horse	200.00
1 colt (2 years)	125.00
1 colt	50.00
3 cows	300.00
3 heifers, 2 years	225.00
2 heifers, 1 year	80.00
1 bull calf	50.00
50 hens	50.00
Total	1,280.00

Machinery.	Cost.
1 potato planter	$52.00
1 potato digger	67.00
1 walking weeder, 12-foot	15.00
1 plow, 14-inch	14.00
1 harrow, 2-section	10.00
1 wagon, secondhand 17 years ago	35.00
1 delivery wagon, mostly homemade	[a]20.00
1 road wagon	[a]40.00
1 mower, 5-foot	45.00
1 dump hayrake, 10-foot, secondhand	7.00
1 side hayrake, secondhand	28.00
1 manure spreader	110.00
1 walking lister, secondhand	[a]3.00
1 plow, 1-shovel	1.50
2 small platform scales	16.00
1 cultivator, 14-tooth, 1-horse	3.50
1 cultivator, 4-shovel, with 6-shovel spring shank attachment	17.00
Total	484.00

[a] Estimates.

SALES, EXPENSES, AND NET INCOME OF FARM IN 1906.

Sales.	Value.	Expenses.	Cost.
3½ tons hay	$25.00	1 cow	$50.00
Potatoes, 2,000 bushels, at 60 cents	1,200.00	257 bushels corn	94.45
4 cows	185.00	16 bushels wheat for poultry	8.60
1 calf	15.00	Oil, meal, and bran	10.00
4½ bulls[a]	257.50	Labor	68.00
1 colt	70.00	Seed potatoes	[b]90.00
Poultry	[b]100.00	Pasture	[b]15.00
Eggs	[b]30.00	Miscellaneous	[b]75.00
Strawberries	60.00	Taxes	[b]25.00
Total	1,942.50	Total	436.05

[a] This item includes a half interest in 1 bull.

[b] Estimates.

Summary:

Value of farm, 40 acres at $200	$8,000.00
Value of live stock	1,280.00
Value of machinery and implements	484.00
Total	9,764.00
Sales	1,942.50
Expenses	436.05
Net income of farm	1,506.45

RETURNS ON INVESTMENT.

It will be seen that the net income derived is 15.4 per cent on $9,764, the total value of the farm, stock, and equipment. While more cattle were disposed of in 1906 than can be sold every year they did not bring more money than it is hoped the smaller number will bring when the herd is better established. In 1907 much more was realized from small fruit, but the acreage of potatoes was reduced one-half.

The sales usually amount to about $1,500 per annum, which, after paying expenses, leaves about $1,100 (or 11¼ per cent on the capital invested) and the produce used, which represents the income of the family or the amount available for living expenses and profits. That the family has been able to live on less than this is shown by the fact that the farm has been paid for practically in eleven years, improvements costing about $1,000 have been added, and the value of the live stock has been considerably increased. The place was purchased at $92.50 an acre, and is now worth about $200 an acre.

Considering the farm at its present value, the average net profit has been approximately $800 per annum. Without considering the rise in value of the land, but counting only the purchase price of the farm, the cost of improvements made, and the increased value of the stock, the net profits actually resulting from what has been produced have been not far from $500 per annum.

In comparing these results with those obtained in other lines of business or by men working for salaries, it must be remembered that all living expenses of the family were paid out of the receipts from the farm and that these profits still remained. The home alone is worth a large proportion of the value of the entire farm, yet this has been included in the investment upon which the percentage of profit has been figured.

All of the produce, poultry, eggs, butter, milk, and some fuel have also been supplied by the farm. These are items which no one would think of including in the business expenses of any other line of work. To rent as good a house and live as well as this family does would require $1,500 a year in almost any city. And to do this and save as much as this farmer has netted would require a salary of about $2,300.

The owner of this farm had previously operated 160 acres for a number of years, but has done so much better on 40 acres that he has no desire for a larger area. He alone does practically all the work of the farm, none of the other three members of the family assisting in the outdoor work.

SUGGESTIONS AS TO IMPROVED METHODS.

Under the present practice one mare does nothing but raise a colt, while the old team is probably not in use more than half the time. The work could easily be done by a team of brood mares. Two colts a year could be raised instead of one, and the expense of keeping an extra horse would be avoided.

The cropping system now in use is very irregular. Two years there are 7 acres of potatoes and the third year 14 acres. Three consecutive crops of potatoes on the same land are not advisable on account of danger from disease, but even if grown for three years the system would still be just as irregular. One year there would be 7 acres of old grass and two years there would be 7 acres of old grass and 7 acres of new seeding. This makes the hay supply irregular. The hay ration, too, can be much improved by the introduction of alfalfa. To correct these difficulties the following changes are suggested: Lay out the fields as shown in figure 2. This will not require any change in fences, as no fences are needed between fields. It will eliminate the sweet corn fodder, but will supply alfalfa, which is more productive and a more valuable feed. A large proportion of the alfalfa will be near to the pasture and can conveniently be cut and thrown over to the stock if necessary. There will be 3¼ acres of alfalfa, 4¾ acres of old grass, 4¾ acres of new grass, and 9½ acres of potatoes each year, with a regular rotation of two years in grass and two years in potatoes. Assuming yields of 200 bushels of potatoes, 6 tons of alfalfa, 4 tons of old grass, and 1¼ tons of new grass to the acre, the proposed plan gives 1,900 bushels of potatoes, 25 tons of timothy a hay, and 19½ tons of alfalfa, while the present plan gives a of 1,833 bushels of potatoes, 34 tons of hay, and 6 tons of :

By the change 67 bushels of potatoes and 4½ tons of feed a a much better quality of feed is obtained, and a regular giving the same acreage in each crop each year, is adop feed supply will therefore be more regular, as there will much danger of a shortage or surplus of hay.



FIG. 2.—Diagram of the Beadle farm showing suggested improvements in

Assuming the above yields, 2 horses, 2 two-year old colts, colts, 2 spring colts, 5 cows, 1 bull, 2 yearling heifers, an can be kept, and about the same quantity of corn as now us needed. The pasture will usually summer this number o at least has furnished feed enough for the last two years of a scarcity of grass, stock could be pastured out at reasona or the pasture could be supplemented with alfalfa, and a purchased in winter, if necessary. Some patches in the will be vacant by the middle of the summer can be utilized for catch crops of feed.

The introduction of alfalfa will considerably improve the feed ration for both cattle and horses, as will be seen by examining the appended table, which shows the food requirements of cattle of different ages according to the Wolff-Lehmann feeding standards, approximately the ration now used, and the proposed ration. The hay is assumed to be an even mixture of timothy and clover. If it should be three-fourths clover and one-fourth timothy, the protein content would be increased by one-fifth and the carbohydrates decreased by one-twentieth.

TABLE I.—*Daily food requirements of cattle of different ages, the quantity now used on the Beadle farm, and the ration proposed.*

Feed.	Dry matter.	Protein.	Carbohydrates.	Fats.
CALVES (600 POUNDS WEIGHT).	*Pounds.*	*Pounds.*	*Pounds.*	*Pounds.*
Quantity required	15.00	1.50	7.9	0.4
Present ration:				
Hay (one-half clover, one-half timothy)——14 pounds	12.11	0.67	5.50	0.22
Corn——4 pounds	3.50	.31	2.67	.17
	15.61	.98	8.17	.39
Proposed ration:				
Hay (one-half clover, one-half timothy)——5 pounds	4.29	0.24	1.98	0.08
Alfalfa——8 pounds	7.30	.88	3.16	.10
Corn——4½ pounds	3.50	.35	3.00	.20
	15.09	1.47	8.14	.38
YEARLINGS (900 POUNDS WEIGHT).				
Quantity required	21.00	1.60	10.80	0.36
Present ration:				
Hay (one-half clover, one-half timothy)——21 pounds	18.90	1.10	8.71	0.33
Corn——3 pounds	2.60	.20	2.00	.12
	21.50	1.30	10.71	.45
Proposed ration:				
Hay (one-half clover, one-half timothy)——10 pounds	8.58	0.48	3.96	0.16
Alfalfa——10 pounds	9.16	1.10	3.96	.12
Corn——4 pounds	3.50	.31	2.67	.15
	21.24	1.89	10.59	.43
COWS (1,200 POUNDS WEIGHT).				
Same basis as cattle eighteen to twenty-four months.				
Quantity required	28.80	2.16	14.40	0.48
Proposed ration:				
Hay (one-half clover, one-half timothy)——20 pounds	17.10	0.96	7.92	0.31
Alfalfa——11 pounds	10.00	1.21	4.35	.13
Corn——3 pounds	2.60	.20	2.00	.13
	29.70	2.37	14.27	.57

To feed the bull all the year and the other cattle six months these rations will require 32,400 pounds of mixed hay and 23,100 pounds of alfalfa. This will leave 17,600 pounds of mixed hay and 15,800 pounds of alfalfa for the horses, which will feed the team nine months and the colts six months. If the cattle were grade stock it would probably be more profitable to feed no grain except, perhaps, to the calves, and even in this herd it may be found economical to feed less grain. When stock is to be prepared for show these rations would be inadequate.

A FORTY-ACRE FARM IN ADAMS COUNTY, NEBRASKA.

INTRODUCTION.

In December, 1895, Mr. H. F. Warren purchased 40 acres of unimproved rough land 10 miles from Hastings, south-central Nebraska. The price was $400 and a mortgage was given for the whole amount. He secured also a lease on 40 acres of tillable land for two years, giving one-third of the crop, and a lease on a house and outbuildings for two years. January 1, 1896, his business statement showed:

Resources	$942.85
Liabilities	648.80
Present worth	294.05

The lease on the buildings was valued at $100. The inventory was detailed and included everything in doors and out.

THE LAND.

The land purchased is cut by several deep draws and is one of the roughest pieces in the county. Most of it was in native grass, one-third is untillable, and the remainder is cut up into small patches by several deep ravines. Two acres were in public roads. There was no timber. The soil is of loessial origin and is mostly the dark silt loam so common in the Missouri basin. On many of the hillsides the dark soil has been washed off and the buff subsoil lies bare. Near the largest draws are some patches of fine sandy loam.

THE OWNER AND HIS PROSPECTS.

No one but the owner believed it possible to make even the most meager living upon such a farm—38 acres of rough pasture 10 miles from town, no buildings, no money, four mouths to feed, two hands to earn. The neighbors thought him foolish to try. It was certainly a hard-looking proposition, but the personal factors at least were in his favor. He was young and strong and possessed energy and determination. Both he and his wife knew how to make the most of everything. He was an experienced farmer and also knew something of garden and nursery work. He was handy with tools and could do practically all of his own smith, carpentry, and mason work. The figures on page 20, taken from the annual balance sheets, show what success has been attained.

MANAGEMENT.

The rented land was planted to corn, and as there was very little stock most of the crop had to be sold, but the price (8 to 15 cents a bushel) was too low to pay the cost of production. From 1898 to 1906, inclusive, no land was rented. Work was at once commenced on the home place. The tillable land was subdued. Orchards were set and the bottoms of the draws, which were too frequently overflowed to produce crops, were set with forest trees.

POTATOES.

Several patches were recognized as good potato soil and in 1898 potatoes became the main crop and continued so for at least five years. One year the cash sales of potatoes amounted to $450. Early marketing was resorted to as much as possible, and potatoes were frequently hauled 14 miles and seldom less than 10. Sale was often slow and continued till spring. Catch crops of sorghum, millet, or turnips frequently followed early potatoes. There was so little tillable land outside the orchards that rotation was not undertaken, and the continued growth of potatoes so filled the ground with disease that the crop had to be abandoned.

MISCELLANEOUS CROPS.

Not much truck has been grown because it is too far to market. Different years various small crops that were not regularly produced have been planted successfully. One year several acres of sorghum made a profitable crop of both seed and sirup. White beans were once an important item of income. Another year a catch crop of turnips after potatoes proved very profitable and the next season considerable turnip seed was sold.

ORCHARDS.

The orchards, of which there were 12 or 15 acres of apples, peaches, cherries, and plums, were ruined by severe storms and became a total loss. Most of the trees have been grubbed out or cut down. The labor and money spent upon them constituted a heavy loss to the owner.

TIMBER.

The forest trees have proved a great success and for several years have supplied an abundance of fuel. Unfortunately, most of the earlier settings were of maple and ash, which, though valuable for fuel, are worthless for posts. Later catalpas were set and promise soon to furnish all the posts needed and some to sell.

It should be emphasized that all these forest trees producing valuable timber are on land that would otherwise have been entirely waste. Many a farm in this region has enough such waste land to produce all the fuel and posts that can be used. If the proper varieties are set no better posts or wood can be had at any price. The importance of this will be seen when it is remembered that common small posts are worth 16 to 25 cents each and soft (bituminous) coal about $8 a ton.

STOCK.

In 1896 a herd of pure-bred hogs was started, but after several years was given up as a failure and for some time no hogs were kept. But since potatoes were abandoned most of the available land has been seeded to timothy, bluegrass, and alfalfa for hog pasture, and hogs for market have been the chief product of the farm in recent years. About 170 pigs were raised last year. All the grain is purchased. The pigs are farrowed in a large pig house, and as soon as conditions permit all sows and pigs are turned out together in the pastures. While the hogs are on pasture only a light feed of grain is given.

Concerning the character of the pasture it may be stated that part of it is rough land not suited to the plow and is in native prairie grass. A small portion of the pasture land is in bluegrass, another small portion in timothy, while several acres are in alfalfa. Sometimes the orchard is utilized as pasture for hogs. During the winter alfalfa hay and corn are fed.

The best old sows are kept over to bring fall pigs. The pigs are marketed at from 9 to 12 months of age. Mr. Warren is gradually bringing all available land on his farm into pasture and forage crops for hogs.

Two horses and 1 to 3 cows have always been kept. A good flock of hens—sometimes over 200—has added considerably to the income, as well as supplying the table with poultry and eggs.

LABOR.

Only a few days' work has ever been hired. Work is exchanged with the neighbors and sometimes grain has been taken in payment for work. Nearly every year a little money has been received for labor. This year (1907) the children are helping a good deal.

EXPENSES.

During the six years, 1896 to 1901, inclusive, the average annual cash expense for living, including clothing, furniture, fuel, groceries, doctor's bills, and every expense connected with the household, was only $66.44. Everything else used was either produced on the farm or secured in exchange for produce. At the beginning of this period there were four persons in the family and at the end seven.

For the eight years ending in 1903 the average annual farm expense, exclusive of permanent improvements, stock, and feed, but including machinery, repairs, and incidentals, was $35.23.

These items show how nearly a family may live upon the produce of the farm and how low an ingenious man may keep the incidental expenses of the farm.

RESULTS ACCOMPLISHED.

From 1896 to 1903 a business statement was made out each year, and the following table shows the financial condition on January 1 of each year:

TABLE II.—*Business statements for the Warren farm from 1896 to 1903, inclusive.*

Year.	Real estate.	Lease.	Cash.	Machinery.	Live stock.	Feed and supplies.	Household goods.	Total resources.	Total liabilities.	Present worth.	Net gain or loss.
1896	$400.00	$100.00	$92.85	$113.00	$96.00	$31.00	$110.00	$942.85	$648.05	$294.80	--------
1897	400.00	50.00	6.90	70.00	165.00	82.25	110.00	849.15	577.00	272.15	−$22.65
1898	550.00	--------	69.48	82.00	402.00	2.95	75.00	1,478.48	613.78	859.70	+587.55
1899	700.00	--------	1.67	57.00	235.00	63.00	75.00	1,131.67	555.70	575.97	−283.73
1900	1,000.00	--------	.02	89.00	220.00	179.00	75.00	1,563.02	450.90	1,112.12	+536.15
1901	1,000.00	--------	.00	79.00	205.00	138.00	75.00	1,497.00	[a]10.00	1,487.00	+374.88
1902	1,200.00	--------	.00	105.00	115.00	145.00	80.00	1,645.00	[a]10.00	1,635.00	+148.00
1903	1,350.00	--------	6.53	95.00	147.00	156.00	80.00	1,834.53	[a]10.00	1,824.53	+189.53

[a] Taxes, estimated.

In the autumn of 1906 land was rented and teams and machinery purchased to operate it, because two of the boys are now large enough to help. Had it not been for this expansion, the hogs sold near the close of 1906 would have paid all debts and the running expenses through the next summer. There were also on hand—

Cash	$65.00	Household goods	[a]$30.00
2 horses	150.00	Machinery and tools	90.00
3 cows	90.00	Feed and supplies	302.00
11 hogs	200.00	Farm	[b]3,000.00
78 fall pigs	273.00		
Poultry	12.00	Total	4,212.00

---

[a] Possibly this is as much as these goods would have brought on the market. This includes a collection of mounted animals and birds which it is not probable that any taxidermist would sell for less than $200, and it is worth much more than it was in 1896 when the owner invoiced it at $40. The writer would estimate the household goods exclusive of the specimens at $150.

[b] The farm was not for sale and could not have been purchased at this price.

The buildings and fences cost probably $1,400 for material alone. The increase of $2,600 in the value of the farm since it was purchased would probably not pay the cost of the improvements that have been made if orchards and groves are included. The owner of this farm has worked hard and the family has lived economically, but most of the time many of the comforts of life, as well as the necessities, have been enjoyed and the children have been kept in school. There has always been time to care for the hundreds of flowering perennials and shrubs and ornamental trees which almost hide the house from view. To start with $294 capital and in eleven years have over $4,200 and care for two to seven children all the time is certainly a very good showing for 38 acres of rough land. Two acres of the 40 are in public roads. No land was rented until 1907, except the first two years, and that did not pay expenses.

A TWENTY-ACRE FARM IN PAWNEE COUNTY, NEBRASKA.

INTRODUCTION.

Ten years ago Mr. Arnold Martin, a young Swiss farmer, who as a result of three years' renting in northeastern Kansas had secured a team, a little farm machinery, and $275 in money, became dissatisfied. He had been raised on a 6-acre farm, had studied agriculture in the public schools, and knew something of intensive methods. He believed he could do better on a small place of his own than on a large rented farm. In Pawnee County he found 20 acres of unimproved rough land mostly covered with brush and small trees. Good land was worth $50 to $70 per acre, but no one seemed to want this piece. He purchased it for $12.50 per acre, paying $100 down and giving a note for $150 at 7 per cent interest for three years. There remained $175 with which to make improvements and start his work. Realizing that it would take several years to subdue most of his own land, he leased an adjoining piece of about 4 acres for five years. This was also unbroken and needed considerable clearing.

While grubbing, plowing, and planting, the owner was studying the markets and his soil to see what he could produce for which there was a home demand. Potatoes, onions, small fruits, pears, and peaches were chosen for the main crops, with corn for any land not otherwise occupied.

THE SOIL AND ITS USE.

A small field of nearly 2 acres of alluvial soil is kept for annual crops. The slopes are rocky in places and the soil is a residual clay loam, having been formed mostly by the weathering of the limestone which underlies it. About 8 acres of this are set to orchards, about 1 acre in alfalfa, 1 in timothy and clover, 3 in pasture (half of which is timbered), and a little in annual crops. One hill is poor soil, largely formed by glacial deposits, and contains some bowlders, locally called "nigger heads." About 2 acres of this is in wild grass, which is used for hay, as is also about half an acre of stony land around the quarry. There is still a little land that has not been put to use.

METHODS AND PRACTICES.

The intensive methods practiced are of particular interest. The land is kept busy from spring till fall. At the last cultivation of the potatoes corn is planted between the rows. A full crop of potatoes is secured and a fair crop of corn also. As many as 75 bushels of corn to the acre have been grown in this way. The corn usually has to be hoed once, but the potato vines nearly cover the ground, so not much working of the corn is required. After the potatoes ripen the corn keeps the weeds down. By the time the corn needs the ground the potatoes are ripe, and the corn is in the shock before it is time to dig the potatoes. Squashes are sometimes planted the same way. Usually parts of the potato patches are sown with millet or sorghum just before the last cultivation. This makes a good crop of feed and does not hurt the potatoes. The smallest yield of potatoes ever secured was 100 bushels an acre and the largest over 700 bushels an acre. The onion patches grow corn and melons, which are planted in the rows between the onions. Part of the orchard is set with small fruit and part is planted with potatoes and truck.

In dry spells all the water the windmill will pump is used for irrigation, and it is here that intensive cropping reaches its height. There is also a small irregular spring which flows into a reservoir and at times furnishes considerable water. The water from the well flows directly to the ditch as pumped. A little manure is scattered in the ditches to prevent washing.

The accompanying diagram (fig. 3) shows the rows of crops in two of the spaces between rows of pear trees. The pears have been set six years and the limbs touch in the rows, yet nearly all the other plants were doing well when the writer visited the farm late in June. The trees are 10 feet apart in the rows and the rows 12 feet apart.

MANURE.

On account of the soil being new, not so much manure has been required as will be needed in the future. All that is made on the farm is used and all that is wanted can be obtained two miles distant. All cornstalks and coarse waste are used to prevent washing or to mulch trees or berries that can not be cultivated. About two loads of wood ashes are secured annually and used on strawberries and pear trees.

FRUIT.

The orchards contain 900 pear, 200 cherry, about 800 peach, and a few apple trees; 200 plums were set, but have been grubbed out because they were not profitable.

Pears have paid the best. Many varieties have been tried. Some varieties are not readily self-fertilized, especially the Kiefer, so it was necessary to find varieties that flowered at the same time, as well as those that were hardy and prolific. The best success has been attained by planting Dwarf Duchess and Standard Kiefer alternately. Standard Flemish Beauty has also done well.


PEAR TREES WITH BEETS BETWEEN.
TOMATOES.
CABBAGE.
"
SWEET POTATOES, KOHL-RABI CLOSE BESIDE.
" " , BEETS CLOSE BESIDE.
PEAR TREES WITH BEANS BETWEEN.
PEAR TREES WITH RASPBERRIES BETWEEN.
BEANS.
POTATOES.
"
CELERY.
PEAR TREES WITH RASPBERRIES BETWEEN.

FIG. 3.—Rows of crops in the pear orchard on the Martin farm.

Of the small fruits strawberries have given the best returns, but a good many raspberries and blackberries have been grown, and some gooseberries and currants.

SEED CORN.

The production of corn for seed and for exhibition has been undertaken as a side issue and is proving very successful. Mr. Martin won a gold medal on corn at the St. Louis Exposition. At other fairs many premiums have been awarded his products. He finds ready sale for seed corn at good prices. When corn is grown without any other crop cultivation is continued until the ears are well matured. Contrary to the practice of most breeders, Mr. Martin plants the best ear in a patch by itself, and the best ear from the crop is selected and planted in the same manner. The prizes he has won do not make a bad showing for his practice.

EXHIBITS OF FARM PRODUCTS.

The last few years considerable attention has been given to growing a large variety of products for exhibition purposes. Last year $243.25 in cash prizes was secured. At the Portland Exposition three gold and two silver medals were won.

SPRAYS.

Mr. Martin is an enthusiastic advocate of dust sprays and uses sal Bordeaux mixture frequently on orchards and truck. Arsenical poisons are used as insecticides. His plants and trees have a very healthy appearance and the pear orchard is probably the best in the State, but it must be remembered that the trees are still young.

LABOR.

No labor is ever hired. The owner, with the help of his wife, does it all, and besides has earned considerable money every year, except the last, by helping his neighbors. He has more work now than he can well do at home and may soon have to hire help.

MISCELLANEOUS.

No butter, eggs, or poultry have ever been sold. Only a few chickens are kept for family use, and these, on account of the crops they might destroy, are closely confined during the growing season. Only one cow is kept. When there is a surplus of rough feed, calves are bought, fed through the winter, and sold in the spring. Some hogs are now kept to make use of unsalable products.

EQUIPMENT.

Stock.	Machinery.
1 team of mules.	1 wagon.
1 cow.	1 mower.
1 1-year-old driving colt.	1 hayrake.
1 sow.	1 cultivator, 4-shovel, 2-horse.
A few chickens.	1 cultivator, 5-shovel, 1-horse.
	1 harrow, 2-section.
	1 walking lister.
	1 walking plow.
	1 hand cultivator.
	1 garden drill.
	1 hand sprayer.

INCOME AND EXPENSES.

The following shows the receipts for produce sold from the farm for the past ten years. Exact accounts of everything have been kept. To this should be added about $100 received for rock quarried on the farm by the owner's labor. The profit on the calves which have been wintered should also be added, but the amount is unknown:

1897.

3 acres potatoes, 678 bushels at 50 cents	$339.00
8 acres corn, 220 bushels at 32 cents	70.40
One-half acre vegetables	72.00
Received for helping neighbors	58.00
Total	539.40

1898.

5 acres potatoes, 930 bushels at 45 cents to $1	$418.50
12 acres corn, 170 bushels	53.20
Strawberries and vegetables	126.30
Received for helping neighbors	103.00
Total	701.00

1899.

7 acres potatoes, 1,085 bushels at 35 cents	$379.75
12 acres corn, 230 bushels at 30 cents	69.00
One-half acre small fruit and vegetables	136.40
Received for helping neighbors	46.20
Total	631.35

1900.

10 acres potatoes, 1,260 bushels at 40 cents	$504.00
12 acres corn, 220 bushels at 32 cents	70.40
One-half acre vegetables	82.60
One-half acre small fruit, 126 crates at $1.60	201.60
Received for helping neighbors	36.40
Total	895.00

If too many acres appear to be accounted for, it must be remembered that much of the land raises two crops.

1901.

5 acres potatoes, 710 bushels at $1 to $2	$810.00
8 acres corn (none sold).	
Small fruit and vegetables	69.50
Received for helping neighbors	28.00
Total	907.50

This was a very dry season and the thorough cultivation practiced told well on the potato crop.

1902.

5 acres potatoes, 1,600 bushels at 25 cents	$400.00
10 acres corn, 280 bushels at 35 cents	98.00
Small fruit	325.40
Received for helping neighbors	42.00
Total	865.40

1903.

Potatoes, at 80 cents to $1.50	$412.00
Received for work at college	175.00
Total	587.00

In 1903 half the land was rented and the owner spent three months away from home starting a farm for a college. This made the receipts for the year very low.

1904.

5 acres potatoes, 8 acres corn, etc.:

Potatoes, 750 bushels at 75 cents	$562.50
Corn, 210 bushels at 40 cents	84.00
Small fruit and vegetables	146.50
Received for helping neighbors	56.25
Total	849.25

1905.

6 acres potatoes, 7 acres corn, etc.:

Potatoes, 892 bushels at 60 cents	$535.20
Corn, 168 bushels at 40 cents	67.20
Seed corn, 46 bushels at $1.50	69.00
Small fruit and vegetables	126.50
Received for helping neighbors	76.80
Total	874.70

1906.

4 acres potatoes, 8 acres corn, etc.:

Potatoes, 350 bushels at 55 cents	$192.50
Corn, 120 bushels at 36 cents	43.20
Pears, 286 bushels at $1.20	343.20
Seed corn, 38 bushels at $1.75	66.50
Premiums	243.25
Hogs	142.50
Total	1,031.15

RESULTS ACCOMPLISHED.

The results accomplished, as shown in the foregoing statements, have not been obtained by catering to fancy city trade. The nearest market of any consequence and the one where most of the produce has been sold is a town of 2,500 inhabitants 7 miles distant.

In 1899 the mortgage of $150 was paid; in 1902 a barn was built at a cost of $100; in 1903 a well, a windmill, etc., were built costing $100, and an addition to the house, costing $200, was made. The fencing used cost about $50.

The home is now comfortably furnished and practically all has been paid for in ten years. The other expenses of the farm have been very light except for nursery stock, which has probably cost $800. The house is a neat little four-room cottage. The barn has a stone basement, 16 feet by 20 feet, for stock and an upper story for grain and hay.

Mr. Martin now owes no one and has some money ahead. The farm could easily be sold for $2,500. The owner has made three pleasure trips to Colorado and spent three months last winter in Switzerland. He has found time also to gain a good command of English, both spoken and written.

Mr. Martin says his place is far from producing what it is capable of; in fact, there are several acres that have as yet produced almost nothing. He expects to do much better in the future. It will readily be seen that much time and money have been spent on orchards which have only just commenced to bear.

The neighbors used to laugh at the young foreigner and nicknamed him "Hazelbrush," but now they say, "He is making more money on 20 acres than we do on 160." He does not want any more land, but wants to farm what he has better. In speaking of the size of farms he once said: "People of moderate means should not farm too much land. A man can start on 20 acres; 40 acres will do; 80 is enough; 160 an abundance; 320 a misfortune; and 640 a calamity."

GENERAL CONCLUSIONS.

Nothing in this bulletin should be interpreted to mean that the time has come when the average farm in the corn belt should be reduced to 20 or 40 acres. We do not mean any such thing. It seems perfectly clear that the majority of farms should contain 80 to 160 acres. There is no reason why the man who owns a large farm and has means and help to operate it should reduce his acreage. But the man who must depend mainly on borrowed money or is unable to secure sufficient help often overreaches and reduces his profits or creates an actual loss in consequence, when if he had been content to work on a smaller scale, depending mostly upon his own labor and as little as possible upon borrowed funds, success would have been much more certain.

Even the man on a 160-acre farm must depend largely upon making a profit from hired labor. His margin usually is not large and his risk is considerable. He must commonly be content with a very moderate return upon his investment. There are many details which must too often be entrusted to incompetent or indifferent persons, and many small losses and leaks occur that could be prevented if the owner had less to look after. The small farmer can not expect to clear as much as the larger one in the most favorable seasons, but on the other hand his loss will be much less in unfavorable seasons. He has less risk not only because he has less invested in land, but especially because he has less invested in teams, machinery, feed, etc., and has entirely eliminated the very important item of expense for hired help, and also because he can keep closer watch of everything and in case of sudden or unforeseen contingencies, such as sudden storms, can care for his smaller acreage more quickly. Generally, too, his income will be more evenly divided between several products than is that of the larger farmer, and consequently his chances of heavy loss are very much reduced. In case of poor crops the small farmer can lose little besides his living expenses because his running expense is very small, but the large farmer who operates on borrowed capital has his interest to pay and heavy running expenses, including hired labor. One adverse season may consume the profits of several favorable ones.

The capital invested in a small farm is often of minor importance, the owner's labor being the main producing factor, but on large farms or even on farms of moderate size interest on the investment may be much more than the value of one man's labor. Nearly everything on the small farm returns a larger percentage of profit because everything receives the owner's personal attention. He does all the work and does it much better than hired men can be expected to, and this difference is often enough to make the difference between a loss and a good profit.

Generally the man on less than 80 acres can not afford to grow much grain. As a rule, he should aim to produce things that are shipped into his home town rather than those that are shipped out. A glance at any grocer's stock is sufficient to show that he is obliged to import much that could be profitably grown in the vicinity. Strawberries, blackberries, grapes, melons, cabbage, tomatoes, onions, sweet potatoes, and potatoes are among the products that are annually shipped into many of the towns in this region and during the season when they could be supplied by the neighboring farms. Of the products adapted to small farms for which there is a more general market, hogs and alfalfa will probably take the lead. Dairying can always be resorted to; the growing of improved seed corn can well be handled on the small farm; 100 or more hens can always be made profitable. No one man will produce all of these, and for that reason there is room for several small farms near every town of even a few hundred inhabitants. Near the larger cities small farmers, truckers, and dairymen are numerous and competition is close, but still there is room for more men with energy and intelligence who are quick to see what can be produced at a good profit.

No small farmer should depend entirely upon any one product unless it be a dairy product. Danger of failure is too great and there is not an economical distribution of labor. There will be too much to do at one season and nothing at another.

A few cows, a few hogs, and a good many hens will work in nicely with almost any combination of crops. If many hogs are kept most of the farm should be in alfalfa, and hay and hogs would be the products sold. Potatoes or seed corn can be handled with hogs and alfalfa. Often a pasture has to be plowed up, and this makes an excellent place for either corn or potatoes. If cream or butter is to be sold, enough hogs should be kept to make profitable use of the milk. The number of types of farming and combinations of crops that can be adopted is very large, and the writer has intended to mention only a few and not to exhaust the list. It will be seen that some of these types are almost independent of local markets.

Every man must make a careful study of the local conditions, his own preferences, and the crops and stock he selects. Of these he should become an expert producer. Every foot of ground should be kept busy as much of the time as possible and to do this catch crops, such as turnips, pumpkins, millet, sorghum, and early varieties of corn planted late for feed, must often be resorted to. Frequently before one crop is off the ground another may be started. The producing power of the soil must be kept at the maximum by the use of manure and leguminous crops.

It is not the intention of the writer to encourage city men who know nothing of farming to go on to farms expecting easy work and large profits. Without economy and hard work success should not be expected on any farm. Experience is as necessary as in any other line of work. The more intensive the methods the more necessary experience becomes. It is true that inexperienced men frequently make successful farmers from the start, but this is also true of any other line of business. It should be emphasized that each of the men whose farms have been described was young, strong, and full of energy; that he was an experienced farmer and already familiar with the locality before starting on his small farm.

FARMERS' BULLETINS.

The following is a list, by number, of the Farmers' Bulletins available for distribution. The bulletins entitled "Experiment Station Work" give in brief the results of experiments performed by the State experiment stations. Titles of other bulletins are self-explanatory. Bulletins in this list will be sent free to any address in the United States on application to a Senator, Representative, or Delegate in Congress, or to the Secretary of Agriculture, Washington, D. C. Numbers omitted have been discontinued, being superseded by later bulletins.

22. The Feeding of Farm Animals. Pp. 40.
24. Hog Cholera and Swine Plague. Pp. 16.
27. Flax for Seed and Fiber. Pp. 16.
28. Weeds and How to Kill Them. Pp. 30.
29. Souring and Other Changes in Milk. Pp. 22.
30. Grape Diseases on the Pacific Coast. Pp. 15.
32. Silos and Silage. Pp. 30.
33. Peach Growing for Market. Pp. 24.
34. Meats: Composition and Cooking. Pp. 31.
35. Potato Culture. Pp. 24.
36. Cotton Seed and Its Products. Pp. 16.
42. Facts About Milk. Pp. 32.
44. Commercial Fertilizers. Pp. 38.
47. Insects Affecting the Cotton Plant. Pp. 32.
48. The Manuring of Cotton. Pp. 16.
51. Standard Varieties of Chickens. Pp. 48.
52. The Sugar Beet. Pp. 48.
54. Some Common Birds. Pp. 48.
55. The Dairy Herd. Pp. 30.
56. Experiment Station Work—I. Pp. 30.
58. The Soy Bean as a Forage Crop. Pp. 24.
59. Bee Keeping. Pp. 48.
60. Methods of Curing Tobacco. Pp. 24.
61. Asparagus Culture. Pp. 40.
62. Marketing Farm Produce. Pp. 31.
63. Care of Milk on the Farm. Pp. 40.
64. Ducks and Geese. Pp. 55.
65. Experiment Station Work—II. Pp. 32.
66. Meadows and Pastures. Pp. 30.
69. Experiment Station Work—III. Pp. 32.
71. Essentials in Beef Production. Pp. 24.
72. Cattle Ranges of the Southwest. Pp. 32.
73. Experiment Station Work—IV. Pp. 32.
74. Milk as Food. Pp. 39.
77. The Liming of Soils. Pp. 24.
78. Experiment Station Work—V. Pp. 32.
79. Experiment Station Work—VI. Pp. 27.
80. The Peach Twig-borer. Pp. 16.
81. Corn Culture in the South. Pp. 24.
82. The Culture of Tobacco. Pp. 22.
83. Tobacco Soils. Pp. 23.
84. Experiment Station Work—VII. Pp. 32.
85. Fish as Food. Pp. 32.
86. Thirty Poisonous Plants. Pp. 32.
87. Experiment Station Work—VIII. Pp. 32.
88. Alkali Lands. Pp. 23.
91. Potato Diseases and Treatment. Pp. 15.
92. Experiment Station Work—IX. Pp. 30.
93. Sugar as Food. Pp. 31.
95. Good Roads for Farmers. Pp. 46.
97. Experiment Station Work—X. Pp. 32.
98. Suggestions to Southern Farmers. Pp. 48.
99. Insect Enemies of Shade Trees. Pp. 30.
100. Hog Raising in the South. Pp. 40.
101. Millets. Pp. 30.
102. Southern Forage Plants. Pp. 48.
103. Experiment Station Work—XI. Pp. 30.
104. Notes on Frost. Pp. 24.
105. Experiment Station Work—XII. Pp. 32.
106. Breeds of Dairy Cattle. Pp. 48.
107. Experiment Station Work—XIII. Pp. 32.
108. Saltbushes. Pp. 20.
110. Rice Culture in the United States. Pp. 28.
111. Farmer's Interest in Good Seed. Pp. 24.
112. Bread and Bread Making. Pp. 40.
113. The Apple and How to Grow It. Pp. 32.
114. Experiment Station Work—XIV. Pp. 28.
116. Irrigation in Fruit Growing. Pp. 48.
118. Grape Growing in the South. Pp. 32.
119. Experiment Station Work—XV. Pp. 30.
120. Insects Affecting Tobacco. Pp. 32.
121. Beans, Peas, and other Legumes as Food. Pp. 38.
122. Experiment Station Work—XVI. Pp. 32.
124. Experiment Station Work—XVII. Pp. 32.
125. Protection of Food Products from Injurious Temperatures. Pp. 24.
126. Practical Suggestions for Farm Buildings. Pp. 48.
127. Important Insecticides. Pp. 46.
128. Eggs and Their Uses as Food. Pp. 40.
129. Sweet Potatoes. Pp. 40.
131. Household Tests for Detection of Oleomargarine and Renovated Butter. Pp. 10.
132. Insect Enemies of Growing Wheat. Pp. 38.
133. Experiment Station Work—XVIII. Pp. 32.
134. Tree Planting in Rural School Grounds. Pp. 32.
135. Sorghum Sirup Manufacture. Pp. 40.
137. The Angora Goat. Pp. 48.
138. Irrigation in Field and Garden. Pp. 40.
139. Emmer: A Grain for the Semiarid Regions. Pp. 16.
140. Pineapple Growing. Pp. 48.
142. Principles of Nutrition and Nutritive Value of Food. Pp. 48.
144. Experiment Station Work—XIX. Pp. 32.
145. Carbon Bisulphid as an Insecticide. Pp. 28.
147. Winter Forage Crops for the South. Pp. 40.
149. Experiment Station Work—XX. Pp. 32.
150. Clearing New Land. Pp. 24.
151. Dairying in the South. Pp. 48.
152. Scabies in Cattle. Pp. 32.
153. Orchard Enemies in the Pacific Northwest. Pp. 39.
154. The Home Fruit Garden: Preparation and Care. Pp. 16.
155. How Insects Affect Health in Rural Districts. Pp. 19.
156. The Home Vineyard. Pp. 22.
157. The Propagation of Plants. Pp. 24.
158. How to Build Small Irrigation Ditches. Pp. 28.
159. Scab in Sheep. Pp. 48.
161. Practical Suggestions for Fruit Growers. Pp. 30.
162. Experiment Station Work—XXI. Pp. 32.
164. Rape as a Forage Crop. Pp. 16.
165. Silkworm Culture. Pp. 32.
166. Cheese Making on the Farm. Pp. 16.
167. Cassava. Pp. 32.
168. Pearl Millet. Pp. 16.
169. Experiment Station Work—XXII. Pp. 32.
170. Principles of Horse Feeding. Pp. 44.
172. Scale Insects and Mites on Citrus Trees. Pp. 43.
173. Primer of Forestry. Pp. 48.
174. Broom Corn. Pp. 30.
175. Home Manufacture and Use of Unfermented Grape Juice. Pp. 16.
176. Cranberry Culture. Pp. 20.
177. Squab Raising. Pp. 32.
178. Insects Injurious in Cranberry Culture. Pp. 32.
179. Horseshoeing. Pp. 30.
181. Pruning. Pp. 39.
182. Poultry as Food. Pp. 40.
183. Meat on the Farm: Butchering, Curing, and Keeping. Pp. 37.
185. Beautifying the Home Grounds. Pp. 24.
186. Experiment Station Work—XXIII. Pp. 32.
187. Drainage of Farm Lands. Pp. 38.
188. Weeds Used in Medicine. Pp. 45.
190. Experiment Station Work—XXIV. Pp. 32.

192. Barnyard Manure. Pp. 32.
193. Experiment Station Work—XXV. Pp. 32.
194. Alfalfa Seed. Pp. 14.
195. Annual Flowering Plants. Pp. 48.
196. Usefulness of the American Toad. Pp. 16.
197. Importation of Game Birds and Eggs for Propagation. Pp. 30.
198. Strawberries. Pp. 24.
199. Corn Growing. Pp. 32.
200. Turkeys. Pp. 40.
201. Cream Separator on Western Farms. Pp. 23.
202. Experiment Station Work—XXVI. Pp. 32.
203. Canned Fruits, Preserves, and Jellies. Pp. 32.
204. The Cultivation of Mushrooms. Pp. 24.
206. Milk Fever and Its Treatment. Pp. 16.
208. Varieties of Fruits Recommended for Planting. Pp. 48.
209. Controlling the Boll Weevil in Cotton Seed and at Ginneries. Pp. 32.
210. Experiment Station Work—XXVII. Pp. 32.
211. The Use of Paris Green in Controlling the Cotton Boll Weevil. Pp. 23.
213. Raspberries. Pp. 38.
215. Alfalfa Growing. Pp. 40.
217. Essential Steps in Securing an Early Crop of Cotton. Pp. 16.
218. The School Garden. Pp. 40.
219. Lessons from the Grain Rust Epidemic of 1904. Pp. 24.
220. Tomatoes. Pp. 32.
221. Fungous Diseases of the Cranberry. Pp. 16.
222. Experiment Station Work—XXVIII. Pp. 32.
223. Miscellaneous Cotton Insects in Texas. Pp. 24.
224. Canadian Field Peas. Pp. 16.
225. Experiment Station Work—XXIX. Pp. 32.
226. Relation of Coyotes to Stock Raising in the West. Pp. 24.
227. Experiment Station Work—XXX. Pp. 32.
228. Forest Planting and Farm Management. Pp. 22.
229. The Production of Good Seed Corn. Pp. 24.
231. Spraying for Cucumber and Melon Diseases. Pp. 24.
232. Okra: Its Culture and Uses. Pp. 16.
233. Experiment Station Work—XXXI. Pp. 32.
234. The Guinea Fowl. Pp. 24.
235. Preparation of Cement Concrete. Pp. 32.
236. Incubation and Incubators. Pp. 32.
237. Experiment Station Work—XXXII. Pp. 32.
238. Citrus Fruit Growing in the Gulf States. Pp. 48.
239. The Corrosion of Fence Wire. Pp. 32.
241. Butter Making on the Farm. Pp. 32.
242. An Example of Model Farming. Pp. 16.
243. Fungicides and their Use in Preventing Diseases of Fruits. Pp. 32.
244. Experiment Station Work—XXXIII. Pp. 32.
245. Renovation of Worn-out Soils. Pp. 16.
246. Saccharine Sorghums for Forage. Pp. 37.
247. The Control of the Codling Moth and Apple Scab. Pp. 21.
248. The Lawn. Pp. 20.
249. Cereal Breakfast Foods. Pp. 36.
250. The Prevention of Wheat Smut and Loose Smut of Oats. Pp. 16.
251. Experiment Station Work—XXXIV. Pp. 32.
252. Maple Sugar and Sirup. Pp. 36.
253. The Germination of Seed Corn. Pp. 16.
254. Cucumbers. Pp. 30.
255. The Home Vegetable Garden. Pp. 47.
256. Preparation of Vegetables for the Table. Pp. 48.
257. Soil Fertility. Pp. 39.
258. Texas or Tick Fever and Its Prevention. Pp. 45.
259. Experiment Station Work—XXXV. Pp. 32.
260. Seed of Red Clover and Its Impurities. Pp. 24.
261. The Cattle Tick. Pp. 22.
262. Experiment Station Work—XXXVI. Pp. 32.
263. Practical Information for Beginners in Irrigation. Pp. 40.
264. The Brown-tail Moth and How to Control It. Pp. 22.
266. Management of Soils to Conserve Moisture. Pp. 30.
267. Experiment Station Work—XXXVII. Pp. 32.
268. Industrial Alcohol: Sources and Manufacture. Pp. 45.
269. Industrial Alcohol: Uses and Statistics. Pp. 29.
270. Modern Conveniences for the Farm Home. Pp. 48.
271. Forage Crop Practices in Western Oregon and Western Washington. Pp. 39.
272. A Successful Hog and Seed-Corn Farm. Pp. 16.
273. Experiment Station Work—XXXVIII. Pp. 32.
274. Flax Culture. Pp. 36.
275. The Gipsy Moth and How to Control It. Pp. 22.
276. Experiment Station Work—XXXIX. Pp. 32.
277. The Use of Alcohol and Gasoline in Farm Engines. Pp. 40.
278. Leguminous Crops for Green Manuring. Pp. 27.
279. A Method of Eradicating Johnson Grass. Pp. 16.
280. A Profitable Tenant Dairy Farm. Pp. 16.
281. Experiment Station Work—XL. Pp. 32.
282. Celery. Pp. 36.
283. Spraying for Apple Diseases and the Codling Moth in the Ozarks. Pp. 42.
284. Insect and Fungous Enemies of the Grape East of the Rocky Mountains. Pp. 48.
285. The Advantage of Planting Heavy Cotton Seed. Pp. 16.
286. Comparative Value of Whole Cotton Seed and Cotton-seed Meal in Fertilizing Cotton. Pp. 14.
287. Poultry Management. Pp. 48.
288. Nonsaccharine Sorghums. Pp. 28.
289. Beans. Pp. 28.
290. The Cotton Bollworm. Pp. 32.
291. Evaporation of Apples. Pp. 38.
292. Cost of Filling Silos. Pp. 15.
293. Use of Fruit as Food. Pp. 38.
294. Farm Practice in the Columbia Basin Uplands. Pp. 30.
295. Potatoes and Other Root Crops as Food. Pp. 45.
296. Experiment Station Work—XLI. Pp. 32.
297. Methods of Destroying Rats. Pp. 8.
298. Food Value of Corn and Corn Products. Pp. 40.
299. Diversified Farming Under the Plantation System. Pp. 14.
300. Some Important Grasses and Forage Plants for the Gulf Coast Region. Pp. 15.
301. Home-grown Tea. Pp. 16.
302. Sea Island Cotton: Its Culture, Improvement, and Diseases. Pp. 48.
303. Corn Harvesting Machinery. Pp. 32.
304. Growing and Curing Hops. Pp. 39.
305. Experiment Station Work—XLII. Pp. 32.
306. Dodder in Relation to Farm Seeds. Pp. 27.
307. Roselle: Its Culture and Uses. Pp. 16.
308. Game Laws for 1907. Pp. 52.
309. Experiment Station Work—XLIII. Pp. 32.
310. A Successful Alabama Diversification Farm. Pp. 24.
311. Sand-clay and Burnt-clay Roads. Pp. 20.
312. A Successful Southern Hay Farm. Pp. 15.
313. Harvesting and Storing Corn. Pp. 32.
314. A Method of Breeding Early Cotton to Escape Boll-weevil Damage. Pp. 24.
315. Progress in Legume Inoculation. Pp. 20.
316. Experiment Station Work—XLIV. Pp. 32.
317. Experiment Station Work—XLV. Pp. 32.
318. Cowpeas. Pp. 26.
319. Demonstration Work in Cooperation with Southern Farmers. Pp. 23.
320. Experiment Station Work—XLVI. Pp. 32.
321. Use of Split-Log Drag on Earth Roads. Pp. 14.
322. Hog Management. In press.
323. Clover Farming on Sandy Jack-Pine Lands of the North. Pp. 24.
324. Sweet Potatoes. In press.

O

INDEX.

	Farmers' Bulletin No.	Page.
lteration, seed, importance of dodder	306	6
›last kiln for hop drying, description	304	29-31
ama diversification farm, successful	310	1-24
game laws, close seasons and hunting licenses, 1907	308	6, 11, 27, 35, 41
ka game laws, close seasons and hunting licenses, 1907	308	6, 11-12, 27, 35, 41
hol production, use of sweet potatoes	324	39
fa, adaptability to rotation in Southern States	310	5, 7, 24
culture, fertilizers, and yield, Alabama	310	12, 16, 20
dodder-infestation, description of seed	306	9, 14, 17-19, 24
feed for horses, tests	316	25
inoculation of soil	315	15, 18, 19
pasture for hogs	305	25
	310	10, 12, 16, 20, 24
protein content	320	14
renovation of poor soils	319	17
thetics, use in forcing plants	320	23-25
nals, farm, feeding cabbage	305	22-24
roots	305	19-22
See also Cattle; Cows; Hogs; Horse; Sheep.		
lope. *See* Game laws, under the several States.		
racnose, cotton, description, cause, and remedies	302	47
's gossypii, yellow aphis, roselle injury from	307	16
yellow, roselle injury	307	16
le diseases, spraying, precaution to avoid foliage injury	305	12-13
varieties, scab-resistant, list	305	13
les, color, effect of fertilizers, experiments	316	8-9
varieties, susceptibility to foliage injury, list	305	13
ona game laws, close seasons, and hunting licenses, 1907	308	6, 12, 27, 35, 41
nsas demonstration work, cooperative, letters from farmers	319	21, 22
game laws, close seasons and hunting licenses, 1907	308	6, 12, 27, 35, 41
rice culture, introduction and experiments	305	5-7
y worm, fall, damage to milo, injury to leaves and stems	322	21
hoke, Jerusalem, tubers, feed for horses, tests	316	24
s, fertilizer for sweet potatoes	324	9
ciations, cooperative, for marketing crops, methods and difficulties	309	20-23
ubon Society, South Carolina, as game commission	308	8
ralia, roselle jelly-making	307	6, 13
eria, cream, relations of age and temperature	309	31-32
cream-ripening, practical use	317	27-28
cultures, applications and reports	315	8-9
legume. *See* Legume bacteria.		
nitrogen gathering, cultures and use, directions	315	7-8
rium malvacearum, description, cause and control	302	41-43
Sea Island cotton, packing methods	302	11-12

	Farmers' Bulletin No.	Page.
Baking powder, effect on quality of flour	320	19
Balers, hop, hand and power presses, description	304	34-35
Bales, hop, measure and weight	304	35
Bales, Sea Island cotton, packing methods	302	11-12
Baling hops, directions, presses, measure and weight of bales	304	33-36
BALL, CARLETON R., and ARTHUR H. LEIDIGH, bulletin on "Milo as a dry-land grain crop"	322	1-23
Barley, comparison with emmer as feeding stuff	305	18
hog feed as supplement to corn	316	26, 27
Barnyard manure. *See* Manure.		
Bean harvester, not satisfactory in use with cowpea seed	318	19
Beans, cull, feed for hogs, methods and experiments	305	25-28
inoculation of soil	315	17, 19
velvet, fertilizer	302	19
value in rotation with Sea Island cotton	302	18
Bear. *See* Game laws, under the several States.		
BEATTIE, W. R., bulletin on "Sweet potatoes"	324	1-39
Beds, sweet potato, heating methods	324	10-12
Beef, baby, fattening, emmer experiments	305	18
Beet, sugar, pulp, feed for horses, tests	316	24
Beetles, potato, control by hand picking	325	9
Beets, sugar, feeding value, comparison with mangels	305	21
Beggarweed, value as hay and green manure	302	19
BENNETT, R. L., bulletin on "Breeding early cotton to escape boll-weevil damage"	314	1-28
BENTON, HARMON, bulletin on "A successful Southern hay farm"	312	1-15
Bermuda grass hay, yield and value, Oklahoma experiments	320	12-13
pasture for hogs	310	10
Binders, corn, description, and cost of use	313	13
history, construction, draft, cost and efficiency	303	10-19
Birds, game. *See* Game laws, under the several States.		
water or shore. *See* Game laws, under the several States.		
Black cowpeas, characteristics	318	26
Black-arm, cotton, description, cause, and control	302	41-43
Black-root, cotton, description, cause, and control	302	43-46
Black-rot, sweet potato, description, and control	324	24, 25
Blight, bacterial, cotton, description, cause, and control	302	41-43
Blind staggers, caused by moldy foodstuffs	322	20
Blue cotton, description and remedies	302	48
Boll-weevil conditions, cotton cultural system	319	10-11
control, breeding early cotton, method	314	1-28
destruction methods	319	11
Bolls, Sea Island cotton, ideal shape	302	36
Boll-spot, cotton, description, cause, and control	302	41-43
Bordeaux mixture, foliage injury, description and prevention	305	12-13
formula, for spraying potatoes	320	22-23
Bran, wheat, laxative properties	305	16-17
Breakfast foods, most economical	316	19
Breeding corn, results of work	317	21
cotton, early, to escape boll-weevil damage	314	1-28
Sea Island cotton, directions, methods	302	26-33
BREWSTER, CHAS. E., T. S. PALMER, and HENRY OLDYS, bulletin on "Game laws for 1907"	308	1-52
Brome grass, protein content	320	16
Buffalo. *See* Game laws, under the several States.		
Buildings, farm, storage house for sweet potatoes	324	30-32
Bulking Sea Island cotton, directions	302	39
Bull cotton, injury to Sea Island cotton, and removal	302	29
Burnt-clay roads, construction and cost	311	16-19
Bushel, corn, legal weight	313	28
Cabbage, cultural directions	305	23
feeding stock	305	22-24
storing methods	305	23-24
Cabbages, ringing, results	316	9
varieties, testing experiments	305	23

	Farmers' Bulletin No.	Page.
us, spineless, less hardy than others	316	17
ornia, game laws, close seasons and hunting licenses, 1907	308	6, 12, 27, 35, 41
hop planting, season and methods	304	10, 11
production per acre, possibility	304	36
roselle seed introduction	307	7
es, fattening, emmer experiments	305	19
ida game laws, 1907	308	4, 5, 9, 22–24, 31–32, 37, 47–48
idian field peas, results of inoculation	315	15, 17
on bisulphid, treatment of corncribs	313	26
dioxid, effect on development of lactic acid in milk	320	30
onated milk, formation of lactic acid	320	29
use for children and invalids	320	30
bou. *See* Game laws, under the several States.		
ot seed, germination and seeding directions	309	8, 15
ots, cultural directions, yield and value as stock feed	309	15
feeding value	305	21
varieties, plants per acre	309	9
in flour, food use	305	14, 16
le, beef, feeding on hay farm	312	8
fattening for market	320	25–28
feeding, cabbage	305	23
roots	305	20, 21
food requirements, daily ration	325	16
parking as means of distributing manure	316	5
ticks. *See* Ticks.		
ar, sweet potato, directions for building	324	30
ars, root storing, directions for construction	305	21, 22
ent, concrete, ditch lining, efficiency and cost	317	11
mortar ditch lining, efficiency and cost	317	11, 12
pipe, small irrigation systems; mixtures, method of molding and cost	317	12, 15
erville cotton, wilt-resistant variety	302	46
al foods, cooking	316	17–19
als, fertilizer formula, fish and chemicals	320	8
rring fence posts	320	31
se, tuna, preparation and use	316	16
stnut, starch content, exceptional among nuts	305	16
ken houses, yards, etc., directions	305	29
kens; feed and care, diseases and insects, remedies	305	28–32
ks, young, causes of death	309	27
ean dodder, description, seed, etc	306	10, 13, 19, 23
santhemums, ringing, results	316	10–11
, amount required in sand-clay roads per mile	311	12
cowpeas, characteristics	318	26
mixing with sand for road	311	7–10
origin and physical properties	311	6–7
roads (sand-clay and burnt-clay)	311	1–19
tile, irrigation systems	317	13
er and grass, without nurse crop	325	10
bacteria culture, use on new clover fields	323	15
bur, use as pasture	312	15
dodder-infestation, description of seed	306	9, 10, 12, 16, 22–23
farming on sandy jack-pine lands of the North	323	1–24
fertilizer formula, fish and chemicals	320	8
inoculation of new lands, methods	323	14–15
kinds adaptable to jack-pine lands	323	11
mammoth, for sandy jack-pine lands	323	11
manures and fertilizers	323	22–23
pasturing first crop, advantages	323	19
protein content	320	14
red, inoculation results	315	15, 16, 18, 19
rotation, sandy lands	323	22

	Farmers' Bulletin No.	Page.
Clover seed growing, customs, yield, etc	323	18-21
harvesting and curing	323	20-21
production on jack-pine lands	323	10
quantity to sow with nurse crop	323	13
seeding with or without nurse crop	323	11-14
stand, securing on jack-pine lands	323	11-15
value as green manure on jack-pine lands	323	10
Coal-tar dyes substitute, roselle, suggestion	307	14
products, use as food	305	15
Coccus hesperidum, roselle scale, distribution by ant	307	16
Colletotrichum gossypii, cause of anthracnose	302	47
Colonche, fermented drink made from tunas	316	16
Color, apples, effect of fertilizers, experiments	316	8-9
jelly and candies, use of tuna juice	316	17
Colorado game laws, close seasons and hunting licenses, 1907	308	6, 12, 27, 35, 41
Grand Junction Fruit Growers' Association, methods and growth	309	22-23
milo growing experiments	322	11, 22
Composting fish fertilizer	320	7
Connecticut game laws, close seasons and hunting licenses, 1907	308	6, 12, 27, 35, 41
Constipation, chickens, remedies	305	31
Cooking cereal foods	316	17-19
Cooling room for storing hops, description	304	31-33
Cooperation, marketing fruit and truck crops	309	20-23
Cooperative associations for marketing crops, methods, difficulties	309	20-23
demonstration work on southern farms	319	1-22
Coot. *See* Game laws, under the several States.		
Copper-sulphate solution for use in chicken houses	305	30
Corn and cowpeas, mixture for silage or forage, planting directions	318	11-12, 27
belt, small farms	325	1-29
best condition for filling silo	313	7
breeding work results	317	21
bushel, legal weight	313	28
comparison with emmer as feeding stuff	305	18-19
cribs, convenient arrangement	313	24
culture, fertilizers, and yield, Alabama diversification farm	310	12, 17, 20, 24
in demonstration work	319	15-16
methods, tests of yield	317	18-20
cutting and husking, comparison with husking from standing stalks	313	9
shocking cost per acre, hand and machine	303	6, 19, 22
time and methods	313	10-14
with knives, methods and cost	303	5-6
Egyptian, and Jerusalem, resemblance to milo	322	5, 22
fertilizers, tests for use	317	20
fodder silage	316	21
See also Fodder.		
forage crop, unprofitable	313	8
frosted, silage, feeding value	309	19
gathering	313	1-29
harvesting and storing	313	1-29
machinery, use	313	11, 12, 13, 21, 22
machines, description, cost, and efficiency	303	7-22
husking. *See* Husking.		
jerking ears unhusked	313	17
kiln-drying made necessary by bad treatment of crop	313	23
knives and husking pins	313	11, 18
machinery, use in harvesting crop	313	11, 12, 13, 21, 22
meal and beans, feed for hogs	305	26-27
moisture content	317	18
productiveness, increasing	317	17-21
protection from insects, mice, and rats	313	26

	Farmers' Bulletin No.	Page.
n seed, selection in field	319	16
shocking, building and tying shock, method of making shocks	313	12, 14–16
shrinkage in cribs	317	22–26
December to June	313	28
shucking	303	26–31
	313	9, 17–19
silage and cotton-seed meal for dairy cows	320	28–29
storing, ears and stover	313	22–27
use in fattening cattle	320	27
varieties, productiveness, comparison	317	17
yield, average per acre	303	26
rn-harvesting machinery	303	1–32
rn-picking machines	313	21
rn-shock loader, description	303	22
rrosive sublimate, use in disinfection of scabby potatoes, cost	316	12
tton, barring off and topping	319	13
breeders' association, sale of seed, restrictions	302	28
breeding, early, to escape boll-weevil damage	314	1–28
characters desired in seed selection	314	14
crop, conditions affecting	314	22
cultivation, intensive	319	13
cultural system under boll-weevil conditions	319	10–11
defoliate, description, value in boll-weevil control	314	21–22
early and rapid fruiting, distinguishing marks	314	7–10, 14
breeding, to escape boll-weevil damage	314	1–28
planting and early maturing varieties	319	12
stand, directions for planting and covering seed	314	24–27
Egyptian, comparison with Sea Island	302	13
susceptibility to "black-arm"	302	13
fiber, length desirable in seed selection	314	15
hybridizing	314	23
late fruiting, characteristics	314	8–10
plant, type recommended for early, rapid fruiting	314	13
planting, obstacles to progress, credit and rental system	302	16
rank growth, control by seed selection	314	23
Sea Island. *See* Sea Island cotton.		
seed improvement by gravity separation	302	33
selection and storing	319	14
seed-bed, preparation to insure early stand	314	27
spacing between plants and rows	319	13
stalks, brushing off infested squares	319	13
yellow, cause and prevention	302	39
tton-seed meal and corn silage for dairy cows	320	28–29
wpea pasture, value for hogs, returns per acre	318	13
seed growing, harvesting, thrashing, and storing	318	15–22, 27
quantity to sow per acre	318	9, 11, 12, 13, 16
wpeas and soy beans, comparative value in crop rotations	309	15–19
culture, uses and feeding value	318	1–28
cutting time, hay or seed	318	9, 19
feeding value, horses, cattle, and poultry	318	14–15
harvesting machinery	318	17–22
hay, planting, cutting, and curing	318	8–10
inoculation, results	315	11, 15, 16, 19
iron, immunity to root-knot	302	18
mixtures for hay	318	11–13, 27
pasture, fattening steers	318	14
for hogs	305	25
	310	10, 18, 21, 23
picking, hand and machine	318	16–19
planting and harvesting, seed quantity per acre, and yield	309	17
rotations for soil improvement, Southern States	318	22–24, 28
soil-renovating crop for poor land	319	17
thrashing machine, modifications, and price	318	21–22
suggestions	309	18

	Farmers' Bulletin No.	Page.
Cowpeas use on hay farm, culture and harvesting	312	9, 11
value as food, hay, and green manure	302	18
to southern farms	318	7, 22–24, 27
varieties, characteristics	318	24–27, 28
comparison, earliness and yield	309	18
Cows, dairy, feeding experiments, emmer comparison with barley	305	18
roots, experiments	305	20
milch, at pasture, feeding cowpea hay	318	14
grain	317	26–27
Cranberries, composition, comparison with roselle	307	13
Cranberry substitute, roselle	307	5, 13
Cream, bacteria, relations of age and temperature	309	31–32
ripening starters, practical use	317	27–28
Creosote treatment of fence posts, cost	320	31
Cribs, corn, convenient arrangement	313	24
Crimson clover, use on hay farm, culture and harvesting	312	9, 10
value as green manure for sweet potatoes	324	7
Crop rotation, Alabama diversification farm	310	7, 23
purposes accomplished	302	17
sweet-potato growing	324	5, 16
rotations, cotton farms	319	14
cowpeas, for soil improvement, Southern States	318	22–24, 28
hay farm	312	9, 15
Oklahoma, suggestions	309	15–16
Cropping systems, small farm	325	7, 14, 22
Crops, Alabama diversification farm, cost and yield, 1904, 1905, 1906	310	14–15, 18–19, 21–22
fruit and truck, marketing, cooperation	309	20–23
rotation to precede corn	317	20
CROSBY, M. A., J. F. DUGGAR, and W. J. SPILLMAN, bulletin on "A successful Alabama diversification farm"	310	1–24
Cultivator, sweet potato, description	324	23
Cultures, pure, nitrogen-gathering bacteria, directions for use	315	7–8
Curing hops, object, theory, and practical methods	304	19–33
tea, black and green, directions	301	12–15
Cuscuta spp., cultivation, host plants, and description	306	7–11, 16–19
Cutters, corn, hand and horsepower	313	11–12
Cutting corn, cost per acre, hand and machine	303	6, 19
cowpeas, time, hay or seed	318	9, 19
Cuttings, hop, use in propagation, setting and cultivating	304	9, 10–12
Dairy cows, feed, cotton-seed meal and corn silage	320	28–29
See also Cows.		
Damping-off, cotton, cause and control	302	41, 47
Deer, private parks, laws, notes	308	5, 6, 7, 8, 13, 16, 19, 20, 23, 35, 51
See also Game laws, under the several States.		
Defoliate cotton, description, value in boll-weevil control	314	21–22
Delaware game laws, close seasons, and hunting licenses, 1907	308	6. 12, 27, 35, 42
Demonstration work, cooperative, on southern farms	319	1–22
plan and scope	319	6–9
Diarrhea, chickens, remedies	305	31
Dibble, setting sweet potatoes	324	19, 21
Diking and drainage, relative cost and value	320	10
Diplosis sorghicola, cause of "blast" in milo	322	21
Disease, fungous, of roselle, control	307	16
Diseases, cotton, control by rotation with immune crops	302	18, 43, 45, 47, 48
poultry, remedies	305	31, 32
Sea Island cotton, causes and prevention	302	41–48
sweet potatoes, description, prevention, and control	324	24–26
Disinfectant, chicken, for intestinal diseases	305	32

Farmers' Bulletin No. Page.
ɪinfection, scabby potatoes.. 316 12
ɪtrict of Columbia game laws, close seasons, and licenses, 1907... 308 6, 13, 27
tch cleaner, construction and use.. 321 13
tcher for cleaning ditches, construction and use.................. 321 13–14
tches, lining to prevent seepage losses........................... 317 10–12
versification crops, benefits.. 302 17
  farm, Alabama, successful........................... 310 1–24
dder, control in Europe.. 306 6
  not poisonous to stock.. 306 26
  plants, detection and destruction........................ 306 22–24
  relation to farm seeds.. 306 1–27
  seed, detection, cleaning.. 306 15–21
    sources, sizes, description........................... 306 12–19
dders, characteristics, varieties, host plants.................... 306 7–11, 27
gfish, use for fertilizer.. 320 7
ve. *See* Game laws, under the several States.
ag, plank, for earth roads, directions for making.................. 321 8
  split-log, for earth roads, directions for construction and use.. 321 1–14
ainage and diking, relative cost and value........................ 320 10
  control of cotton rust.. 302 48
  road construction.. 311 11
ugs, poultry, list.. 305 31–32
ying hops, practical methods.. 304 23–26
y-land grain crop, milo.. 322 1–23
ck, wild. *See* Game laws, under the several States.
ɪGGAR, J. F., M. A. CROSBY and W. J. SPILLMAN, bulletin on
'A successful Alabama diversification farm".................... 310 1–24
ɪrra varieties, characteristics.. 322 5–6
.rum wheats, baking tests.. 320 21
'e, roselle, suggestion.. 307 14

rth roads, split-log drag, directions for construction and use...... 321 1–14
gplant, ringing, results.. 316 9
gs, incubation, evaporation and other factors affecting............ 309 24–26
  turning and cooling.. 309 25–26
yptian corn, resemblance to milo.. 322 5, 22
  cotton. *See* Cotton, Egyptian.
ɪ. *See* Game laws, under the several States.
ɪmer, composition, comparison with other cereals.................. 305 17
  feeding stuff.. 305 17–19
gines, gasoline, shocking and shredding corn.................... 303 30
rope, dodder control.. 306 6
aporation, eggs, relation to incubation........................ 309 24–26
periment Station Work, XLII, XLIII, XLIV, XLV, XLVI..... {305, 309, 316, 317, 320} 1–32 each.
port, game, State laws prohibiting.. 308 26–32

ina, wheat, cooking long and short period, digestibility.......... 319 18
m animals. *See* Animals.
  diversification, Alabama, successful........................ 310 1–24
  hay. *See* Hay farm.
  home, improving conveniences.. 317 5–10
  one-horse, management as hay farm........................ 312 6–13
  twenty-acre, Nebraska, cost, management, equipment, and returns.. 325 21–27
mers, southern, cooperative demonstration work................ 319 1–22
ming, clover, sandy jack-pine lands of the North.................. 323 1–24
ms, demonstration, South, plan, number, and scope............ 319 6–8
  forty-acre, Nebraska, cost, management, equipment, and returns.. 325 7–21
  small, corn belt.. 325 1–29
tening cattle for market.. 320 25–28

	Farmers' Bulletin No.	Page.
Fattening hogs, cowpea pasture	318	13
methods, cost	310	11, 15, 19, 22
pigs, cull beans, comparison with other feeds	305	25
sheep and lambs, emmer experiments	305	18
steers, cowpea pasture and hay	318	14
Feed, chickens, directions	305	28
hoppers for poultry	316	30-32
musty, chicks, cause of death	309	27
stock, sweet potatoes, use and value	324	38-39
Feeding, grain, milch cows at pasture	317	26-27
hog, supplements to corn	316	25-28
horse, tests	316	22-25
mixtures for hogs	316	26
stuff, use of emmer	305	17-19
Fence posts, cutting, time and manner	320	32
preservation methods	320	30-32
Fences, hog pastures, directions	305	25
Fertilizer distributers for sowing fertilizers	324	8
distribution, methods and cost	316	5, 6
fish, origin, composition, and value	320	5-9
formulas combining fish and chemicals	320	7
roselle, formula, quantity per acre	307	11-12
Fertilizers, alfalfa	310	11-21
clover on jack-pine lands	323	23
commercial, use on sweet potatoes, application	324	7-9, 17
corn	310	13, 17, 20
tests for yield	317	20
cotton, recommended in demonstration work	319	12
effect on color of apples, experiments	316	8-9
quality of wheat	320	21
leguminous hay crops	312	8, 14
need not be supplied by inoculation of legumes	315	13
Sea Island cotton, general principles and formula, quantity per acre	302	20-23
sweet potatoes	324	6-9
use and general principles	302	20-22
Fiber, cotton, length desirable in seed selection	314	15
roselle, quality and uses	307	14
Fibers, cotton, short or weak, cause and prevention	302	38
Firing burnt-clay road, directions	311	18
Fish fertilizer, origin, composition, and value	320	5-9
Flavor, milk, from feed, prevention	305	19, 23
Flax, dodder infestation, description of seed	306	9, 10, 12, 16, 23
Florida game laws, close seasons, and hunting licenses, 1907	308	6. 13, 27, 35, 42
roselle introduction from Jamaica	307	7
Sea Island cotton, annual crop	302	8
Flours, gluten, and similar foods, examination, results	305	13-16
Fodder, corn, feeding value	313	10
preparation, cost	303	30-32
protein content	320	16
silage	316	21
hauling rack	313	23
shredding and storing	313	22-2
cost	303	3
storing and protection	313	2-
Foliage injury, Bordeaux mixture, description and prevention	305	1
Food preparation, necessity of knowledge of nutritive value of foods	317	7-
Foods, cereal, cooking	316	1 3-
diabetic, examination, results	305	1 3
Forage crops, protein content	320	1 3
Forcing plants, use of anesthetics	320	2
Formaldehyde gas, generation for disinfection of scabby potatoes	316	
Formalin, use in disinfection of scabby potatoes, cost	316	

	Farmers' Bulletin No.	Page.
st, injury to sweet potatoes	324	26
sted corn silage, feeding value	309	19
iit crops marketing, cooperation	309	20–23
growers' associations	309	22–23
small, profit on small farms	325	11, 23, 25
ls, nematode, similarity to nodules	315	12
ne, close seasons, United States and Canada, 1907	308	11–24
export, state laws prohibiting	308	26–32
laws for 1907	308	1–52
legislation, U. S. and Canada, 1907	308	3–10
packages, marking, laws	308	25–26
preserves, establishment in States and Canada	308	5
sale, restrictions	308	34–39
shipment, federal laws	308	25
transportation, laws	308	25–33
warden service, laws, 1907	308	5
s, illuminating, effects on trees, symptoms	316	12–14
soline engine, farm, for husking and shredding corn	303	30
orgia game laws, close seasons, and hunting licenses, 1907	308	6, 13, 27, 42
Sea Island cotton, annual crop	302	8
tea-planting experiments	301	7
ning Sea Island cotton, special equipment and care	302	11, 40
dling herbaceous plants	316	9, 11
iten flours and similar foods, examination, results	305	13–16
t, mountain. *See* Game laws, under the several States.		
ose, wild. *See* Game laws, under the several States.		
ose-neck heads, objectionable in grain	322	8
in feeding, milch cows at pasture	317	26–27
musty, cause of death of young chicks	309	27
ss, Bermuda. *See* Bermuda grass.		
brome, protein content	320	16
fertilizer formula, fish and chemicals	320	8
sowing without nurse crop	325	10
vity separation, cotton-seed improvement	302	33
y crowder cowpeas, characteristics	318	26
en manuring, value increased by inoculation	315	12
enhouse tomatoes, pollination	317	15–17
enhouses, summer mulch, use of manure	305	9–10
it cowpeas, characteristics	318	25
mbo clay, description	311	16
ns, automatic, hunting, prohibitions	308	4, 8, 10
re. *See* Game laws, under the several States.		
RTLEY, C. P., bulletin on "Harvesting and storing corn"	313	1–29
rvesters, corn, sled, construction, cost and efficiency	303	7–10
rvesting corn	313	1–29
cost of different methods	303	32
machinery	303	1–32
methods, relation to soil fertility	313	27
cowpeas, directions	309	17
milo crop	322	17
roots	305	21–22
roselle calyces	307	12
soy beans, directions	309	17
sweet potatoes, time, methods, implements, grading and packing	324	26–28
waii game laws, close seasons, and hunting licenses, 1907	308	6, 13, 35
y, Bermuda grass, yield and value, Oklahoma experiments	320	12–13
cowpea, harvesting and storing	312	12
mixtures, planting directions	318	11–13
planting, cutting, and curing	318	8–10
farm, management, equipment cost, expenses and receipts	312	6–13
southern, successful	312	1–15
growing on southern farms	312	13–15

	Farmers' Bulletin No.	Page.
Hay, mixed grasses, protein content	320	16, 17
shed, description	312	12
winter, mixture of oats, vetch, and crimson clover	312	14
Hemp, wild, results of inoculation	315	11
Hens, feeding, substitution of snow for water	309	28
Herbaceous plants, ringing, experiments	316	9-11
Heterodera radicicola, cause of root-knot	302	47
roselle, danger and avoidance	307	11, 16
Hibiscus sabdariffa. *See* Roselle.		
HILLMAN, F. H., bulletin on "Dodder in relation to farm seeds"	306	1-27
Hog farm, Alabama black belt	310	1-24
feeding, pasturage and dry-lot comparison	316	28
supplements to corn	316	25-28
management, Alabama diversification farm	310	9-12
raising on small farm	325	19
Hogs, cowpea pasture, returns	318	13
fattening after cattle, effects of different feeds	320	28
methods, cost	310	11, 15, 19, 22
feeding beans, experiments, methods	305	25-28
roots	305	21
suggestions	305	28
tankage for hogs following cattle	316	28-30
pasture, alfalfa, Bermuda grass, cowpeas, and peanuts	310	10, 12, 16, 18, 20, 21, 23, 24
pasturing, alfalfa and cowpeas	305	24, 25
Home, farm, improving conveniences	317	5-10
Home-grown tea	301	1-16
Honduras rice, description	305	6
Honey, tuna, manufacture	316	16
Hop growers' associations, Pacific coast, advantages	304	39
growing conditions, climate and soil, area of production, United States	304	7-8
kilns, types, construction, details	304	26-31
planting directions	304	10-12
production, cost	304	36
United States, 1901-1906	304	37
propagation, seedlings and cuttings	304	9
pruning methods	304	12
roots, price per thousand	304	11
training systems	304	16-17
trellises, description	304	13-16
yield per acre, 1879, 1889, 1899	304	36
Hoppers, poultry feeding	316	30-32
Hops, baling, directions, presses, measure and weight of bales	304	33-36
cooling and storing	304	31-33
curing, object, theory, and practical methods	304	19-33
growing and curing	304	1-39
marketing, conditions, needs	304	37-39
picking and testing for ripeness	304	17-1
trampling, injuries	304	3
unripe, disadvantages	304	
Horse feeding, carrots and parsnips	305 309	
cowpea hay	318	2-
tests	316	2 0-
Hotbeds, sweet-potato propagation, heating methods	324	1
Houses, storage, sweet potato, directions for building, temperature and ventilation	324	3 0-
Hunting licenses, laws, 1907; details	308	4-5, 3 9-
Huskers, corn, description	303	2 6-2
Husking corn, cost per acre	303	30, 3
from shock	313	17-19
standing stalks	313	17-19
methods, cost	313	9
machines, use	313	21, 22

	Farmers' Bulletin No.	Page.
brid plants, elimination from Sea Island cotton fields	302	15, 23
bridizing cotton	314	29
s. *See* Game laws, under the several States.		
for household use, danger of pollution	309	5–7
iho game laws, close seasons, and hunting licenses, 1907	308	6, 13, 28, 35, 42
inois game laws, close seasons, and hunting licenses, 1907	308	6, 13, 28, 35, 42
plements, corn cutting and harvesting	303 313	1–32 11, 18, 21–22
hops, baling	304	33–36
sweet potatoes, planting and harvesting	324	19–21, 23, 27
ubation, eggs, evaporation, temperature and moisture	309	24–26
lian Territory game laws, close seasons, and hunting licenses, 1907.	308	6, 28
liana game laws, close seasons, and hunting licenses, 1907	308	6, 13–14, 28, 38, 42
dians, hunting laws, notes	308	9, 11, 22, 24, 28
oculation by soil transfer, danger	315	14
clover, new lands, methods	323	14–15
effect on value of green manuring	315	12
legume, effect on crop composition	315	10–12, 15–20
progress	315	1–20
when desirable and when useless	315	13
ect enemies, roselle, control	307	16
pests, introduction by soil transfer in legume inoculation	315	14
ects, control by rotation of crops	302	18
poultry, remedies	305	30–32
stored grain, control	313	26
estinal disinfectants for chickens	305	32
va game laws, close seasons, and hunting licenses, 1907	308	6, 14, 28, 36, 42
omœa batatas. *See* Sweet potatoes.		
n cowpeas, characteristics	318	26
igation systems, cement pipes, molding and cost	317	12–15
k-pine lands, description, cost, clearing and breaking	323	5–10
securing stand of clover	323	11–15
sandy lands of North, clover farming	323	1–24
n, roselle, directions, characteristics	307	13
nnovitch cotton. *See* Cotton, Egyptian.		
oan rice, description	305	6
ly, roselle, directions for making, and characteristics	307	13
usalem corn, resemblance to milo	322	5, 22
nson grass and cowpeas, mixture for hay, planting directions	312	15
use for hay	312	15
init, source of potash, comparison with muriate of potash	302	22
le, use as stock feed, Europe	305	22
nsas game laws, close seasons, and hunting licenses, 1907	308	6, 14, 28, 36, 42
milo growing	322	11, 22
LLERMAN, KARL F., and T. R. ROBINSON, bulletin on "Progress n legume inoculation"	315	1–20
ntucky game laws, close seasons, and hunting licenses, 1907	308	14, 28, 36, 42
rosene emulsion for use in chicken houses	305	30
lns, hop, types, construction details	304	26–31
NG, D. WARD, bulletin on "The use of the split-log drag on earth oads"	321	1–14
tchen conveniences, suggestions	317	6–7
APP, S. A., bulletin on "Demonstration work in cooperation with outhern farmers"	319	1–22
ives for cutting corn, description	303 313	5–6 11

Farmers' Bulletin No. — Page.

Kohl-rabi, varieties, and value as feed for stock........ 309 14
Koumiss, formation of lactic acid........ 320 30

Labor, cost, Alabama diversification farm........ 310 11
Labor-saving appliances, farmer's wife........ 317 7
Lambs, fattening, emmer experiments........ 305 18
Laphygma frugiperda, damage to milo crop........ 322 21
Laws, game, for 1907........ 308 1-52
  proposed but failing to pass, 1907........ 308 9-10
Leaf, cotton, large size objectionable in seed selection........ 314 14
Leaf-spot, angular, cotton, description, cause and control........ 302 41-43
Legislation, game, United States and Canada, 1907........ 308 3-10
Legume bacteria, effect on crop composition........ 315 10-12, 15-20
  effects of soil conditions........ 315 9-10
  inoculation, cooperative field tests, results........ 315 14-15
    effect on crop composition........ 315 10-12, 15-20
    progress........ 315 1-20
    when desirable and when useless........ 315 13
Legumes use in rotation with Sea Island cotton........ 302 18-20
  on cotton farms........ 319 14
LEIDIGH, ARTHUR H., and CARLETON R. BALL, bulletin on "Milo as a dry-land grain crop"........ 322 1-23
Lettuce diseases, prevention, use of manure as summer mulch in forcing house........ 305 10
Lice, chickens, remedies........ 305 31
Licenses, hunting, alien and guest, notes........ 308 6, 7, 8, 9, 39, 40
  and shipping game, 1907........ 308 4-5, 41-48
Lime, use on sweet-potato land........ 324 9
Lining ditches and reservoirs, to prevent seepage losses........ 317 10-12
Live stock, keeping on small farms........ 324 11, 12, 16, 19, 24
Long Island, close seasons for game, 1907........ 308 18
Louisiana, demonstration work, cooperative letters from farmers........ 319 21
  game laws, close seasons, and hunting licenses, 1907........ 308 14, 28, 42

Machinery, corn harvesting, use........ {313 11, 12, 13, 21, 22; 303 1-32}
  cowpea picking, mowing, and thrashing........ 318 17-22
  equipment on small farms........ 325 12, 24
  milo harvesting and thrashing........ 322 18, 19
  sweet-potato planting........ 324 21
Machines, corn-harvesting, description, cost, and efficiency........ 303 7-22
Maine game laws, close seasons, and hunting licenses, 1907........ 308 6, 14-15, 28, 36, 42-43
[illegible] comparison with corn, etc........ 305 21
[illegible] and plants per acre........ 309 9
[illegible] cultural directions, harvesting and [illegible]........ 309 10-12
[illegible] corn........ 317 20
[illegible] for forcing houses........ 305 9-10
[illegible]........ 312 8
[illegible]........ 316 5-6
[illegible] forage crops........ 320 15, 16, 17
[illegible] cowpeas and soy beans, comparison........ 309 18
[illegible] and cost........ 316 5
[illegible] of cotton rust........ 302 48
[illegible]........ 302 45
[illegible]........ 324 6
[illegible] commercial fertilizers........ 302 20
[illegible] clover in sandy land........ 323 22
Manuring, green, value increased by inoculation........ 315 12
Marketing crops, cooperation........ 309 20-23
[illegible] conditions and needs........ 304 37-39

	Farmers' Bulletin No.	Page.
Marketing roselle calyces	307	12
sweet potatoes	324	28, 34
Marl, effect on clover lands	323	23
Marsh lands, New Jersey, description and value after reclamation	320	10–11
Marshes, salt, reclamation	320	9–12
Maryland county laws for close seasons for game, 1907	308	49–50
Eastern Shore, Peninsula Producer Exchange, methods	309	23
game laws, close seasons, and hunting licenses, 1907	308	15, 28, 36, 43
Massachusetts game laws, close seasons, and hunting licenses, 1907	308	7, 15, 28, 36, 43
Menhaden, use for oil and fertilizer	320	5-6
Mice, protection of corn in cribs	313	27
Michaux, tea introduction into the United States	301	7
Michigan bean crop	305	25
game laws, close seasons, and hunting licenses, 1907	308	7, 15, 29, 36, 43
sandy jack-pine lands, clover farming	323	1–24
Midge, clover-flower, control	323	19
sorghum, cause of "blast" in milo	322	21
Miel de tuna, manufacture	316	16
Milch cows. *See* Cows, milch.		
Mildew, roselle, description and control	307	16
Milk, carbonated, formation of lactic acid	320	29
flavor from feed, prevention	305	19, 23
production from feeding cotton-seed meal and corn silage	320	29
results from cowpea-hay feeding	318	14
Millet and cowpeas, mixture for hay, planting directions	318	13
protein content	320	17
Millo. *See* Milo.		
Milo, area where grown	322	10–12
classification, common names, varieties, and characteristics	322	5-7
dry-land grain crop	322	1-23
feed use and value	322	20
freedom from fungous diseases	322	22
grain yields	322	19, 23
growing, planting, cultivation, and harvesting, directions	322	12-19
insect enemies	322	21
ordinary and improved, characters	322	7-10
seed, planting methods and rate	322	13-15
selecting and saving, directions	322	15-17
Minnesota game laws, close seasons, and hunting licenses, 1907	308	7, 15, 29, 36, 43
sandy jack-pine lands, clover farming	323	1-24
Mississippi game laws, close seasons, and hunting licenses, 1907	308	16, 29, 36, 44
Missouri game laws, close seasons, and hunting licenses, 1907	308	7, 16, 29, 36, 44
peach varieties adapted to climate	316	7
MITCHELL, GEORGE F., bulletin on "Home-grown tea"	301	1-16
Mites, chicken, prevention	305	30, 32
Moisture content, ear corn	317	18
Molasses, feed for horses, tests	316	22-24
Montana game laws, close seasons, and hunting licenses, 1907	308	7, 16, 29, 36, 44
Moose. *See* Game laws, under the several States.		
Mowing cowpeas for seed	318	19-22
Mulch, growing seed potatoes	305	8-9
winter, forcing houses, use of manure	305	9-10
Mules, feeding, cowpea hay	318	14
Nebraska, farms, small, management, cost, and profits	325	7-27
game laws, close seasons, and hunting licenses, 1907	308	7, 16, 29, 36, 44
milo-growing experiments	322	11
Nematode galls, similarity to nodules	315	12
root-knot, roselle susceptibility, avoidance infested soil	307	11 16

	Farmers' Bulletin No.	Page.
Neocosmospora vasinfecta, cause of cotton wilt or black-root	302	44
Nep, cotton defect, causes and prevention	302	15, 37
Nevada game laws, close seasons, and hunting licenses, 1907	308	7, 16, 29, 36, 44
New Era cowpeas, characteristics	318	25
Hampshire game laws, close seasons, and licenses, 1907	308	7, 16, 29, 36, 44
Jersey game laws, close seasons, and hunting licenses, 1907	308	7, 16–17, 29, 36, 44
marsh lands, description, value after reclamation	320	10, 11
Mexico game laws, close seasons, and hunting licenses, 1907	308	7, 17, 29, 36, 44
milo growing	322	11, 22
York game laws, close seasons, and hunting licenses, 1907	308	7, 17–18, 29, 36, 45
hop growing, season and methods of training	304	10, 17
production per acre, possibility	304	36
NIELSON, H. T., bulletin on "Cowpeas"	318	1–28
Nitrate, soda, effect on yield of corn	317	20
use on cabbage	305	23
Nitrogen, fertilizer, sources and effects	302	21
increase in plants by inoculation	315	10–12
Nitrogen-gathering bacteria cultures, use and reports	315	7–9
Nodule formation, effect on crop composition	315	10–12, 15–20
North Carolina county laws for close seasons for game, 1907	308	51–52
game laws, close seasons, and hunting licenses, 1907	308	7, 18, 30, 45
Dakota game laws, close seasons, and hunting licenses, 1907	308	7, 18, 30, 36, 45
milo-growing experiments	322	12, 22
Nuts, value as food for diabetics	305	15
Oats, feed for horses, tests	316	22
planting for hay, handling	312	10
rolled, cooking long and short period, digestibility	319	18
Ohio game laws, close seasons, and hunting licenses, 1907	308	18, 30, 36, 45
Oidium sp., fungous disease of roselle, control	307	16
Oklahoma crop rotations, suggestions	309	15–16
game laws, close seasons, and hunting licenses, 1907	308	18, 30, 36, 45
Okra, susceptibility to wilt or black-root	302	44
OLDYS, HENRY, CHAS. E. BREWSTER, and T. S. PALMER, bulletin on "Game laws for 1907"	308	1–52
Open-tank treatment of fence posts, cost	320	31
Opossum. *See* Game laws, under the several States.		
Orchards, old, renewal, directions for pruning and fertilizing	305	11
Oregon game laws, close seasons, and hunting licenses, 1907	308	7, 18–19, 30, 37, 45
[illegible] Growers' Union	309	23
[illegible] season and methods	304	10, 11
[illegible] per acre, possibility	304	36
[illegible] Cotton"	302	1–48
[illegible]	305	11
[illegible]ys, and CHAS. E. BREWSTER, bulletin [illegible] for 1907"	308	1–52
[illegible]lder, in relation to farm seeds	306	1–27
[illegible] distributing manure	316	5
[illegible]	305	21
[illegible] Game [illegible]s, under the several States.		
[illegible]as, va[illegible] or hogs, returns per acre	318	13
[illegible]ion, meth[illegible] of cattle-tick eradication	309	30
[illegible], fencing directions	305	25
Pasturin[illegible], alfalfa and cowpeas	305	24–25
Pea h[illegible]otein content	320	15
[illegible]ls, winterkilling prevention, studies	316	6–8
[illegible] winterkilling	316	[illegible]

	Farmers' Bulletin No.	Page.
Peanuts, pasture for hogs	310	21, 23
renovation of poor soil	319	17
Peas, garden, results of inoculation	315	17–19
Peck, corn harvester, principles	303	11
Pedigree breeding, Sea Island cotton	302	31–33
Pennsylvania game laws, close seasons, and hunting licenses, 1907	308	8, 17, 30, 37, 45
Petroleum treatment of fence posts	320	31
use in ditch lining	317	11, 12
Pheasant. *See* Game laws, under the several States.		
Phosphoric acid fertilizer for leguminous hay crops	312	14
Phosphorus, fertilizer, effect on Sea Island cotton	302	22
Phytin, laxative constituent of wheat bran and other foods	305	17
Pickers, corn, description, objections and advantages, cost and efficiency	303	23–26
Picking corn, cost	303	26
hops, directions for testing ripeness	304	17–19
Pigs, fattening, cull beans, comparison with other feeds	305	25
Pine, jack. *See* Jack-pine.		
Pipe, cement, small irrigation systems; mixtures, method of molding, and cost	317	12–15
Pipes, wood, clay, and cement, use in irrigation systems	317	13, 14
Pit, root storing, directions	305	22
sweet potato, directions for building	324	29
Plants, forcing, use of anesthetics	320	23–25
herbaceous, ringing, experiments	316	9–11
Plaster, land, effect on clover lands	323	23
Plover. *See* Game laws, under the several States.		
Plowing for Sea Island cotton, methods	302	23–26
shallow, sandy land	323	9
Poisoning, danger from green sorghums	322	21
Pollination, tomatoes, forced	317	15–17
Pollution, ice, danger, need of prevention by public regulations	309	5–7
Posts, fence, preservation methods	320	30–32
Potash fertilizer, control of cotton rust	302	48
for leguminous hay crops	312	14
muriate, comparison with kainit, effectiveness	302	22
salts, addition to fish fertilizer	320	7, 8
Potassium fertilizer, sources and effects	302	21
permanganate, use in disinfection of scabby potatoes, cost	316	12
Potato beetles, control by hand picking	325	9
growing, cost	325	10
scab, causes and prevention	316	11–12
Potatoes, fertilizer formula, fish and chemicals	320	8
growing on small farms	325	8–10, 18, 22
seed, growing under mulch	305	8–9
spraying methods and results	320	22–23
sweet. *See* Sweet potatoes.		
Poultry catching hook	317	31–32
feed hopper	316	30–32
feeding, cowpeas seed and hay	318	15
healthy, feed and care, diseases and insects, remedies	305	28–32
keeping, small farms	325	12, 19
water, experiments with snow as substitute	309	28
pans	317	28–31
Preserves, game, establishment in States and Canada, 1907	308	5
Presses, hop-baling, hand and power, description	304	34–35
Protein content of forage crops	320	13–17
Pruning orchard trees for renewal	305	11
tea plants, directions	301	11
Prussic acid poisoning, occurrence in green sorghums	322	21
Ptarmigan. *See* Game laws, under the several States.		
Puddle, lining for ditches, efficiency and cost	317	11
Puddling roots, sweet potato sets	324	16
Pulp, beet-sugar, feed for horses, tests	316	24

	Farmers' Bulletin No.	Page.
Quail. *See* Game laws, under the several States.		
Queso de tuna, preparation, use	316	16
Quincy, Edmund W., invention of corn-harvesting machinery	303	10
Rabbit. *See* Game laws, under the several States.		
Rail. *See* Game laws, under the several States.		
Rape, protein content	320	15
Ration, daily, cattle different ages	325	16
Rats, protection of corn in cribs	313	27
Reclamation, salt marshes	320	9-12
Red clover, inoculation, results	315	15, 16, 18, 19
rice, prevention	305	7-8
Ripper cowpeas, characteristics	318	26
Reservoirs, lining to prevent seepage losses	317	10-12
Rhizoctonia, fungus, cause of sore-shin and damping-off, cotton	302	41
Rhode Island game laws, close seasons and hunting licenses, 1907	308	8, 19, 30, 37, 45
Rice culture extension	305	5-8
production, United States, 1889, 1899, 1905	305	5
red, prevention	305	7-8
varieties, characteristics	305	6
Ridge culture, Sea Island cotton, directions	302	23
Ringing herbaceous plants	316	9-11
Ripening cream starters, practical use	317	27-28
Rivers cotton, wilt-resistant variety	302	45
Road repairing, suggestion	311	15
Roadbed preparation for burnt-clay road	311	17
Roads, earth, maintenance, cost with and without drags	321	11-12
split-log drag, directions for construction and use	321	1-14
rocky or gravelly, use of drag	321	11
sand-clay and burnt-clay	311	1-19
Robinson, T. R., and Karl F. Kellerman, bulletin on "Progress in legume inoculation"	315	1-20
"Roguing" in seed selection, Sea Island cotton	302	28
Root crops, culture and varieties	309	7-15
seeds, weight, germination, seeding directions	309	8
use as stock feed	309	9
Root-knot, cotton, cause and control	302	42
Roots, feeding, composition, comparative value	305	20-21
farm animals	305	19-22
quantity and method	305	19
harvesting and storing	305	21
Roselle, botanical characters and relationships	307	7-8
calyces, harvesting and marketing	307	12
composition and uses, comparison with cranberries	307	13
cultural directions, and fertilizers, formula	307	10-12
culture and uses	307	1-16
diseases and insect enemies, control suggestions	307	16
fiber, quality, uses	307	14
history and geographical distribution	307	6-7
jelly making	307	6, 13
varieties, breeding possibilities	307	8-10, 14
yield per plant	307	12
Rot, black, sweet potato, description and control	324	24, 25
Rotation, crop, Alabama diversification farm	310	7-23
cotton farms	319	14
cowpeas for southern soils	318	22-24, 28
for control of cotton diseases	302	45
sweet-potato growing	324	5, 16
crops, purposes accomplished, weed control, etc	302	17
to precede corn	317	21
systems, Sea Island cotton planting	302	18-20
Rots, sweet potato, description, control	324	25
Roughage, use in fattening cattle	320	26
Russeting fruit, Bordeaux mixture, description, prevention	305	12-13

	Farmers' Bulletin No.	Page.
Rust, cotton, description, causes and prevention	302	47–48
Ruta-baga, cultural directions, fertilizers, seed per acre, and yield	309	12–14
Rye fodder, protein content	320	17
Saccharine, coal-tar product, use as sugar substitute	305	15
Sale, game, restrictions	308	34–39
Salt marshes, reclamation	320	9–12
use in feeding hogs	305	28
Sand mixing with clay for road	311	7–10
origin, physical properties	311	6
Sand-clay roads, construction methods and cost	311	11–15
value and use	311	5, 15
Sandpiper. *See* Game laws, under the several States.		
Sandy land, shallow plowing	323	9
wind prevention by rough fields	323	17
wind-breaks, necessity	323	16–17
Scab, potato, causes and prevention	316	11–12
Scab-resistant apple varieties, list	305	13
Scale, soft, roselle, distribution by ant	307	16
Sea Island cotton, adaptation to colder climate by breeding	307	15
annual crop in Florida, Georgia, and South Carolina	302	8
baling and packing methods	302	11–12
cultivation, rotation, and diversification	302	16–20
culture, improvement, and diseases	302	1–48
defects influencing grade, remedies	302	37–41
diseases, causes and prevention	302	41–48
fertilizers, general principles, formula, quantity per acre	302	20–23
geographical distribution in U. S	302	7–8
handling, method in Sea Islands	302	40
markets, packing methods	302	11–12
packing and marketing	302	11–12, 13
pedigree breeding, directions	302	31–33
planting seed, distance, early or late planting	302	25
preparation of land, ridge and level culture	302	23–26
prices, factors governing	302	12–14
seed selection and breeding, directions, methods	302	26–33
soil, moisture, humus, location, etc	302	9–11
staple, preparation for market	302	15, 37–40
varieties, changes, sale of seed	302	27–28
Sea Islands, cotton growers' methods of seed selection	302	27–33
South Carolina, superior grade of cotton	302	9–11
Seed adulteration, importance of dodder	306	6
alfalfa, quantity per acre	310	12, 21
carrot, low germination and seeding quantity per acre	309	8, 15
clover, growing, customs, yield, etc	323	18–21
production on jack-pine lands	323	10
quantity to sow with nurse crops	323	13
corn selection in field	319	16
cotton, early, selection, method, directions	314	6, 10–13, 17–21
improvement by gravity separation	302	33
quantity per acre for seed patch	314	19
selection and storing	319	14
cowpea, growing, harvesting, thrashing, and storing	318	15–22, 27
quantity to sow per acre	309 310 312 318	17 13, 17 11 9, 11, 12, 13, 16
crimson clover, quantity to sow per acre	312	10
dodder, detection, cleaning	306	15–21
sources, sizes, description	306	12–19
forage plants, selection for protein content, by color of seed	320	14, 15

	Farmers' Bulletin No.	Page.
Seed milo, planting methods and rate	322	13-15
selecting and saving, directions	322	15-17
peanuts, quantity to sow der acre	310	21
potatoes, growing under mulch	305	8-9
production in cooperative demonstration work	319	17
ruta-baga, quantity to sow per acre	309	12, 13
Sea Island cotton, description	302	36
selection and breeding, Sea Island cotton, directions, methods.	302	15, 26-33
in breeding early cotton, method, directions	314	6, 10-13, 17-21
sweet potatoes for planting	324	10
sorghum, quantity per acre	310	14, 21
soy beans, quantity to sow per acre	309	17
sweet potato, bedding	324	13-14
tea, planting directions	301	9
timothy and clover, quantity per acre without nurse crop	325	10
treatment for inoculation with nitrogen gathering bacteria	315	7-8
turnip, quantity to sow per acre	309	12, 13
Seed-bed cotton, preparation for early stand	314	27
Seeds, farm, relation of dodder	306	1-27
root-crop, weight and germination, comparison	309	8
Seepage losses, ditches and reservoirs, prevention	317	10-12
Selection, seed, in breeding early cotton, method, directions	314	6, 10-13, 17-21
Sea Island cotton, methods	302	27-33
Sesbania macrocarpa, results of inoculation	315	11
Sets, sweet potato, drawing, care in handling	324	15-16
Shallow planting necessary for early stand of cotton	314	25-27
Shed, hay, description	312	12
Sheep fattening, emmer experiments	305	18
feeding, cabbage and roots	305	21, 23
mountain. *See* Game laws, under the several States.		
SHEPARD, Dr. CHARLES U., tea gardens, Summerville, South Carolina	301	8
Shipment, game, federal laws	308	25
laws, State and Canadian	308	25-32
Shipping game, licenses, 1907	308	39-48
Shock, corn, building and tying, directions	313	12, 15, 16
Shocker, corn, construction, cost and efficiency	303 313	19-22 14
Shocking corn, building and tying shock, method of making shocks	313	12, 14-16
cost per acre, hand and machine	303	6, 19, 22
Shorts, hog feed as supplement to corn	316	25, 27
Shredders, corn, description	303	26-29
Shredding corn fodder	313	22
and husks, cost	303	31
Shrinkage, corn in cribs	317	22-26
December to June	313	28
sweet potatoes, loss in storage	324	34
Shucking corn	303 313	26-31 9, 17-19, 21
Sieves, seed sifting, description	306	20, 21
Silage, corn, and cotton-seed meal for dairy cows	320	28-29
cowpeas, planting	318	11
feed for horses, tests	316	24
from cured corn fodder	316	21
frosted corn, feeding value	309	19
steaming to reduce acidity, experiment	316	19-21
Silo filling, best condition of corn	313	7
SMITH, C. BEAMAN, bulletin on "Clover farming on the sandy jack-pine lands of the North"	323	1-24
Snipe. *See* Game laws, under the several States.		
Snow for poultry, experiments	309	28
Soda nitrate, effect on yield of corn	317	20
use on cabbage	305	23
Soil conditions, effect upon legume bacteria	315	9-10
fertility, relation of methods of harvesting corn	313	27

	Farmers' Bulletin No.	Page.
Soil inoculation clover fields, advantages, dangers	323	15
renovation, demonstration work	319	17
requirements, sweet-potato growing	324	4-6
selection for hop growing	304	8
transfer for legume inoculation, danger	315	14
Sore-shin, cotton, cause and control	302	41
Sorghum and cowpeas, hay, planting and seeding methods	318	11
as green feed for hogs	310	14, 18, 21
Sorghums, classification, groups	322	5
poison in green state	322	21
South Carolina game laws, close seasons, and hunting licenses, 1907	308	8, 19, 30, 37, 45
Sea Island cotton, annual crop	302	8
tea planting, history	301	7
Dakota game laws, close seasons, and hunting licenses, 1907	308	8, 19, 30, 37, 46
Southern farmers, cooperative demonstration work	319	1-22
hay farm, successful	312	1-15
Soy beans and cowpeas, comparative value in crop rotations	309	15-19
mixture for hay, planting directions	318	13
planting, harvesting, and yield	309	17
protein content	320	15
results of inoculation	315	11, 18, 19
seed, quantity to sow per acre	309	17
thrashing, suggestions	309	18
varieties, comparative yield	309	18
Soy-bean meal and biscuit, examination, results	305	14-15
SPILLMAN, W. J., M. A. CROSBY, and J. F. DUGGAR, bulletin on "A successful Alabama diversification farm"	310	1-24
Split-log drag for earth roads, directions for construction and use	321	1-14
SPOON, WILLIAM L., bulletin on "Sand-clay and burnt-clay roads"	311	1-19
Spraying apple diseases, precautions to avoid foliage injury	305	12-13
potatoes, methods and results	320	22-23
Squirrel. *See* Game laws, under the several States.		
Stable manure. *See* Manure, stable.		
Stalk cutters, corn, description	313	27
Stalks, cotton, brushing off infested squares	319	13
Staple, Sea Island cotton, ideal length, strength, color, and fineness	302	33-35
preparation for market	302	15, 37-40
Starch, removal from flours	305	13
Starters, cream ripening, practical use	317	27-28
Steamed silage experiments	316	19-21
Steers, fattening, cowpea pasture and hay	318	14
emmer experiments	305	19
Stock feed, sweet potato, use and value	324	38-39
feeding, use of cabbage	305	22-24
STOCKBERGER, W. W., bulletin on "Growing and curing hops"	304	1-39
Stooling, objectionable habit in grain crop, reasons	322	7
Storage, flour, effect on quality	320	19
houses, sweet potato, directions for building, temperature and ventilation	324	30-34
sweet potatoes, methods, buildings	324	29-33
Storing cabbage, methods	305	23-24
corn, ears and stover	313	22-27
roots, directions	305	21-22
Stove kiln for hop drying, description	304	27-29
Stover. *See* Fodder.		
Straw, clover, value for feed or for manure	323	21
cowpea, value as feed	318	15
Sugar beets, feeding value, comparison with mangels	305	21
substitutes	305	15
Sulphur, rock, use in curing hops	304	26
Sulphuric acid, addition to fish fertilizer	320	6, 7
Sulphuring hops, object, kind of sulphur required	304	26
Sweet potato hotbeds, methods of heating, coverings, etc	324	10-14
insect enemies	324	
planting and harvesting, implements	324	19-21

	Farmers' Bulletin No.	Page.
Sweet potato seed, selection, and planting	324	10-14
sets, drawing, care in handling	324	15-16
Sweet potatoes, area, climate, and soil adapted to growing	324	4-6
cultivation, directions, implements	324	22-24
diseases, description, prevention and control	324	24-26
fertilizers	324	6-9
growing, storing, and marketing	324	1-39
harvesting, time, methods, implements, grading and packing	324	26-28
injury by frost	324	26
land preparation	324	16-18
marketing	324	28, 34
origin, botanical classification	324	3
plants, setting by hand or machine	324	18-22
production, cost and returns	324	38
propagation of plants, directions	324	9-16
shrinkage, loss in storage	324	34
soil suitable	324	5-6
storage, methods, buildings	324	29-34
varieties, characteristics	324	35-37
Tankage for hogs following cattle	316	28-30
hog feed as supplement to corn	316	26, 27
Taylor cowpeas, characteristics	318	26
Tea, black, curing and rolling	301	13-14
cultivation, United States, history	301	7
drawing for use as beverage	301	15
green, curing and rolling	301	14
home-grown	301	1-16
plant, climate and soil requirements	301	8
planting and care, directions	301	9-12
plucking, curing, and rolling, directions	301	12-14
Temperature, storage house, sweet potatoes	324	33-34
Tennessee game laws, close seasons, and hunting licenses, 1907	308	8, 20, 30, 37, 46
Texas, Amarillo, experimental farms, milo improvement, yield, etc.	322	10, 19, 22
demonstration work, cooperative, letters from farmers	319	17-21
game laws, close seasons, and hunting licenses, 1907	308	8, 20, 30, 37, 46
milo growing	322	11, 19, 22
Thinning peach fruit, effect on winterkilling	316	7
Thrashing cowpeas and soy beans	309	18
for seed	318	19-22
machine modifications, price	318	21-22
milo seed	322	18
Threshing. *See* Thrashing.		
Ticks, cattle, annual loss, estimate	309	29
eradication, methods and progress	309	29-30
Tide lands, reclamation	320	9-12
Timber preservation, fence-post treatment, methods, and cost	320	30-32
Tires, pneumatic, manufacture, use of Sea Island cotton	302	7
Tomatoes, forced, pollination	317	15-17
ringing, results	316	9-11
Tools, sweet potato planting and harvesting	324	19-21, 23, 27
Topping corn	313	8
cotton	319	13
Training hops, systems	304	16-17
Transportation, game, laws	308	25-33
Trees, orchard, pruning and dressing wounds	305	11
poisoning by illuminating gas, symptoms, and effects	316	12-14
Trellis, hop, description	304	13-16
Tropical fruits, roselle, culture and uses	307	1-16
Truck crops, marketing, cooperation	309	20-23
farming reclaimed marsh lands	320	11-12
Tubers, feeding, composition, comparative value	305	20-21

	Farmers' Bulletin No.	Page.
Tuna juice, use for coloring jelly and candies	316	17
products, value as food	316	16–17
Tunas, dried, use as food	316	16
Turkeys, wild. *See* Game laws, under the several States.		
Turnips, cultural directions, seed per acre, fertilizers, and yield	309	12–14
feeding value, especially for sheep	305	21
varieties, plants per acre	309	9
Unknown cowpeas, characteristics	318	25
Utah game laws, close seasons, and hunting licenses, 1907	308	8, 20, 30, 37, 46
Velvet beans. *See* Beans, velvet.		
Ventilation, storage house, sweet potatoes	324	33–34
Vermont game laws, close seasons, and hunting licenses, 1907	308	8, 20, 30, 37, 46
Vetch, results of inoculation	315	17, 19
sowing with oats for hay	312	9, 14
Victor roselle, description	307	9–10
Virginia game laws, close seasons, and hunting licenses, 1907	308	20–21, 31, 37, 46
Wapiti. *See* Game laws, under the several States.		
Warden, game, service, laws 1907	308	5
WARREN, J. A., bulletin on "Small farms in the corn belt"	325	1–29
Washington game laws, close seasons, and hunting licenses, 1907	308	8, 21, 31, 37, 46
hop planting, season and methods	304	10, 11
production per acre, possibility	304	36
Water pans, sanitary, for poultry	317	28–31
supply for poultry	305	28
Waterfowl. *See* Game laws, under the several States.		
Weeds, control by rotation of crops	302	17
introduction by soil transfer in legume inoculation	315	14
protein content	320	17
Weevil. *See* Boll weevil.		
Weevils, corn, destructiveness	313	17
West Indies, Sea Island cotton production	302	14
Virginia game laws, close seasons, and hunting licenses, 1907	308	8, 21, 31, 46
WESTER, P. J., bulletin on "Roselle, its culture and uses"	307	1–16
Wheat bran, feeding value, comparison with cowpea hay	318	14
laxative properties	305	16–17
qualities, factors affecting	320	18–22
varieties, milling and baking tests	320	18–22
Whippoorwill cowpeas, names, characteristics	318	25
Whitewash, government recipe	305	31
Wilt, cotton, description, cause and control	302	43–46
Wilt-resistant cotton, varieties, description and use	302	45–46
Wind-breaks, necessity for sandy lands	323	16–17
Winds, effect on clover catch	323	15–16
Winterkilling peach buds, prevention, studies	316	6–8
Wire netting, protection of corn from mice and rats	313	27
use in hop trellis, size, and cost per acre	304	14, 15
Wisconsin game laws, close seasons, and hunting licenses, 1907	308	8, 22, 31, 37, 47
sandy jack-pine lands, clover farming	323	1–24
Wood pipes, irrigation system, use and cost	317	13, 14
Woodcock. *See* Game laws, under the several States.		
Worm, fall army, damage to milo, injury to leaves and stems	322	21
Worms, chicken, remedies	305	31
Wounds, orchard trees, dressing with paint	305	11
Wyoming game laws, close seasons, and hunting licenses, 1907	308	8, 22, 31, 37, 47
ZINTHEO, C. J., bulletin on "Corn-harvesting machinery"	303	1–32

O

LIBRARY OF CONGRESS
0 002 892 351 A